

Street Projects

City of Angleton

January 2026

Large Scale Replacement Projects

Swift Street – Full concrete road replacement. 2,334 total feet at an approximate cost of \$260,241.00 based on the 2023 Paving Assessment. This street had a rating of 3.

San Felipe – Full concrete road replacement. 7,092 total feet at an approximate cost of \$790,758.00 based on the 2023 Paving Assessment. This street had a rating of 3.

Rayburn Ridge/Richland Circle – Road rebuilds and drainage repairs are needed; the roadway is asphalt C&G and approximately 940 feet. HDR evaluated this street in 2024 and determined an OPCC of \$1,911,900.00. This street had a rating of 3 in the 2023 Paving Assessment.

Gifford Rd/Gifford Lane – Asphalt road rebuild on both roadways at approximately 12,422 feet. We received quotes from contractors in 2025 at a cost of \$677,620.10. This street had a rating of 4 on the 2023 Paving Assessment.

Wayne Street – Asphalt road rebuild at approximately 970 feet. We received quotes from contractors in 2025 at an approximate cost of \$100,000.00. This street had a rating of 2 in the 2023 Paving Assessment.

Arcola St – Asphalt road rebuild of approximately 56,500 SF. Based on previous costs received this project would cost approximately \$360,000. This street had a rating of 3 on the 2023 Paving Assessment.

Locust St - Asphalt Road rebuild of approximately 56,500 SF. Based on previous costs received this project would cost approximately \$360,000. This street had a rating of 6 on the 2023 Paving Assessment.

Maintenance Project Areas – These projects listed below are various concrete roadways that need at least a single panel replacement, some may need multiple. There may also need to be drainage, or sanitary sewer, repairs that need to be made as well once the pavement is removed. These are the typical causes of panel failures in the concrete roadways. We did not pursue individual costs on these projects. However, as an example the cost of the most recent paving maintenance project was completed at Hospital Drive and Downing. This was at \$177,069.38 and included replacement of storm sewer pipe, new inlets, sanitary sewer pipe, and pouring the new roadway, sidewalk and curbs.

Northview Drive – Panel Replacements

Oriole Lane – Panel Replacements

Crossing – Panel Replacements

Downing/Dennis – Panel Replacements

905 Plantation – Panel Replacements

808 Noreda - Panel Replacements

Sarita - Panel Replacements

Cannan/Valderas - Panel Replacement

1200 blk Buchta - Panel Replacement

Buchta/Bastrop/Angleton Blvd - Panel Replacements

Cay Court - Panel Replacement