


Angleton King Municipal Operations Center

Geotechnical Engineering Report

June 23, 2023 | Terracon Project No. AS225036

Prepared for:

iAD Architects
107 West Way, Suite 16
Lake Jackson, Texas 77566



Nationwide
[Terracon.com](https://www.terracon.com)

- Facilities
- Environmental
- Geotechnical
- Materials



22535 N Highway 288-B
Angleton, TX 77515
P (979) 202-1113
Terracon.com

June 23, 2023

iAD Architects
107 West Way, Suite 16
Lake Jackson, Texas 77566

Attn: Ms. Terri Jordan – Office Manager
E: tjordan@iadarchitects.com

Re: Geotechnical Engineering Report
Angleton King Municipal Operations Center
901 South Velasco Street
Angleton, Texas
Terracon Project No. AS225036


Dear Ms. Jordan:

Terracon Consultants, Inc. (Terracon) is pleased to submit our geotechnical engineering report for the project referenced above in Angleton, Texas. We trust that this report is responsive to your project needs. Please contact us if you have any questions or if we can be of further assistance.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further assistance, please contact us.

Sincerely,
Terracon Consultants, Inc.
(Texas Firm Registration No.: F-3272)

Ramses Macias, E.I.T.
Geotechnical Senior Staff Engineer



Bobbie Sue Hood, P.E.
Geotechnical Services Manager

Table of Contents

| | |
|--|-----------|
| Introduction | 1 |
| Project Description | 1 |
| Site Conditions | 2 |
| Geotechnical Characterization | 3 |
| Geology | 3 |
| Subsurface Profile..... | 3 |
| Groundwater Conditions..... | 4 |
| Geotechnical Overview | 5 |
| Earthwork | 5 |
| Site Preparation..... | 6 |
| Fill Material Types..... | 6 |
| Fill Compaction Requirements..... | 7 |
| Grading and Drainage..... | 7 |
| Wet Weather/Soft Subgrade Considerations | 8 |
| Shallow Foundations | 9 |
| Design Recommendations – Shallow Spread/Strip Footings | 9 |
| Construction Considerations – Shallow Foundations..... | 10 |
| Foundation Construction Monitoring | 11 |
| Floor Slabs | 11 |
| Pavements | 12 |
| General Comments | 17 |

Attachments

- Exploration and Testing Procedures**
- Site Location and Exploration Plans**
- Exploration and Laboratory Results**
- Supporting Information**

Note: Refer to each individual Attachment for a listing of contents.

Introduction

This report presents the results of our subsurface exploration and Geotechnical Engineering services performed for the proposed pre-engineered metal building (PEMB), covered parking structures, associated pavement and driveways, and demolition considerations for existing building to be located at 901 South Velasco Street in Angleton, Texas. This project was authorized by Mr. Brent Bowles with iAD Architects through signature of our Agreement for Services on May 24, 2023. This project was performed in general accordance with Terracon Document No. PAS225036.Rev1 dated May 24, 2023.

The purpose of these services was to provide information and geotechnical engineering recommendations relative to:

- Subgrade preparation/earthwork recommendations;
- Demolition considerations;
- Recommended foundation options and engineering design parameters;
- Estimated settlement of foundations; and
- Pavement design guidelines.

The geotechnical engineering Scope of Services for this project included the advancement of three test borings to depths ranging from approximately 6 to 25 feet below existing grade, laboratory testing, engineering analysis, and preparation of this report.

Maps showing the site and boring locations are shown on the [Site Location](#) and [Exploration Plan](#), respectively. The results of the laboratory testing performed on soil samples obtained from the site during our field exploration are included on the boring logs in the [Exploration Results](#) section.

Project Description

Our initial understanding of the project was provided in our proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

| Item | Description |
|-----------------------------|---|
| Information Provided | An updated drawing of the site location and proposed development were received on May 15, 2023. |

| Item | Description |
|--|---|
| Project Description¹ | We understand that the proposed development includes a one-story pre-engineered metal building (PEMB) with an approximate footprint of 14,800 square feet, covered parking structures, pavement and driveways, and demolition of the existing building located on site. |
| Finished Floor Elevation | Within up to 2 feet above existing grade |
| Proposed Foundations | Shallow spread footings |
| Maximum Loads | <ul style="list-style-type: none"> ■ Columns: 50 kips ■ Slabs: 125 pounds per square foot (psf) |

1. Information provided by iAD Architects.

Terracon should be notified if any of the above information is inconsistent with the planned construction, especially the grading limits, as modifications to our recommendations may be necessary.

Site Conditions

The following description of site conditions is derived from our site visit in association with the field exploration.

| Item | Description |
|------------------------------|--|
| Parcel Information | The project site is located at 901 South Velasco Street in Angleton, Texas. See Site Location |
| Existing Improvements | At the time of our field exploration, one-story buildings, pavement and driveways, containers, and a transmission line were located within the general vicinity of the site. |
| Current Ground Cover | Asphaltic pavement near the existing building, grass and weeds outside the existing developments. |
| Existing Topography | Relatively level |

Geotechnical Characterization

Geology

Based on the geologic maps published by the Bureau of Economic Geology, the site for the proposed construction is located on the Beaumont formation, a deltaic nonmarine Pleistocene deposit. The Beaumont formation is heterogeneous containing thick interbedded layers of clay, fine sand, and silt.

The clay present in the formation has been reconsolidated by a process of desiccation. Numerous wetting and drying cycles have produced a network of randomly oriented and closely-spaced joints, which are sometimes slickensided, that is, have shiny appearance when exposed. The joint pattern strongly influences the engineering behavior of the soil.

The sand layers vary in compactness from loose to very dense, and in thickness from a fraction of an inch to many feet due to an irregular depositional environment. Sands are generally subrounded to subangular and vary from coarse to very fine, are poorly graded, and often contain significant amounts of silt-sized particles in the sand matrix.

The coastal plain in this region has a complex tectonic geology, several major features of which are: Gulf Coastal geosyncline, salt domes, and major sea level fluctuations during the glacial stages, subsidence and geologic faulting activities. Most of these geologic faulting activities have ceased for millions of years, but some are still active.

Subsurface Profile

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of the site. Conditions observed at each exploration point are indicated on the individual logs. The individual logs can be found in the [Exploration Results](#) and the GeoModel can be found in the [Figures](#) attachment of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

| Model Layer | Layer Name | General Description |
|-------------|------------|-----------------------|
| 1 | Asphalt | about 1 to 1.5 inches |
| 2 | Base | about 4 inches |

| Model Layer | Layer Name | General Description |
|-------------|---|--|
| 3 | Lean Clay and Sandy Lean Clay | dark tan, tan, and gray, medium stiff to very stiff with calcareous and ferrous nodules, and shell fragments |
| 4 | Fat Clay | dark gray and tan, very stiff, with calcareous nodules |
| 5 | Sandy Silt, Silty Sand, Clayey Sand, and Poorly Graded Sand with Silt | tan, very loose to dense, with shell fragments |

Groundwater Conditions

Borings B-1 and B-2 were advanced using dry drilling techniques to a depth of approximately 10 to 12 feet in an effort to evaluate groundwater conditions at the time of the field program. Wet rotary techniques were used thereafter to the termination depth of these borings (about 25 feet). Boring B-3 was advanced using dry drilling techniques to its termination depth (approximately 6 feet) in an effort to evaluate groundwater conditions at the time of the field program. Upon reaching groundwater, drilling was suspended for a period of about 15 minutes to allow the groundwater to rise and the groundwater levels to be recorded. The water levels observed in the boreholes can be found on the boring logs in [Exploration Results](#), and are summarized below.

| Summary of Groundwater Level Observations | | | | | |
|---|---------------------------------|--|--|-----------------|------------------|
| Boring No. | Approximate Boring Depth (feet) | Approximate Depth of Dry Drilling (feet) | Approximate Depth of Groundwater Below Existing Grade (feet) | | |
| | | | Initial/During Dry Drilling | After 5 Minutes | After 15 Minutes |
| B-1 | 25 | 10 | 7 | 6 | 5 |
| B-2 | 25 | 12 | 9 | 7 | 6½ |
| B-3 | 6 | 6 | No groundwater observed | | |

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than the levels indicated on the boring logs. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project and should be evaluated prior to construction.

Geotechnical Overview

Based on the information obtained from our subsurface exploration, the site can be developed for the proposed project. A summary of our findings and recommendations is provided below.

- Expansive soils were observed at this site. This report provides recommendations to help reduce the effects of soil shrinkage and expansion. However, even if these procedures are followed, some movement and distress in the grade supported foundations should be anticipated. The severity of distress will increase if any modification of the site results in excessive wetting or drying of the expansive soils. Eliminating the risk of movement associated with expansive soils may not be feasible. However, this risk can be significantly reduced if the foundations are designed as a structural beam or slab over a void space with the structural loads supported by a deep foundation system terminated below the active zone.
- We understand the proposed structure at this site is planned to be supported on a foundation system consisting of shallow spread/strip footings. This type of foundation may be utilized to support the proposed structure planned at this site provided the subgrade is prepared as discussed in this report.
- A minimum 12-inch-thick select fill pad should be placed under the proposed grade-supported slab to provide uniform support to the slab and reduce the estimated PVR to approximately one inch or less.
- Both flexible pavement systems (consisting of asphaltic concrete and base material) and rigid pavement systems may be considered for this project. The **Pavements** section addresses the design of pavement systems.

The recommendations contained in this report are based upon the results of field and laboratory testing (presented in the **Exploration Results**), engineering analyses, and our current understanding of the proposed project. The **General Comments** section provides an understanding of the report limitations.

Earthwork

Earthwork is anticipated to include clearing and grubbing, excavations, and select fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations, floor slabs, and pavements.

Site Preparation

Construction areas should be stripped of vegetation, topsoil, existing pavements (including crushed stone material) and other debris/unsuitable surface material. Proper site drainage should be maintained during construction so that ponding of surface runoff does not occur and cause construction delays and/or inhibit site access.

Demolition of existing structures and their below-grade portions, pavements/flatwork, utilities, etc. should be addressed as recommended in **Demolition Considerations**. Once final subgrade elevations have been achieved, the exposed subgrade should be carefully proofrolled with a 20-ton pneumatic roller or equivalent equipment, such as a fully loaded dump truck, to detect weak zones in the subgrade. Weak areas detected during proofrolling, as well as zones containing organic matter and/or debris, should be removed and replaced with soils exhibiting similar classification, moisture content, and density as the adjacent in-situ soils.

Subsequent to proofrolling, and just prior to placement of fill, the exposed subgrade within the construction area should be evaluated for moisture and density. If the moisture and/or density do not meet the criteria described in **Fill Compaction Requirements** for on-site soils, the subgrade should be scarified to a minimum depth of 6 inches, moisture adjusted, and compacted to at least 95 percent of the Standard Effort (ASTM D 698) maximum dry density.

Fill Material Types

Select fill and on-site soils to be used at this site for grade adjustments should meet the following criteria:

| Fill Type | USCS Classification | Acceptable location for Placement |
|-------------------|--|---|
| Select fill soils | CL and/or SC ($10 \leq PI \leq 20$) | Must be used to construct the select fill building pad under the floor slab and for all grade adjustments within the building area. |
| On-site soils | Varies | The on-site soils appear suitable for use as fill within the pavement areas, provided they are free of organics and debris. |

If blended or mixed soils are intended for use as select fill, Terracon should be contacted to provide additional recommendations. Blended or mixed soils do not occur naturally. These soils are a blend of sand and clay and will require mechanical mixing at the site with a pulvimixer. If these soils are not mixed thoroughly to break down the clay clods and blend-in the sand to produce a uniform soil matrix, the fill material may be detrimental

to the performance of the foundations. If blended soils are used, we recommend that additional samples of the blended soils as well as the clay clods, be obtained prior to and during earthwork operations to evaluate if the blended soils can be used in lieu of select fill. The actual type and amount of mechanical mixing at the site will depend on the amount of clay and sand, and properties of the clay.

Fill Compaction Requirements

| Item | Description |
|--------------------------------|---|
| Fill Lift Thickness | The fill soils should be placed on prepared surfaces in lifts not to exceed 8 inches loose measure. |
| Compaction Requirements | <ul style="list-style-type: none"> ■ Select fill and on-site soils should be compacted to at least 95 percent of the Standard Effort (ASTM D 698) maximum dry density. ■ The select fill soils should be moisture adjusted to within 2 percent of the optimum moisture content. ■ The on-site clay soils should be moisture conditioned to between optimum and +4 percent of the optimum moisture content. |

Prior to any filling operations, samples of the proposed borrow and on-site materials should be obtained for laboratory moisture-density testing. The tests will provide a basis for evaluation of fill compaction by in-place density testing. A qualified soil technician should perform sufficient in-place density tests during the filling operations to evaluate that proper levels of compaction, including dry unit weight and moisture content, are being attained.

Grading and Drainage

All grades must provide effective drainage away from the proposed building during and after construction. Water permitted to pond next to the building can result in distress in the building. These greater movements can result in unacceptable differential slab movements, cracked slabs and walls, and roof leaks. Slabs and foundation performances described in this report are based on effective drainage for the life of the building and cannot be relied upon if effective drainage is not maintained.

Exposed ground should be sloped away from the building for at least 10 feet beyond the perimeter of the building. After construction and landscaping, we recommend verifying final grades to document that effective drainage has been achieved. Grades around the building should also be periodically inspected and adjusted as necessary, as part of the buildings' maintenance program.

Discharge roof drains and downspouts onto pavements and/or flatworks which slope away from the building or extend down spouts a minimum of 10 feet away from the building.

Flatworks will be subject to post construction movement. Maximum grades practical should be used for flatwork to prevent water from ponding. Allowances in final grades should also consider post-construction movement of flatwork, particularly if such movement would be critical. Where flatwork abuts the structures, effectively seal and maintain joints to prevent surface water infiltration.

Utility trenches are a common source of water infiltration and migration. All utility trenches that penetrate beneath the structures should be effectively sealed to restrict water intrusion and flow through the trenches, which could migrate below the structure. The trench should provide an effective trench plug that extends at least 5 feet out from the face of the structure exterior. The plug material should consist of clay compacted at a water content at or above the soils optimum water content. The clay fill should be placed to completely surround the utility line and be compacted in accordance with recommendations in this report.

Wet Weather/Soft Subgrade Considerations

Construction operations may encounter difficulties due to wet or soft surface soils becoming a general hindrance to equipment, especially following periods of wet weather. If the subgrade cannot be adequately compacted to the minimum densities as described previously, one of the following measures will be required: 1) removal and replacement with select fill, 2) chemical treatment of the soil to dry and improve the condition of the subgrade, or 3) drying by natural means if the schedule allows. Based on our experience with similar soils in this area, chemical treatment is generally an efficient and effective method to increase the supporting value of wet and weak subgrade. Terracon should be contacted for additional recommendations if chemical treatment is needed due to soft and wet subgrade.

Demolition Considerations

We understand that the site is currently occupied by an existing building and associated asphaltic parking areas. Special care should be exercised to demolish and/or remove any existing foundations, pavements, utilities, and buried structures to help reduce the disturbance of the subgrade and potential detrimental effects on construction of the proposed development at this site.

We anticipate that the existing building is supported on shallow footings or grade beams and/or drilled-and-underreamed footings. Shallow footings and grade beams should be removed and the excavation backfilled with properly placed and compacted select fill. If drilled footings are observed, we recommend that the shaft should be broken off at an

elevation about 24 to 36 inches below the bottom of the proposed grade beam depth. The remainder of the drilled footing should be left in place. Remnants of the foundation elements to remain should be surveyed. The existing foundations should be superimposed on the proposed development plans to evaluate the potential for obstructions with the new construction. If drilled footings are planned to be excavated and completely removed, Terracon should be contacted for additional recommendations. Complete removal of drilled footings will require significant earthwork activities to backfill the resulting excavations in such a manner as to make the site suitable for new construction.

All utilities and associated bedding material that are planned to be abandoned should be completely removed from within the proposed building areas. As an alternate to complete removal, the existing utilities may be abandoned in-place if they do not interfere with the planned development. If the utilities are abandoned in-place, they should be properly pressure grouted to completely fill the utility.

The excavations resulting from the utilities or other buried structures should be backfilled in accordance with the recommendations provided in the **Fill Compaction Requirements** section. If situations are encountered where compaction of fill would not be efficient because of the size or location of an excavation, the use of cement stabilized sand or flowable fill may be considered as a suitable alternative to select fill. The compressive strength of the cement stabilized sand or flowable fill utilized should be between 50 and 100 pounds per square inch (psi).

Shallow Foundations

If the site has been prepared in accordance with the requirements noted in **Earthwork**, the following design parameters are applicable for shallow foundations.

Design Recommendations – Shallow Spread/Strip Footings

| Item | Description |
|---|---|
| Minimum Embedment Depth ¹ | 3 feet below final grade |
| Allowable bearing pressures (individual footings) ² | Net dead plus sustained live load – 1,700 psf Net total load – 2,500 psf |
| Allowable bearing pressure (strip footing) ³ | Net total load – 1,700 psf |
| Approximate post-construction settlement ⁴ | Approximately one inch |

| Item | Description |
|--|---|
| Estimated post-construction differential settlement⁵ | Approximately ½ of post-construction settlement |
| Allowable passive pressure⁶ | 750 psf |
| Allowable frictional resistance⁷ | 250 psf |
| Uplift resistance⁸ | Foundation Weight (150 pcf) & Soil Weight (120 pcf) |

1. The footings should bear upon the compacted select fill or undisturbed native clay soils.
2. Whichever condition yields a larger bearing area.
3. Defined as a footing at least twice as long as it is wide.
4. This estimated post-construction settlement of the shallow footings is based on proper construction practices being followed. A clear distance between footings of one footing size of the larger of the two footings should not produce overlapping stress distributions and would essentially behave as independent foundations.
5. The post-construction differential settlements may result from variances in subsurface conditions, loading conditions, and construction procedures. The settlement response of the footings will be more dependent upon the quality of construction than upon the response of the subgrade to the foundation loads.
6. The passive pressure along the exterior face of the footings should be neglected within the upper 4 feet due to surface effects and the presence of fill and expansive soils unless pavement is provided up to the edge of the structures. For interior footings, the allowable passive pressure may be used for the entire depth of the footing.
7. To be utilized on the base of the footings.
8. Structural uplift loads on the shallow footings may be resisted by the weight of the foundation plus the weight of any soil directly above the foundation. The ultimate uplift capacity of shallow footings should be reduced by an appropriate factor of safety to compute allowable uplift capacity.

Construction Considerations – Shallow Foundations

Excavations for the shallow foundations should be performed with equipment capable of providing a relatively clean bearing area. The bottom 6 inches of the excavations should be performed using a smooth-mouthed excavation bucket or by hand labor. The excavations should be neatly excavated and properly formed. Disturbance of the bearing area of the foundations should be minimized during the excavation operations. Soft zones observed during construction should be over-excavated to a firm and undisturbed soil layer and all loose materials in the excavation bottom should be removed before placement of concrete. Water should not be allowed to accumulate at the bottom of the foundation excavations. To reduce the potential for groundwater seepage into the excavations and to minimize disturbance to the bearing area, we recommend that steel and concrete be placed as soon as possible after the excavations are completed and properly cleaned. Excavations should not be left open for more than 24 hours. The bearing surface of the foundations should be evaluated immediately prior to placing concrete.

A thin seal slab (approximately 2 to 4 inches thick) should be placed at the bottom of the footing excavation to protect the bearing surface of the footing from disturbance if the footing cannot be poured within 24 hours following excavation.

Foundation Construction Monitoring

The performance of the foundation systems will be highly dependent upon the quality of construction. Thus, we recommend that subgrade preparation, fill compaction, and foundation installation be observed full time by an experienced Terracon soil technician under the direction of our geotechnical engineer. During foundation construction, the base of the footing excavations should be observed to evaluate the condition of the subgrade. We would be pleased to develop a plan for compaction and foundation installation observation to be incorporated in the overall quality control program.

Floor Slabs

Planned finished grades for the proposed building were not available at the time of this report. We anticipate that the finished floor elevation of the proposed building is planned to be within about 2 feet above existing grade. If the grading is planned to be altered from what has been previously described, Terracon should be notified to review and/or modify our recommendations given in this subsection.

The near-surface soils observed at this site generally exhibit a moderate to high expansion potential. These soils can subject the interior floor slab of the building to significant movements (due to shrinking and swelling) with fluctuations in their moisture content. This movement potential is influenced primarily by the properties of the subgrade soils, as well as the moisture content of the subgrade at the time of construction, overburden pressures, and the stability of the moisture contents throughout the life of the building. Based on the information developed from our field and laboratory programs and on method TEX-124-E in the Texas Department of Transportation (TxDOT) Manual of Testing Procedures, we estimate that the subgrade soils at this site exhibit a Potential Vertical Rise (PVR) of up to approximately 1¼ inches. Therefore, we recommend that the near-surface soils be prepared as stated below to reduce the potential for slab movement associated with volumetric changes of the near-surface clay soils due to moisture variations to a more acceptable level. The actual movements could be greater if poor drainage, ponded water, and/or other sources of moisture are allowed to infiltrate beneath the structure after construction.

The most common method of subgrade preparation to reduce potential expansion of the subgrade would be to provide a pad of properly placed and compacted select fill beneath the grade-supported floor slabs. The corresponding decrease in the potential soil movements is primarily a function of the fill pad thickness and the moisture levels of the

underlying clay subgrade. While the indicated preparations do not eliminate the potential for soil movement, the magnitude of such movements should be reduced to more acceptable levels. To provide uniform support to the floor slab and to reduce the estimated PVR to approximately one inch or less, we recommend that a minimum 12 inches of properly placed and compacted select fill material be constructed immediately beneath the floor slab. The select fill pad should extend a minimum of 3 feet beyond the edge of the building area. The final exterior grade adjacent to the structure should be sloped to promote effective drainage away from the structure.

Select fill should be utilized for all grade adjustments within the proposed building area. The subgrade and select fill soils should be prepared as outlined in the **Earthwork** section of this report, which contains material and placement requirements for select fill, as well as other subgrade preparation recommendations.

The subgrade soils for flatwork outside of the structure which will be sensitive to movement should be prepared as discussed previously. This preparation will be important on surrounding sidewalks and paving immediately adjacent to the structure. If these adjacent flatwork areas are not prepared as stated above for the building area, the estimated PVR for these areas could approach those indicated previously for in-situ conditions. If the soils swell in these areas, this movement could result in significant distress to the adjacent sidewalks and paving and possibly result in reversed drainage (flow of runoff toward the structure) around the perimeter of the structure.

Pavements

Once the subgrade is properly prepared, both flexible pavement systems (consisting of asphaltic concrete and base material) and rigid pavement systems may be considered for this project. Detailed traffic loads and frequencies were not available. However, we understand that traffic will primarily consist of passenger vehicles and fire trucks in the parking areas and passenger vehicles combined with fire trucks, garbage trucks, and large multi-axle trucks from time-to-time in driveway areas.

Tabulated in the following table are the assumed traffic frequencies and loads used to design pavement sections for this project. When actual traffic conditions have been determined Terracon should be contacted to review the information to consider a need for revision of the pavement designs and related recommendations.

| Pavement Area | Traffic Design Index ¹ | Description |
|---------------------------------|-----------------------------------|--|
| Automobile Parking Areas | DI-1 | Light traffic (Few vehicles heavier than passenger cars, no regular use by heavily loaded two axle trucks.) (EAL ² < 6) |

| Pavement Area | Traffic Design Index ¹ | Description |
|--|-----------------------------------|--|
| Driveways (Light Duty) | DI-2 | Medium to light traffic (Similar to DI-1 including not over 50 loaded two axle trucks or lightly loaded larger vehicles per day. No regular use by heavily loaded trucks with three or more axles.) (EAL = 6-20) |
| Driveways and Truck Traffic Areas (Medium Duty) | DI-3 | Medium traffic (Including not over 300 heavily loaded two axle trucks plus lightly loaded trucks with three or more axles and no more than 30 heavily loaded trucks with more than three axles per day.) (EAL = 21-75) |

1. Based on NSSGA traffic design indices.
2. Equivalent daily 18-kip single-axle load applications.

The top 6 inches of the finished subgrade soils directly beneath the pavements should be chemically treated with lime or a mixture of lime and flyash. Chemical treatment will increase the supporting value of the subgrade and decrease the effect of moisture on subgrade soils. This 6 inches of treatment is a required part of the pavement design and is not a part of the site and subgrade preparation for wet/soft subgrade conditions.

Listed below are pavement component thicknesses, which may be used as a guide for pavement systems at the site for the traffic classifications stated herein. These systems were derived based on general characterization of the subgrade. Specific testing (such as CBR's, resilient modulus tests, etc.) was not performed for this project to evaluate the support characteristics of the subgrade.

| Flexible Pavement Section | | |
|---------------------------|----------------------------|------|
| Component | Material Thickness, Inches | |
| | DI-1 | DI-2 |
| Asphaltic concrete | 2.0 | 2.5 |
| Base material | 8.0 | 10.0 |
| Treated subgrade | 6.0 | 6.0 |

| Rigid Pavement Section | | | |
|----------------------------|----------------------------|------|------|
| Component | Material Thickness, Inches | | |
| | DI-1 | DI-2 | DI-3 |
| Reinforced concrete | 5.0 | 6.0 | 7.0 |
| Treated subgrade | 6.0 | 6.0 | 6.0 |

Waste dumpster areas should be constructed of at least 7 inches of reinforced concrete pavement. The concrete pad areas should be designed so that the vehicle wheels of the collection truck are supported on the concrete while the dumpster is being lifted to support the large wheel loading imposed during waste collection.

Presented below are our recommended material requirements for the various pavement sections.

Reinforced Concrete Pavement – The materials and properties of reinforced concrete pavement should meet applicable requirements in the ACI Manual of Concrete Practice. The portland cement concrete mix should have a minimum 28-day compressive strength of 3,500 psi.

If river gravel is planned to be utilized in the portland cement concrete mix, Terracon should be contacted for additional services. The presence of river gravel in the portland cement concrete mix can result in excessive cracking and distress to the concrete pavement as a result of differing thermal expansion properties between the river gravel and cement paste. Special care should be taken in developing the project's portland cement concrete mix design, joint layout, and placement to help reduce the potential for excessive cracking and distress if river gravel is planned to be utilized for the project.

Reinforcing Steel – ACI recommendations indicate that distributed steel reinforcement is not necessary when the pavement is properly jointed to form short panel lengths that will help reduce intermediate cracking. Provided the concrete pavement is designed and constructed as stated herein, the installation of reinforcing steel is optional and should be evaluated by the design team. Proper layout and installation of the joints within the pavement is critical to help control intermediate cracking.

If reinforcing steel is planned to be utilized in the concrete pavement by the design team, the following amount of reinforcing steel should be used as a guideline:

DI-1: #3 bars spaced at 18 inches or #4 bars spaced at 24 inches on centers in both directions.

DI-2: #3 bars spaced at 12 inches or #4 bars spaced at 18 inches on centers in both directions.

DI-3: #4 bars spaced at 18 inches on centers in both directions.

Control Joint Spacing – ACI recommendations indicate that control joints should be spaced at a maximum spacing of 30 times the thickness of the pavement for unreinforced parking lot pavements. Furthermore, ACI recommends a maximum control joint spacing of 12.5 feet for 5-inch pavements and a maximum control joint spacing of 15 feet for 6-inch or thicker pavements. Sawcut control joints should be cut within 4 to 12 hours of concrete placement to help control the formation of plastic shrinkage cracks as the concrete cures. The depth of the joint should be at least one-quarter of the slab depth when using a conventional saw or one inch when using early entry saws. The width of the cut should be in accordance with the joint sealant manufacturer recommendations.

Expansion Joint Spacing – ACI recommendations indicate that regularly spaced expansion joints may be deleted from concrete pavements. Therefore, the installation of expansion joints is optional and should be evaluated by the design team.

Construction Joints – When concrete is planned to be placed at different times, we recommend the use of a construction joint between paving areas. The construction joint should consist of a butt joint (not a keyway joint).

Concrete Curing Compound – A concrete curing compound, such as a Type 2 membrane curing compound conforming to TxDOT DMS-4650, “Hydraulic Cement Concrete Curing Materials and Evaporation Retardants” or equivalent, should be applied to the concrete surface immediately after placement of the concrete in accordance with TxDOT 2014 Standard Specifications Item 360.

Dowels at Expansion/Construction Joints – The dowels at expansion/construction joints should be spaced at 12-inch centers and consist of the following:

DI-1: 5/8-inch diameter, 12-inches long with 5-inch embedment.

DI-2: 3/4-inch diameter, 14-inches long with 6-inch embedment.

DI-3: 7/8-inch diameter, 14-inches long with 6-inch embedment.

Hot Mix Asphaltic Concrete Surface Course – The asphaltic concrete surface course should be plant mixed, hot laid Type D (Fine Graded Surface Course) meeting the requirements in TxDOT 2014 Standard Specifications Item 340. Specific criteria for the job specifications should include compaction to within an air void range of 3.8 to 8.5 percent calculated using the maximum theoretical specific gravity of the mix measured by TxDOT Tex-227-F. The asphalt cement content by percent of total mixture weight should be within ± 0.5 percent asphalt cement from the job mix design.

Base Material – Base material should be composed of crushed limestone or crushed concrete meeting the requirements of TxDOT 2014 Standard Specifications Item 247, Type A or D, Grade 1-2. The base material should be compacted to at least 95 percent of the Modified Effort (ASTM D1557) maximum dry density at moisture content within 2 percent of the optimum moisture content.

Chemical Treatment

Lime Treated Subgrade – We anticipate that the pavement subgrade will generally consist of on-site medium to high plasticity clay soils. The pavement subgrade should be treated with lime in accordance with the TxDOT 2014 Standard Specifications Item 260. The amount of lime should be determined for subgrade soils by conducting laboratory tests just prior to construction. Based on the classification test results, we anticipate that about 6 to 7 percent lime by dry weight may be used for estimating and planning. The percentages are given as application by dry weight and are typically equivalent to about 30 to 35 pounds of lime per square yard per 6-inch depth. The pulverization, mixing and curing of the lime treated subgrade is of particular importance in these clays. The subgrade should be compacted to a minimum of 95 percent of the Standard Effort (ASTM D 698) maximum dry density at a moisture content between optimum and 4 percent wet of the optimum moisture content.

Lime-Flyash Treated Subgrade –The on-site silty sand and clayey sand soils should be treated with lime-flyash in accordance with TXDOT 2014 Standard Specifications for Construction of Highways, Streets, and Bridges Item 265. Based on the classification test results, we recommend that about 2 to 3 percent lime and 7 to 8 percent flyash by dry weight of soil be used for estimating and planning. The percentages are given as application by dry weight and are typically equivalent to about 10 to 15 pounds of lime and 35 to 40 pounds of flyash per square yard per 6-inch depth. Lime-flyash is also available pre-mixed, typically in percentages of 20 to 30 percent lime and 70 to 80 percent flyash. These pre-mixed products may be used if preferred at a rate of 50 pounds per square yard per 6-inch depth. The subgrade soils should be compacted to a minimum of 95 percent of the material's Standard Effort (ASTM D 698) maximum dry density at a moisture content within 2 percent of the optimum moisture content.

Preferably, traffic should be kept off the treated subgrade for 7 days to facilitate curing of the soil-chemical mixture. In addition, the subgrade is not suitable for heavy construction traffic prior to paving.

The pavement design methods described above are intended to provide structural sections with adequate thickness over a particular subgrade such that wheel loads are reduced to a level the subgrade can support. The support characteristics of the subgrade for pavement design do not account for shrink/swell movements of an expansive clay subgrade such as the soils observed at this site. Thus, the pavement may be adequate from a structural standpoint, yet still experience cracking and deformation due to shrink/swell related movement of the subgrade. Post-construction subgrade movements and some cracking of pavements are not uncommon for clay subgrade conditions such as those observed at this site. Reducing moisture changes in the subgrade is important to reduce shrink/swell movements. Although chemical treatment will help to reduce such movement/cracking, this movement/cracking cannot be feasibly eliminated.

Related civil design factors such as subgrade drainage, shoulder support, cross-sectional configurations, surface elevations and environmental factors which will significantly affect the service life must be included in the preparation of the construction drawings and specifications. Normal periodic maintenance will be required.

Long-term pavement performance will be dependent upon several factors, including maintaining subgrade moisture levels and providing for preventative maintenance. The following recommendations should be implemented to help promote long-term pavement performance:

- The subgrade and the pavement surface should be designed to promote proper surface drainage, preferably at a minimum grade of 2 percent;
- Install joint sealant and seal cracks immediately;
- Extend curbs into the treated subgrade for a depth of at least 4 inches to help reduce moisture migration into the subgrade soils beneath the pavement section; and

- Place compacted, low permeability clayey backfill against the exterior side of the curb and gutter.

Preventative maintenance should be planned and provided for the pavements at this site. Preventative maintenance activities are intended to slow the rate of pavement deterioration, and consist of both localized maintenance (e.g. crack and joint sealing and patching) and global maintenance (e.g. surface sealing). Prior to implementing any maintenance, additional engineering observations are recommended to determine the type and extent of preventative maintenance.

General Comments

Our work is conducted with the understanding of the project as described in the cost estimate document and will incorporate collaboration with the design team as we complete our services to verify assumptions. Revision of our understanding to reflect actual conditions important to our work will be based on these verifications and will be reflected in the final report. The design team should collaborate with Terracon to confirm these assumptions and to prepare the final design plans and specifications. This facilitates the incorporation of our opinions related to implementation of our geotechnical recommendations. Any information conveyed prior to the final report is for informational purposes only and should not be considered or used for decision-making purposes.

Our analysis and opinions are based upon our understanding of the geotechnical conditions in the area, the data obtained from our site exploration and from our understanding of the project. Variations will occur between exploration point locations, across the site, or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in the final report, to provide observation and testing services during grading, excavation, foundation construction and other earth-related construction phases of the project. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other services should be undertaken.

Our services and any correspondence are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third party

Geotechnical Engineering Report

Angleton King Municipal Operations Center | Angleton, Texas

June 23, 2023 | Terracon Project No. AS225036



beneficiaries intended. Any third party access to services or correspondence is solely for information purposes only. Reliance upon the services and any work product is limited to our client, and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly impact excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing.

Geotechnical Engineering Report

Angleton King Municipal Operations Center | Angleton, Texas
June 23, 2023 | Terracon Project No. AS225036




Figures

Contents:

GeoModel

GeoModel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

| Model Layer | Layer Name | General Description |
|-------------|---|--|
| 1 | Asphalt | about 1 to 1.5 inches |
| 2 | Base | about 4 inches |
| 3 | Lean Clay and Sandy Lean Clay | dark tan, tan, and gray, medium stiff to very stiff with calcareous and ferrous nodules, and shell fragments |
| 4 | Fat Clay | dark gray and tan, very stiff, with calcareous nodules |
| 5 | Sandy Silt, Silty Sand, Clayey Sand, and Poorly Graded Sand with Silt | tan, very loose to dense, with shell fragments |

LEGEND

- | | | |
|--------------------|-----------------|------------------------------|
| Asphalt | Sandy Lean Clay | Poorly-graded Sand with Silt |
| Base | Sandy Silt | Lean Clay with Sand |
| Fat Clay with Sand | Silty Sand | Clayey Sand |

- First Water Observation
- Second Water Observation
- Third Water Observation

The groundwater levels shown are representative of the date and time of our exploration. Significant changes are possible over time. Water levels shown are as measured during and/or after drilling. In some cases, boring advancement methods mask the presence/absence of groundwater. See individual logs for details.

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

Geotechnical Engineering Report

Angleton King Municipal Operations Center | Angleton, Texas

June 23, 2023 | Terracon Project No. AS225036



Attachments

Exploration and Testing Procedures

Field Exploration

| Number of Borings | Approximate Boring Depth (feet) | Location |
|-------------------|---------------------------------|-------------------------|
| 2 (B-1 and B-2) | 25 | Building areas |
| 1 (B-3) | 6 | Pavement/driveway areas |
| Total: | 56 | |

Boring Layout and Elevations: We used handheld Global Positioning System (GPS) equipment to locate the approximate latitude and longitude of the borings with an accuracy of +/-25 feet. The boring depths were measured from the existing ground surface at the time of our field activities.

Subsurface Exploration Procedures: We advanced soil borings with an all-terrain vehicle (ATV) mounted drilling equipment using dry auger and wet rotary drilling techniques. Samples were obtained at intervals of 2 feet in the upper 12 feet of each boring and at intervals of 5 feet thereafter.

Cohesive soil samples were generally recovered using open-tube samplers. Hand penetrometer tests were performed on samples of cohesive soils in the field to serve as a general measure of consistency.

Granular soils and soils for which good quality open-tube samples could not be recovered were sampled by means of the Standard Penetration Test (SPT). This test consists of measuring the number of blows (N) required for a 140-pound hammer free falling 30 inches to drive a standard split-spoon sampler 12 inches into the subsurface material after being seated six inches. This blow count or SPT "N" value is used to evaluate the stratum.

The samples were placed in appropriate containers, taken to our soil laboratory for testing, and classified by a geotechnical engineer. In addition, we observed and record groundwater levels during drilling and sampling.

Our exploration team prepared field boring logs as part of standard drilling operations including sampling depths, penetration distances, and other relevant sampling information. Field logs include visual classifications of materials observed during drilling, and our interpretation of subsurface conditions between samples. Final boring logs, prepared from field logs, represent an interpretation of the field logs by a geotechnical engineer and include modifications based on laboratory observation and tests on select samples.

Property Disturbance: We backfilled our borings with auger cuttings and patched them at the surface with asphaltic concrete cement after completion. Our services do not include repair of the site beyond backfilling our borings. Excess auger cuttings were dispersed in the general vicinity of the boring. Because backfill material often settles below the surface after a period, we recommend borings be checked periodically and backfilled, if necessary

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests. The laboratory testing program included the following types of tests:

- Moisture Content
- Dry Unit Weight
- Atterberg Limits
- Percent finer than No. 200 sieve
- Unconfined Compression

The laboratory testing program included examination of soil samples by an engineer. Based on the results of our field and laboratory programs, we described and classified the soil samples in accordance with the Unified Soil Classification System.

Samples not tested in the laboratory will be stored for a period of 30 days subsequent to submittal of this report and will be discarded after this period, unless we are notified otherwise

Geotechnical Engineering Report

Angleton King Municipal Operations Center | Angleton, Texas

June 23, 2023 | Terracon Project No. AS225036




Site Location and Exploration Plans

Contents:

Site Location Plan

Exploration Plan

Site Location



Geotechnical Engineering Report

Angleton King Municipal Operations Center | Angleton, Texas

June 23, 2023 | Terracon Project No. AS225036



Exploration Plan



Exploration and Laboratory Results

Contents:

Boring Logs (B-1 through B-3)

Boring Log No. B-1

| Model Layer | Graphic Log | Location: See Exploration Plan Latitude: 29.1560° Longitude: -95.4307° Depth (Ft.) | Depth (Ft.) | Water Level Observations | Sample Type | Field Test Results | Strength Test | | | Water Content (%) | Dry Unit Weight (pcf) | Atterberg Limits LL-PL-PI | Percent Fines |
|-------------------------------------|-------------|--|-------------|--------------------------|-------------|--------------------|---------------|----------------------------|------------|-------------------|-----------------------|------------------------------|---------------|
| | | | | | | | Test Type | Compressive Strength (tsf) | Strain (%) | | | | |
| 1 | | 0.2 | 0.2 | | | | | | | | | | |
| 2 | | 0.4 | 0.4 | | | | | | | | | | |
| 4 | | | | | | 2.5 (HP) | | | | | | | |
| 3 | | | | | | 2.5 (HP) | | | 15.5 | | 36-13-23 | | |
| | | | 5 | ▼ | | 1.5 (HP) | UC | 0.96 | 5.7 | 21.1 | 117 | | |
| | | | 6.0 | ▼ | | | | | | | | | |
| | | | 8.0 | ▼ | | 0.25 (HP) | | | | 25.4 | | 21-19-2 51 | |
| | | | 10 | | | 2-1-3 N=4 | | | | | | | |
| | | | | | | 4-6-8 N=14 | | | 23.5 | | | 14 | |
| | | | 15 | | | 7-10-10 N=20 | | | | | | | |
| | | | 20 | | | 9-12-15 N=27 | | | 24.1 | | | 7 | |
| | | | 25 | | | 9-16-13 N=29 | | | | | | | |
| Boring Terminated at 25 Feet | | | 25 | | | | | | | | | | |

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (If any).
 See [Supporting Information](#) for explanation of symbols and abbreviations.

Notes

Water Level Observations

- ▼ While drilling
- ▼ After 5 minutes
- ▼ After 15 minutes

Drill Rig
ATV

Hammer Type
Rope and Cathead

Driller
East Texas Drilling

Logged by
JC

Boring Started

Boring Completed

Advancement Method

Dry augered to 10 feet, wet rotary thereafter.

Abandonment Method

Boring backfilled with auger cuttings.
 Surface capped with asphalt.

Boring Log No. B-2

| Model Layer | Graphic Log | Location: See Exploration Plan Latitude: 29.1561° Longitude: -95.4303° Depth (Ft.) | Depth (Ft.) | Water Level Observations | Sample Type | Field Test Results | Strength Test | | | Water Content (%) | Dry Unit Weight (pcf) | Atterberg Limits LL-PL-PI | Percent Fines |
|-------------|-------------|---|-------------|--------------------------|-------------|--------------------|---------------|----------------------------|------------|-------------------|-----------------------|------------------------------|---------------|
| | | | | | | | Test Type | Compressive Strength (tsf) | Strain (%) | | | | |
| 1 | | 0.2 | 0.2 | | | | | | | | | | |
| 2 | | 0.4 | 0.4 | | | | | | | | | | |
| 3 | | ASPHALT , about 1 inch BASE , about 4 inches LEAN CLAY WITH SAND (CL) , dark tan, stiff to very stiff, with calcareous nodules - with shell fragments 0.4 to 2 feet - tan and gray 2 to 6 feet - with ferrous nodules 4 to 6 feet | | | | 4.5 (HP) | | | 10.8 | | 24-16-8 | | |
| | | 6.0 | 6.0 | | | | | | | | | | |
| | | CLAYEY SAND (SC) , tan, very loose | | | | | | | | | | | |
| | | SILTY SAND (SM) , tan, loose to medium dense | | | | | | | | | | | |
| | | 8.0 | 8.0 | ▽ | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | 10 | | | 5-6-7 N=13 | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | 5-4-4 N=8 | | | 27.8 | | | 43 | |
| | | | | | | | | | | | | | |
| | | | 15 | | | 6-15-18 N=33 | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | 12-18-24 N=42 | | | 23.1 | | | 9 | |
| | | | | | | | | | | | | | |
| | | | 20 | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | 8-15-18 N=33 | | | | | | | |
| | | | | | | | | | | | | | |
| | | | 25 | | | | | | | | | | |
| | | Boring Terminated at 25 Feet | | | | | | | | | | | |

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (If any).
 See [Supporting Information](#) for explanation of symbols and abbreviations.

Notes

Water Level Observations

- ▽ While drilling
- ▽ After 5 minutes
- ▽ After 15 minutes

Drill Rig
ATV

Hammer Type
Rope and Cathead

Driller
East Texas Drilling

Logged by
JC

Boring Started

Boring Completed

Advancement Method

Dry augered to 12 feet, wet rotary thereafter.

Abandonment Method

Boring backfilled with auger cuttings.
 Surface capped with asphalt.

Boring Log No. B-3

| Model Layer | Graphic Log | Location: See Exploration Plan Latitude: 29.1563° Longitude: -95.4308° | Depth (Ft.) | Water Level Observations | Sample Type | Field Test Results | Strength Test | | | Water Content (%) | Dry Unit Weight (pcf) | Atterberg Limits LL-PL-PI | Percent Fines |
|-------------|-------------|---|-------------|--------------------------|-------------|--------------------|---------------|----------------------------|------------|-------------------|-----------------------|------------------------------|---------------|
| | | | | | | | Test Type | Compressive Strength (tsf) | Strain (%) | | | | |
| 1 | | 0.2 | | | | | | | | | | | |
| 2 | | 0.4 | | | | | | | | | | | |
| 3 | | ASPHALT , about 1.5 inches BASE , about 4 inches LEAN CLAY WITH SAND (CL) , tan and gray, medium stiff to stiff - with calcareous nodules 2 to 4 feet | | | | 1.25 (HP) | | | 23.7 | | 49-14-35 | | |
| | | | | | | 1.0 (HP) | | | | | | | |
| | | | | | | | 1.25 (HP) | | | | | | |
| | | 4.0 | | | | | | | | | | | |
| | | 6.0 | | | | | | | | | | | |
| | | Boring Terminated at 6 Feet | | | | | | | | | | | |

| | |
|---|---|
| <p>See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations.</p> <p>Notes</p> | <p>Water Level Observations No groundwater Observed</p> <p>Drill Rig ATV</p> <p>Driller East Texas Drilling</p> <p>Logged by JC</p> <p>Boring Started</p> <p>Boring Completed</p> |
| <p>Advancement Method Dry augered to termination depth.</p> <p>Abandonment Method Boring backfilled with auger cuttings. Surface capped with asphalt.</p> | |








Supporting Information

Contents:

General Notes

Unified Soil Classification System

General Notes

| Sampling | Water Level | Field Tests |
|---|---|---|
|  Auger Cuttings  Shelby Tube  Standard Penetration Test |  Water Initially Encountered  Water Level After a Specified Period of Time  Water Level After a Specified Period of Time  Cave In Encountered Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated. Groundwater level variations will occur over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level observations. | N Standard Penetration Test Resistance (Blows/Ft.) (HP) Hand Penetrometer (T) Torvane (DCP) Dynamic Cone Penetrometer UC Unconfined Compressive Strength (PID) Photo-Ionization Detector (OVA) Organic Vapor Analyzer |

Descriptive Soil Classification

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

Location And Elevation Notes

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See Exploration and Testing Procedures in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

Strength Terms

| Relative Density of Coarse-Grained Soils (More than 50% retained on No. 200 sieve.) Density determined by Standard Penetration Resistance | | Consistency of Fine-Grained Soils (50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance | | |
|---|---|---|--|---|
| Relative Density | Standard Penetration or N-Value (Blows/Ft.) | Consistency | Unconfined Compressive Strength Qu (tsf) | Standard Penetration or N-Value (Blows/Ft.) |
| Very Loose | 0 - 3 | Very Soft | less than 0.25 | 0 - 1 |
| Loose | 4 - 9 | Soft | 0.25 to 0.50 | 2 - 4 |
| Medium Dense | 10 - 29 | Medium Stiff | 0.50 to 1.00 | 4 - 8 |
| Dense | 30 - 50 | Stiff | 1.00 to 2.00 | 8 - 15 |
| Very Dense | > 50 | Very Stiff | 2.00 to 4.00 | 15 - 30 |
| | | Hard | > 4.00 | > 30 |

Relevance of Exploration and Laboratory Test Results

Exploration/field results and/or laboratory test data contained within this document are intended for application to the project as described in this document. Use of such exploration/field results and/or laboratory test data should not be used independently of this document.

Unified Soil Classification System

| Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests ^A | | | | Soil Classification | |
|--|---|--|---|---|--|
| | | | | Group Symbol | Group Name ^B |
| Coarse-Grained Soils: More than 50% retained on No. 200 sieve | Gravels: More than 50% of coarse fraction retained on No. 4 sieve | Clean Gravels: Less than 5% fines ^C | Cu ≥ 4 and 1 ≤ Cc ≤ 3 ^E | GW | Well-graded gravel ^F |
| | | Gravels with Fines: More than 12% fines ^C | Cu < 4 and/or [Cc < 1 or Cc > 3.0] ^E | GP | Poorly graded gravel ^F |
| | | | Fines classify as ML or MH | GM | Silty gravel ^{F, G, H} |
| | Sands: 50% or more of coarse fraction passes No. 4 sieve | Clean Sands: Less than 5% fines ^D | Fines classify as CL or CH | GC | Clayey gravel ^{F, G, H} |
| | | | Cu ≥ 6 and 1 ≤ Cc ≤ 3 ^E | SW | Well-graded sand ^I |
| | | Sands with Fines: More than 12% fines ^D | Cu < 6 and/or [Cc < 1 or Cc > 3.0] ^E | SP | Poorly graded sand ^I |
| Fine-Grained Soils: 50% or more passes the No. 200 sieve | Silts and Clays: Liquid limit less than 50 | Inorganic: | PI > 7 and plots above "A" line ^J | CL | Lean clay ^{K, L, M} |
| | | | PI < 4 or plots below "A" line ^J | ML | Silt ^{K, L, M} |
| | | Organic: | $\frac{LL \text{ oven dried}}{LL \text{ not dried}} < 0.75$ | OL | Organic clay ^{K, L, M, N} Organic silt ^{K, L, M, O} |
| | | | Inorganic: | PI plots on or above "A" line | CH |
| | PI plots below "A" line | MH | | Elastic silt ^{K, L, M} | |
| | Silts and Clays: Liquid limit 50 or more | Organic: | $\frac{LL \text{ oven dried}}{LL \text{ not dried}} < 0.75$ | OH | Organic clay ^{K, L, M, P} Organic silt ^{K, L, M, Q} |
| | | | Highly organic soils: | Primarily organic matter, dark in color, and organic odor | PT |

^A Based on the material passing the 3-inch (75-mm) sieve.

^B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

^C Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.

^D Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

^E $Cu = D_{60}/D_{10}$ $Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$

^F If soil contains ≥ 15% sand, add "with sand" to group name.

^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

^H If fines are organic, add "with organic fines" to group name.

^I If soil contains ≥ 15% gravel, add "with gravel" to group name.

^J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.

^K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.

^L If soil contains ≥ 30% plus No. 200 predominantly sand, add "sandy" to group name.

^M If soil contains ≥ 30% plus No. 200, predominantly gravel, add "gravelly" to group name.

^N PI ≥ 4 and plots on or above "A" line.

^O PI < 4 or plots below "A" line.

^P PI plots on or above "A" line.

^Q PI plots below "A" line.

