



CHANGE ORDER City Of Angels

Sheet 1 of 2

Change requested by: ☒ Engineer ☐ Contractor

CHANGE ORDER NO.	CONTRACT NUMBER	PROJECT	FEDERAL NUMBER(S)
003		Water Meter Replacement Project Phase 1 and Phase 2	

TO

Moyle Excavation, Inc., Contractor

You are directed to make the following changes from the plans and specifications or do the following described work not included in the plans and specifications for this contract. **NOTE: This change order is not effective until approved by the engineer.**

Description of work to be done, estimate of quantities, and prices to be paid.

Adjustments to Bid Items through April 30, 2026

Item Description	Unit	Unit Cost	Original Contract		Completed thru 4/30/2026		Net Change
			Qty	Amount	Qty	Amount	
Phase 1, Level 1 Water Meter Replacement	EA	\$300.50	553	\$166,176.50	59	\$17,729.50	(\$148,447.00)
Phase 1, Level 2 Water Meter Replacement	EA	\$300.50	380	\$114,190.00	508	\$152,654.00	\$38,464.00
Phase 1, Level 3 Water Meter Replacement	EA	\$567.50	75	\$42,562.50	9	\$5,107.50	(\$37,455.00)
Phase 2, Level 1 Water Meter Replacement	EA	\$300.50	223	\$67,011.50	196	\$58,898.00	(\$8,113.50)
Phase 2, Level 2 Water Meter Replacement	EA	\$300.50	104	\$31,252.00	780	\$234,390.00	\$203,138.00
Phase 2, Level 3 Water Meter Replacement	EA	\$567.50	487	\$276,372.50	36	\$20,430.00	(\$255,942.50)
Subtotal Adjustments this Change Order				\$697,565.00		\$489,209.00	(\$208,356.00)

Water Service Lateral Replacements – Phase 1

Work includes locating and abandoning in place the existing service laterals, reusing existing corporation stops, and installing new 1-inch polyethylene water service laterals into the meter box. New material shall be bedded with sand and backfilled the full depth with aggregate base and asphalt placed at 3-inch depth where applicable. Where appropriate, tunnel under curb and gutter. If work cannot be accomplished by tunneling, sawcut and replace the curb at trench width (approximately 24-inches). Where applicable, sidewalk flags will be removed and hauled off, and new flags will be poured after service lateral is installed.

City of Angels will supply all fittings. Contractor to furnish sand, aggregate, cutback, AC, 1-inch CTS, HDPE tubing, and tracer wire. Contractor to restripe existing thermoplastic striping with 4-inch torch down tape. All asphalt and concrete to be disposed of by Contractor. All excess backfill to be disposed of by the Contractor at the City "Hydrocks" Yard.

1. Replace water service lateral at Live Oak Court. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$17,260.
2. Replace water service lateral at 653 Lakeview Court. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$10,670.
3. Replace water service lateral at 361 Acorn Drive. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$10,905.



CHANGE ORDER NO.	CONTRACT NUMBER	PROJECT	FEDERAL NUMBER(S)
003		Water Meter Replacement Project Phase 1 and Phase 2	

4. Replace water service lateral at 301 Acorn Drive. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$10,905.
5. Replace water service lateral at Leaf Court. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$11,185.
6. Replace water service lateral at 220 Acorn Drive. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$9,165.
7. Replace water service lateral at 1282 Minna Street. Work includes service lateral removal, trenching and excavation for new lateral, installation of new service lateral, and coordination of meter replacement. The lump sum amount for completion of this task is \$10,890.
8. Pavement patching and restoration of the sites to original condition for replacement of service laterals. The lump sum amount for completion of this task is \$20,220.
9. Mobilization of equipment, materials, and labor forces for the above work. The lump sum amount for completion of this task is \$500.

Subtotal Water Service Lateral Replacements – Phase 1 \$101,700.00

The Total Amount for this Change Order is (\$106,656.00)

Estimated Cost: ☐ Increase ☒ Decrease (\$106,656.00)

For this order, the time of completion will be adjusted as follows: No Change

SUBMITTED BY

SIGNATURE	(PRINT NAME AND TITLE)	DATE
	Dave Richard, PE, Water/Wastewater Engineer	7/29/2026

CITY APPROVAL BY

SIGNATURE	(PRINT NAME AND TITLE)	DATE

We, the undersigned contractor, have given careful consideration to the change proposed and agree to provide equipment, furnish materials, and perform the work specified above, and will accept as full payment the prices shown above. **NOTE: If you do not sign this order, you are directed to proceed with the ordered work. You may file a Request for Information within 15 days.**

CONTRACTOR ACCEPTANCE BY

SIGNATURE	(PRINT NAME AND TITLE)	DATE