

# Construction Material List

Approx 1800.00

|                                               |       |         |
|-----------------------------------------------|-------|---------|
| 3- 2x4 10'                                    | 13.50 | 40.50   |
| 25- 2x4 Studs,                                | 10.99 | 274.75  |
| 4 lbs 3" Black Screws.                        | 4.99  | 19.96   |
| 5- 3/8" x 4" Anchor Bolts.                    | 4.99  | 24.95   |
| 9- sheets 4'x8' 1/2" Sheet rock.              | 14.99 | 134.91  |
| 4 lbs 1 1/2" black screws,                    | 4.99  | 19.96   |
| 1- 5 gal bucket of Sheet rock mud.            |       | 21.99   |
| 1- roll paper tape.                           |       | 4.99    |
| 100' of wood trim for both sides of the wall. |       | 100.00  |
| 2- 10"x12" Flat Vents for return air.         | 10.99 | 21.98   |
| 2- gal Flat latex paint.                      | 44.99 | 89.98   |
| 3- rollers                                    |       |         |
| 4- 2" paint brushes.                          | 3.99  |         |
| 1- 2" roll of masking tape.                   |       | 10.99   |
| 1- 3/0 Hard wood door pre hung                |       | 305.99  |
|                                               |       | outside |
| 1- Push button coded lock for entry.          |       | 179.99  |
| 1- Pack door shims.                           |       | 2.99    |
| Wood to finish in door both sides to match.   |       | 50.00   |
| 1- pack door shims.                           |       | 2.99    |

Needing to make a window ~ 30"x30" out of tempered glass with a slide sheet under with for paper work to be passed through.

1522.87

+ 300 Leeway