

STATEMENT OF TOWN COUNCIL AND ORDINANCE AMENDING THE OFFICIAL ZONING DISTRICT MAP OF THE TOWN OF APEX TO CHANGE THE ZONING OF APPROXIMATELY 15.3 ACRES LOCATED AT 0 & 0 MT. ZION CHURCH RD FROM RURAL RESIDENTIAL (RR) TO PLANNED UNIT DEVELOPMENT-CONDITIONAL ZONING (PUD-CZ)

#24CZ10

WHEREAS, Ashburn Development, applicant (the "Applicant"), submitted a completed application for a conditional zoning on June 1, 2024 (the "Application"). The proposed conditional zoning is designated #24CZ10;

WHEREAS, the Planning Director for the Town of Apex, Dianne Khin, caused proper notice to be given (by publication and posting) of a public hearing on #24CZ10 before the Planning Board on the July 14, 2025;

WHEREAS, the Apex Planning Board held a public hearing on the July 14, 2025, gathered facts, received public comments and formulated a recommendation regarding the application for conditional zoning #24CZ10. A motion was made by the Apex Planning Board to recommend approval; the motion passed unanimously for the application for #24CZ10;

WHEREAS, pursuant to N.C.G.S. §160D-601 and Sec. 2.2.11.E of the Unified Development Ordinance, the Planning Director caused proper notice to be given (by publication and posting), of a public hearing on #24CZ10 before the Apex Town Council on August 12, 2025;

WHEREAS, the Apex Town Council held a public hearing on the August 12, 2025. Joshua Killian, Planner II, presented the Planning Board's recommendation at the public hearing;

WHEREAS, all persons who desired to present information relevant to the application for #24CZ10 were allowed to present evidence at the public hearing before the Apex Town Council. No one who wanted to speak was turned away;

WHEREAS, the Apex Town Council finds that the approval of the rezoning is consistent with the 2045 Land Use Plan and other adopted plans in that: The 2045 Land Use Map designates this area as Medium Density Residential. This designation on the 2045 Land Use Map includes the zoning district Planned Unit Development-Conditional Zoning (PUD-CZ) and the Apex Town Council has further considered that the proposed rezoning to Planned Unit Development-Conditional Zoning (PUD-CZ) will maintain the character and appearance of the area and provide the flexibility to accommodate the growth in population, economy, and infrastructure consistent with that contemplated by the 2045 Land Use Map;

WHEREAS, the Apex Town Council finds that the approval of the rezoning is reasonable and in the public interest in that: The rezoning will permit a variety of housing types as an infill development, utilizing existing street stubs to provide additional vehicular and pedestrian ingress and egress to the existing residential developments; and

WHEREAS, the Apex Town Council by a vote of 5 to 0 approved #24CZ10 rezoning the subject tract located at 0 & 0 Mt. Zion Church Rd from Rural Residential (RR) to Planned Unit Development-Conditional Zoning (PUD-CZ).

NOW, THEREFORE, BE IT ORDAINED BY THE TOWN COUNCIL OF THE TOWN OF APEX

Section 1: The lands that are the subject of the Ordinance are those certain lands described in Attachment "A" – Legal Description which is incorporated herein by reference, and said lands are hereafter referred to as the "Rezoned Lands."

Section 2: The Town of Apex Unified Development Ordinance, including the Town of Apex North Carolina Official Zoning District Map which is a part of said Ordinance, is hereby amended by changing the zoning classification of the "Rezoned Lands" from Rural Residential (RR) to Planned Unit Development-Conditional Zoning (PUD-CZ) District, subject to the conditions stated herein.

Ordinance Amending the Official Zoning District Map #24CZ10

Section 3: The Planning Director is hereby authorized and directed to cause the said Official Zoning District Map for the Town of Apex, North Carolina, to be physically revised and amended to reflect the zoning changes ordained by this Ordinance.

Section 4: The "Rezoned Lands" are subject to the conditions in Attachment "B" Ashburn PUD which were imposed as part of this rezoning.

Section 5: The "Rezoned Lands" shall be perpetually bound to the conditions imposed including the uses authorized, unless subsequently changed or amended as provided for in the Unified Development Ordinance. Site plans for any development to be made pursuant to this amendment to the Official Zoning District Map shall be submitted for site plan approval as provided for in the Unified Development Ordinance.

Section 6: This Ordinance shall be in full force and effect from and after its adoption.

Motion by Council Member Gray


Seconded by Council Member Zegeman

With 5 Council Member(s) voting "aye."

With 0 Council Member(s) voting "no."

This the 13th day of November 2025.

TOWN OF APEX




Jacques K. Gilbert
Mayor

ATTEST:



Allen Coleman, CMC, NCCCC
Town Clerk

APPROVED AS TO FORM:



Town Attorney



Legal Description TRACT 1

Beginning at a CONTROL CORNER IRON PIPE SET having coordinates of **N:714695.43, E:2024516.24**; thence with a bearing of **N 79°30'09" E** a distance of **511.74** feet to a IRON ROD FOUND; thence with a bearing of **S 02°38'21" W** a distance of **514.71** feet to a IRON PIPE FOUND; thence with a bearing of **S 74°13'11" W** a distance of **134.17** feet to a IRON PIPE SET; thence and along the Eastern Right of Way of Mount Zion Church Road with a bearing of **N 39°46'07" W** a distance of **14.76** feet to a COMPUTED POINT; thence with a bearing of **N 43°16'07" W** a distance of **28.65** feet to a COMPUTED POINT; thence with a bearing of **N 45°10'11" W** a distance of **27.50** feet to a COMPUTED POINT; thence with a bearing of **N 44°59'53" W** a distance of **53.64** feet to a COMPUTED POINT; thence with a bearing of **N 45°28'43" W** a distance of **53.65** feet to a COMPUTED POINT; thence with a bearing of **N 45°53'23" W** a distance of **53.67** feet to a COMPUTED POINT; thence with a bearing of **N 43°26'50" W** a distance of **52.19** feet to a COMPUTED POINT; thence with a bearing of **N 41°14'19" W** a distance of **25.43** feet to a COMPUTED POINT; thence with a bearing of **N 37°36'11" W** a distance of **25.39** feet to a COMPUTED POINT; thence with a bearing of **N 34°00'02" W** a distance of **25.89** feet to a COMPUTED POINT; thence with a bearing of **N 32°05'39" W** a distance of **24.72** feet to a COMPUTED POINT; thence with a bearing of **N 27°36'38" W** a distance of **26.31** feet to a COMPUTED POINT; thence with a bearing of **N 29°18'23" W** a distance of **13.26** feet to a COMPUTED POINT; thence with a bearing of **N 28°41'19" W** a distance of **51.85** feet to a COMPUTED POINT; thence with a bearing of **N 27°09'54" W** a distance of **104.55** feet to a IRON PIPE SET; which is the Point of beginning, containing approximately 175,840.87 square feet or 4.0367 acres, as shown on a survey entitled "Boundary Survey For Ashburn Development, LLC" by Daniel J. Burud, Professional Land Surveyor of Priest Craven and Associates, Inc. dated 10/18/2022.

Legal Description TRACT 2

COMMENCING at a IRON PIPE FOUND having coordinates of **N:713838.8111, E:2023762.5241E**; thence with a bearing of **N 02°48'41" E** a distance of **360.92** feet to a IRON PIPE FOUND; thence with a bearing of **N 66°29'35" E** a distance of **824.42** feet to a IRON PIPE FOUND; thence and along the Western Right of Way of Mount Zion Church Road with a bearing of **S 29°25'34" E** a distance of **12.05** feet to a COMPUTED POINT; thence with a bearing of **S 27°36'38" E** a distance of **28.74** feet to a COMPUTED POINT; thence with a bearing of **S 32°05'39" E** a distance of **28.07** feet to a COMPUTED POINT; thence with a bearing of **S 34°00'02" E** a distance of **28.78** feet to a COMPUTED POINT; thence with a bearing of **S 37°36'11" E** a distance of **29.18** feet to a COMPUTED POINT; thence with a bearing of **S 41°14'19" E** a distance of **28.49** feet to a COMPUTED POINT; thence with a bearing of **S 43°26'50" E** a distance of **54.62** feet to a COMPUTED POINT; thence with a bearing of **S 45°53'23" E** a distance of **54.73** feet to a COMPUTED POINT; thence with a bearing of **S 45°28'43" E** a distance of **53.19** feet to a COMPUTED POINT; thence with a bearing of **S 44°59'53" E** a distance of **53.48** feet to a COMPUTED POINT; thence with a bearing of **S 45°10'11" E** a distance of **26.59** feet to a COMPUTED POINT; thence with a bearing of **S 43°16'07" E** a distance of **25.82** feet to a COMPUTED POINT; thence with a bearing of **S 39°46'07" E** a distance of **25.44** feet to a COMPUTED POINT; thence with a bearing of **S 35°33'43" E** a distance of **24.72** feet to a COMPUTED POINT; thence with a bearing of **S 32°15'36" E** a distance of **25.41** feet to a COMPUTED POINT; thence with a bearing of **S 26°39'44" E** a distance of **24.07** feet to a COMPUTED POINT; thence with a bearing of **S 20°21'19" E** a distance of **23.32** feet to a COMPUTED POINT; thence with a bearing of **S 12°34'16" E** a distance of **23.56** feet to a COMPUTED POINT; thence with a bearing of **S 04°55'42" E** a distance of **23.24** feet to a COMPUTED POINT; thence with a bearing of **S 01°38'37" W** a distance of **24.73** feet to a COMPUTED POINT; thence with a bearing of **S 04°32'08" W** a distance of **3.05** feet to a IRON PIPE SET; thence with a bearing of **N 78°15'38" W** a distance of **361.61** feet to a IRON PIPE FOUND; thence with a bearing of **S 01°09'18" W** a distance of **290.68** feet to a IRON ROD FOUND; thence with a bearing of **N 88°08'03" W** a distance of **759.49** feet to a IRON PIPE FOUND; which is the Point of Beginning, containing approximately 491,617.13 square feet or 11.2860 acres, as shown on a survey entitled "Boundary Survey For Ashburn Development, LLC " by Daniel J. Burud, Professional Land Surveyor of Priest Craven and Associates, Inc. dated 10/18/2022.

ASHBURN

PROPOSED PLANNED UNIT DEVELOPMENT

APEX, NORTH CAROLINA

ORIGINAL SUBMITTAL JUNE 3, 2024

V.2 - FEBRUARY 7, 2025, V.3 - MARCH 7, 2025, V.4 - APRIL 4, 2025,

V.5 - MAY 2, 2025, V.6 - JUNE 6, 2025, V.7 - SEPTEMBER 15, 2025

V.8 - OCTOBER 21, 2025



Developer/Applicant/Authorized Agent:

Ashburn Development LLC

933 Old Knight Road, Knightdale N. Carolina

(919) 422-3933 - [Mike Jordan - Mike.Jordan@jvmgmt.net](mailto:Mike.Jordan@jvmgmt.net)

Master Planning:

Entitlement Preservation Group

275 North Pea Ridge Road, Pittsboro N. Carolina

(919) 625-9760

Engineering/Surveying

Priest Craven and Associates Inc


3803 B Computer Drive Suite 104, Raleigh N. Carolina

(919) 919-781-0300 PCA@PriestCraven.com Firm #: C-0488

<u>1.0 – Table of Contents</u>	<u>Page(s)</u>
Section 1: Table of Contents	2
Section 2: Vicinity Maps	3-4
Section 3: Overall PUD Data	5
Section 4: Purpose Statement- PUD Development Standards	6-9
Section 5: Consistency with Zoning Standards	10
Section 6: Proposed Design Controls	10-11
Section 7: Architectural Controls	12-14
Section 8: Affordable Housing	14
Section 9: Conceptual Building Elevations	15-20
Section 10: Proposed Parking	21
Section 11: Proposed Signage	21
Section 12: Natural Resource and Environmental Data	21-22
Section 13: Stormwater	23
Section 14: Parks, Recreation & Cultural Resources Commission	23
Section 15: Public Facilities	23-25
Section 16: Phasing Plan	25
Section 17: Land Use Plan Consistency	25
Section 18: Compliance with UDO	25

2.0 Vicinity Maps





AERIAL MAP

3.0 Overall PUD Data

Name of PUD	Ashburn
Property Owners	Anthony and Delois Richardson 1825 Car Creek Road Sanford, NC 27332
Prepared by	Entitlement Preservation Group 275 North Pea Ridge Road Pittsboro, N. Carolina 27312 919-625-9760 Priest Craven and Associates Inc 3803 Computer Drive Suite 104 Raleigh, N. Carolina 27609 919-781-0300 PCA@PriestCraven.com
Developer	Ashburn Development LLC 933 Old Knight Road, Knightdale N. Carolina (919) 422-3933 Mike.Jordan@jvmgmt.net
2045 LUM Designation	Medium Density Residential
Total Acreage	15.3
Area designated Mixed Use on LUM	none
Proposed Building Heights	Max 42 ft. Single Family Detached Max 45 ft. Townhomes
Watershed Protection Overlay	Primary, Jordan Lake Basin
Current Zoning	Rural Residential (RR)
Proposed Zoning	Planned Unit Development (PUD-CZ)
Site Address	0 Mt. Zion Church Road (both tracts)
Property Identification Number	0721448562 and 0721442048

4.0 Purpose Statement and PUD Standards

This document and the accompanying exhibits submitted herewith (collectively, the “PUD”) are provided pursuant to the Town of Apex Unified Development Ordinance (“UDO”) Planned Unit Development provisions. This PUD addresses the development of approximately 15.3 acres on Mt. Zion Church Road, near the intersection of Mt. Zion Church Road and Milano Avenue. The Properties are currently vacant.

Ashburn is a proposed Planned Unit Development in the Buckhorn Township in Apex, N. Carolina.

The tracts are surrounded on three sides by the existing Bella Casa and Buckhorn Preserve subdivisions that were constructed over the last 10 years and existing rural properties to the South. Currently, both Bella Casa and Buckhorn Preserve have a combination of townhomes and alley-loaded, single-family detached style lots.

The goals of the PUD, in return for greater flexibility in site design requirements, are to deliver exceptional quality community designs that preserve critical environmental resources; provide high-quality community amenities; incorporate creative design in the layout of buildings, Resource Conservation Area, and circulation; ensure compatibility with surrounding land uses and neighborhood character; provide high-quality architecture; and provide greater efficiency in the layout and provision of roads, utilities, and other infrastructure.

Ashburn PUD will have both single-family detached, alley-loaded and townhomes in the community, it is designed to respect environmental features, extend existing development styles and have a well-connected pedestrian network. The PUD will match the density envisioned by the Medium Density Residential Land Use Map (“LUM”) designation and will be generally consistent with the Apex Comprehensive Plan’s (“Peak Plan”) goals for accommodating a mix of housing types to serve the Town’s growing and increasingly diverse population, as well as a well-connected pedestrian network, and protection of environmental and natural resources.

CONSISTENCY WITH PLANNED UNIT DEVELOPMENT STANDARDS

- (i) *The uses proposed to be developed in the PD plan for PUD-CZ are those uses permitted in Sec. 4.2.2 Use Table*

RESPONSE: The uses permitted within The Ashburn PUD are permitted within this designation in UDO Section 4.2.2 Use Table.

- (ii) *The uses proposed in the PD Plan for PUD-CZ can be entirely residential, entirely non-residential, or a mix of residential and non-residential uses, provided a minimum percentage of non-residential land area is included in certain mixed-use areas as specified on the 2045 Land Use Map. The location of uses proposed by the PUD-CZ must be shown in the PD Plan with a maximum density for each type of residential use and a maximum square footage for each type of non-residential use.*

RESPONSE: The Ashburn PUD will have both residential single-family detached and townhomes in the community. It is not shown as a mixed-use designation on the 2045 LUM.

- (iii) *The dimensional standards in Sec. 5.1.3 Table of Intensity and Dimensional Standards, Planned Development Districts may be varied in the PD Plan for PUD-CZ. The PUD-CZ shall demonstrate compliance with all other dimensional standards of the UDO, North Carolina Building Code, and North Carolina Fire Code.*

RESPONSE: This PUD specifies intensity and dimensional standards for the PUD. The PUD's standards, which includes multiple pedestrian connections are consistent with the UDO's vision for Planned Unit Developments – to provide site specific, high-quality neighborhoods that preserve natural features and exhibit compatibility with, and connectivity to, surrounding land uses. Except as specifically stated in this PUD, Ashburn will comply with all other requirements of the UDO and will comply with all applicable requirements of the North Carolina Building Code and the North Carolina Fire Code. The proposed PUD will comply with all applicable Supplemental Use Standards in UDO Section 4.4.

- (iv) *The development proposed in the PD Plan for PUD-CZ encourages cluster and compact development to the greatest extent possible that is interrelated and linked by pedestrian ways, bikeways and other transportation systems. At a minimum, the PD Plan must show sidewalk improvements as required by the Advance Apex: The 2045 Transportation Plan and the Town of Apex Standard Specifications and Standard Details, and greenway improvements as required by the Town of Apex Parks, Recreation, Greenways, and Open Space Plan and the Advance Apex: The 2045 Transportation Plan. In addition, sidewalks shall be provided on both sides of all streets for single-family detached homes.*

RESPONSE: Ashburn PUD will feature sidewalks throughout. Sidewalks will connect the PUD and the adjacent Bella Casa and Buckhorn Preserve neighborhoods improving pedestrian connectivity.

Specifically:

Transportation Plan, the proposed PUD street network, will require an amendment to the current Transportation Plan. Hammocks Beach Trail and Baronial Street extensions will now intersect Mt. Zion Church Road with a small roundabout as specified by the Town Staff.

Parks Plan, the PUD is not part of the current New Park Search Area, meaning the developers of the PUD will pay a fee-in-lieu for local improvements.

Greenway Plan, does not designate any extensions in the area; however, as part of the Transportation amendment, the cross section of Hammocks Beach Trail within the PUD will now include a ten-foot wide pedestrian path.

- (v) *The design of development in the PD Plan for PUD-CZ results in land use patterns that promote and expand opportunities for walkability, connectivity, public transportation, and an efficient compact network of streets. Cul-de-sacs shall be avoided unless the design of the subdivision and the existing or proposed street system in the surrounding area indicate that a through street is*

not essential in the location of the proposed cul-de-sac, or where sensitive environmental areas such as streams, floodplains, and wetlands would be substantially disturbed by making road connections.

RESPONSE: The proposed street layout has been designed to enhance pedestrian and vehicular connectivity while protecting as much sensitive environmental features possible and being mindful of existing residential development. Generally, the Development will extend three existing streets: Hammocks Beach Trail, Blue Jay Point and Baronial Street and adding two direct connections to Mt. Zion Church Road. The Development will also provide a stub street to the southern property line.

(vi) *The development proposed in the PD Plan for PUD-CZ is compatible with the character of surrounding land uses and maintains and enhances the value of surrounding properties.*

RESPONSE: The proposed development is compatible with the character of the existing and planned uses in the surrounding area. This PUD is surrounded by single-family lots, single family lots that are alley loaded and townhomes. This PUD will extend existing alley-loaded lots from Bella Casa and extend existing townhome areas from Buckhorn Preserve.

Ashburn PUD will provide high quality housing supply to the Town and improve overall pedestrian connectivity in the area. The proposed overall maximum density of 4.8 units/acre, together with the offered architectural conditions, will ensure the PUD is compatible with existing neighborhoods in the area.

(vii) *The development proposed in the PD Plan for PUD-CZ has architectural and design standards that are exceptional and provide higher quality than routine developments. All residential uses proposed in a PD Plan for PUD-CZ shall provide architectural elevations representative of the residential structures to be built to ensure the Standards of this Section are met.*

RESPONSE: Ashburn PUD will feature high quality and thoughtful design. Architectural standards, design controls, and conceptual elevations are included in this PUD.

5.0 Consistency with Conditional Zoning Standards

Ashburn PUD is consistent with the conditional zoning standards set forth in UDO Section 2.3.3.F.1-10. See the accompanying PUD-CZ Application for the statements of consistency addressing each standard.

6.0 Proposed Design Controls

PERMITTED USES

The Rezoned lands may be used for, and only for, the uses listed below. The permitted uses are subject to the limitations and regulations stated in the UDO and any additional limitations or regulations stated below. For convenience, some relevant sections of the UDO may be referenced; such references do not imply that other sections of the UDO do not apply.

Residential Uses

Single-Family	Permitted
Townhomes	Permitted
Accessory Apts.	
HOA shall not restrict the construction of ADU	Permitted

Recreational

Parks, active	Permitted
Recreational, private facility	Permitted

Utilities

Minor	Permitted
-------	-----------

OVERALL

Total Project Area	15.3 Acres
Maximum Built-Upon Area	70%
Maximum Residential Units	74
Maximum Residential Density and Buffers)	4.8 Dwelling Units /AC (incl. RCA, ROW

SINGLE-FAMILY

Minimum Lot Size	3800 SQ. FT.
Minimum Lot Width	30 FT.
Minimum Lot Setbacks	
Front	10 FT.
Corner	8 FT.
Side	3 FT.
Rear	20 FT.
Rear Detached Garage	5 FT. from alley easement
Maximum Building Height	42 FT.
RCA	1.41 AC (35%)

TOWNHOME

Minimum Lot Size	1800 SQ. FT.
Minimum Lot Width	20 FT.
Minimum Lot Setbacks	
Front	20 FT.
Corner	12 FT.
Side	0 FT.
Rear	15 FT.
Min. Building Separation	8 FT.
Maximum Building Height	Up to 45 FT. from FFE to highest peak
RCA	3.39 AC (30%)
Minimum Buffer/RCA Setback	10 FT. buildings, 5FT. parking areas

7.0 Proposed Architectural Controls

Townhomes

1. Vinyl siding is not permitted; however, vinyl windows, decorative elements and trim are permitted.
2. The roofline cannot be a single mass; it shall be broken horizontally and vertically between, at a minimum, every other unit.
3. Garage doors shall have windows, decorative details or carriage-style adornments on them.
4. House entrances for units with front-facing single-car garages shall have a prominent covered porch/stoop area leading to the front door.
5. The garage cannot protrude more than 2 feet out from the front façade or front porch.
6. The visible side of a townhome on a corner lot facing the public street shall contain at least 3 decorative elements such as, but not limited to, the following elements:
 - Windows
 - Bay window
 - Recessed window
 - Decorative window
 - Trim around the windows
 - Wrap around porch or side porch
 - Two or more building materials
 - Decorative brick/stone
 - Decorative trim
 - Decorative shake
 - Decorative air vents on gable
 - Decorative gable
 - Decorative cornice
 - Column
 - Portico
 - Balcony
 - Dormer
7. Building front facades shall have horizontal relief achieved by the use of recesses and projections.
8. A varied color palette shall be utilized on homes throughout the subdivision to include a minimum of three-color families for siding and shall include varied trim, shutter, and accent colors complementing the siding color.

9. The rear and side elevations of the units that front on the public right-of-way shall have trim around the windows.

Single-Family Detached

1. Vinyl siding is not permitted; however, vinyl windows, decorative elements and trim are permitted.
2. The roof shall be pitched at 5:12 or greater for 50% of the building designs.
3. Eaves shall project at least 12 inches from the wall of the structure.
4. Garage doors shall have windows, decorative details or carriage-style adornments on them.
5. The garage, if used, shall be accessed by a rear alley, regardless whether it is attached or detached.
6. Garages, if used, will front and be limited to access to public rear alleys.
7. The visible side of a home on a corner lot facing the public street shall contain at least 3 decorative elements such as, but not limited to, the following elements:

▪ Windows	▪ Decorative trim
▪ Bay window	▪ Decorative shake
▪ Recessed window	▪ Decorative air vents on gable
▪ Decorative window	▪ Decorative gable
▪ Trim around the windows	▪ Decorative cornice
▪ Wrap around porch or side porch	▪ Column
▪ Two or more building materials	▪ Portico
▪ Decorative brick/stone	▪ Balcony
	▪ Dormer
8. A varied color palette shall be utilized on homes throughout the subdivision to include a minimum of three-color families for siding and shall include varied trim, shutter, and accent colors complementing the siding color.
9. The rear and side elevations of the units that front on public right-of-way shall have trim around the windows.

8.0 Affordable Housing

Prior to recording the first Master Subdivision Final Plat, the developer shall make a donation to the Town of Apex Affordable Housing Fund in the amount equal to 10% of the total number of units at a rate of \$218,000.00 per unit. If the 10% of total units calculation results in a fraction between 0.50 and 0.99, the total units shall be rounded up to the nearest whole number. If the 10% of total units calculation results in a fraction between 0.01 and 0.49, the units shall be rounded down to the nearest whole number.

9.0 Conceptual Building Elevations

While building elevations are conceptual, actual elevations shall be substantially consistent with those provided.

Townhomes












Single-Family Detached







Detached Garage Units



10.0 Proposed Parking

Parking shall comply with minimum parking standards set forth in UDO Section 8.3.

11.0 Proposed Signage

Signage shall comply with UDO Section 8.7.

In addition, the PUD shall install at least one (1) sign per SCM discouraging the use of fertilizer and to reduce pet waste near SCM drainage areas. The sign(s) shall be installed in locations that are publicly accessible, such as adjacent to, but outside of public property and/or public easement(s), sidewalks, or side paths.

12.0 Natural Resource and Environmental Data

The Property is within the Jordan Lake Watershed, and Primary Watershed Protection Overlay District as shown on the Town of Apex Watershed Protection Overlay Map 2019. This PUD will comply with all built upon area, vegetated conveyances, structural SCMs and riparian stream buffer requirements of UDO Section 6.1.8.

RESOURCE CONSERVATION AREA (RCA)

The PUD will be mass graded, it shall designate a minimum of 30% of the Property as RCA on the townhome portion of the PUD and 35% on the single-family portion.

FLOODPLAIN

The PUD is not located in a designated current or future 100-year floodplain as shown on the Town of Apex's Flood Risk Information System (FRIS) or FEMA FIRM Panel 3720072100K with an effective date of July 19, 2022.

HISTORIC STRUCTURES

There are no known historic structures present on the Property.

ENVIRONMENTAL COMMITMENTS SUMMARY

The following environmental conditions shall apply to the Development:

- The PUD shall install at least one (1) sign per SCM discouraging the use of fertilizer and to reduce pet waste near SCM drainage areas. The sign(s) shall be installed in locations that are publicly accessible, such as adjacent to, but outside of public property and/or public easement(s), sidewalks, or side paths.

- The PUD shall install at least three (3) pet waste stations units throughout the community in locations that are publicly accessible, such as adjacent to amenity centers, SCMs, sidewalks, greenways or side paths.
- The PUD shall plant drought resistant warm season grasses throughout the development to minimize irrigation and chemical use.
- Stormwater control devices shall be designed and constructed so that post development peak runoff does not exceed pre-development peak runoff conditions for the 24-hour, 1 year, 10 year, and 25-year storm events.
- Landscaping shall include at least four (4) native hardwood tree species throughout the Development.
- No clearing or land disturbance shall be permitted within the riparian buffer, except the minimum necessary to install required road crossings, utility infrastructure, and SCM outlets. The SCM water storage and treatment area shall not be permitted within the riparian buffer. The grading shall be designed to minimize impacts to the riparian buffer.
- Any outdoor lighting installed on private amenities, signs, landscaping, walls, or fences in common areas shall be full cutoff LED fixtures with a maximum color temperature of 3000k. This condition shall not apply to lighting on Single-family lots, Townhome lots, or street lighting.
- At least 75% of plants shall be native species. Landscaping will be coordinated with and approved by the Planning Department at site or subdivision review.
- The PUD shall preserve at least 15% of existing tree canopy.
- At least 50% of the total units shall include solar conduit in building design.
- The developer shall install at least 2 electric vehicle charging stations in common area parking lots.
- All homes shall have a 220/240 outlet in garages for electric vehicle charging.
- In order to reduce water consumption and promote pollinator friendly habitat and biodiversity, Homeowner Association covenants shall not restrict clover lawns throughout the neighborhood.
- Homeowner Association covenants shall not restrict solar panel installation throughout the neighborhood.

13.0 Stormwater Management

Stormwater control devices shall be designed and constructed to exceed UDO standards so that post development peak runoff does not exceed pre-development peak runoff conditions for the 24-hour, 1 year, 10 year, and 25-year storm events. Otherwise, the Development shall meet all stormwater management requirements for quality and quantity treatment in accordance with Section 6.1 of the UDO.

The PUD shall provide additional water quality stormwater controls to reduce the overall nitrogen export for the site to less than 10 lbs/ac/yr through the installation of State approved Stormwater Control Measures (SCMs). The final selection of the SCMs used to reduce the nitrogen export from the site shall be selected by the design team and coordinated with staff during Subdivision and Construction Document design and review.

Acceptable stormwater structures shall include detention ponds, constructed wetlands, bio-retention areas, or other approved devices consistent with the NC DEQ Stormwater Design Manual and the Town of Apex UDO.

14.0 Parks, Recreation and Cultural Resources Commission

This PUD was reviewed by the Parks, Recreation, and Cultural Resources Advisory Commission on 10/30/24, and a fee-in-lieu of dedication was recommended.

Single-family detached Units: \$ 4,244.42 x 21 = \$ 89,132.82

Townhome Units: \$ 2,858.65 x 51 = \$ 145,791.15

The final unit count and total fee-in-lieu will be calculated at Master Subdivision Plan and Construction Document review.

15.0 Public Facilities

The PUD shall meet all Public Facilities requirements as set forth in UDO Section 2.3.4(F)(1)(f) and be designed to comply with the Town's Sewer and Water Master Plan and Standards and Specifications.

Road and utility infrastructure shall be as follows:

GENERAL ROADWAY INFRASTRUCTURE

Except as set forth herein, all proposed roadway infrastructure and right-of-way dedications will be consistent with the Town of Apex Comprehensive Transportation Plan and Bicycle and Pedestrian System Plan in effect as of the submission date of this rezoning.

The planting in the proposed Roundabout will replace the requirement of the entrance landscape median.

TRANSPORTATION IMPROVEMENTS

The following conditions regarding transportation improvements apply. Access and improvements proposed along NCDOT roadways are subject to Town of Apex and NCDOT review and approval at the time of site and subdivision plans.

1. Developer shall extend Baronial Street from its existing stub to Mt Zion Church Rd as a Residential Street typical section, a 27-foot-wide curb and gutter street, and dedicate a 50-foot-wide right of way, with 5-foot-wide sidewalks on both sides.
2. Developer shall construct and dedicate right of way for a Residential Street stub street from Baronial Street to Parcel PIN 0721436885.
3. Developer shall extend Blue Jay Point from its existing stub to Baronial St as a Residential Street typical section, a 27-foot-wide curb and gutter street, and dedicate a 50-foot-wide right of way, with 5-foot-wide sidewalks on both sides.
4. Developer shall extend Hammocks Beach Trail based on a Minor Collector Street typical section, a 27-foot-wide curb and gutter street, and dedicate a reduced (50-foot-wide) right of way, with a 5-foot-wide sidewalk on the east side and 10-foot-wide Side Path on the west side.
5. Developer shall construct a single-lane, four-legged mini roundabout at the intersection of Mt Zion Church Rd and the extensions of Hammocks Beach Trail and Baronial Street.
6. Developer shall construct improvements and dedicate right of way along Mt. Zion Church Road, for the entire project frontage, is based on a Residential Street typical section north of the mini-roundabout and based on the Minor Collector Street typical section south of the mini-roundabout. North of the mini-roundabout Developer shall construct 5-foot-wide sidewalks on both sides. South of the mini-roundabout Developer shall construct a 5-foot-wide sidewalk on the west side and a 10-foot-wide Side Path on the east side.

PEDESTRIAN AND BICYCLE IMPROVEMENTS

Per UDO requirements for residential development with a PUD zoning designation, sidewalks shall be provided along both sides of all streets.

WATER AND SANITARY SEWER

All lots within the Development will be served by Town of Apex water and sanitary sewer. The utility design will be finalized at the time of Master Subdivision Plan or Site Plan approval and be based on available facilities adjacent to the site at that time. The design will meet the current Town of Apex master plans for water and sewer. A conceptual utility plan is included in the PUD Concept Plan for reference. An exception will be needed that the Water Main along Mt. Zion will be installed within the NCDOT right-of-way.

OTHER UTILITIES

Electricity will be provided by Duke Energy Progress or Apex Electric, depending on whether Apex Electric is capable of serving the Property. Phone, cable, and gas will be provided by the Developer and shall meet Town of Apex standards as outlined in the UDO.

16.0 Phasing Plan

The PUD will be completed in phases. Final locations of phases will be determined at the time of Master Subdivision Review and Approval.

17.0 Consistency with Land Use Plan

The PUD proposes density than is recommended by the Medium Density Residential Land Use Map designation, it is generally consistent with the goals of the 2045 Land Use Map. The Medium Density Residential designation recommends “single-family and townhome residential uses” that will extend existing similar development/ The proposed maximum density of 4.8 units/acre is consistent with recommended density for Medium Density Residential, as defined in the Comp Plan. The PUD, together with conditions of this PUD, will extend a mixture of single-family and townhome housing, and providing more pedestrian connections.

- Protection of environmental and natural resources.
- A variety of housing types are available to a range of incomes.
- Extend medium density residential uses

18.0 Compliance with UDO

The development standards adopted for this PUD are in compliance with those set forth in the current version of the Town’s Unified Development Ordinance (UDO). This PUD shall be the primary governing document for the development of Ashburn. All standards and regulations in this PUD shall control over general standards of the UDO. Provided, however, that if a specific regulation is not addressed in this PUD, UDO regulations shall control.

ASHBURN

APEX, NC

REZONING: 24CZ10

PLANNED UNIT DEVELOPMENT PLAN DRAWINGS FOR A MEDIUM DENSITY RESIDENTIAL DEVELOPMENT

PROJECT STATISTICS

PROPERTY OWNER	ANTHONY & DELOIS RICHARDSON 1825 CAR CREEK RD. SANFORD, NC 27332
DEVELOPER	ASHBURN DEVELOPMENT, LLC 933 OLD KNIGHT ROAD KNIGHTDALE, NC 27545
APPLICANT	ENTITLEMENT PRESERVATION GROUP 275 NORTH PEA RIDGE RD PITTSBORO, NC 27312
EXISTING USE	VACANT
PROPOSED USE(S)	SINGLE FAMILY, TOWNHOUSE
EXISTING ZONING	RR
PROPOSED ZONING	PUD-CZ
CURRENT 2045 LAND USE MAP DESIGNATION	MEDIUM DENSITY RESIDENTIAL
WATERSHED PROTECTION OVERLAY DISTRICT	PRIMARY
RIVER BASIN	CAPE FEAR
FEMA FLOOD PANEL	2100K <i>THIS SITE DOES NOT CONTAIN FEMA DESIGNATED FLOOD ZONES</i>
HISTORIC STRUCTURES LOCATED ON SITE	NONE

AREA CALCULATIONS

AREA DESIGNATED AS MIXED USE ON 2045 LAND USE MAP	NA/0.00 AC
AREAS OF MIXED USE PROPOSED AS NON-RESIDENTIAL DEVELOPMENT	0.00 AC/0%
GROSS AREA OF PROJECT BASED ON SURVEY	15.32 AC
AREA IN TRACT 1 (SINGLE FAMILY)	4.03 AC
AREA IN TRACT 2 (TOWNHOMES)	11.29 AC
PLAY AREA REQUIRED (0.006 AC PER D.U., 0.3 AC MIN.)	0.006 AC PER DWELLING UNIT, 0.3 AC MINIMUM
RESOURCE CONSERVATION AREA REQUIRED OVER ENTIRE DEVELOPMENT	*30% PER 8.1.2.C 4.80 AC
AREA REQUIRED IN SINGLE FAMILY TRACT	35% 1.41 AC
AREA REQUIRED IN TOWNHOME TRACT	30% 3.39 AC
*5% ADDITIONAL RCA REQUIRED FOR SINGLE FAMILY TRACT PER 7.2.5.B.8	


MAXIMUM BUILT UPON AREA	70%	10.72 AC
-------------------------	-----	----------

BUILDING SETBACK REQUIREMENTS

SINGLE FAMILY (REAR ALLEY) SETBACKS		TOWNHOUSE SETBACKS	
FRONT	10'	FRONT	20'
CORNER	8'	CORNER	12'
SIDE	3'	SIDE	0'
REAR	20'	REAR	15'
REAR DETACHED GARAGE	5'	MIN. BUILDING SEPARATION	8'


FROM BUFFER OR RCA	10'
--------------------	-----

MAXIMUM ALLOWABLE BUILDING HEIGHT	UP TO 42' FOR DETACHED SINGLE FAMILY HOMES UP TO 45' FROM FFE TO HIGHEST PEAK FOR TOWNHOMES
-----------------------------------	--



VICINITY MAP

1" = 500'



AERIAL MAP

1" = 400'

PARKS AND RECREATION SITE DATA TABLE

DATE REVIEWED BY PRCR ADVISORY COMMISSION:	10/30/2024
☒ FEE-IN-LIEU OF DEDICATION:	
21 SINGLE-FAMILY DETACHED UNITS X \$4,244.42 PER UNIT =	\$ 89,132.82
51 SINGLE-FAMILY ATTACHED UNITS X \$2,858.65 PER UNIT =	\$ 145,791.15
0 MULTI-FAMILY UNITS X \$2,516.93 PER UNIT =	\$
TOTAL FEE-IN-LIEU:	\$ 234,923.97
☐ ACRES OF LAND DEDICATION	YES ☐ NO ☒
☐ PUBLIC GREENWAY TRAIL CONSTRUCTION	

SHEET LIST

SHEET #	SHEET TITLE
PD0.0	COVER SHEET
PD1.0	EXISTING CONDITIONS PLAN
PD2.0	PRELIMINARY LAYOUT AND UTILITY PLAN

DEVELOPER

ASHBURN DEVELOPMENT, LLC
933 OLD KNIGHT ROAD
KNIGHTDALE, NC 27545

APPLICANT

ENTITLEMENT
PRESERVATION
GROUP

CHARLES R. WALKER III, PLA
275 NORTH PEA RIDGE ROAD
PITTSBORO, NORTH CAROLINA 27312
PHONE: 919-625-9760
EMAIL: CWALKER@EPGROUPONLINE.COM

PLANS PREPARED BY:

PRIEST, CRAVEN & ASSOCIATES, INC.

PLANNERS / LANDSCAPE DESIGNERS / SURVEYORS / ENGINEERS
3803 - B COMPUTER DRIVE, SUITE 104, RALEIGH, N.C. 27609
PHONE 919 / 781-0300 FAX 919 / 782-1288
EMAIL PCA@PRIESTCRAVEN.COM FIRM#: C-0488

GENERAL NOTES:

- BOUNDARY INFORMATION IS TAKEN FROM A SURVEY BY THIS OFFICE.
- SITE TOPOGRAPHIC INFORMATION IS TAKEN FROM A COMBINATION OF DATA FROM A SURVEY PERFORMED BY THIS OFFICE AND TOWN OF APEX LIDAR DATA.
- PLANIMETRIC AND TOPOGRAPHIC INFORMATION FOR AREAS OUTSIDE OF THIS SITE ARE TAKEN FROM TOWN OF APEX AND WAKE COUNTY GIS INFORMATION.
- THERE ARE NO FEMA DESIGNATED FLOOD ZONES LOCATED ON THIS PROPERTY PER FEMA MAP 3720072100K, DATED 7/19/22.
- FLOODPLAIN INFORMATION IS TAKEN FROM A FLOOD STUDY PREPARED BY PRIEST, CRAVEN & ASSOCIATES, INC. AND SUBMITTED WITH THE MASTER SUBDIVISION PLAN STORMWATER IMPACT ANALYSIS, SCM DESIGN CALCULATIONS AND FLOOD STUDY.
- EXISTING UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR RESPONSIBLE FOR LOCATION OF ALL EXISTING ABOVE AND BELOW GROUND UTILITY FIELD LOCATION PRIOR TO ANY CONSTRUCTION.
- NO NEW BUFFER IMPACTS SHALL OCCUR PRIOR TO APPROVAL FROM NCDEQ.
- WETLAND AND STREAM BUFFER LOCATIONS ARE SUBJECT TO FIELD VERIFICATION.

UTILITY EXCEPTION TABLE

The following items have been approved as exceptions for this drawing by the Town of Apex Department Director(s), and to the best of my knowledge and belief, this drawing conforms to the requirements established by the Director(s) allowing deviation from the Standard Specifications and Standard Details of the Town of Apex. The signature below represents that the requesting Engineer has been granted a variance ONLY for the items listed. The developer/engineer/contractor is solely responsible for meeting all applicable requirements.

APPROVED EXCEPTION	DIRECTOR GRANTING EXCEPTION
1.	
2.	
3.	
By: _____	Date: _____
Requesting Engineer	

PROPOSED SEWER FLOWS:

NUMBER OF SINGLE FAMILY HOMES:	51 UNITS
NUMBER OF TOWNHOMES:	21 UNITS
AVG DAILY FLOW PER HOME:	300 GPD/UNIT
TOTAL AVERAGE DAILY FLOW:	21,600 GPD (15.0 GPM)


REVISIONS:	SUBMITTAL DATE:	6/3/2024	SHEET # PD0.0
REVISION 1	TOWN STAFF REVIEW:	2/7/2025	
REVISION 2	TOWN STAFF REVIEW:	3/7/2025	
REVISION 3	TOWN STAFF REVIEW:	4/4/2025	
REVISION 4	TOWN STAFF REVIEW:	5/2/2025	
REVISION 5	TOWN STAFF REVIEW:	6/5/2025	
RELEASED FOR CONSTRUCTION DATE:			NOT RELEASED

PRELIMINARY
FOR REVIEW
ONLY

24CZ10

ADJACENT LAND OWNERS TABLE:

ID	PIN	OWNER	SITE ADDRESS	LAND CLASS	ZONING
1	0721-33-1136	BUCKHORN PRESERVE HOMEOWNERS ASSC INC.	O BARONIAL ST	HOA	PUD-CZ
2	0721-34-5646	BUCKHORN PRESERVE HOMEOWNERS ASSC INC.	O BARONIAL ST	HOA	PUD-CZ
3	0721-33-6473	HOSHMAN, PRASHANT S/DHARAM ALUSHE, MAHESHWARI MALINATH	1181 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
4	0721-33-6480	BAKSH, PARTHATUL KAPADIA, PRACHI NIKHIL	1183 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
5	0721-34-1022	GADDAY, KISHORE REDDI PULASAM, SOUJANYA	1181 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
6	0721-34-1008	RYU, WON HEE SHIN, HEEWON	1121 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
7	0721-24-1110	LI, ZHILI, JIE	1123 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
8	0721-34-1114	EVANS, BRANDON L	1119 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
9	0721-34-1118	ERL, MALLORY MARSHBURN, WILLIAM GM	1115 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
10	0721-34-1212	PATEL, CHARM M PATEL, SANGITABEN M	1111 KINGS KNOT CT	RESIDENTIAL <10AC	PUD-CZ
11	0721-34-8441	ADKINS, CHRISTOPHER BRETT TRUSTEE ADKINS, CHRISTINA MILLER TRUSTEE	1860 BLUE JAY PT	RESIDENTIAL <10AC	PUD-CZ
12	0721-34-4542	BELLA CASA TOWNES HOMEOWNERS ASSOCIATION INC	O BLUE JAY PT	HOA	PUD-CZ
13	0721-44-2412	JU, IN HWAN LIM, SORI	1108 BLUE JAY PT	RESIDENTIAL <10AC	PUD-CZ
14	0721-44-3458	HUANG, RONG	1104 BLUE JAY PT	RESIDENTIAL <10AC	PUD-CZ
15	0721-44-3588	BELLA CASA TOWNES HOMEOWNERS ASSOCIATION INC	O CROWDERS RDGE LN	HOA	PUD-CZ
16	0721-44-4573	GROSS, MATTHEW J GAUSE, INDIA D	2334 MT ZION CHURCH RD	RESIDENTIAL <10AC	PUD-CZ
17	0721-44-4566	YU, FEI GONG, PENGYUAN	2332 MT ZION CHURCH RD	RESIDENTIAL <10AC	PUD-CZ
18	0721-44-4544	LAUTEMANN, ROBIN LAUTEMANN, CHRISTOPHER	2330 MT ZION CHURCH RD	RESIDENTIAL <10AC	PUD-CZ
19	0721-44-4631	ANDERSON, DAISY	2328 MT ZION CHURCH RD	RESIDENTIAL <10AC	PUD-CZ
20	0721-44-4614	BANA, VMAL ITR BANA, SONIA ITR	2326 MT ZION CHURCH RD	RESIDENTIAL <10AC	PUD-CZ
21	0721-44-5745	ZHANG, HUA SHI, LINGLING	2324 MT ZION CHURCH RD	RESIDENTIAL <10AC	PUD-CZ
22	0721-44-7127	BELLA CASA HOMEOWNERS ASSOCIATION INC	O HANWOODS BEACH TRL	HOA	PUD-CZ
23	0721-44-4911	KANDURI, RAJASOPALA A KANDURI, ANURADHA	1862 HANWOODS BEACH TRL	RESIDENTIAL <10AC	PUD-CZ
24	0721-34-0421	BELLA CASA HOMEOWNERS ASSOCIATION INC	O BALDHEAD BLAND DR	HOA	PUD-CZ
25	0721-43-9868	WINDY ROAD PROPERTIES LLC	O MT ZION CHURCH RD	VACANT	PUD-CZ
26	0721-44-4210	WINDY ROAD PROPERTIES LLC	O MT ZION CHURCH RD	VACANT	PUD-CZ
27	0721-43-6885	RICHARDSON, DOROTHY MAE HEIRS	2432 MT ZION CHURCH RD	RESIDENTIAL <10AC	RR-CZ
28	0721-43-1173	2105 RICHARDSON ROAD LLC	2105 RICHARDSON RD	RESIDENTIAL <10AC	RR-CZ



LINE	BEARING	DISTANCE	LINE	BEARING	DISTANCE
L1	S24°25'34"E	12.05	L24	N45°10'11"W	27.50
L2	S27°36'38"E	28.74	L25	N44°35'53"W	53.64
L3	S32°05'34"E	28.07	L26	N45°28'43"W	53.65
L4	S34°00'02"E	28.78	L27	N45°53'23"W	53.67
L5	S37°36'11"E	24.18	L28	N43°26'50"W	52.14
L6	S41°14'19"E	28.44	L29	N41°14'19"W	25.43
L8	S45°53'23"E	54.73	L31	N34°00'02"W	25.84
L9	S45°28'43"E	53.19	L32	N32°05'59"W	24.72
L10	S44°54'53"E	53.48	L33	N27°36'38"W	26.31
L11	S45°10'11"E	26.54	L34	N29°18'23"W	13.26
L12	S43°16'07"E	25.82	L35	N28°41'19"W	51.85
L13	S39°46'07"E	25.44	L36	N27°04'54"W	104.55
L14	S35°33'43"E	24.72	L37	N19°30'09"E	460.35
L15	S32°15'36"E	25.41	L38	N19°30'09"E	51.34
L16	S26°34'44"E	24.07	L39	N02°48'41"E	8.62
L17	S20°21'19"E	23.32	L40	N02°48'41"E	50.00
L18	S12°34'16"E	23.56	L41	N02°48'41"E	302.30
L19	S04°55'42"E	23.24	L42	N66°24'35"E	313.49
L20	S01°38'37"W	24.73	L43	N66°24'35"E	230.03
L21	N04°32'08"E	3.05	L44	N66°24'35"E	50.81
L22	N39°46'07"W	14.76	L45	N66°24'35"E	230.04
L23	N43°16'07"W	28.65			

SURVEY LINETYPES

---	PROPERTY LINE
---	P/L NOT SURVEYED
---	EASEMENT
---	ADJOINER
-X-X-	FENCE LINE
XSS	SANITARY SEWER
XST	STORM SEWER
UPL	UNDERGROUND POWER
XFO	FBER OPT C/COMMUN CATION
TS	TRAFFIC SIGNAL
XWL	WATERLINE
UT	UNDERGROUND TELEPHONE
	100 YR FLOODPLAIN
---	GUARD RAIL

SURVEY SYMBOL LEGEND


AC UNIT	SWAMP
BACK FLOW VALVE	TELEPHONE PEDESTAL
BOLLARD	TELEPHONE MANHOLE
CABLE PEDESTAL	TEMPORARY BENCHMARK
CABLE VAULT	TREE
CATCH BASIN	UNDERGROUND ELECTRIC
CLEAN OUT	UNDERGROUND POWER
COMMUN CATION BOX	UNDERGROUND TELEPHONE
CURB NLET	UTILITY POLE
ELECTRIC BOX	WATER LINE
ELECTRIC VAULT	WATER LINE HOTBOX
FIRE HYDRANT	WATER LINE MANHOLE
FENCE LINE	WATER METER
FBER OPT C	WATER VALVE
FBER OPT C VAULT	WELL
FLARED END SECTION	YARD NLET
GAS	
GAS VALVE	
GRATED NLET	
GUY WIRE	
REGGATION VALVE	
LIGHT POLE	
OVERHANG	
OVERHEAD ELECTRIC	
REINFORCED CONCRETE DRAINAGE PIPE	
SEWER MANHOLE	
STORM MANHOLE	
STORM JUNCTION BOX	
	PROPERTY CORNERS
	CONC MONUMENT SET
	CONC MONUMENT FOUND
	PROP CORNER FOUND
	COMPUTED POINT
	CONTROL CORNER
	IRON PIPE SET
	IRON PIPE FOUND
	HATCH LEGEND
	TRASH/DEBRIS
	EXISTING RIPRAP

GENERAL NOTES:

- BOUNDARY INFORMATION IS TAKEN FROM A SURVEY BY THIS OFFICE.
- SITE TOPOGRAPHIC INFORMATION IS TAKEN FROM A COMBINATION OF DATA FROM A SURVEY PERFORMED BY THIS OFFICE AND TOWN OF APEX LIDAR DATA.
- PLANIMETRIC AND TOPOGRAPHIC INFORMATION FOR AREAS OUTSIDE OF THIS SITE ARE TAKEN FROM TOWN OF APEX AND WAKE COUNTY GIS INFORMATION.
- THERE ARE NO FEMA DESIGNATED FLOOD ZONES LOCATED ON THIS PROPERTY PER FEMA MAP 3120072100K, DATED 7/14/22.
- FLOODPLAIN INFORMATION IS TAKEN FROM A FLOOD STUDY PREPARED BY PREST, CRAVEN & ASSOCIATES, NC, AND SUBMITTED WITH THE MASTER SUBDIVISION PLAN STORMWATER IMPACT ANALYSIS, SCHEMATIC CALCULATIONS AND FLOOD STUDY.
- EXISTING UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR RESPONSIBLE FOR LOCATION OF ALL EXISTING ABOVE AND BELOW GROUND UTILITY FIELD LOCATION PRIOR TO ANY CONSTRUCTION.
- NO NEW BUFFER IMPACTS SHALL OCCUR PRIOR TO APPROVAL FROM NCDEQ.
- WETLAND AND STREAM BUFFER LOCATIONS ARE SUBJECT TO FIELD VERIFICATION.
- STREAM BUFFER WHERE CONFIRMED BY THE TOWN OF APEX WITH BUFFER CALL 14-007.

REFERENCES:

- BM 2014 PG 2208
- BM 2011 PG 227
- BM 2015 PG 1492
- BM 2015 PG 1237
- BM 2014 PG 1352
- BM 2013 PG 1590



PRELIMINARY FOR REVIEW ONLY

LEGEND:

--- PROJECT BOUNDARY

↔ POTENTIAL ROADWAY ACCESS POINT

▬ POTENTIAL ROADWAY ALIGNMENT

▬ POTENTIAL 10' SIDEWALK ALIGNMENT

▬ POTENTIAL 5' SIDEWALK ALIGNMENT

⊗ SANITARY SEWER CONNECTION POINT

⊗ WATER MAIN CONNECTION POINT

--- POTENTIAL WATERMAIN LOCATION

GENERAL NOTES:

- BOUNDARY INFORMATION IS TAKEN FROM A SURVEY BY THE OFFICE.
- SITE TOPOGRAPHIC INFORMATION IS TAKEN FROM A COMBINATION OF DATA FROM A SURVEY PERFORMED BY THE OFFICE AND TOWN OF APEX LAND DATA.
- PLANIMETRIC AND TOPOGRAPHIC INFORMATION FOR AREAS OUTSIDE OF THIS SITE ARE TAKEN FROM TOWN OF APEX AND WAKE COUNTY GIS INFORMATION.
- THERE ARE NO FEMA DESIGNATED FLOOD ZONES LOCATED ON THIS PROPERTY PER FEMA MAP 3720072100K, DATED 7/19/22.
- FLOODPLAIN INFORMATION IS TAKEN FROM A FLOOD STUDY PREPARED BY PREST, CRAVEN & ASSOCIATES, INC. AND SUBMITTED WITH THE MASTER SUBDIVISION PLAN STORMWATER IMPACT ANALYSIS, SC-1 DESIGN CALCULATIONS AND FLOOD STUDY.
- EXISTING UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR RESPONSIBLE FOR LOCATION OF ALL EXISTING ABOVE AND BELOW GROUND UTILITY FIELD LOCATION PRIOR TO ANY CONSTRUCTION.
- NO NEW BUFFER IMPACTS SHALL OCCUR PRIOR TO APPROVAL FROM NCEC.
- WETLAND AND STREAM BUFFER LOCATIONS ARE SUBJECT TO FIELD VERIFICATION.
- FINAL LOCATION OF DEVELOPMENT ACCESS AND STREET SUBSTATION LOCATIONS TO BE COORDINATED AT MASTER SUBDIVISION PLAN DESIGN AND APPROVAL.
- FINAL LOCATION OF OPEN SPACE, RESOURCE CONSERVATION AREAS, AND PLAY LAWN TO BE COORDINATED AT MASTER SUBDIVISION PLAN DESIGN AND APPROVAL.
- ALL PLAN SHEETS ARE PROVIDED FOR ILLUSTRATIVE PURPOSES ONLY. FINAL DESIGN TO BE COORDINATED AT MASTER SUBDIVISION PLAN DESIGN AND APPROVAL.
- REFER TO PD TEXT DOCUMENTS FOR A DETAILED LISTING OF ALLOWABLE USES, DESIGN INFORMATION STANDARDS, AND ZONING CONDITIONS.
- ALL CONSTRUCTION AND MATERIALS TO BE IN STRICT ACCORDANCE WITH THE ACCEPTED POLICIES OF THE TOWN OF APEX, AND UNLESS SPECIFIED, DEFERS TO THE NC DEPT. OF TRANSPORTATION (NCDOT) STANDARDS, SPECIFICATION, AND DETAILS.
- THIS PROJECT SHALL UTILIZE FULL TOWN SERVICES - WATER, SEWER, AND ELECTRICITY.
- THIS PROJECT SHALL NOT UTILIZE PRIVATE SEWAGE DISPOSAL (SEPTIC SYSTEM).
- NO SITE DEVELOPMENT ACTIVITY INCLUDING, BUT NOT LIMITED TO, TESTING, CLEARING, INSTALLATION OF SEE MEASURES, OR GRADING SHALL OCCUR UNTIL REQUIRED TREE PROTECTION FENCING HAS BEEN INSTALLED AND INSPECTED. A TREE PROTECTION FENCING INSTALLATION PERMIT MAY BE OBTAINED AT THE PLANNING DEPARTMENT.
- TREE PROTECTION FENCING MUST BE PLACED:
 - ONE FOOT AWAY FROM ANY SAVED TREE FOR EACH INCH OF DIAMETER AT BREAST HEIGHT.
 - ALONG THE OUTSIDE LINE OF THE 100-YEAR FLOODPLAIN AND THE OUTSIDE EDGE OF ANY RIPARIAN BUFFER; AND
 - AT LEAST 10 FEET AWAY FROM ANY OTHER DESIGNATED RCA SUCH AS, BUT NOT LIMITED TO, HISTORIC BUILDINGS AND STRUCTURES, WETLANDS, AND PONDS.
- ADDITIONAL TREE PROTECTION FENCING MAY BE REQUIRED IN OTHER LOCATIONS CLOSE TO CONSTRUCTION ACTIVITY WHERE IT IS DEEMED NECESSARY BY THE ZONING ENFORCEMENT OFFICER. SUCH AREAS MAY INCLUDE, BUT ARE NOT LIMITED TO, COMMON PROPERTY LINES OR NEAR PUBLIC AREAS (SIDEWALKS, ETC.).

UTILITY NOTES:

- ALL DEVELOPMENT / REZONING PLANS MUST MEET THE NEW / CURRENT TOWN OF APEX MASTER WATER AND SEWER PLANS. REZONING OR NEW SITE DEVELOPMENT PLANS DO NOT GUARANTEE THE UTILITY LOCATION, ALIGNMENTS, AND DESIGN FOR TOWN APPROVAL. UTILITY DESIGNS WILL BE SUBJECT TO CHANGE UNTIL TOWN APPROVAL. DESIGNS ARE APPROVED.
- THIS PLAN SET WILL BE UNDER THE NEW 2024 SPEC (EFFECTIVE DATE: JUNE 11, 2024). SINCE THIS PLAN WAS NOT IN CONFORMANCE BEFORE THE EFFECTIVE DATE.
- ANY REQUESTED UTILITY EXCEPTION MUST BE FILED ON THE EXCEPTION FORM THAT IS LOCATED IN THE CD PROJECT PACKET. NO EXCEPTIONS WILL BE APPROVED UNLESS THIS FORM(S) IS COMPLETED AND SIGNED BY TOWN ADMINISTRATION.
- IN PREPARING ENGINEERING DESIGN PLANS, ALL ELEVATIONS SHALL BE TIED TO NC GRID SYSTEM AND THE BENCHMARK SHALL BE DESCRIBED ON THE PLANS. A FIELD SURVEY OF ALL WATERWAYS AND WATERBODIES WITHIN PROJECT AREA MUST BE PERFORMED, INCLUDING BUT NOT LIMITED TO: CREEKS, STREAMS, RIVERS, LAKES, PONDS, TRENCHES, AND CULVERTS. SURVEY MUST INCLUDE ADEQUATE POINTS TO ACCURATELY REPRESENT THE CROSS SECTION OF THE WATERWAY/WATERBODY, I.E. TOP OF BANK, TOE, CENTERLINE, ETC. 100-2 TOWN OF APEX STANDARD SPECIFICATIONS AND DETAILS: ADOPTED FEBRUARY 23, 2021

HATCH LEGEND

Single Family Home Area

Townhome Area

Resource Conservation Area

Perimeter Buffer Area

Stormwater Control Measure Area

ASHBURN

PLANNED UNIT DEVELOPMENT REZONING PLANS

APEX, NC

SCALE: 1"=50'

DATE: JUNE 3, 2024

PROJECT NUMBER: 2022-008-001

CLIENT: ENTITLEMENT PRESERVATION GROUP

PLAN TYPE: PRELIMINARY

PRELIMINARY LAYOUT AND UTILITY PLAN

OWN COMMENTS	2.7.2023
OWN COMMENTS	3.1.2023
OWN COMMENTS	4.4.2023
OWN COMMENTS	5.2.2023
OWN COMMENTS	6.9.2023

RELEASED FOR CONSTRUCTION (ON DATE) (SEE COVER) NO CHANGES

PRIEST, CRAVEN & ASSOCIATES, INC.

LAND USE CONSULTANTS / PLANNERS / LANDSCAPE DESIGNERS / SURVEYORS / ENGINEERS

3803 - B Computer Drive, Suite 104 Raleigh, N.C. 27609 / Phone 919 / 781-0300 / Fax 919 / 782-1288 / Email PCA@PriestCraven.com / Firm #: C-0488

SHEET #

PD2.0