



Quotation No. EL-1432-25
September 4, 2025

City of Arkansas City, KS Waste Water
Attn: Spencer
1701 M St.
Arkansas City, KS 67005
P: 620-506-8205

Subject: Cage Manlift Repair – Ark City, KS Waste water treatment plant Phase 2

Dear Spencer:

After performing a service report on your manlift, we recommend the following repairs, based on the current ASME standards. At your discretion, you may do all, some or none of the recommended repairs. BarnesCo Inc. is completely insured and guarantees all of our work and equipment for the first year of operation, if all completed work is given the proper maintenance by your qualified personnel. If you have any questions about this quote, please give us a call at 800-821-7486.

SCOPE OF WORK REQUIRED:

- * Replace (2) hoistway swing door assemblies
- * Replace existing controller with a constant pressure controller – N4/12
- * Rewire hoistway – wire, boxes, conduit, hall push button station, car station
- * Add cams as needed

COST OF MATERIALS REQUIRED:

2 – hoistway swing door assemblies @ \$3,000.00 each.....	6,000.00
1 – N4/12 constant pressure controller.....	12,000.00
1 – rewire hoistway – wire, conduit, (2) hall push buttons, car station.....	8,000.00
T & M – add cams as needed.....	T & M
TOTAL COST OF MATERIALS REQUIRED:.....\$	26,000.00
TOTAL COST OF INSTALLATION:	<u>5,000.00</u>
TOTAL COST OF MATERIALS AND INSTALLATION:\$	31,000.00

TERMS:

MATERIALS: Due on Receipt of Invoice

INSTALLATION: Due on Receipt of Invoice

NOTES:

- **There can be no wires in the stack other than elevator control wiring for the lift.**
- **Fire Service Requirements, mandated by the Authority having Jurisdiction, by others.**
- ** Must follow current ASME A17.1 Section 5.7**
- **Quote does not include seismic/specialty equipment. If needed, please notify us.**
- **After 30 days, approved quotes may have to be adjusted due to the increase in
The price of materials and fuel costs.**
- **Unforeseen tariffs surcharged as needed.**

ITEMS FURNISHED BY OTHERS IF NEEDED:

- *Manlift hoistway, machine room and pit area.**
- *480V 3 Phase 30 AMP disconnect in the machine room**

TAXES, FREIGHT & PERMITS BY OTHERS
ALLOW 10-12 WEEKS FOR DELIVERY OF MATERIALS
AFTER RECEIPT OF SIGNED CONTRACT

Spencer:

If you have any questions, please give us a call at 800-821-7486. If you wish to order these repairs, please sign, date and add your purchase order number below and fax a copy to us at 620-442-2008. If your company is tax exempt, please fax us a copy of the exempt certificate. Thank you for your consideration.

Very truly yours,
BarnesCo Inc.

Chase Demaree

SIGNATURE _____ DATE _____

PURCHASE ORDER NUMBER _____