


Bid Opening Arkansas City CDBG Housing

Contractor:	NWOA	Arambula				
1422 W Oklahoma:	26,050	33,725				
Rental						
1507 N 10th:	21,000	21,276	+			
1417 N 10th:	25,000	33,016	+			
only NWFA						
1209 W Oklahoma:	40,000	57,498	+			
1328 W Oklahoma:	20,600	20,123	+			

(620) 307-6183

Joanie Kormos
1209 W. Oklahoma
Arkansas City

Description	Estimated Cost	Estimated KWAP Cost
Exterior: LSWP Install vinyl siding over deteriorated siding. Wrap all fascia, soffit, and trim including porch ceilings. Paint anything that cant be wrapped.	9000	
Exterior: Replace existing deteriorated roof with new 30 year laminate heritage style roof with all required accessories. Replace sheeting as necessary.	9500	7500
Exterior: LSWP Install a new solid core self storing storm door to front and back door.	1100	
Exterior: Install new guttering with downspouts and concrete splash blocks.	1800	
Exterior: Build a new cellar door. Prep, Prime and paint.	1000	1000
Exterior: LSWP Replace deteriorated wood windows on the house with single hung double pane vinyl replacements.	9000	
Electrical: Raise the mast head. Secure any loose fixtures or recepts. Make sure all recepts, lights and switches are working as designed.(open ground in dining room) All Recepts within six feet of water source must have GFCI protection. Install smoke detectors in accordance with local codes. Eliminate any wiring hazards.	2500	
Radon: Install a radon mitigation system	2500	
Total of Part 1	36,400	
	7500	
Part 2 Lead Activities	1000	= 27,900
Costs for using lead safe work practices.	1800	
Cost for preparing for clearance.	1800	
Total of Part 2	\$3600 -	
Total of part 1 and 2	\$40,000 -	
New Windows For America, LLC 3949 N. Bridgeport Cir. Wichita, KS 67219		
Company		
Contact	HEATH MARX	
Signature		
Date	02-22-23	

KS Grant

KWAP

Client owes

\$ 2900