



smith construction
License #67 • Est. 1967 co., inc.

4620 W. Esthner • P.O. Box 13213 • Wichita, KS 67213
(316) 942-7989 • Fax (316) 942-4881
www.smithconstco.com

PROPOSAL

PROPOSAL SUBMITTED TO: Tony Tapia
Company: City of Arkansas City, KS

PHONE: (620) 441-3766 DATE: June 14, 2021
FAX: (N/A)

STREET
1407 w. Madison

JOB NAME
Wall panel replacement

CITY, STATE AND ZIP CODE
Arkansas City, KS, 67005

JOB LOCATION
1407 Madison, Arkansas City, KS

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from specifications below involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Worker's compensation insurance.

Authorized
Signature _____

Note: This proposal may be
Withdrawn by us if not accepted within **30** days.

We propose hereby to furnish material and labor – complete in accordance with specifications below, for the sum of: **\$17,202.00**

SEVENTEEN THOUSAND TWO HUNDRED TWO AND NO/100 DOLLARS. TAX EXEMPT.

Payment to be made as follows:

Due 10 days net.

We hereby submit specifications and an estimate:

Provide and install the following:
44 – PBR 26 gauge 14' x 3' width metal panels. (Desert Sand)
4 – PBR 26 gauge 2' x 3' width metal panels. Desert Sand)
16 – 12' 26 gauge Jamb trims. (Polar White)
2 – 14' 26 gauge Header trims. (Polar White)
5 – 12'-2" 26 gauge Header trims. (Polar White)
1 – 14' 26 gauge Downspout with kick out. (Desert Sand)
2 – 20' 2" x 4" 14 gauge base angle. (Galvanized)
1000 – 1 1/4" SDS. (Desert Sand)
750 – 7/8" SDS lap. (Desert Sand)
200 – 1/8" pop rivets. (Desert Sand)

The cost for material only is **\$5,958.00. Tax exempt.**

Note: If the insulation crumbles as the panels are removed, the cost to add new 4" VRR plus insulation would be \$3,672.00. Tax exempt.

Acceptance of Proposal – The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance _____ Signature _____

City of Arkansas City, KS

Maintenance Building 1407 W. Madison

Exterior metal wall panel installation

SCOPE OF WORK

GENERAL CONDITIONS

Building Permit Fees – By the City.

Temporary Facilities – Smith Construction Co., Inc.

Builders Risk Insurance - Smith Construction Co., Inc.

Final Clean Up – New construction debris created by Smith Construction only.

C and D Dumpster or haul debris to Cowley County Land Fill.

Supervision - Smith Construction Co., Inc.

Mobilize Equipment - Smith Construction Co., Inc.

Temporary Electricity – by City.

METAL BUILDING

Remove 140 lf of exist gutter including downspouts and set aside for Reinstallation.

Remove 44 wall panels that are 14' in height.

Remove 20 lf +/- of 2" x 4" base angle.

Remove the metal framed opening trims on all of the east overhead doors, one walk door on the east side and one overhead door on the west side.

NOTE: Only two consecutive will be removed at one time so that the existing insulation will stay in place.

NOTE: All removed wall panels and debris to be taken to Cowley County Landfill. If any employee would like the wall panels it must be cleared with Tony Tapia first.

Install up to 40 lf of new 2" x 4" galvanized base angle using 3/8" x 3 1/2" wedge Anchors.

Install 44 PBR style 26 gauge wall panels from sheet ledge to 14' eave and 4 PBR style wall panels over overhead doors.

Install 26 gauge J-trims at framed openings that were removed and one new downspout.

Note: All new wall panels to be Desert Sand in color and all new trims to be Polar White.

Note: The Owner is responsible for the electrical removal and reinstallation of the existing conduits, light fixtures, junction boxes and receptacles etc.

Note: The Owner shall remove all obstacles that would hinder Smith Construction Co., Inc. from completing job as quoted.

All materials and labor are tax exempt.