

WILSON PARK
 Summit St. & Birch St.
 Fall 2006

<u>LOCATION / DEFICIENCY</u>	<u>ADAAG REQUIREMENT(S)</u>	<u>PRIORITY</u> L = Low M = Medium H = High	<u>Barrier Removal Target Date & Notes</u>	<u>RECOMMENDATIONS</u>
<p><u>PARK FEATURES</u></p> <p>Parking:</p> <ul style="list-style-type: none"> - There is an existing parking area in the alley but has no designated parking. <p>The big shelter has an amphitheater/stage that is not accessible (<u>picture</u>).</p> <p>Drinking fountain has 22" knee clearance (<u>picture</u>).</p> <p>Playground:</p> <ul style="list-style-type: none"> - There is no accessible route to playground (<u>picture</u>). - Surface and equipment lack accessible features. <p>Tennis Courts:</p> <ul style="list-style-type: none"> - Route to entrances is 32" wide (<u>picture</u>). <p>Restrooms:</p> <ul style="list-style-type: none"> - Signage is mounted too high and is not in an accessible format (<u>picture</u>). 	<p>Minimum of 1 spaces designated as being "van accessible" with adjacent access aisle at least 96" wide (4.1.2(5)(b)).</p> <p>Changes in level greater than $\frac{1}{2}$" shall be accomplished by means of a ramp (4.5.2)</p> <p>27" minimum (4.15.5).</p> <p>At least one accessible route shall connect accessible buildings, facilities, elements, and spaces that are on the same site (4.3.2).</p> <p>See "<u>Best Practice</u>" guidance for Parks in the Transition Plan.</p> <p>The minimum clear width of an accessible route shall be 36" (4.3.3).</p> <p>Signs shall be installed on the wall adjacent to the latch side of the door. Where there is no wall space to the latch side of the door,</p>	<p>H</p> <p>L</p> <p>L+</p> <p>L+</p> <p>L</p> <p>M-</p> <p>H</p>		



The shelter's amphitheater/stage is not accessible.



This drinking fountain does not have adequate knee clearance.



The playgrounds are not on an accessible route and lack accessible components.



These routes to tennis court entrances are too narrow.



This ramp at the men's restroom is too steep, lacks edge protection, handrails and slopes to the doorway. The sign is mounted too high and is not in an accessible format.



There is enough wall space in the men's restroom to widen the toilet stall. The urinal rim is too high and the lavatory has round faucet controls and exposed drain pipes.



Toilet stalls are too narrow and have improper grab placements and lack bars on rear walls.



The women's restroom ramp has an excessive threshold.



This ramp at the women's restroom is too steep, lacks adequate handrails and edge protection.



The route to the lavatory in the women's restroom is too narrow.