

**AUGUSTA ENGINEERING DEPARTMENT
MCNUTT RD IMPROVEMENTS 2023**

SECTION 3: BID PROPOSAL

Date: 9/6/2024

Gentlemen:

In compliance with your Invitation for bids dated July 18, 2024, the undersigned hereby proposed to furnish all labor, equipment, and materials, and to perform all work for the installation of roadway improvements, and appurtenances referred to herein as:

**AUGUSTA ENGINEERING DEPARTMENT
MCNUTT RD IMPROVEMENTS PROJECT**

In strict accordance with the Contract Documents and in consideration of the amounts shown on the Bid Schedule attached hereto and totaling:

Five Million One Hundred Fifty-Two Thousand Nine Hundred Eighty-Eight Dollars and 90/100 Cents **DOLLARS**

(\$ 5,152,988.90)

The undersigned hereby agrees that, upon written acceptance of this bid, he will within 10 days of receipt of such notice execute a formal contract agreement with the OWNER, and that he will provide the bond or guarantees required by the Contract Documents.

The undersigned hereby agrees that, if awarded the contract, he will commence the work within 10 calendar days after the date of written notice to proceed, and that he will complete all work within 360 calendar days.

The undersigned acknowledges receipt of the following addenda:

Addendum Number:	Addendum Date:
<u>1</u>	<u>8/23/2024</u>
<u>2</u>	<u>8/28/2024</u>



Respectfully submitted:

Reeves Construction Company
(Name of the Firm)

1 APAC Industrial Way Augusta, GA 30907
(Business Address)

By: [Signature]

Title: Region Manager/Assistant Secretary

**AUGUSTA ENGINEERING DEPARTMENT
MCNUTT RD IMPROVEMENTS 2023**

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	PRICE
ROAD ITEMS					
001-1000	FORCE ACCOUNT	LS	1	\$300,000	\$300,000
150-1000	TRAFFIC CONTROL	LS	1	\$115,400.00	\$115,400.00
210-0100	GRADING COMPLETE	LS	1	\$1,770,000.00	\$1,770,000.00
ASPHALT PAVING (INCL DRIVEWAYS)					
310-1101	GR AGGR BASE CRS, INCL MATL (6")	TN	12326	\$50.00	\$616,300.00
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME (2")	TN	3496	\$110.00	\$384,560.00
402-3100	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 2, INCL BITUM MATL & H LIME (1.5")	TN	2932	\$130.00	\$381,160.00
412-1000	TACK COAT	TN	1613	\$5.00	\$8,065.00
CONCRETE PAVING DRIVEWAYS					
441-0016	DRIVEWAY CONCRETE 6 IN THK	SY	775	\$90.00	\$69,750.00
STORM SYSTEM					
550-4218	FLARED END SECTION 18 IN, STORM DRAIN	EA	8	\$1,450.00	\$11,600.00
550-4230	FLARED END SECTION 30 IN, STORM DRAIN	EA	4	\$1,850.00	\$7,400.00
550-4236	FLARED END SECTION 36 IN, STORM DRAIN	EA	2	\$2,500.00	\$5,000.00
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	196	\$97.00	\$19,012.00
550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	LF	104	\$155.00	\$16,120.00
550-1360	STORM DRAIN PIPE, 36 IN, H 1-10	LF	70	\$165.00	\$11,550.00
550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	2060	\$68.00	\$140,080.00
550-2240	SIDE DRAIN PIPE, 24 IN, H 1-10	LF	72	\$125.00	\$9,000.00
550-3618	SAFTY END SECTION, 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	114	\$1,160.00	\$132,240.00
550-3624	SAFTY END SECTION, 24 IN, SIDE DRAIN, 6:1 SLOPE	EA	4	\$1,625.00	\$6,500.00
GUARDRAIL					
641-1200	GUARDRAIL, TP W	LF	1940	\$22.10	\$42,874.00
641-5001	GUARDRAIL ANCHORAGE, TP1	EA	6	\$1,300.00	\$7,800.00
641-5015	GUARDRAIL TERMINAL, TP 12A, 31 IN, TANGENT, ENERGY ABSORBING	EA	6	\$3,500.00	\$21,000.00
643-4000	WOVEN WIRE FENCE	LF	1000	\$20.00	\$20,000.00
643-1133	CH LK FENCE, ZC COAT, 4 FT, 11 GA	LF	250	\$20.00	\$5,000.00
643-8040	GATE, GALVANIZED METAL - 6-FT	EA	4	\$1,000.00	\$4,000.00

**AUGUSTA ENGINEERING DEPARTMENT
MCNUTT RD IMPROVEMENTS 2023**

EROSION CONTROL ITEMS					
163-0300	CONSTRUCTION EXIT	EA	2	\$2,800.00	\$5,600.00
163-0232	TEMPORARY GRASSING	AC	23	\$915.00	\$21,045.00
700-6910	PERMANENT GRASSING	AC	23	\$1,225.00	\$28,175.00
163-0240	MULCH	TN	138	\$325.00	\$44,850.00
163-0501	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 1	EA	5	\$1,600.00	\$8,000.00
163-0527	CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	EA	235	\$650.00	\$152,750.00
163-0528	CONSTRUCT AND REMOVE FABRIC CHECK DAMS, TYPE C SILT FENCE	EA	107	\$200.00	\$21,400.00
171-0030	TEMPORY SILT FENCE, TYPE C	LF	26444	\$3.55	\$93,876.20
603-2181	STONE DUMPED RIP RAP, TP 3, 18 IN	SY	330	\$136.50	\$45,045.00
165-0030	MAINTENACE OF TEMPORARY SILT FENCE, TYPE C	LF	26444	\$2.10	\$55,532.40
165-0041	MAINTENACE OF CHECK DAMS - ALL TYPES	EA	342	\$65.00	\$22,230.00
165-0085	MAINTENACE OF SILT CONTROL GATE, TP 1	EA	5	\$290.00	\$1,450.00
603-7000	PLASTIC FILER FABRIC	SY	330	\$3.55	\$1,171.50
700-7000	AGRIUCULTUAL LIME	TN	23	\$325.00	\$7,475.00
700-8000	FERTILIZER MIXED GRADE	TN	14	\$810.00	\$11,340.00
711-0100	TURF REINFORCING MATTING, TP 1	SY	6000	\$4.80	\$28,800.00
SIGNING AND MARKING ITEMS					
663-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	23582	\$0.45	\$10,611.90
663-1502	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	23582	\$0.45	\$10,611.90
652-5701	24 IN STOP BAR	LF	72	\$15.00	\$1,080.00
636-1014	HIGHWAY SIGNS,TP 1 MATL, REFL SHEETING, TP 1	SF	153	\$30.00	\$4,590.00
636-2010	GALV STEEL POST, TP1	LF	102	\$16.00	\$1,632.00
636-1033	WY SIGNS, TP 1 MATL, REFL SHT TP. 9	SF	7	\$28.00	\$196.00
652-1036	HWY SIGNS, TP 2 MATL, REFL SHT TP. 11	SF	118	\$32.00	\$3,776.00
WATER MAIN					
W-1	6" DIA., PVC, C-900, STANDARD PIPE	LF	3000	\$31.00	\$93,000.00
W-2	6" DIA., PVC, C-900, RESTRAINED PIPE	LF	1800	\$35.00	\$63,000.00
W-4A	6" 45 DEGREE BEND, DIP MECHANICAL JOINT	EA	40	\$345.00	\$13,800.00
W-4B	6" 22.5 DEGREE BEND, DIP MECHANICAL JOINT	EA	15	\$325.00	\$4,875.00

**AUGUSTA ENGINEERING DEPARTMENT
MCNUTT RD IMPROVEMENTS 2023**

W-4C	6" 11.25 DEGREE BEND, DIP MECHANICAL JOINT	EA	15	\$325.00	\$4,875.00
W-4D	6" END CAP, DIP MECHANICAL JOINT	EA	18	\$240.00	\$4,320.00
W-10	6" X 6" TAPPING SLEEVE AND VALVE, INSTALLED	EA	9	\$7,000.00	\$63,000.00
W-13	1" NEW WATER SERVICE AND RECONNECT EXISTING METER	EA	69	\$2,330.00	\$160,770.00
W-16	WATER MAIN TIE-IN	EA	9	\$3,000.00	\$27,000.00
W-17	MISC 3000 PSI CONCRETE	CY	10	\$710.00	\$7,100.00
M-4	SELECT BACKFILL, GDOT TYPE I, CLASS I & II (SAND/CLAY) – MEASURED IN-PLACE VOLUME	CY	500	\$38.00	\$19,000.00
P-7	DRIVEWAY REPLACEMENT	SY	100	\$66.00	\$6,600.00
GRAND TOTAL					\$5,152,988.90

GRAND TOTAL (IN WORDS):

Five Million One Hundred Fifty-Two Thousand Nine Hundred Eighty-Eight Dollars and 90/100 Cents -----

----- **DOLLARS**

***GRADING COMPLETE:** *Shall include any work without a specific pay item such as:* removal and disposal of all miscellaneous roadway items, utility items, and drainage items (i.e., demolition items). Additional items shall be included in the item of grading complete, unless otherwise established as separate contract items, including, but not limited to: removal/demolition of pavement, removal/demolition of concrete sidewalks and driveways / valley gutter, removal of curb and gutter, removal of abandoned drainage structures, removal of street signs, and any other miscellaneous removal items whether shown on the plans or not. The items of grading complete shall also include other miscellaneous items of construction not otherwise shown as a separate pay item such as fine grading, general clearing, cut and fill, constructing shoulder and subgrade, finish grading, construction layout, the hauling and disposal of undesirable or surplus materials, removing and/or resetting mailboxes, removing and/or resetting gates and fences, removing and/or resetting irrigation sprinkler heads, mobilization and demobilization, required bonds and insurance etc. Remove/reconnect water services, reconnect sanitary services, remove/reset signs (type varies), remove/reset water sprinkler systems(complete), remove/reset water valves (size varies), remove/reset yard lamps (type varies) shall be included in grading complete where no separate bid item is established.

****LS (LUMP SUM)** – For all Lump Sum items, attach itemized break of lump sum amount on separate sheet

Breakdown of Grading Complete/Traffic Control

McNut Road

GRADING COMPLETE	1 LS	\$ 1,770,000.00	\$ 1,770,000.00
Mobilization/Gen Conditions	1 LS	\$ 175,000.00	\$ 175,000.00
Removals and Demo	1 LS	\$ 250,000.00	\$ 250,000.00
Earthwork	1 LS	\$ 745,000.00	\$ 745,000.00
Subgrade Prep/Finish and Dress	1 LS	\$ 250,000.00	\$ 250,000.00
Misc/Closeout	1 LS	\$ 350,000.00	\$ 350,000.00
 TRAFFIC CONTROL	 1 LS	 \$ 115,400.00	 \$ 115,400.00
Advanced Warning Signs	1 LS	\$ 25,000.00	\$ 25,000.00
Flagging/Misc Traf Cntrl	1 LS	\$ 75,000.00	\$ 75,000.00
Temp Striping	1 LS	\$ 15,400.00	\$ 15,400.00