

ACE ALLEY CONSTRUCTION WORK WRITE UP

CAPITALRISE, LLC

PAY ITEM	DESCRIPTION	UNITS	QTY	UNIT PRICE	AMOUNT
210 - 0100	GRADING COMPLETE (TO INCLUDE THE FOLLOWING MOBILIZATION, CO, & TESTING) (SUB – BASE TO COMPACTED TO 95% STANDARD PROCTOR) SURVEYING TO INCLUDE(CONSTRUCTION STAKING, LOT & HOUSE STAKING, ASBUILT AND RECORDED PLAT OF ACE ALLEY	LS	1		14,900
310-5060	GABC,6 IN, INCL. MATL. (UNDER CURB/ GUTTER & ROADWAY) (TO COMPACTOR TO 100% STANDARD PROCTOR)	SY	760		23,499.20
441-0016	ROADWAY CONCRETE, 6 IN TK (3,500 PSI)	CY	110		48,400
441-6012	CONC. CURB & GUTTER, ROLL CURB	LF	500		22,000
700-6910	PERMANENT GRASSING (TO INCLUDE DRESS UP & BACKFILL C & G)	LS	1		2,860
	H/C RAMPS	EA	2		15,800
	SILT FENCE	LF	300		2,001
	FORCE ACCOUNT		1		5,000
	MANAGEMENT OF PROJECT TO INCLUDE RECORDS AND INSPECTIONS		1		15,539.80
	Total				\$150,000

CAPITALRISE, LLC
 2924 AYLESBURY Dr.
 AUGUSTA, GA, 30909

678-735-0781

capitalrisebuilders@gmail.com