



April 9, 2025

452 Walker Street
Suite 110
Augusta, GA 30901
Attn: Peter Adeleke

RE: City of Augusta
ERS Job: 50422-25
Geogrid Seg II

Dear Mr Adeleke,

Please see the following pricing for the Geogrid on Broad St. This pricing was requested by the COA due to the current site conditions in the full depth section between 15th and St Sebastian. Attached separately is additional information regarding the Geogrid specifications.

Description	Quantity	Units	Unit Price	Amount
Geogrid	5,515	SY	\$8.00	\$44,120.00
			TOTAL	\$44,120.00

Attachments/Additional Clarifications

1. Spec Sheet
2. 5,515 SY would cover entire area between 15th and St Sebastian
3. Pricing can be used in the next full depth section if found to be required due to poor soil conditions.

If any additional information is needed, please let me know.

A handwritten signature in black ink, appearing to read 'RB' or 'Banks', is written above the typed name.

Sincerely,
Richard Banks
Project Manager
E.R. Snell Contractors, INC



April 25, 2025

452 Walker Street
Suite 110
Augusta, GA 30901
Attn: Peter Adeleke

RE: City of Augusta
ERS Job: 50422-25
Full Depth Subgrade Undercut

Dear Mr Adeleke,

Per the request of the COA and Atlas, please see the following pricing for the undercuts per recommendation from Atlas. This pricing is to be used in the full depth section of the project between 15th and St Sebastian. If this situation were to arise in the next section, this pricing is to be used for that issue as well. Please see the following:

Biditem	GDOT Code	Description	Quantity	Unit	Bid Price	Bid Total
5	210-0250	UNDERCUT EXCAVATION - UP TO 750 CY AT \$18.00	750	CY	\$18.00	\$13,500.00
10	210-0250	UNDERCUT EXCAVATION - OVER 750 CY	1,506	CY	\$47.00	\$70,782.00
15	208-0200	6" ROCK EMBANKMENT	967	CY	\$118.50	\$114,589.50
20	207-0203	8" TP II BACKFILL	1,290	CY	\$114.00	\$147,060.00
25	603-7000	FILTER FABRIC	11,582	SY	\$8.80	\$101,921.60
					Total =	\$447,853.10

If any additional information is needed, please let me know.

Sincerely,
Richard Banks
Project Manager
E.R. Snell Contractors, INC



May 12, 2025

452 Walker Street
Suite 110
Augusta, GA 30901
Attn: Peter Adeleke

RE: City of Augusta
ERS Job: 50422-25 Full Depth Section
Full Depth 15th-13th Water & Sewer

Dear Mr Adeleke,

Per the request of the COA, please find the following narrative as a request for compensation on the anticipated Water & Sewer items between 15th and 13th St (Full Depth Section). Currently, our subcontractor has already began performing work in order to keep the project from not entirely being shut down. Due to what information has been received and current on-site conditions, ERS is estimating **\$400,000.00** be added to this section of the project for Water & Sewer items. While ERS does not anticipate this amount being fully utilized, this should cover enough of the work anticipated and additional work that will be required once construction crosses 13th St and allow the subcontractor to continue working while additional funding is discussed with the COA for the next areas of construction if needed. If any additional information is needed, please reach out via cell or email.

A handwritten signature in black ink, appearing to be "RB" followed by a flourish.

Sincerely,
Richard Banks
Project Manager
E.R. Snell Contractors, INC