

ACE ALLEY CONSTRUCTION WORK WRITE UP

CAPITALRISE, LLC

| PAY ITEM | DESCRIPTION | UNITS | QTY | UNIT PRICE | AMOUNT |
|------------|--|-------|-----|------------|------------------|
| 210 - 0100 | GRADING COMPLETE (TO INCLUDE THE FOLLOWING MOBILIZATION, CO, & TESTING) (SUB – BASE TO COMPACTED TO 95% STANDARD PROCTOR) SURVEYING TO INCLUDE(CONSTRUCTION STAKING, LOT & HOUSE STAKING, ASBUILT AND RECORDED PLAT OF ACE ALLEY | LS | 1 | | 14,900 |
| 310-5060 | GABC,6 IN, INCL. MATL. (UNDER CURB/ GUTTER & ROADWAY) (TO COMPACTOR TO 100% STANDARD PROCTOR) | SY | 760 | | 23,499.20 |
| 441-0016 | ROADWAY CONCRETE, 6 IN TK (3,500 PSI) | CY | 110 | | 48,400 |
| 441-6012 | CONC. CURB & GUTTER, ROLL CURB | LF | 500 | | 22,000 |
| 700-6910 | PERMANENT GRASSING (TO INCLUDE DRESS UP & BACKFILL C & G) | LS | 1 | | 2,860 |
| | H/C RAMPS | EA | 2 | | 15,800 |
| | SILT FENCE | LF | 300 | | 2,001 |
| | FORCE ACCOUNT | | 1 | | 5,000 |
| | MANAGEMENT OF PROJECT TO INCLUDE RECORDS AND INSPECTIONS | | 1 | | 15,539.80 |
| | Total | | | | \$150,000 |

CAPITALRISE, LLC
 2924 AYLESBURY Dr.
 AUGUSTA, GA, 30909

678-735-0781

capitalrisebuilders@gmail.com