

## 2023 LMIG Bids

1. Pittman Construction Company, Conyers, Ga: \$1,115,721.35
2. Reeves Construction Company, Macon, Ga: \$1,183,566.00

**Russel Drive (FROM Nth Columbia TO Latta Terrace): Length 1003 ft, Width 20 ft (2,229 sy)**

TREATMENT:	ITEM #:	QUANTITIY:	UNITS:	NOTES:
Overlay	402-3100	245	TONS	12.5 mm recycled asphalt superpave @ 220 lbs/sy
Patching	402-1802	75	TONS	19mm Recycled asphalt incl bitum matl and H lime 4" Depth
Bitum Tack Coat	413-1000	89	GAL	0.04 Gal/SY
Striping	652-2501	0.38	L. MILE	Solid Traffic Edge Stripe, 5 in White
Striping	652-2502	0.38	L. MILE	Solid Traffic CL Stripe, 5 in Yellow
Striping	653-1704	10	L. FOOT	Thermoplastic Solid Traffic Stripe Stop Bar, 24 in White
TOTAL:				

Additional Comments:

**Fox Lair Road (FROM Carrs Station Road TO Lair Road): Length 2,497 ft, Width 21 ft (5,826 sy)**

TREATMENT:	ITEM #:	QUANTITIY:	UNITS:	NOTES:
Overlay	402-3100	641	TONS	12.5 mm recycled asphalt superpave @ 220 lbs/sy
Patching	402-1802	250	TONS	19mm Recycled asphalt incl bitum matl and H lime 4" Depth
Bitum Tack Coat	413-1000	233	GAL	0.04 Gal/SY
Striping	652-2501	0.95	L. MILE	Solid Traffic Edge Stripe, 5 in White
Striping	652-2502	0.95	L. MILE	Solid Traffic CL Stripe, 5 in Yellow
Striping	653-1704	10	L. FOOT	Thermoplastic Solid Traffic Stripe Stop Bar, 24 in White

Additional Comments:

**Lawerence Road (FROM Nelson Road TO County Line): Length 3,696 ft, Width 20 ft (8,213 sy)**

TREATMENT:	ITEM #:	QUANTITIY:	UNITS:	NOTES:
Overlay	402-3100	903	TONS	12.5 mm recycled asphalt superpave @ 220 lbs/sy
Suface Treatment	424-6089	8213	SY	Double Surface Trtmnt, Stone size 7 and 89, GP 1 or 2
Bitum Tack Coat	413-1000	329	GAL	0.04 Gal/SY
Striping	652-2501	1.4	L. MILE	Solid Traffic Edge Stripe, 5 in White
Striping	652-2502	1.4	L. MILE	Solid Traffic CL Stripe, 5 in Yellow
Striping	653-1704	10	L. FOOT	Thermoplastic Solid Traffic Stripe Stop Bar, 24 in White

Additional Comments: Double Surface Treatment first then overlay

**FORTE AVE (FROM Marked TO Marked): Length 1,000 ft, Width 12 ft (1,333 sy)**

TREATMENT:	ITEM #:	QUANTITIY:	UNITS:	NOTES:
Overlay	402-3100	147	TONS	12.5 mm recycled asphalt superpave @ 220 lbs/sy

Additional Comments:

TREATMENT:	ITEM #:	QUANTITIY:	UNITS:	NOTES:	UNIT PRICE:	LINE ITEM TOTAL:
Overlay	402-3100	1936	TONS	12.5 mm recycled asphalt superpave @ 220 lbs/sy		
Patching	402-1802	325	TONS	19mm Recycled asphalt incl bitum matl and H lime 4" Depth		
Bitum Tack Coat	413-1000	651	GAL	0.04 Gal/SY		
Suface Treatment	424-6089	8213	SY	Double Surface Trtmnt, Stone size 7 and 89, GP 1 or 2		
Striping	652-2501	2.73	L. MILE	Solid Traffic Edge Stripe, 5 in White		
Striping	652-2502	2.73	L. MILE	Solid Traffic CL Stripe, 5 in Yellow		
Striping	653-1704	30	L. FOOT	Thermoplastic Solid Traffic Stripe Stop Bar, 24 in White		

Page 1 Total

<b>Merry Lane/Court (FROM Little Road to Cul-De-Sacs): Length 1,320 ft, Width 20 ft (2,933 sy)</b>				
TREATMENT:	ITEM #:	QUANTITY:	UNITS:	NOTES:
Triple Surface Treatment	424-6089	2933	SY	Stone size 5, 7 and 89, GP 1 or 2
Additional Comments:				

<b>Union Hill Church Road (FROM CC Camp Road TO County Line): Length 17,635 ft, Width 20 ft (39,190 sy)</b>				
TREATMENT:	ITEM #:	QUANTITY:	UNITS:	NOTES:
Triple Surface Treatment	424-6089	39190	SY	Stone size 5, 7 and 89, GP 1 or 2 with sand seal
Leveling	402-1812	1470	TONS	9.5 mm recycled asphalt superpave @ 75 lbs/sy
Additional Comments:				

<b>Watson Reynolds Road (FROM Hwy 24/22 TO Lake Laurel Road ): Length 3,036 ft, Width 20 ft (6,747 sy)</b>				
TREATMENT:	ITEM #:	QUANTITY:	UNITS:	NOTES:
Triple Surface Treatment	424-6089	6747	SY	Stone size 5, 7 and 89, GP 1 or 2 with sand seal
Leveling	402-1812	253	TONS	9.5 mm recycled asphalt superpave @ 75 lbs/sy
Additional Comments:				

TREATMENT:	ITEM #:	QUANTITY:	UNITS:	NOTES:	UNIT PRICE:	LINE ITEM TOTAL:
Triple Surface Treatment	424-6089	2933	SY	Stone size 5, 7 and 89, GP 1 or 2		
Triple Surface Treatment	424-6089	45937	SY	Stone size 5, 7 and 89, GP 1 or 2 with sand seal		
Leveling	402-1812	1723	TONS	9.5 mm recycled asphalt superpave @ 75 lbs/sy		
					<b>Page 2 Total</b>	

<b>Grand Total</b>	
--------------------	--