

CLS Sealcoating & Striping

382 Old Camp Rd
Bandera, Tx. 78003

Estimate

Date	Estimate #
10/1/2025	2493

Name / Address
Bandera EDC 511 Main St. Bandera, Tx. 78003

Project

Description	Qty	Rate	Total
Lay asphalt Approx. 12000 Sq. Ft. -Excavate and haul off approx 8 1/2 to 9 inches of subgrade. -Import 6 inches compacted road base. -Deliver and install 2 inches of Type D Hot Mix asphalt, to be machine laid, rolled and compacted using flat wheel and pneumatic rollers on entire area. Layout with chalk line to stripe all lines, hashes, 2 ADA HC symbols Install Signs- 2 ADA HC signs Job location: corner of 10th/ Maple st. stephanie.biggs@banderatx.gov		61,000.00	61,000.00
		0.00	0.00
		0.00	0.00

Thank you for your business.	Subtotal	\$61,000.00
	Sales Tax (0.0%)	\$0.00
	Total	\$61,000.00

Phone # 8304960845

clssealcoat@yahoo.com

clssealcoat.com