

**A METES AND BOUNDS
DESCRIPTION OF A
56.620 ACRE TRACT OF LAND**

BEING a 56.620 acre (2,466,385 square feet) tract of land situated in the Nancy Blakey Survey, Abstract 98, Bastrop County, Texas; and being a portion of a tract called "Reserve" on the plat of Lone Star Storage Subdivision, recorded in Cabinet 4, Page 163-A of the Official Public Records of Bastrop County, also being a portion of that certain 74.974 acre tract described in instrument to PRC 01 Bastrop, LLC, recorded in Document No. 202200112 of the Official Public Records of Bastrop County; and being more particularly described by metes and bounds as follows:

COMMENCING, at a "TXDOT" Concrete Monument found marking the southwest corner end of a cutback at the intersection northerly right-of-way line of State Highway 71 (300' right-of-way wide) and the easterly right-of-way line of Farm to Market Road 969 (80' right-of-way wide), and marking the southern-most southwest corner of the herein described tract;

THENCE, in a northwesterly direction along a said Farm to Market Road 969, the following four (4) courses and distances.

1. North 43°37'41" West, 370.98 feet to a "TXDOT" Concrete Monument found for corner;
2. in a northerly direction along a non-tangent curve to the right, having a radius of 2824.79 feet, a chord North 17°41'54" West, 146.68 feet, a central angle of 2°58'32", and an arc length of 146.69 feet to a **POINT OF BEGINNING** and southwest corner of the herein described tract;
3. in a northerly direction continuing along a tangent curve to the right, having a radius of 2824.79 feet, a chord North 08°36'51" West, 746.83 feet, a central angle of 15°11'33", and an arc length of 749.02 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for corner;
4. North 02°26'48" West, 243.14 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for corner;

THENCE, North 87°41'49" East, 2687.44 feet departing the westerly right-of-way line of said Farm to Market Road 969 and along the southerly line of Blakey Lane "North Road Segment II" recorded in Volume 1799, Page 356 of the Official Public Records of Bastrop County, to a 1/2-inch iron rod with plastic cap stamped "KHA" set marking the northwest end of a right-of-way cutback curve at the intersection with the westerly line of Duff Drive (60' wide right-of-way) recorded in Cabinet 5, Page 145A of the Amended Plat of Lots 1, 2, and 3, Block A, Burleson Crossing;

THENCE, along westerly line of said Duff Drive, the following five (5) courses and distances;

1. in a southeasterly direction along a non-tangent curve to the right, having a radius of 25.00 feet, a chord South 47°18'11" East, 35.36 feet, a central angle of 90°00'54", and an arc length of 39.28 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for a point of curvature;
2. South 02°18'11" East, 211.62 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for corner;
3. in a southerly direction along a tangent curve to the left, having a radius of 1030.00 feet, a chord of South 07°52'45" East, 200.16 feet, a central angle of 11°09'07", and an arc length of 200.48 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for point of tangency;
4. South 13°27'19" East, 85.21 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for a point of curvature;
5. in a southerly direction along a tangent curve to the right, having a radius of 970.00 feet, a chord of South 09°19'29" East, 139.73 feet, a central angle of 08°15'40", and an arc length of 139.86 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for corner marking the northwest corner of Lot 1 of a said Lonestar Storage Subdivision;

THENCE, along the northwest boundary line of said Lot 1, the following two (2) courses and distances;

1. South 87°45'06" West, 663.82 feet to a 1/2-inch iron rod with plastic cap stamped "KHA" set for corner;
2. South 02°14'54" East, 330.32 feet to a point for corner;

THENCE, South 87°45'51" West, 2018.62 feet to the **POINT OF BEGINNING**, and containing 56.620 acres of land in Bastrop County, Texas. The basis of this description is the Texas State Plane Coordinate System, Central Zone (FIPS 4203) (NAD'83). All distances are on the Surface and shown in U.S. Survey Feet. The Combined Surface to Grid Scale Factor is 1.0000139976. This description was generated on 8/8/2022 at 5:40 PM, based on geometry in the drawing file K:\SNA_Survey\069300300-PEARL RVR-BASTROP 75AC\DWG\Exhibits\56.620 AC - Pearl River Bastrop Core.dwg, in the office of Kimley-Horn and Associates in San Antonio, Texas.



**EXHIBIT OF A
56.620 ACRE
NANCY BLAKEY SURVEY,
ABSTRACT NO. 98
BASTROP COUNTY, TEXAS**

JOHN G. MOSIER
REGISTERED PROFESSIONAL
LAND SURVEYOR NO. 6330
601 NW LOOP 410, SUITE 350
SAN ANTONIO, TEXAS 78216
PH. 210-541-9166
greg.mosier@kimley-horn.com

John G. Mosier
8-9-22

Kimley»Horn

10101 Reunion Place, Suite 400
San Antonio, Texas 78216 FIRM # 10193973

Tel. No. (210) 541-9166
www.kimley-horn.com

Scale	Drawn by	Checked by	Date	Project No.	Sheet No.
N/A	DJG	JGM	8/9/2022	069300300	1 OF 2



0 250 500

GRAPHIC SCALE IN FEET

LEGEND:

P.O.C. = POINT OF COMMENCING

P.O.B. = POINT OF BEGINNING

IRSC = 1/2" IRON ROD W/ "KHA" CAP SET

1/2" IRF = IRON ROD FOUND

1/2" IRFC = IRON ROD FOUND (W/CAP STAMPED "____")

CMF = CONCRETE MONUMENT FOUND

CAB. = CABINET NUMBER

DOC. = CABINET NUMBER

PG. = PAGE

OPRBC = OFFICIAL PUBLIC RECORDS BASTROP COUNTY


PRBC = DEED AND PLAT RECORDS BASTROP COUNTY

CURVE TABLE

NO.	DELTA	RADIUS	LENGTH	CHORD BEARING	CHORD
C1	2°58'32"	2824.79'	146.69'	N17°41'54"W	146.68'
C2	15°11'33"	2824.79'	749.02'	N08°36'51"W	746.83'
C3	90°00'54"	25.00'	39.28'	S47°18'11"E	35.36'
C4	11°09'07"	1030.00'	200.48'	S07°52'45"E	200.16'
C5	8°15'40"	970.00'	139.86'	S09°19'29"E	139.73'

LINE TABLE

NO.	BEARING	LENGTH
L1	N43°37'41"W	370.98'
L2	N02°26'48"W	243.14'
L3	N87°41'49"E	2687.44'
L4	S02°18'11"E	211.62'
L5	S13°27'19"E	85.21'
L6	S87°45'06"W	663.82'
L7	S02°14'54"E	330.32'
L8	S87°45'51"W	2018.62'



GEODETIC NOTE: THE BEARINGS SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (FIPS 4203) (NAD'83), AS DETERMINED BY THE GLOBAL POSITIONING SYSTEM (GPS). ALL DISTANCES SHOWN HEREON ARE ON THE SURFACE. THE COMBINED GRID TO SURFACE SCALE FACTOR FOR THE PROJECT IS 1.0000139976. THE UNIT OF LINEAR MEASUREMENT IS U.S. SURVEY FEET.

CERTIFICATION: THIS IS A LEGAL DESCRIPTION BASED ON A FIELD SURVEY BY KIMLEY-HORN PERSONNEL. NO IMPROVEMENTS ARE SHOWN. ALL EXISTING EASEMENTS ARE NOT SHOWN. THIS IS NOT A LAND TITLE SURVEY. SEE THE SEPARATE LAND TITLE SURVEY UNDER JOB NUMBER 069300300 FOR ADDITIONAL INFORMATION.

JOHN G. MOSIER
REGISTERED PROFESSIONAL
LAND SURVEYOR NO. 6330
601 NW LOOP 410, SUITE 350
SAN ANTONIO, TEXAS 78216
PH. 210-541-9166
greg.mosier@kimley-horn.com



John G. Mosier
8-9-22

EXHIBIT OF A
56.620 ACRE
NANCY BLAKEY SURVEY,
ABSTRACT NO. 98
BASTROP COUNTY, TEXAS

Kimley»Horn

10101 Reunion Place, Suite 400

San Antonio, Texas 78216

FIRM # 10193973

Tel. No. (210) 541-9166

www.kimley-horn.com

Scale	Drawn by	Checked by	Date	Project No.	Sheet No.
1" = 500'	DJG	JGM	8/9/2022	069300300	2 OF 2