



A W&S COMPANY

**Baxter Water Treatment Plant Backwash Trough Proposal
Baxter, MN**

Proposal

March 6, 2026

TO: **City of Baxter, c/o Kevin Young @ SEH**
kbyoung@sehinc.com

	Amount
Improvements to existing backwash waste troughs in filters 1-4	\$ 50,850.00

Scope of Work:

Add SS angle with EPDM Gasket around end of filter troughs
JBWeld Waterweld between new angle & existing trough

Bid Clarifications:

- Lead time on materials is 2 weeks. The March schedule deadline will not be made.
- Confined space entry into the filters has been accounted for
- Additional EPDM gasket material is included

MAIN OFFICE

22360 County Road 12
PO Box 517
Deerwood, MN 56444
PH 218-546-5519
FX 218-546-7016

www.ricelake.org

Please call with any questions.

Craig M. Habighorst
Rice Lake Construction Group
763-229-1157