# RENARDS® LUMBER YARD AND PARKING LOT EXPANSION **CITY OF BAXTER**, **PROJECT INFORMATION CROW WING COUNTY, MINNESOTA OWNER - MENARD, INC CONTACT: TYLER EDWARDS** 5101 MENARD DR,


RED SAND

WHITE

SAND LAKE

## **DRAWING INDEX**

C0.0 C0.1	TITLE SHEET GENERAL NOTES
C1.0	EXISTING CONDITIONS MAP
C2.0	OVERALL REMOVAL PLAN
C2.1	REMOVAL PLAN - YARD EXPANSION
C2.2	<b>REMOVAL PLAN - PARKING LOT EXPANSION</b>
C3.0	OVERALL SITE PLAN
C3.1	SITE PLAN - YARD EXPANSION
C3.2	SITE PLAN - PARKING LOT EXPANSION
C4.0	STORMWATER POLLUTION PREVENTION PLAN
C5.0	OVERALL GRADING PLAN AND EROSION
	CONTROL PLAN
C5.1	GRADING PLAN - YARD EXPANSION
C5.2	<b>GRADING PLAN - PARKING LOT EXPANSION</b>
C6.0	OVERALL UTILITY PLAN
C6.1	UTILITY PLAN - YARD EXPANSION
C6.2	UTILITY PLAN - PARKING LOT EXPANSION
C7.0	SITE DETAILS
C7.1	SITE DETAILS
C7.2	UTILITY DETAILS







EAU CLAIRE, WI 54703 P: 715.876.2143 TEDWARDS@MENARD-INC.COM

PROJECT CONSULTANT JSD PROFESSIONAL SERVICES 161 HORIZON DRIVE, SUITE 101 **VERONA, WI 53593** 

**PROJECT MANAGER** 

**ENGINEER OF RECORD** 

MAYOR

**CITY COUNCIL** 

UTILITIES COMMISSION

**CITY ENGINEER** 

HANS P. JUSTESON P: 608.848.5060 HANS.JUSTESON@JSDINC.COM

PAUL PHILLIPS, PE P: 920.733.2800 EXT. 221 PAUL.PHILLIPS@JSDINC.COM

## **MUNICIPAL CONTACTS**

MARK CROSS **CONNIE LYSCIO** ZACH TABATT JOHN WARD

DARREL OLSON

**ROCK YLINIEMI - CHAIR** JACK CHRISTOFFERSON **DOUGLAS STENBERG** JOHN BRENNY

**CITY ADMINISTRATIOR** 

**PUBLIC WORKS DIRECTOR /** 

**TREVOR WALTER** 

**BRADLEY CHAPULIS** 



					5		
CRE	ATE TH	IE VIS	SION		TELL	THE	STOR
		js	din	C.CO	m		
	16	1 HOR /ERON	RIZON NA, W	GION DRIVE ISCONS .848.5	, SUITE SIN 535	101	E
CLIEN							
ME	ENAF	KD,	ING	J.			
	NT ADDRI <b>1 MEN</b>		) DF	RIVE			
EAU	JCLA	RE,	WI	5470	3		
PROJ							
	ECI						
	ENAF					Y	ARD
AN		٩R	KIN			Y	ARD
AN	ENAF ID P/	٩R	KIN			Υ <b>Α</b>	ARD
AN	ENAF ID P/	٩R	KIN			YA	ARD
AN EX PROJ 152				G L	OT		
PROJ 152 BAX		ARP SIC		D DR	OT		
PROJ 152 BAX		ARP SIC		D DR	OT		
PROJ 152 BAX		ARP SIC		D DR	OT		
PROJ 152 BAX		ARP SIC		D DR	OT		
PROJ 152 BAX		ARP SIC		D DR	OT		
PROJ 152 BAX		ARP SIC		D DR	OT		
AN EX PROJ 152 BAX MIN		ARP SIC	(IN )N (00) 5640	D DR	OT		
PROJ 152 BAX MIN		ARP SIC		Cription: DOCU			Y
PROJ 152 BA) MIN		ARP SIC		Cription:			Y
PROJ 152 BA) MIN		ARP SIC		Cription: DOCU			Y
AN EX PROJ 152 BAX MIN PLAN # 1 2 3 4 5 6 7 8		ARP SIC		Cription: DOCU			Y
AN EX PROJ 152 BAX MIN # 1 2 3 4 5 6 7 8 9 10		ARP SIC		Cription: DOCU			Y
AN EX PROJ 152 BAX MIN PLAN # 1_2 3 4 5 6 7 8 9		ARP SIC		Cription: DOCU			Y
AN EX PROJ 152 BAX MIN PLAN # 12 34 5 6 7 8 9 10 11 12		ARP SIC		Cription: DOCU			Y
ANEX PROJ 152: BAX MIN PLAN # 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 15 15 15 15 15 15 15 15 15		ARP SIC		Cription: DOCU			Y
ANEX PROJ 152: BAD MIN PLAN # 1 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 12 13 14 15 15 15 15 15 15 15 15 15 15		ARP SIC		Cription: DOCU			Y
ANEX           PROJ           152:           BAD           MIN           PLAN           #           1           2           3           4           5           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           11           12           13           14           15	MODIFIC Date: 07.01.20 07.15.20			Cription: DOCUI			Y //
ANEX           PROJ           152:           BAD           MIN           PLAN           #           1           2           3           4           5           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           11           12           13           14           15	MODIFIC Date: 07.01.20 07.15.20 07.15.20 07.15.20 07.15.20 07.15.20 07.15.20			Cription: DOCUI			Y //
ANEX           PROJ           152:           BAD           MIN           PLAN           #           1           2           3           4           5           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           11           12           13           14           15	MODIFIC Date: 07.01.20 07.15.20			Cription: DOCUI			Y //
ANEX           PROJ           152:           BAD           MIN           PLAN           #           1           2           3           4           5           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           10           12           3           4           5           6           7           8           9           11           12           13           14           15	MODIFIC Date: 07.01.20 07.15.20			Cription: DOCUI			Y //
AN EX PROJ 152: BAD MIN PLAN # 1 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 12 10 10 10 10 10 10 10 10 10 10 10 10 10	MODIFIC Date: 07.01.20 07.15.20			Cription: DOCUI			Y //

22-11222

#### **GENERAL NOTES**

- 1. REFER TO THE EXISTING CONDITIONS SURVEY (PREFORMED BY OTHERS) FOR EXISTING CONDITIONS NOTES AND LEGENDS.
- 2. ALL WORK IN THE ROW AND/OR PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS.
- 3. JSD SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER/CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY ANY OR ALL REGULATORY AGENCIES.
- 4. CONTRACTOR SHALL PROVIDE ADEQUATE TRAFFIC CONTROL AND PROVIDE ACCESS TO ALL ADJACENT PROPERTIES AT ALL TIMES. CONTRACTOR SHALL PROVIDE VEHICULAR AND PEDESTRIAN TEMPORARY TRAFFIC CONTROL AS REQUIRED PER ALL STATE AND LOCAL CODES AND SPECIFICATIONS. CONTRACTOR PROVIDE A TRAFFIC CONTROL AND SEQUENCING PLAN TO THE MUNICIPALITY FOR APPROVAL PRIOR TO CONSTRUCTION.
- 5. CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL AND CONSTRUCTION SEQUENCING PLAN TO THE CITY OF BAXTERS FOR APPROVAL PRIOR TO COMMENCING WORK. ACCESS TO ADJACENT PROPERTIES SHALL BE MAINTAINED AS MUCH AS PRACTICAL. IF ACCESS NEEDS TO BE RESTRICTED FOR A PERIOD OF TIME. THE CONTACTOR SHALL RESTORE ACCESS AS SOON AS PRACTICAL AND PROVIDED A MINIMUM 48 HOUR NOTICE TO AFFECTED PROPERTIES.

#### **DEMOLITION NOTES**

- THIS PLAN INDICATES ITEMS ON THE PROPERTY INTENDED FOR DEMOLITION BASED ON THE CURRENT SITE DESIGN THAT HAVE BEEN IDENTIFIED BY A REASONABLE OBSERVATION OF THE EXISTING CONDITIONS THROUGH FIELD SURVEY RECONNAISSANCE, "MINNESOTA ONE CALL" LOCATION, AND GENERAL "STANDARD OF CARE". THERE MAY BE ADDITIONAL ITEMS THAT CAN NOT BE IDENTIFIED BY A REASONABLE ABOVE GROUND OBSERVATION, OF WHICH THE ENGINEER WOULD HAVE NO KNOWLEDGE OR MAY BE A PART OF ANOTHER DESIGN DISCIPLINE. IT IS THE CONTRACTOR'S /BIDDER'S RESPONSIBILITY TO REVIEW THE PLANS. INSPECT THE SITE AND PROVIDE THEIR OWN DUE DILIGENCE TO INCLUDE IN THEIR BID WHAT ADDITIONAL ITEMS, IN THEIR OPINION, MAY BE NECESSARY FOR DEMOLITION. ANY ADDITIONAL ITEMS IDENTIFIED BY THE CONTRACTOR/BIDDER SHALL BE IDENTIFIED IN THE BID AND REPORTED TO THE ENGINEER OF RECORD. JSD TAKES NO RESPONSIBILITY FOR ITEMS ON THE PROPERTY THAT COULD NOT BE LOCATED BY A REASONABLE OBSERVATION OF THE PROPERTY OR OF WHICH THEY WOULD HAVE NO KNOWLEDGE
- CONTRACTOR SHALL KEEP ALL STREETS AND PRIVATE DRIVES FREE AND CLEAR OF ALL CONSTRUCTION RELATED DIRT, DUST AND DEBRIS.
- ALL TREES AND VEGETATION WITHIN THE PROPOSED PUBLIC RIGHT-OF-WAY SHALL BE REMOVED UNLESS SPECIFICALLY CALLED OUT FOR PROTECTION. ALL TREES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY AND STUMPS SHALL BE GROUND TO PROPOSED SUBGRADE. CONTRACTOR TO FIELD VERIFY CLEARING AND GRUBBING LIMITS AND TREES TO BE REMOVED.
- ALL LIGHT POLES TO BE REMOVED SHALL BE REMOVED IN THEIR ENTIRETY, INCLUDING BASE AND ALL APPURTENANCES. SALVAGE FOR RELOCATION. COORDINATE RELOCATION AND/OR ABANDONMENT OF ALL ELECTRIC LINES WITH ELECTRICAL ENGINEER AND OWNER PRIOR TO DEMOLITION.
- 5. REMOVED ITEMS SHALL BE DISPOSED OF OFF SITE UNLESS OTHERWISE NOTED.
- 6. CONTRACTOR TO REPLACE ALL SIDEWALK AND CURB AND GUTTER ABUTTING THE PROPERTIES, WHICH IS DAMAGED BY THE CONSTRUCTION, OR ANY SIDEWALK AND CURB AND GUTTER THAT THE CITY ENGINEER DETERMINES NEEDS TO BE REPLACED BECAUSE IT IS NOT AT A DESIRABLE GRADE REGARDLESS OF WHETHER THE CONDITION EXISTED PRIOR TO BEGINNING CONSTRUCTION.
- PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR: 7.1. EXAMINE ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED IMMEDIATELY TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF CONSTRUCTION.
- 7.2. VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCIES. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCIES ARE RESOLVED.
- 7.3. NOTIFYING ALL UTILITIES PRIOR TO THE REMOVAL OF ANY UNDERGROUND UTILITIES. 7.4. NOTIFYING THE DESIGN ENGINEER AND LOCAL CONTROLLING MUNICIPALITY 48 HOURS PRIOR TO
- THE START OF CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION INSPECTION. ANY UTILITIES, WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE CONTRACTOR'S EXPENSE.
- 9. CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY DURING THE CONSTRUCTION OF THESE IMPROVEMENTS.
- 10. CONTRACTOR TO COORDINATE PRIVATE UTILITY REMOVAL / ABANDONMENT AND NECESSARY RELOCATION WITH RESPECTIVE UTILITY COMPANY. COORDINATION REQUIRED PRIOR TO CONSTRUCTION. 11. ALL DEMOLITION SHALL BE IN ACCORDANCE WITH THE APPROVED MUNICIPALITY RECYCLING PLAN.
- 12. ANY CONTAMINATED SOILS SHALL BE REMOVED IN ACCORDANCE WITH FEDERAL AND STATE
- REGULATIONS TO AN APPROVED LANDFILL. 13. ALL EXISTING UTILITIES TO BE FIELD LOCATED AND FLAGGED BY CONTRACTOR.
- 14. EXISTING FIBER OPTIC LINE TO BE CLEARLY MARKED PRIOR TO ANY EXCAVATION. CONTRACTOR TO NOTIFY ENGINEER IMMEDIATELY IF ANY DISCREPANCIES OCCUR IN THE LOCATION SHOWN OR PROPOSED IMPROVEMENTS IMPACTING EXISTING FIBER OPTIC LINE LOCATION.
- 15. SEWER ABANDONMENT SHALL BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 16. WATER ABANDONMENT SHALL BE IN ACCORDANCE WWITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 17. ALL EROSION CONTROL DEVICES SHALL BE INSTALLED PRIOR TO THE START OF DEMOLITION ACTIVITIES. CONTRACTOR SHALL KEEP ALL STREETS AND PAVEMENT FREE AND CLEAR OF ALL CONSTRUCTION RELATED DIRT. DUST AND DEBRIS.
- 18. CONTRACTOR TO REMOVE EXISTING UTILITY PIPE AND PROVIDE PIPE BACK-FILLING AFTER REMOVAL OF EXISTING UTILITIES.

#### CONSTRUCTION ACTIVITIES AND SEQUENCING

- PRIOR TO ANY STRIPPING OF EXISTING VEGETATION OR DISTURBANCE. INSTALL ALL BMP'S NEEDED AND ASSOCIATED WITH THE GRADING PHASE SUCH AS STABILIZED CONSTRUCTION ENTRANCES, SILT BASINS, RISER PIPES, OUTLET PIPES, SILT TRAPS, SILT FENCE, DIVERSIONS, TERRACES, AND
- 2. INSPECTOR APPROVAL MUST BE OBTAINED BEFORE THE START OF ANY STRIPPING OF EXISTING VEGETATION OR GRADING.
- 3. PROCEED WITH STRIPPING OF EXISTING VEGETATION AND GRADING IN ACCORDANCE WITH THE GRADING PLAN, WHILE DISTURBING NO MORE THAN NECESSARY.
- 4. STRIP AND STOCKPILE TOPSOIL, INSTALL SILT FENCE AROUND PERIMETER OF STOCKPILE.
- 5. PROCEED WITH INFRASTRUCTURE INSTALLATION. INFRASTRUCTURE INSTALLATION MUST OCCUR PRIOR TO ANY LOT DEVELOPMENT.
- 5. COMPLETE DEMOLITION WITHIN PROPOSED RIGHT-OF-WAY
- 6. ROUGH GRADE STORMWATER BASIN AND INSTALL POND OUTLET.
- 7. CONDUCT ROUGH GRADING EFFORTS AND INSTALL CHECK DAMS WITHIN DRAINAGE DITCHES AS NEEDED.
- 10. IMPLEMENT THE INSTALLATION OF TEMPORARY SEEDING, PERMANENT SEEDING, AND/OR MULCHING. 11. STABILIZATION MEASURES MUST BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.
- 12. INSTALL UTILITY PIPING AND STRUCTURES, IMMEDIATELY INSTALL INLET PROTECTION IN ALL STORM
- 13. COMPLETE FINAL GRADING, INSTALLATION OF GRAVEL BASE COURSES, PLACEMENT OF CURBS, PAVEMENTS, WALKS, ETC.
- 14. IMPLEMENT THE INSTALLATION ALL BMP'S NEEDED AND ASSOCIATED WITH THE BUILDING PHASE. BUILDING PHASE BMP'S MUST BE INSTALLED CONCURRENTLY WITH LOT DEVELOPMENT. 15. PLACE TOPSOIL AND IMMEDIATELY STABILIZE DISTURBED AREAS WITH EROSION CONTROL MEASURES
- 16. RESTORE STORMWATER BASIN (FINAL GRADE PER PLAN REQUIREMENTS)

AS INDICATED ON PLANS.

- 17. EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL SITE IS FULLY STABILIZED OR 70% VEGETATIVE COVER IS ESTABLISHED.
- 18. PROCEED WITH REMOVAL OF BMP'S. BMP'S MAY NOT BE REMOVED UNTIL EACH IMPACTED DRAINAGE BASIN HAS BEEN FULLY DEVELOPED. FULL DEVELOPMENT SHALL MEAN INSTALLATION OF PAVEMENT, BUILDINGS, AND UTILITIES, LANDSCAPING, AND FULLY ESTABLISHED PERMANENT SEEDING. FURTHERMORE, INSPECTOR APPROVAL MUST BE OBTAINED BEFORE THE REMOVAL OF ANY BMP'S.

CONTRACTOR MAY MODIFY SEQUENCING AFTER ITEM NO. 1 AS NEEDED TO COMPLETE CONSTRUCTION IF EROSION CONTROLS ARE MAINTAINED IN ACCORDANCE WITH THE CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS.

#### **PAVING NOTES**

- 1. GENERAL 1.1. ALL PAVING SHALL CONFORM WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 1.3. SURFACE PREPARATION NOTIFY ENGINEER/OWNER OF UNSATISFACTORY CONDITIONS. DO NOT BEGIN PAVING WORK UNTIL DEFICIENT SUBBASE AREAS HAVE BEEN CORRECTED AND ARE READY
- TO RECEIVE PAVING
- MUNICIPALITY REQUIREMENTS.
- 2. ASPHALTIC CONCRETE PAVING SPECIFICATIONS
- BASE COURSE AND ASPHALTIC CONCRETE SURFACE COURSE SHALL BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- COURSE DURING CONSTRUCTION.
- AND SPECIFICATIONS
- 2.4. BINDER COURSE AGGREGATE SHALL CONFORM WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 2.5. SURFACE COURSE AGGREGATE SHALL CONFORM WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 2.6. ASPHALTIC MATERIALS SHALL CONFORM TWITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 3. <u>CONCRETE PAVING SPECIFICATIONS</u>
- IN THE PROCESS OF BEING ADJUSTED), CONTRACTOR TO CONFIRM FINAL MIX WITH CITY.
- 3.1. CONCRETE PAVING SHALL CONFORM WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS 3.2. PCC PAVING SHALL MEET CITY OF BAXTERS SUPPLEMENTAL SPECIFICATIONS FOR PCC MIX (MIX IS 3.3. CURING COMPOUNDS SHALL CONFORM WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 3.4. CONTRACTOR SHALL PROVIDE CONTROL JOINTS AND CONSTRUCTION JOINTS OF ONE-QUARTER CONCRETE THICKNESS AT AN EQUAL RATIO OF LENGTH TO WIDTH WHEREVER POSSIBLE WITH A MAXIMUM LENGTH BETWEEN JOINTS OF 8' ON CENTER.
- 3.5. CONTRACTOR SHALL PROVIDE EXPANSION JOINTS IN SIDEWALKS AT A MAXIMUM 25' ON CENTER.
- 3.6. EXTERIOR CONCRETE SURFACES SHALL BE BROOM FINISHED.
- 3.7. ALL CONCRETE SURFACES TO BE SEALED WITH TYPE TK-26UV CONCRETE SEALANT.
- 4. PAVEMENT MARKING SPECIFICATIONS
- 4.1. ALL PAVEMENT MARKINGS INCLUDING: STOP BARS, CROSSWALKS, DIRECTIONAL ARROWS, PARKING STALL LINES, ADA STALL MARKINGS, NO PARKING ZONES, DROP-OFF/PICK-UP ZONES SHALL BE PAINTED WITH LATEX PAINT PER SPECIFICATIONS.
- 4.2. 2' x 4' TRUNCATED DOME WARNING DETECTION FIELD SHALL BE PLACED AT ALL ADA RAMPS.

#### UTILITY NOTES

- TO BE ACCURATE OR ALL INCLUSIVE. THE CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OWN DETERMINATION AS TO THE TYPE AND LOCATIONS OF UNDERGROUND UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE THERETO. CONTRACTOR/OWNER SHALL CALL "DIGGER'S HOTLINE" PRIOR TO ANY CONSTRUCTION.
- 2. PRIOR TO CONSTRUCTION, THE PRIME CONTRACTOR IS RESPONSIBLE FOR: EXAMINING ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED TO THE ENGINEER AND RESOLVED PRIOR TO
- THE START OF CONSTRUCTION. • OBTAINING ALL PERMITS INCLUDING PERMIT COSTS, TAP FEES, METER DEPOSITS, BONDS, AND ALL OTHER FEES REQUIRED FOR PROPOSED WORK TO OBTAIN OCCUPANCY • VERIFYING ALL ELEVATIONS, LOCATIONS AND SIZES OF SANITARY, WATER AND STORM LATERALS AND CHECK ALL UTILITY CROSSINGS FOR CONFLICTS. NOTIFY ENGINEER OF ANY DISCREPANCY. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCY IS RESOLVED.
- CONSTRUCTION TO ARRANGE FOR APPROPRIATE CONSTRUCTION OBSERVATION.
- NOTIFYING ALL UTILITIES PRIOR TO INSTALLATION OF ANY UNDERGROUND IMPROVEMENTS. • NOTIFYING THE DESIGN ENGINEER AND MUNICIPALITY 48 HOURS PRIOR TO THE START OF COORDINATING ALL CONSTRUCTION WITH OTHER CONTRACTORS INVOLVED WITH CONSTRUCTION OF THE PROPOSED DEVELOPMENT AND FOR REPORTING ANY ERRORS OR DISCREPANCIES BETWEEN THESE PLANS AND PLANS PREPARED BY OTHERS.
- 3. ALL UTILITY WORK SHALL BE DONE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS. IT IS THE CONTRACTORS RESPONSIBILITY TO DETERMINE WHICH SPECIFICATIONS AND CODES APPLY, AND TO COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE APPROPRIATE LOCAL AND STATE AUTHORITIES.
- 4. LENGTHS OF ALL UTILITIES ARE TO CENTER OF STRUCTURES OR FITTINGS AND MAY VARY SLIGHTLY FROM PLAN. LENGTHS SHALL BE VERIFIED IN THE FIELD DURING CONSTRUCTION. 5. CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY DURING THE CONSTRUCTION OF IMPROVEMENTS.
- 6. CONTRACTOR SHALL INSTALL A PEDESTRIAN FENCE AROUND ALL EXCAVATIONS TO BE LEFT OPEN OVER NIGHT AS REQUIRED IN CONSTRUCTION SITES WHERE THE POTENTIAL FOR PEDESTRIAN INJURY EXISTS.
- 7. CONTRACTOR SHALL ADJUST AND/OR RECONSTRUCT ALL UTILITY COVERS (SUCH AS MANHOLE COVERS, VALVE BOX COVERS, ETC.) TO MATCH THE FINISHED GRADES OF THE AREAS EFFECTED BY THE CONSTRUCTION.
- 8. THE PRIME CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL CONSTRUCTION WITH OTHER CONTRACTORS INVOLVED WITH CONSTRUCTION OF THE PROPOSED DEVELOPMENT AND FOR REPORTING ANY ERRORS OR DISCREPANCIES BETWEEN THESE PLANS AND PLANS PREPARED BY OTHERS. 9. ANY UTILITIES WHICH ARE DAMAGED BY THE CONTRACTORS, SHALL BE REPAIRED TO THE OWNER'S
- SATISFACTION AT THE CONTRACTOR'S EXPENSE.
- 10. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE ENGINEER WITH AS-BUILT CONDITIONS OF THE DESIGNATED IMPROVEMENTS IN ORDER THAT THE APPROPRIATE DRAWINGS CAN BE PREPARED, IF REQUIRED. ANY CHANGES TO THE DRAWINGS OR ADDITIONAL ITEMS MUST BE REPORTED TO THE ENGINEER AS WORK PROGRESSES.
- 11. STORM AND SANITARY SEWER SHALL BE IN ACCORDANCE ALL STATE AND LOCAL CODES AND SPECIFICATIONS.
- 12. SANITARY SEWER SHALL BE INSULATED WHEREVER THE DEPTH OF COVER IS LESS THAN THE MINIMUM REQUIRED. INSULATION AND INSTALLATION OF INSULATION SHALL BE CONFORMING WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS.

#### STORMWATER FACILITIES CONSTRUCTION NOTES

- ENGINEER SHALL BE NOTIFIED PRIOR TO INSTALLATION OF STORMWATER MANAGEMENT FACILITIES. CONSTRUCTION OF STORMWATER MANAGEMENT FACILITIES SHALL BE OBSERVED AND DOCUMENTED BY THE ENGINEER, OR AN OWNER'S REPRESENTATIVE.
- CODES AND SPECIFICATIONS. FINAL SITE GRADING AND SOILS HAVE BEEN STABILIZED.
- 2. ALL STORMWATER MANAGEMENT FACILITIES SHALL BE IN CONSTRUCTED PER ALL STATE AND LOCAL 3. STORMWATER MANAGEMENT FACILITIES SHALL BE INSTALLED AFTER SUBSTANTIAL COMPLETION OF
- 4. AREAS USED FOR TEMPORARY SEDIMENT BASINS SHALL BE REMOVED IN THEIR ENTIRETY AFTER
- 5. CONSTRUCTION TRAFFIC, HEAVY EQUIPMENT AND SOIL STOCKPILES SHALL NOT BE PLACED IN AREAS WHERE PROPOSED STORMWATER MANAGEMENT FACILITIES ARE LOCATED.
- CONSTRUCTION OF STORMWATER MANAGEMENT FACILITIES.

- 1.2. ALL PAVING DIMENSIONS ARE TO FACE OF CURB UNLESS SPECIFIED OTHERWISE.
- 1.4. ANY REQUIRED REPLACEMENT OF PUBLIC CURB AND GUTTER SHALL MATCH EXISTING AND MEET

### 2.1. CODES AND STANDARDS - THE PLACING, CONSTRUCTION AND COMPOSITION OF THE ASPHALTIC

2.2. GRADE CONTROL - ESTABLISH AND MAINTAIN REQUIRED LINES AND ELEVATIONS FOR EACH 2.3. CRUSHED AGGREGATE BASE COURSE - SHALL CONFORM WITH ALL STATE AND LOCAL CODES

# 1. ALL EXISTING UTILITIES ARE SHOWN FOR INFORMATIONAL PURPOSES ONLY AND ARE NOT GUARANTEED

#### **GRADING AND SEEDING NOTES**

- 1. ALL PROPOSED GRADES SHOWN ARE FINISHED GRADES. CONTRACTOR SHALL VERIFY ALL GRADES, MAKE SURE ALL AREAS DRAIN PROPERLY AND SHALL REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO CONSTRUCTION
- . CONTRACTOR SHALL ASSUME SOLE RESPONSIBILITY FOR COMPUTATIONS OF ALL GRADING QUANTITIES. WHILE JSD PROFESSIONAL SERVICES, INC. ATTEMPTS TO PROVIDE A COST EFFECTIVE APPROACH TO BALANCE EARTHWORK, GRADING DESIGN IS BASED ON MANY FACTORS, INCLUDING SAFETY, AESTHETICS, AND COMMON ENGINEERING STANDARDS OF CARE. THEREFORE, NO GUARANTEE CAN BE MADE FOR A BALANCED SITE.
- EXISTING GRADE SPOT ELEVATIONS SHOWN FOR INFORMATIONAL PURPOSES. DURING CONSTRUCTION MATCH EXISTING GRADES AT CONSTRUCTION LIMITS.
- 4. NO SITE GRADING OUTSIDE OR DOWNSLOPE OF PROPOSED SILT FENCE LOCATION. NO LAND DISTURBANCE BEYOND PROPERTY LINES.
- CONTRACTOR SHALL PROVIDE NOTICE TO THE MUNICIPALITY IN ADVANCE OF ANY SOIL DISTURBING ACTIVITIES, IN ACCORDANCE WITH MUNICIPAL REQUIREMENTS.
- 6. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 6-INCHES OF TOPSOIL PLACEMENT.
- 7. ALL DISTURBED AREAS SHALL BE SODDED AND/OR SEEDED AND MULCHED IMMEDIATELY FOLLOWING GRADING ACTIVITIES. SOD/SEED MIX TO BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS
- 8. CONTRACTOR TO DEEP TILL ALL COMPACTED PERVIOUS SURFACES PRIOR TO SODDING AND/OR SEEDING AND MULCHING.
- 9. ALL SLOPES 20% OR GREATER SHALL BE TEMPORARY SEEDED, MULCHED, OR OTHER MEANS OF COVER PLACED ON THEM WITHIN 2 WEEKS OF DISTURBANCE.
- 10. ALL EXPOSED SOIL AREAS THAT WILL NOT BE BROUGHT TO FINAL GRADE OR ON WHICH LAND DISTURBING ACTIVITIES WILL NOT BE PERFORMED FOR A PERIOD GREATER THAN 30 DAYS AND REQUIRE VEGETATIVE COVER FOR LESS THAN 1 YEAR. REQUIRE TEMPORARY SEEDING FOR EROSION CONTROL. SEEDING FOR EROSION CONTROL SHALL BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES AND SPECIFICATIONS

#### **EROSION CONTROL NOTES**

- CONTRACTOR IS RESPONSIBLE TO NOTIFY ENGINEER OF RECORD AND OFFICIALS OF ANY CHANGES TO THE EROSION CONTROL AND STORMWATER MANAGEMENT PLANS. ENGINEER OF RECORD AND APPROPRIATE CITY OF BAXTER OFFICIALS MUST APPROVE ANY CHANGES PRIOR TO DEVIATION FROM THE APPROVED PLANS.
- 2. ALL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED BY THE CONTRACTOR IN ACCORDANCE WITH THE MINNESOTA DEPARTMENT OF NATURAL RESOURCES (IDNR) TECHNICAL STANDARDS (REFERRED TO AS BMP'S) AND CITY OF BAXTER ORDINANCE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN A COPY OF THESE STANDARDS. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY ADDITIONAL EROSION CONTROL MEASURES WHICH MAY BE NECESSARY TO MEET UNFORESEEN FIELD CONDITIONS.
- 5. INSTALL PERIMETER EROSION CONTROL MEASURES (SUCH AS CONSTRUCTION ENTRANCES, SILT FENCE AND EXISTING INLET PROTECTION) PRIOR TO ANY SITE WORK, INCLUDING GRADING OR DISTURBANCE OF EXISTING SURFACE COVER. ÁS SHOWN ON PLAN. MODIFICATIONS TO THE APPROVED EROSION CONTROL DESIGN IN ORDER TO MEET UNFORESEEN FIELD CONDITIONS IS ALLOWED IF MODIFICATIONS CONFORM TO BMP'S. ALL DESIGN MODIFICATIONS MUST BE APPROVED BY THE CITY OF BAXTER PRIOR TO DEVIATION OF THE APPROVED PLAN.
- 4. ADDITIONAL EROSION CONTROL MEASURES, AS REQUESTED BY STATE INSPECTORS, LOCAL INSPECTORS, COUNTY INSPECTORS AND/OR ENGINEER OF RECORD SHALL BE INSTALLED WITHIN 24 HOURS OF REQUEST.
- INSPECTIONS AND MAINTENANCE OF ALL EROSION CONTROL MEASURES SHALL BE ROUTINE (ONCE PER WEEK MINIMUM) TO ENSURE PROPER FUNCTION OF EROSION CONTROLS AT ALL TIMES. EROSION CONTROL MEASURES ARE TO BE IN WORKING ORDER AT THE END OF EACH WORK DAY.
- 6. ALL EROSION AND SEDIMENT CONTROL ITEMS SHALL BE INSPECTED WITHIN 24 HOURS OF ALL RAIN EVENTS EXCEEDING 0.5 INCHES. ANY DAMAGED EROSION CONTROL MEASURES SHALL BE REPAIRED OR REPLACED IMMEDIATELY UPON INSPECTION.
- CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT ALL LOCATIONS OF VEHICLE INGRESS/EGRESS POINTS. ADDITIONAL LOCATIONS OTHER THAN AS SHOWN ON THE PLANS MUST BE PRIOR APPROVED BY THE MUNICIPALITY. CONSTRUCTION ENTRANCES SHALL BE 50' LONG AND NO LESS THAN 12" THICK BY USE OF 3" CLEAR STONE. CONSTRUCTION ENTRANCES SHALL BE MAINTAINED BY THE CONTRACTOR IN A CONDITION WHICH WILL PREVENT THE TRACKING OF MUD OR DRY SEDIMENT ONTO ADJACENT PUBLIC STREETS AFTER EACH WORKING DAY OR MORE FREQUENTLY AS REQUIRED.
- 8. PAVED SURFACES ADJACENT TO CONSTRUCTION SITE VEHICLE ACCESS SHALL BE SWEPT AND/OR SCRAPED TO REMOVE ACCUMULATED SOIL, DIRT AND/OR DUST AFTER THE END OF EACH WORK DAY AND AS REQUESTED BY THE CITY OF BAXTER.
- 9. INLET PROTECTION SHALL BE IMMEDIATELY FITTED AT THE INLET OF ALL INSTALLED STORM SEWER AND SILT FENCE SHALL BE IMMEDIATELY FITTED AT ALL INSTALLED CULVERT INLETS TO PREVENT SEDIMENT DEPOSITION WITHIN STORM SEWER SYSTEMS.
- 10. INSTALL EROSION CONTROLS ON THE DOWNSTREAM SIDE OF STOCKPILES. IF STOCKPILE REMAINS UNDISTURBED FOR MORE THAN SEVEN (7) DAYS, TEMPORARY SEEDING AND STABILIZATION IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES IS REQUIRED. IF DISTURBANCE OCCURS BETWEEN NOVEMBER 15TH AND MAY 15TH, THE MULCHING SHALL BE PERFORMED BY HYDRO-MULCHING WITH A "TACKIFIFR "
- 11. DITCH CHECKS AND APPLICABLE EROSION NETTING/MATTING SHALL BE INSTALLED IMMEDIATELY AFTER COMPLETION OF GRADING EFFORTS WITHIN DITCHES/SWALES TO PREVENT SOIL TRANSPORTATION.
- 12. EROSION CONTROL FOR UTILITY CONSTRUCTION (STORM SEWER, SANITARY SEWER, WATER MAIN, ETC.): A. PLACE EXCAVATED TRENCH MATERIAL ON THE HIGH SIDE OF THE TRENCH. B. BACKFILL, COMPACT, AND STABILIZE THE TRENCH IMMEDIATELY AFTER PIPE CONSTRUCTION. C. DISCHARGE TRENCH WATER INTO A SEDIMENTATION BASIN OR FILTERING TANK IN ACCORDANCE WITH THE DEWATERING TECHNICAL STANDARD NO. 1061 PRIOR TO RELEASE INTO THE STORM SEWER, RECEIVING STREAM, OR DRAINAGE DITCH.
- 13. ALL SLOPES 5:1 OR GREATER SHALL BE STABILIZED WITH CLASS I. TYPE B EROSION MATTING OR APPLICATION OF A MINNESOTA DEPARTMENT OF TRANSPORTATION (IDOT) APPROVED POLYMER SOIL STABILIZATION TREATMENT OR A COMBINATION THEREOF, AS REQUIRED WITHIN 7 DAYS OF REACHING FINAL GRADE AND/OR AS SOON AS CONDITIONS ALLOW. DRAINAGE SWALES SHALL BE STABILIZED WITH CLASS II, TYPE B EROSION MATTING. EROSION MATTING AND/OR NETTING USED ONSITE SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S GUIDELINES AND WDNR TECHNICAL STANDARDS 1052 AND 1053.
- 14. CONTRACTOR SHALL TAKE ALL NECESSARY STEPS TO CONTROL DUST ARISING FROM CONSTRUCTION OPERATIONS.
- 15. EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL ALL LAND DISTURBING CONSTRUCTION ACTIVITY AT THE SITE HAS BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE COVER HAS BEEN ESTABLISHED WITH A DENSITY OF AT LEAST 70% FOR UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES OR THAT EMPLOY EQUIVALENT PERMANENT STABILIZATION MEASURES.
- 16. ALL STABILIZATION METHODS THAT INCORPORATE SEEDING ARE TO INCLUDE THE USE OF MULCH.

#### 17. STABILIZATION PRACTICES:

- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. NO MORE THAN SEVEN (7) DAYS SHALL PASS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS CEASED UNLESS: THE INITIATION STABILIZATION MEASURES BY THE SEVENTH (7) DAY AFTER CONSTRUCTION 17.2.
- ACTIVITY HAS CEASED IS PRECLUDED BY SNOW COVER. IN THAT EVENT, STABILIZATION SHALL BE INITIATED AS SOON AS PRACTICABLE. 17.3. CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN FOURTEEN (14)
- DAYS FROM WHEN ACTIVITY CEASED, (I.E. THE TOTAL TIME PERIOD THAT THE CONSTRUCTION ACTIVITY IS TEMPORARILY CEASED IS LESS THAN FOURTEEN (14) DAYS. IN THAT EVENT, STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE BY THE SEVENTH (7) DAY AFTER CONSTRUCTION ACTIVITY HAS TEMPORARILY CEASED. 17.4. STABILIZATION MEASURES SHALL BE DETERMINED BASED ON SITE CONDITIONS AT THE TIME OF CONSTRUCTION ACTIVITY HAS CEASED, INCLUDING BUT NOT LIMITED TO WEATHER
  - CONDITIONS AND LENGTH OF TIME MEASURE MUST BE EFFECTIVE. THE FOLLOWING ARE ACCEPTABLE STABILIZATION MEASURES: • PERMANENT SEEDING; IN ACCORDANCE WITH APPROVED CONSTRUCTION SPECIFICATION • TEMPORARY SEEDING; MAY CONSIST OF SPRING OATS(100LBS/ACRE) AND/OR WHEAT
  - OR CEREAL RYE (150LB/ACRE) HYDRO-MULCHING WITH A TACKIFIER
  - GEOTEXTILE EROSION MATTING SODDING

#### **EROSION CONTROL MAINTENANCE SCHEDULE**

THE FOLLOWING MAINTENANCE SCHEDULE HAS BEEN PROVIDED. THE INSPECTOR MUST PERFORM THE INSPECTIONS. THE OPERATOR/CONTRACTOR MUST PERFORM ALL NEEDED MAINTENANCE. FURTHERMORE, ALL EROSION CONTROL FEATURE REQUIRING MAINTENANCE MAY NOT BE LISTED BELOW. THE OPERATOR/CONTRACTOR AND INSPECTOR MUST PERFORM THEIR RESPECTIVE DUTIES ON ALL BMP'S THAT ARE NOT LISTED BELOW AS WELL.

- UNDER ANY CIRCUMSTANCES.

- HAS BEEN PROPERLY STABILIZED.

- MOWING

1. CONSTRUCTION ENTRANCE — THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE OR THE WASHING AND REWORKING OF EXISTING STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED. DROPPED, WASHED. OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED ONTO ROADWAYS WILL NOT BE PERMITTED

2. STRAW BALE BARRIER - THE MAINTENANCE MEASURES ARE AS FOLLOWS: (2.1) STRAW BALE BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL; (2.2) CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED BALES, END RUNS AND UNDERCUTTING BENEATH BALES; (2.3) NECESSARY REPAIRS TO BARRIERS OR REPLACEMENT OF BALES SHALL BE ACCOMPLISHED PROMPTLY; (2.4) SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH RAINFALL, THEY MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER; AND (2.5) ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE STRAW BALE BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

3. SILT FENCE - THE MAINTENANCE MEASURES ARE AS FOLLOWS: (3.1) SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL, ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY; (3.2) CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM END RUNS AND UNDERCUTTING: (3.3) SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER IS STILL NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY; (3.4) SEDIMENT DEPOSITS MUST BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER; AND (3.5) ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

4. STORM DRAIN INLET PROTECTION - THE MAINTENANCE MEASURES ARE AS FOLLOWS: (4.1) STRUCTURES SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NECESSARY AND (4.2) STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA

TEMPORARY DIVERSION DIKE - THE MEASURE SHALL BE INSPECTED AFTER EVERY STORM AND REPAIRS MADE TO THE DIKE, FLOW CHANNEL, OUTLET OR SEDIMENT TRAPPING FACILITY, AS NECESSARY. ONCE EVERY TWO WEEKS, WHETHER A STORM EVENT HAS OCCURRED OR NOT, THE MEASURE SHALL BE INSPECTED AND REPAIRS MADE IF NEEDED. DAMAGES CAUSED BY CONSTRUCTION TRAFFIC OR OTHER ACTIVITY MUST BE REPAIRED BEFORE THE END OF EACH WORKING DAY.

6. TEMPORARY FILL DIVERSION - SINCE THE PRACTICE IS TEMPORARY AND UNDER MOST SITUATIONS WILL BE COVERED THE NEXT WORKING DAY. THE MAINTENANCE REQUIRED SHOULD BE LOW. IF THE PRACTICE IS TO REMAIN IN USE FOR MORE THAN ONE DAY, AN INSPECTION SHALL BE MADE AT THE END OF EACH WORK DAY AND REPAIRS MADE TO THE MEASURE IF NEEDED. THE OPERATOR/CONTRACTOR SHOULD AVOID THE PLACEMENT OF ANY MATERIAL OVER THE STRUCTURE WHILE IT IS IN USE. CONSTRUCTION TRAFFIC SHOULD NOT BE PERMITTED TO CROSS THE DIVERSION.

7. TEMPORARY SEDIMENT TRAP - THE MAINTENANCE MEASURES ARE AS FOLLOWS: (7.1) SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE HALF THE DESIGN VOLUME OF THE WET STORAGE, SEDIMENT REMOVAL FROM THE BASIN SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE AND CAUSE SEDIMENTATION PROBLEMS; (7.2) FILTER STONE SHALL BE REGULARLY CHECKED TO ENSURE THAT FILTRATION PERFORMANCE IS MAINTAINED, STONE CHOKED WITH SEDIMENT SHALL BE REMOVED AND CLEANED OR REPLACED; AND (7.3) THE STRUCTURE SHOULD BE CHECKED REGULARLY TO ENSURE THAT IT IS STRUCTURALLY SOUND AND HAS NOT BEEN DAMAGED BY EROSION OR CONSTRUCTION EQUIPMENT, THE HEIGHT OF THE STONE OUTLET SHOULD BE CHECKED TO ENSURE THAT ITS CENTER IS AT LEAST 1 FOOT BELOW THE TOP OF THE EMBANKMENT.

8. TEMPORARY SEDIMENT BASIN - THE BASIN EMBANKMENT SHOULD BE CHECKED REGULARLY TO ENSURE THAT IT IS STRUCTURALLY SOUND AND HAS NOT BEEN DAMAGED BY EROSION OR CONSTRUCTION EQUIPMENT. THE EMERGENCY SPILLWAY SHOULD BE CHECKED REGULARLY TO ENSURE THAT ITS LINING IS WELL ESTABLISHED AND EROSION-RESISTANT. THE BASIN SHOULD BE CHECKED AFTER EACH RUNOFF PRODUCING RAINFALL FOR SEDIMENT CLEANOUT AND TRASH REMOVAL. WHEN THE SEDIMENT REACHES THE CLEANOUT LEVEL, IT SHALL BE REMOVED AND PROPERLY DISPOSED OF.

9. TEMPORARY SEEDING - AREAS WHICH FAIL TO ESTABLISH VEGETATIVE COVER ADEQUATE TO PREVENT RILL EROSION WILL BE RE-SEEDED AS SOON AS SUCH AREAS ARE IDENTIFIED. CONTROL WEEDS BY

10. PERMANENT SEEDING - THE MAINTENANCE MEASURES ARE AS FOLLOWS: (10.1) IN GENERAL, A STAND OF VEGETATION CANNOT BE DETERMINED TO BE FULLY ESTABLISHED UNTIL IT HAS BEEN MAINTAINED FOR ONE FULL YEAR AFTER PLANNING; (10.2) NEW SEEDLINGS SHALL BE SUPPLIED WITH ADEQUATE MOISTURE, SUPPLY WATER AS NEEDED, ESPECIALLY LATE IN THE SEASON, IN ABNORMALLY HOT OR DRY CONDITIONS, OR ON ADVERSE SITES, WATER APPLICATIONS SHALL BE CONTROLLED TO PREVENT EXCESSIVE RUNOFF; (10.3) INSPECT ALL SEEDED AREAS FOR FAILURES AND MAKE NECESSARY REPAIRS, REPLACEMENTS, AND RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE; [10.3.A] IF STAND IS INADEQUATE FOR EROSION CONTROL, OVER SEED AND FERTILIZE USING HALF OF THE RATES ORIGINALLY SPECIFIED; [10.3.B] IF STAND IS 60% DAMAGED, RE-ESTABLISH FOLLOWING SEEDBED AND SEEDING RECOMMENDATIONS: [10.3.C] IF STAND HAS LESS THAN 40% COVER. RE-EVALUATE CHOICE OF PLANT MATERIALS AND QUANTITIES OF LIME AND FERTILIZER, THE SOIL MUST BE TESTED TO DETERMINE IF ACIDITY OR NUTRIENT IMBALANCES ARE RESPONSIBLE, RE-ESTABLISH THE STAND FOLLOWING SEEDBED AND SEEDING RECOMMENDATIONS.

11. MULCHING - ALL MULCHES AND SOIL COVERINGS SHOULD BE INSPECTED PERIODICALLY (PARTICULARLY AFTER RAINSTORMS) TO CHECK FOR EROSION. WHERE EROSION IS OBSERVED IN MULCHED AREAS, ADDITIONAL MULCH SHOULD BE APPLIED. NETS AND MATS SHOULD BE INSPECTED AFTER RAINSTORMS FOR DISLOCATION OR FAILURE. IF WASHOUTS OR BREAKAGE OCCUR. REINSTALL NETTING OR MATTING AS NECESSARY AFTER REPAIRING DAMAGE TO THE SLOPE OR DITCH. INSPECTIONS SHOULD TAKE PLACE UNTIL GRASSES ARE FIRMLY ESTABLISHED. WHERE MULCH IS USED IN CONJUNCTION WITH ORNAMENTAL PLANTINGS. INSPECT PERIODICALLY THROUGHOUT THE YEAR TO DETERMINE IF MULCH IS MAINTAINING COVERAGE OF THE SOIL SURFACE; REPAIR AS NEEDED.

12. SOIL STABILIZATION BLANKETS & MATTING - ALL SOIL STABILIZATION BLANKETS AND MATTING SHOULD BE INSPECTED PERIODICALLY FOLLOWING INSTALLATION, PARTICULARLY AFTER RAINSTORMS TO CHECK FOR EROSION AND UNDERMINING. ANY DISLOCATION OR FAILURE SHOULD BE REPAIRED IMMEDIATELY. IF WASHOUTS OR BREAKAGE OCCURS, REINSTALL THE MATERIAL AFTER REPAIRING DAMAGE TO THE SLOPE OR DITCH. CONTINUE TO MONITOR THESE AREAS LINTIL WHICH TIME THEY BECOME PERMANENTLY STABILIZED; AT THAT TIME AN ANNUAL INSPECTIONS SHOULD BE ADEQUATE.


13. STREET CLEANING / SWEEPING - THE MAINTENANCE MEASURES ARE AS FOLLOWS: (13.1) EVALUATE ACCESS POINTS DAILY FOR SEDIMENT TRACKING; (13.2) WHEN TRACKED OR SPILLED SEDIMENT IS FOUND ON PAVED SURFACES, IT WILL BE REMOVED DAILY, DURING TIMES OF HEAVY TRACK-OUT SUCH AS DURING RAINS, CLEANING MAY BE DONE SEVERAL TIMES THROUGHOUT THE DAY; (13.3) UNKNOWN SPILLS OR OBJECTS WILL NOT BE MIXED WITH THE SEDIMENT; AND (13.4) IF SEDIMENT IS MIXED WITH OTHER POLLUTANTS, IT WILL BE DISPOSED OF PROPERLY AT AN AUTHORIZED LANDFILL.



SD PROJECT NO:


	JSL	J
CREATE THE \	VISION TELL THE S	STORY
MADISC	jsdinc.com DN REGIONAL OFFICI ORIZON DRIVE, SUITE 101	 E
VER	NN2.0N DRIVE, SOITE 101 20NA, WISCONSIN 53593 P. 608.848.5060	_
CLIENT: MENARD	, INC.	
CLIENT ADDRESS 5101 MENAF EAU CLAIRE	RD DRIVE	
PROJECT:		
	S LUMBER YA RKING LOT	RD
	ON: WOOD DRIVE	
	ROW WING COUNTY	
		FIELO ROOM
		L F
PLAN MODIFICATI <u>#</u> Date: 1 07.01.2022	IONS: Description: 50% DOCUMENT REVIEW	
2 07.15.2022 3	MUNICIPAL SUBMITTAL	
4 5		
6 7		
8		
10 11 12		
12 13		
14 15		
Designed Pro		
Designed By: Reviewed By:		JAW PMP
Approved By: SHEET TITLE:		HPJ H
	L NOTES	
SHEET NUMBER:		JAW PMP HPJ HPJ
(	CO.1	

22-11222





-ile: I:\2022\2211222\DWG\Civil Sheets\C1.0 - EXCON.dwg Lavout: C1.0 User: iwebb Plotted: Jul 15. 2022 - 1:04pm Xref


	<section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><section-header><text></text></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header>
	CLIENT ADDRESS: 5101 MENARD DRIVE EAU CLAIRE, WI 54703
	PROJECT: <b>MENARDS LUMBER YARD</b> <b>AND PARKING LOT</b> <b>EXPANSION</b> PROJECT LOCATION: 15236 DELLWOOD DRIVE BAXTER, CROW WING COUNTY MINNESOTA, 56401
<b>GENERAL NOTES</b> 1. EXISTING CONDITIONS SURVEY DATA AND BASEMAP COMPLETED AND PROVIDED BY OTHERS. 2. REFER TO THE EXISTING CONDITIONS SURVEY (PREFORMED BY OTHERS) FOR EXISTING CONDITIONS NOTES AND LEGENDS. 3. EXISTING CONDITIONS WERE SUPPLEMENT WITH DESIGN INFORMATION FROM PREVIOUS STORE IMPROVEMENTS PROVIDED BY THE OWNER 3. IT IS THE CONTRACTOR'S/BIDDER'S RESPONSIBILITY TO VERIFY ALL EXISTING CONDITIONS. 4. PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR: 4.1 FXAMINE ALL STIE CONDITIONS BELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING	PLAN MODIFICATIONS:         #       Date:       Description:         1       07.01.2022       50% DOCUMENT REVIEW         2       07.15.2022       MUNICIPAL SUBMITTAL         3
<ul> <li>4. PRIOR TO CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR:</li> <li>4.1. EXAMINE ALL SITE CONDITIONS RELATIVE TO THE CONDITIONS INDICATED ON THE ENGINEERING DRAWINGS. ANY DISCREPANCIES ARE TO BE REPORTED IMMEDIATELY TO THE ENGINEER AND RESOLVED PRIOR TO THE START OF CONSTRUCTION.</li> <li>4.2. VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCIES. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCIES ARE RESOLVED.</li> <li>A.2. VERIFYING UTILITY ELEVATIONS AND NOTIFYING ENGINEER OF ANY DISCREPANCIES. NO WORK SHALL BE PERFORMED UNTIL THE DISCREPANCIES ARE RESOLVED.</li> </ul>	Approved By: HPJ SHEET TITLE: EXISTING CONDITIONS MAP SHEET NUMBER: C1.0





	CREATE THE VISION TELL THE STORY jsdinc.com MADISON REGIONAL OFFICE 161 HORIZON DRIVE, SUITE 101 VERONA, WISCONSIN 53593 P. 608.848.5060 CLIENT: MENARD, INC.
VAL OF	CLIENT ADDRESS: 5101 MENARD DRIVE EAU CLAIRE, WI 54703
REMOVAL/ABANDONING OF WELL, CONTRACTOR TO COORDINATE WITH ALL STATE AND LOCAL REQUIREMENTS CONTRACTOR TO FIELD VERIFY EXTENTS OF CLEARING AND GRUBBING, TYP. DETENTION POND	PROJECT: MENARDS LUMBER YARD AND PARKING LOT EXPANSION PROJECT LOCATION: 15236 DELLWOOD DRIVE BAXTER, CROW WING COUNTY MINNESOTA, 56401
	#       Date:       Description:         1       07.01.2022       50% DOCUMENT REVIEW         2       07.15.2022       MUNICIPAL SUBMITTAL         3
SCALE IN FEET	EXAMPLE 22-11222


















22/2211222/DWG/Civil Sheets/C4.0 - SWPPP.dwg Lavout: C4.0 User: jwebb Plotted: Jul 15, 2022 - 3:34r







			<section-header><text><text><text><text><text><text></text></text></text></text></text></text></section-header>
			CLIENT ADDRESS: 5101 MENARD DRIVE EAU CLAIRE, WI 54703
			PROJECT: MENARDS LUMBER YARD AND PARKING LOT EXPANSION PROJECT LOCATION: 15236 DELLWOOD DRIVE BAXTER, CROW WING COUNTY MINNESOTA, 56401
			PLAN MODIFICATIONS:           #         Date:         Description:           1         07.01.2022         50% DOCUMENT REVIEW           2         07.15.2022         MUNICIPAL SUBMITTAL           3
40'	SCALE IN FEET	<b>EXAMPLE 1</b> <b>EXAMPLE 1</b> <b>EXAM</b>	Designed By:       JAW         Reviewed By:       PMP         Approved By:       HPJ         SHEET TITLE:       GRADING AND DRAINAGE         PLAN - YARD EXPANSION       SHEET NUMBER:         SHEET NUMBER:       C55.1         JSD PROJECT NO:       22-11222









		[]
LEGEND		
	PROPERTY LINE	
	RIGHT-OF-WAY EASEMENT LINE	
	BUILDING OUTLINE	<b>NJSD</b>
	BUILDING OVERHANG	
	EDGE OF PAVEMENT	
	STANDARD CURB AND GUTTER	CREATE THE VISION TELL THE STORY
	REJECT CURB AND GUTTER	
	MOUNTABLE CURB AND GUTTER	jsdinc.com
•••••	ASPHALT PAVEMENT HEAVY DUTY ASPHALT PAVEMENT	MADISON REGIONAL OFFICE
	CONCRETE PAVEMENT	161 HORIZON DRIVE, SUITE 101 VERONA, WISCONSIN 53593
+ + + + + + + + + + + + + + + + + + + +	HEAVY DUTY CONCRETE PAVEMENT	P. 608.848.5060
· · · ·	STORMWATER MANAGEMENT AREA	CLIENT: MENARD, INC.
	RETAINING WALL	
S S	SANITARY SEWER	
	WATERMAIN STORM SEWER	
<u> </u>		
		CLIENT ADDRESS:
		5101 MENARD DRIVE
		EAU CLAIRE, WI 54703
 <u>.</u>		
i I		
İ		
i		
i I		MENARDS LUMBER YARD
		EXPANSION
		PROJECT LOCATION:
		BAXTER, CROW WING COUNTY
		15236 DELLWOOD DRIVE BAXTER, CROW WING COUNTY MINNESOTA, 56401
İ		
i		
ľ		
l		
ł		l ا
		PLAN MODIFICATIONS:         Description:         Home           1         07.01.2022         50% DOCUMENT REVIEW         Home           2         07.15.2022         MUNICIPAL SUBMITTAL         Home         Home           3
 		PLAN MODIFICATIONS:
		#         Date:         Description:           1         07.01.2022         50% DOCUMENT REVIEW
		2     07.15.2022     MUNICIPAL SUBMITTAL     2       3     07.15.2022     07.15.2022
		· · · · · · · · · · · · · · · · · · ·
		$\left[\frac{7}{8}\right]$ $\left[\frac{3}{2}\right]$
		9 []
		$\frac{12}{12}$
		Reviewed By:     PMP       Approved By:     HPJ
		SHEET TITLE:
		UTILITY PLAN - YARD
	north	EXPANSION
	SCALE IN FEET	
	40' 0 40'	
		SHEET NUMBER:
		C5.1
	GOPHER STATE ONE CALL	
	811   800-252-1166	JSD PROJECT NO: 22-11222







22\2211222\DWG\Civil Sheets\C7.0 - DETAILS.dwg Layout: C7.1 User: jwebb Plotted: Jul 15, 2022 - 4:32pm

