
HERITAGE CHURCH PARKING LOT ADDITION

13242 BERRYWOOD DR. BAXTER, MN 56425



	SHEET INDEX
SHEET NUMBER	SHEET TITLE
C1.00	TITLE SHEET
C1.01	CIVIL LEGEND
C2.01 - C2.04	SWPPP DETAILS
C2.05 - C2.09	CIVIL DETAILS
C2.10 - C2.11	ADA DETAILS
C3.01	SWPPP NARRATIVE
C3.02	SWPPP MAPS
C4.01	EXISTING CONDITIONS & REMOVALS PLAN
C5.01	SITE PLAN
C5.02	ADA STALL PLAN
C6.01	GRADING PLAN
C7.01	EROSION CONTROL PLAN
C8.01	UTILTIY PLAN
L1.01	LANDSCAPE PLAN
L9.01	LANDSCAPE DETAILS



SURVEY MONUMENTS	EXISTING UTILITY MUNICIPAL SYMBOLS (cont.)	PROPOSED UTILITY MUNICIPAL SYMBOLS	EXISTING TOPOGRAPHIC LINES	PROPOSED CONSTRUCTION LINES
◆ BENCH MARK	STORM MANHOLE	■ APRON PROPOSED		—○—○—○— FENCE CHAIN LINK PROPOSED
FOUND CIM	*So WATER CURB STOP	● ^{CO} SANITARY CLEANOUT PROPOSED	EDGE OF WOODS	——————— FENCE WOOD PROPOSED
▲ FOUND CPNT.	(H) WATER HANDHOLE	SANITARY LIFT STATION PROPOSED		
● FOUND JLM	WATER HYDRANT	SANITARY LIFT STATION VALVE MANHOLE PROPOSED	-○○	——FM —— FORCEMAIN PROPOSED
× FOUND LATH	W WATER MANHOLE	SANITARY MANHOLE PROPOSED		> SANITARY SEWER PROPOSED
• NS FOUND PIPE	-₩ WATER METER	SANITARY PLUG PROPOSED	——— FM ———— FORCEMAIN	— ss — ss — SANITARY SERVICE PROPOSED
× FOUND READING	⋈ ^W WATER VALVE	■ STORM CATCH BASIN PROPOSED	—— онс—— OVERHEAD CABLE TV	——→ STORM SEWER PROPOSED
© STAKED CIM	WATER WELL	STORM MANHOLE PROPOSED	OVERHEAD ELECTRIC	—— DT ——— STORM SEWER DRAIN TILE PROPOSED
△ STAKED CPNT.	UTILITY SIZE & TYPE	WATER 11 1/4° BEND PROPOSED	——— онт ———— OVERHEAD TELE	
© ^{IIN} STAKED JLM		✓ WATER 22 1/2° BEND PROPOSED	++++++++++++++++++++++++++++++++++++++	— ws — ws — WATERMAIN SERVICE PROPOSED
O STAKED PIPE	EXISTING UTILITY PRIVATE SYMBOLS	✓ WATER 45° BEND PROPOSED		REPORT SION AND
	€ ELEC GROUND LIGHT	₩ATER 90° BEND PROPOSED	> SANITARY SEWER	EROSION CONTROL LINES
	(H) ELEC HANDHOLE	[WATER CAP PROPOSED	ss SANITARY SEWER SERVICE	BALE CHECK
EXISTING TOPO SYMBOLS	ELEC LIGHT POLE	₩ WATER CROSS PROPOSED	——⇒—— STORM SEWER	- о -віо- о -віо- BIO ROLL
AC UNIT	© ELEC MANHOLE	WATER CURB STOP PROPOSED	——— DT ———— STORM SEWER DRAIN TILE	SILT FENCE
○ FENCE POST	ELEC METER	WATER HYDRANT PROPOSED	——— ugc——— UNDERGROUND CABLE TV	- ★ HD ★ HD ★ HD ─ SILT FENCE TYPE HEAVY DUTY
FLAG POLE	E ELEC PEDESTAL		——— uge——— UNDERGROUND ELECTRIC	- * MS * MS * MS SILT FENCE TYPE MACHINE SLICED
GUARD POST	© ELEC POLE	□ WATER SLEEVE PROPOSED	——— FOC ——— UNDERGROUND FIBER OPTIC	→ PA → PA → PA → PA → SILT FENCE TYPE PREASSEMBLED
>— GUY ANCHOR	ELEC SIGNAL	₩ WATER TEE PROPOSED	——— GAS ——— UNDERGROUND GAS	
- GUY POLE	ELEC TRANSFORMER BOX	₩ WATER VALVE PROPOSED	——— ugt ———— UNDERGROUND TELE	DESCRIE
ட் HANDICAP SYMBOL	GAS METER		WATERMAIN	HATCH PATTERN AND SHADING LEGEND
▼ MAILBOX	⋈ ^G GAS VALVE		ws WATERMAIN SERVICE	HATCH PATTERN AND SHADING LEGEND
SHRUB	C LP TANK	PROPOSED UTILITY PRIVATE SYMBOLS	· · · WETLAND EDGE	RANDOM RIPRAP
── SIGN DOUBLE POST	H TELE HANDHOLE	ELEC LIGHT POLE PROPOSED		SOD
→ SIGN SINGLE POST	TELE MANHOLE		R/W, LOT & EASEMENTS LINES	SEED SEED
** TREE CONIFER	T TELE PEDESTAL		BUILDING SETBACK LINE	HYDRAULIC STABILIZER
TREE DECIDUOUS	TELE POLE	EROSION CONTROL SYMBOLS SUBFACE DRAINAGE ARROW	LOT LINE PROPOSED	EROSION CONTROL BLANKET
和 TREE STUMP	HTV TV HANDHOLE	SURFACE DRAINAGE ARROW	EASEMENT LINE	TEMP. ROCK CONSTRUCTION ENTRANCE
○ ^{SD} TV DISH	□ TV PEDESTAL	STORM DRAIN INLET PROTECTION	EASEMENT LINE PROPOSED	BUILDING WALL HATCH
<u>₩</u> WETLAND SYMBOL			LOT LINE	BITUMINOUS SURFACE
Ç [™] YARD LIGHT		TRAFFIC CONTROL DEVICES & SYMBOLS	- O —— O —— MNDOT CONTROLLED ACCESS LINE	CONCRETE SURFACE
	SOIL BORING SYMBOLS	TRAFFIC CONTROL SIGN (1 POST)	RIGHT OF WAY EXISTING	GRAVEL SURFACE
	LASER-INDUCED FLUORESCE BORING LYSIMETER	TRAFFIC CONTROL SIGN (2 POST)		EASEMENT PATTERN
EXISTING UTILITY MUNICIPAL SYMBOLS		TYPE III BARRICADE		IG LOT
□ APRON		O DRUM CHANNELIZER		DOCUMENTATION SYMBOLS
(LS) LIFT STATION	P ^{PT} PERC TEST	••• FLASHING ARROW OR MESSAGE BOARD		SECTION APPOW
⊗ SANITARY CLEANOUT	PZ PIEZOMETER			SECTION ARROW - SECTION NUMBER TOP; PAGE OF SECTION BOTTOM
S SANITARY MANHOLE	RECOVERY WELL SB RECOVERY WELL			FAGE
□ STORM CATCH BASIN	Soil Boring			· · · · · · · · · · · · · · · · · · ·
CTODM INLET	△ ^{VP} SOIL VAPOR POINT			

STORM INLET

△^{VS} VAPOR SURVEY POINT

SHEET NO.
C1.01

J:\Heritage Church-49314\2024-10685\CADD\Civil\C-LG-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:11:28 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, INC.

SHEET NO.

1" X 2" X 24" LONG WOODEN STAKES.
STAKES SHALL BE DRIVEN THROUGH THE
BACK HALF OF THE SEDIMENT CONTROL LOG
AT AN ANGLE OF 45 DEGREES WITH THE
TOP OF THE STAKE POINTING UPSTREAM. (1)

BACKFILL AND COMPACT SOIL FROM
TRENCH ON UPGRADIENT SIDE OF
SEDIMENT CONTROL LOG

PLACE SEDIMENT CONTROL
LOG IN SHALLOW TRENCH
(1" TO 2" DEPTH)

TYPES: STRAW, WOOD FIBER, OR COIR


1" X 2" X 24" LONG WOODEN STAKES AS NEEDED. STAKES SHALL BE DRIVEN OVER THE SEDIMENT CONTROL LOG AT AN ANGLE OF 45 DEGREES WITH THE TOP OF THE STAKE POINTING UPSTREAM. (2)

FLOW


8"-10" EMBEDMENT DEPTH

TYPES: WOOD CHIP, COMPOST, OR ROCK

SEDIMENT CONTROL LOGS




TYPE 3 (ROCK WEEPER)




TYPE 5 (ROCK)

FILTER BERMS



TYPE 1 (COMPOST), TYPE 2 (SLASH MULCH), OR TYPE 4 (TOPSOIL)



BALE BARRIERS 3

NOTES:

REPP = ROLLED EROSION PREVENTION PRODUCT.

SEE SPECS. 2573, 3149, 3874, 3882, 3885, 3886, AND 3897.

- 1 SPACE BETWEEN STAKES SHALL BE A MAXIMUM OF 1'FOR DITCH CHECKS OR 2'FOR OTHER APPLICATIONS.
- 2 PLACE STAKES AS NEEDED TO PREVENT MOVEMENT OF SEDIMENT CONTROL LOGS PLACED ON SLOPES OR AS NEEDED DUE TO OTHER FACTORS. STAKES SHALL BE INCIDENTAL.
- 3 TO BE USED FOR CRITICAL PERIMETER CONTROL AREAS WHERE STANDING WATER OCCURS (6" MAXIMUM DEPTH). BALES SHALL CONSIST OF TYPE 1 MULCH OF APPROXIMATELY 14" X 18" X 36" LONG. BALES SHALL BE PLACED ON EDGE AND BUTTED TIGHT TO ADJACENT BALES.
- 4 INSTEAD OF TRENCHING, PLACE BALE ON THE REPP (BLANKET) AND WRAP BLANKET AROUND THE BALE. PLACE STAKE THROUGH BALE AND BLANKET.



STANDARD PLAN 5-297.405 2 OF 8

APPROVED: 1-8-2020
REVISED:

TEMPORARY SEDIMENT CONTROL

FILTER BERMS, SEDIMENT CONTROL LOGS, AND BALE BARRIERS


STATE PROJ. NO.: Mentage Church-49314\2024-10685\CADD\CivinC-D1-2024-10665.dwg Plotted by:Thomas Neits 6/28/2024-2:12-1 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, INC.


REVISION:

APPROVED: JANUARY 8, 2020

MARNI KARNOWSKI


CHIEF ENVIRONMENTAL OFFICER






HIGH STRENGTH GEOTEXTILE FABRIC (TWO LAYERS SEWN TOGETHER TO FORM POCKETS) TRAFFIC FLOW MIN. 2" DIA. HIGH TENSIL — REINFORCED RIBS

SHEET PAD





RUMBLE PAD CONSTRUCTION EXIT 57

~~~

ENTRANCE WIDTH

AS REQUIRED

SPECIFICATION.

NOTES:

SEE SPECS. 2573 & 3882.

- (1) MINIMUM LENGTH SHALL BE THE GREATER OF 50 FEET OR A LENGTH SUFFICIENT TO ALLOW A MINIMUM OF 5 TIRE ROTATIONS ON THE PROVIDED PAD. MINIMUM LENGTH SHALL BE CALCULATED USING THE LARGEST TIRE WHICH WILL BE USED IN TYPICAL OPERATIONS.
- (2) PROVIDE RADIUS OR WIDEN PAD SUFFICIENTLY TO PREVENT VEHICLE TIRES FROM TRACKING OFF OF PAD WHEN LEAVING SITE.
- (3) IF RUNOFF FROM DISTURBED AREAS FLOWS TOWARD CONSTRUCTION EXITS, PREVENT RUNOFF FROM DRAINING DIRECTLY TO PUBLIC ROAD OVER CONSTRUCTION EXIT BY CROWNING THE EXIT OR SLOPING TO ONE SIDE. IF SURFACE GRADING IS INSUFFICIENT, PROVIDE OTHER MEANS OF INTERCEPTING RUNOFF.
- (4) IF RUNOFF FROM CONSTRUCTION EXITS WILL DRAIN OFF OF PROJECT SITE, PROVIDE SEDIMENT TRAP WITH STABILIZED OVERFLOW.
- (5) IF A TIRE WASH OFF IS REQUIRED THE CONSTRUCTION EXITS SHALL BE GRADED TO DRAIN THE WASH WATER TO A SEDIMENT TRAP.
- (6) MINIMUM LENGTH OF RUMBLE PAD SHALL BE 20 FEET, OR AS REQUIRED TO REMOVE SEDIMENT FROM TIRES. IF SIGNIFICANT SEDIMENT IS TRACKED FROM THE SITE, THE RUMBLE PAD SHALL BE LENGTHENED OR THE DESIGN MODIFIED TO PROVIDE ADDITIONAL VIBRATION. WASH-OFF LENGTH SHALL BE AS REQUIRED TO EFFECTIVELY REMOVE CONSTRUCTION SEDIMENT FROM VEHICLE TIRES.
- (7) MAINTENANCE OF CONSTRUCTION EXITS SHALL OCCUR WHEN THE EFFECTIVENESS OF SEDIMENT REMOVAL HAS BEEN REDUCED. MAINTENANCE SHALL CONSIST OF REMOVING SEDIMENT AND CLEANING THE MATERIALS OR PLACING ADDITIONAL MATERIAL (SLASH MULCH OR CRUSHED ROCK) OVER SEDIMENT FILLED MATERIAL TO RESTORE EFFECTIVENESS.



**TRANSPORTATION** 

STANDARD PLAN 5-297.405 5 OF 8 APPROVED: 2-28-2017 **REVISED:** 


TEMPORARY SEDIMENT CONTROL


STABILIZED CONSTRUCTION EXIT STATE PROJ. NO. 10-11-12024-10685\CADD\CivinC-D1-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:12:20 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, I

C2.03

**REVISION:** APPROVED: 2-28-2017 CHIEF ENVIRONMENTAL OFFICER

SLASH MULCH OR CRUSHED ROCK





(A) MINIMUM TRENCH WIDTH SHALL ALLOW FOR SIX INCHES CLEARANCE ON EACH SIDE OF PIPE JOINT HUB.

(B) THE TRENCH MAY BE OVEREXCAVATED A MIN. OF 6" & BACKFILLED WITH COMPACTED GRANULAR MATERIALS WHEN ROCK, INCOMPRESSIBLE MATERIALS, OR UNSTABLE SOILS ARE ENCOUNTERED.

C) COMPACTED GRANULAR ENCASEMENT MATERIAL SHALL COVER THE TOP OF PIPE BY AT LEAST 12 " AND EXTEND THE FULL WIDTH OF THE TRENCH OR AT LEAST 2 1/2" TIMES THE PIPE DIAMETER ON EACH SIDE OF THE PIPE.


(D) BEDDING AND HAUNCHING MATERIAL SHALL BE PLACED AND COMPACTED TO PROVIDE FULL SUPPORT FOR THE LENGTH OF THE PIPE.


1 0-12' DEPTH TRENCH SLOPE DEPENDS ON SOIL TYPE.


2 12'-20' DEPTH TRENCH SLOPE DEPENDS ON SOIL TYPE.

3 0-20' DEPTH TRENCH SUPPORT OR SHIELD SYSTEM CAN BE UTILIZED TO REDUCE TRENCH WIDTH.

20' OR GREATER DEPTH TRENCH
EXCAVATION MUST BE DESIGNED BY A
LICENSED PROFESSIONAL ENGINEER.
CONTRACTOR SHALL HAVE THE DESIGN
COMPLETED AT HIS EXPENSE AND PROVIDE
A COPY TO THE OWNER AND THE PROJECT
ENGINEER (WSN).







HOT DIP GALVANIZED PER MN/DOT 3392 OR ASTM-A153

|       |              |                     |                  | BOLT           | HOL  | ES            |                     |              |             |
|-------|--------------|---------------------|------------------|----------------|------|---------------|---------------------|--------------|-------------|
|       |              | STANDARD            | DESIGN           |                |      |               | HEAVY DI            | ESIGN        |             |
|       | PIPE<br>SIZE | HOLE DIA.<br>REQ'D. | BOLT<br>DIA.     | BAR<br>SIZE    |      | PIPE<br>SIZE  | HOLE DIA.<br>REQ'D. | BOLT<br>DIA. | BAR<br>SIZE |
| 9     | 12"-24"      | 3/4"                | 5/8"             | 5/8"           | 9    | 12"-18"       | 3/4"                | 5/8"         | 3/4"        |
| ROUND | 27"-48"      | 7/8"                | 3/4"             | 3/4"           | OUND | 21"-48"       | 7/8"                | 3/4"         | 1"          |
|       | 54"-90"      | 1 1/8"              | 1"               | 1"             | ]윤[  | 54"-90"       | 1 1/8"              | 1"           | 1 1/4"      |
| I     | 22"-29"      | 3/4"                | 5/8"             | 5/8"           |      | 22"           | 3/4"                | 5/8"         | 3/4"        |
| ARCH  | 36"-59"      | 7/8"                | 3/4"             | 3/4"           | ARCI | 29"-59"       | 7/8"                | 3/4"         | 1"          |
| ₹     | 65"-88"      | 1 1/8"              | 1"               | 1"             | ₹    | 65"-88"       | 1 1/8"              | 1"           | 1 1/4"      |
| '     |              |                     | BOL <sup>-</sup> | T LG. = PIPE \ | ΝAL  | L THK. + 2 1/ | 2"                  |              |             |

TYPICAL PIPE BEDDING

TYPICAL PIPE BEDDING

--/--/--
© 2024 WIDSETH SMITH NOLTING

TRASH GUARD FOR CONC. FLARED ENDS

TRASH GUARD FOR CONC. FLARED ENDS

TRASH GUARD FOR CONC. FLARED ENDS

--/--/---
308A

\*\*EVISED DETAIL NO.


306A

\*\*ODE AND DETAIL NO.

306A


\*\*ODE AND DETAIL NO.

306A



THIS DETAIL APPLIES TO

SANITARY SEWER, STORM SEWER, WATERMAIN, AND ALL SERVICE PIPE.



SEE FLEXAMAT SPILLWAY DETAIL OR FLEXAMAT SWALE WITH GEOTEXTILE CHANNEL LINING DETAIL; AS SHOWN ON PLANS FOR CONSTRUCTION

NOTE:
WHERE THE STRUCTURE EDGE THAT CONNECTS TO THE FLEXAMAT IS CURVED OR WHERE THE FLEXAMAT TILES CAN NOT ALIGN PERFECTLY TO MATCH THE SHAPE OF THE STRUCTURE; TRIM THE FLEXAMAT BETWEEN BLOCKS TO BEST FIT THE STRUCTURE SHAPE & STILL ALLOW A SUFFICIENT GROUT CONNECTION.

### FLEXAMAT ANCHOR TRENCH DETAIL

SCALE: NONE

ERITAGE CHURCH PARKING LOT ADDITION
ERITAGE CHURCH
SCALE: AS SHOWN
DRAWN BY: TMR
CHECKED BY: WW
JOB NUMBER: 2024-10685


SCALE: AS SHOWN
DRAWN BY: TMR
CHECKED BY: WW
JOB NUMBER: 2024-10685


- 11

SHEET NO.

C2.05

J:\Heritage Church-49314\2024-10685\CADD\Civil\C-DT-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:12:41 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, INC







NOTE:
ALL PAINT USED FOR STRIPING SHALL CONFORM TO
STANDARD MNDOT REQUIREMENTS AS OUTLINED IN
MNDOT SPECIFICATION No. 3591. COLOR SHALL BE BRIGHT
WHITE.

#### **ACCESSIBLE STALL STRIPING DETAIL**

SCALE: NONE



SHEET NO. C2.07



SECURE THE ABUTMENT PARALLEL WITH FLOW BY INSTALLING 18" U-ANCHORS IN 2' INCREMENTS OR 20" STAINLESS STEEL ZIP TIES IN 1' INCREMENTS THROUGH THE EXTENSION OVERLAP.

FOR ADDITIONAL SECTIONS OF MAT, SECURE SEAM PERPENDICULAR WITH FLOW BY OVERLAPPING THE DOWNSTREAM SECTION 18" WITH UPSTREAM SECTION OF MAT. PRIOR TO INSTALLING OVERLAP, FLIP

UPSTREAM MAT BACK 24". EXCAVATE 2.25" OF SOIL 18" FROM END OF UPSTREAM MAT. DOWNSTREAM SECTION IS LAID IN THE SHALLOW TRENCH. RETURN AND TAMP SOIL OVER INITIAL EDGE AND SEED.

AT THE INITIAL LEADING EDGE OF THE FLEXAMAT PLUS ARMORED CHANNEL, EMBED THE MAT 18" IN A VERTICAL ANCHOR TRENCH. FILL AND COMPACT ANCHOR TRENCH WITH SUITABLE FILL. AT ENDING

SECURE OVERLAPS PERPENDICULAR TO FLOW BY INSTALLING 18" U-ANCHORS IN 2' INCREMENTS OR 20" STAINLESS STEEL ZIP TIES IN 1' INCREMENTS THROUGH THE OVERLAP. ZIP TIES SHALL

U ANCHORS OR ZIP TIES TO BE INSTALLED PERPENDICULAR TO FLOW. ZIP TIES SHALL ENCOMPASS 3 CORDS OF GEOGRID FROM EACH MAT.

FLIP END OF UPSTREAM MAT OVER THE SOIL COVERED AND SEEDED INITIAL LEADING EDGE OF DOWNSTREAM MAT.

ENCOMPASS 3 CORDS OF GEOGRID FROM EACH MAT.

4.2.


5.1.

Info@Flexamat.com

Flexamat.com



C2.08



## IFLEXAMAT STANDARD - SLOPE ARMORING

#### **CONSTRUCTION NOTES:**

- 1. AN ENGINEER OR MANUFACTURERS REPRESENTATIVE SHALL BE ONSITE FOR THE START OF THE INSTALLATION.
- 2. ALL SUBGRADE SURFACES PREPARED FOR PLACEMENT OF MATS SHALL BE SMOOTH AND FREE OF ALL ROCKS, STICKS, ROOTS, OTHER PROTRUSIONS, OR DEBRIS OF ANY KIND.
- 3. PRIOR TO FLEXAMAT STANDARD INSTALLATION SEED AND FERTILIZE SUBGRADE WITH SITE SPECIFIC SEED MIX IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS.
- 4. INSTALL FLEXAMAT STANDARD ROLLS THAT ARE CONTINUOUS FOR ENTIRE SLOPE LENGTH. FOR SLOPES LONGER THAN 16', USE MATS WITH EXTENSIONS CUT TO THE LENGTH OF THE SLOPE. INSTALL MATS TO THAT THE MATTING EXTENDS PAST THE CREST OF SLOPE AND INTO AN 18" ANCHOR TRENCH.
  - 4.1. FOR ARMORED SLOPE LENGTHS 16' OR LESS, INSTALL CURLEX ECB EQUALLY UNDER ADJACENT MATS. SECURE SEAM WITH #3 REBAR 18" U-ANCHORS IN 2' INCREMENTS THE LENGTH OF THE ABUTMENT.
- 4.2. ARMORED SLOPE LENGTHS LONGER THAN 16', INSTALL NEXT MAT OVER EXTENSIONS.
- 5. INSTALL SUBSEQUENT MATS OVER THE GEOGRID EXTENSION AND STANDARD UNDERLAYMENT EXTENSION OF THE PREVIOUSLY INSTALLED MAT. ENSURE THE GEOGRID AND STANDARD UNDERLAYMENT EXTENSIONS ARE LAYING FLAT ON THE SUBGRADE BEFORE INSTALLING ADJACENT MAT OVER THE EXTENSIONS.
- 6. INSTALL #3 REBAR 18" U-ANCHORS IN 2' INCREMENTS ACROSS THE GEOGRID AND STANDARD EXTENSION ABUTMENT. INSTALL ANCHORS PERPENDICULAR TO THE SLOPE DIRECTLY BEHIND FIRST ROW OF BLOCKS ON THE ADJACENT MAT.
- 7. AT THE END OF THE ARMORED SLOPE, IF HEAD CUT IS ANTICIPATED, EMBED THE MAT 18" IN A TERMINATION TRENCH. FILL AND COMPACT TERMINATION TRENCH WITH SUITABLE FILL.


## MOTZ ENTERPRISES, INC.

Flexamat
(513)772-6689
Info@Flexamat.com
Flexamat.com




HERITAGE CHURCH PARKING
HERITAGE CHURCH
13242 BERRYWOOD DR. BAX

C2.09



TRANSPORTATION



#### STORM WATER POLLUTION PREVENTION PLAN NARRATIVE:

#### Project Location

The Heritage Church site is located in the City of Baxter at 13242 Berrywood Dr, Baxter, MN 56425. A site location map has been provided detailing the location of the proposed improvements.

#### Existing Site Description:

The existing site consists of a church, school, parking lots, sidewalk, storm sewer and site related utilities. The stormwater runoff from the buildings and parking lots currently drain to existing catch basins that are connected by underground storm sewer that carry the stormwater to the College Pond infiltration basin east of the site. The south end of the property drains to an onsite depression in the southeast corner of the site. Access to the property is off Berrywood Drive and College Road.

#### Proposed Site Description:

The proposed improvements consist of an addition to the parking lot, storm sewer, and construction of an infiltration basin. The property is 13.34 acres in size and the total land disturbance will be 2.57 acres. The existing site is covered by 5.48 acres of impervious surface and the proposed site will be covered by 6.62 acres of impervious surface. The total impervious area will increase; therefore, permanent stormwater treatment is required from the NPDES and the City of Baxter. The construction of the infiltration basin will be completed to accommodate the necessary stormwater treatment required by the NPDES and City of Baxter.

The proposed infiltration basin will have a top elevation of 1197.0, an emergency overflow at 1196.0 and a bottom elevation of 1192.0. Runoff from the parking lot addition and part of the existing parking lot will sheet flow to nearby curb cuts that will direct the runoff to a grass swale where it then flows into the infiltration basin. A stormwater management plan has been developed and is available upon request and shall be considered part of this SWPPP.

The project will be disturbing under 5 acres; therefore, a temporary sediment control basin will not be required.

The disturbed area consists of Zimmerman-Urban land complex, which is hydrologic group A soil. The proposed drainage will not alter offsite drainage significantly by the proposed improvements. Only modifications will be incorporated to the interior drainage area boundaries.

#### Waters Within One Mile (Not Receiving Waters):

| *****        | *****         | ***** | *****   | *****    |
|--------------|---------------|-------|---------|----------|
| Water Body   | Water Body    | Type  | Special | Impaired |
| ID           | Name          |       | Water   | Water    |
| ******       | *****         | ***** | *****   | *****    |
| 07010104-656 | Mississippi   | River | Yes     | Yes      |
| 07010104-695 | Buffalo Creek | River | Yes     | Yes      |
| *****        | *****         | ***** | *****   | *****    |

#### Dates of Construction:

The project will be started summer 2024, with construction being completed in fall 2024.

#### Contact Information:

#### Owner:

Heritage Church Chad Sundberg, Director of Operations 13242 Berrywood Drive Baxter, MN 56425 218-829-3209

#### Contractor:

**TBD** 

| Estimated Erosion Prevention and Sediment Control Quantities          | <u>es</u> |        |
|-----------------------------------------------------------------------|-----------|--------|
| **************************************                                | У         |        |
| Seed Mixture MnDOT, Mix 22-111 Application Rate (100 LBS/ACRE)        | 1.26      | AC     |
| Seed Mixture MnDOT, Mix 25-151<br>Application Rate (400 LBS/ACRE)     | 1.26      | AC     |
| Seed Mixture MnDOT, Mix 33-261<br>Application Rate (35 LBS/ACRE)      | 0.21      | AC     |
| Hydraulic Reinforced Fiber Matrix<br>Application Rate (3900 LBS/ACRE) | 1.26      | AC     |
| Fertilizer Type 3 (10-10-20) Application Rate (300 LBS/ACRE)          | 1.26      | AC     |
| Stabilized Construction Exit                                          | 1         | EA     |
| Storm Drain Inlet Protection (MNDOT Spec. 2573)                       | 5         | EA     |
| Rolled Erosion Prevention Category 30<br>Natural (MNDOT Spec. 2575)   | 1,177     | SQ YDS |
| Articular Concrete Riprap (MNDOT Spec. 2511)                          | 90        | SQ YDS |
| Sediment Control Log                                                  | 104       | LF     |

(MNDOT Spec. 2575)

Silt Fence Type MS (MnDOT Spec. 2573) 737 LF

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

#### Dewatering:

It is anticipated that dewatering will not be required during portions of the utility installation.

#### Total disturbed area within project areas are as follows:

#### \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* Project Disturbed Area = 2.57 AC Existing Impervious Area = 5.48 AC 6.62 AC Proposed Impervious Area = \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

#### Unique Storm Water Management Features

There are two special and impaired waters (Mississippi River and Buffalo Creek) within one mile of the project site, but do not receive runoff from the site.

#### TMDL Implementation Plans Containing Storm Water Requirements

No TMDL Implementation Plans currently exist for the receiving waters on this project.

#### Long Term Maintenance

Long term maintenance of the permanent storm water management system will be by Heritage Church. The sump in drainage structure DS-01 and the infiltration basin shall be inspected annually. The infiltration basin shall be cleaned and restored to design grade after one half of the storage volume has been filled with sediment. The sump in the drainage structure DS-01 shall be cleaned out annually or if one half of the sump has been filled with sediment.

#### Erosion Control Supervisor Requirements

The Contractor must identify an Erosion Control Supervisor (ECS) who is knowledgeable and experienced in the application of erosion and sediment control Best Management Practices (BMP's). The ECS must work with the Contractor to oversee and implement the SWPPP, and the installation, inspection, and maintenance of erosion and sediment control BMP's before, during and after construction. The Contractor/ECS is required to comply with the training requirements in 2023 Permit Reference 21 of the NPDES Permit. The permittee(s) shall ensure that employees are properly trained in the following areas with certification proof provided at the pre-construction conference.

#### SWPPP Preparation:

Name: Thomas Rients

Dates of instruction and training specifics are on file at Widseth and are available upon request.

#### Site Manager:

|    | Name: <u>TBD</u>                     |
|----|--------------------------------------|
|    | Dates of Training:                   |
|    | Instructors Name providing Training: |
|    | Content of Training (incl. hours):   |
| ΜP | Installer:                           |
|    | Name: TBD                            |
|    | Dates of Training:                   |
|    | Instructors Name providing Training: |
|    | Content of Training (incl. hours):   |
|    |                                      |

The Contractor/ECS shall develop a chain of responsibility with all operators on the site to ensure that the SWPPP will be implemented and stay in effect until the project site has undergone Permit Termination Conditions in accordance with 2023 Permit Reference 13 of the NPDES Permit and a Notice of Termination (NOT) has been submitted to the MPCA in accordance with 2023 Permit Reference 4 of the NPDES Permit. The Contractor/ECS must routinely inspect the entire construction site at least once every seven days during active construction and within 24 hours after a rainfall event greater than 0.5 inch in 24 hours. The Contractor shall take action to eliminate any deficiencies found during these inspections. The Contractor must provide two rain gauges to be installed on the construction site. Inspections, maintenance, and documentation must be in accordance with the NPDES Permit 2023 Permit Reference 11. See 2023 Permit Reference 24.5 of the NPDES Permit for record retention requirements. Copies of the inspection records are to be submitted to the Engineer.

The Contractor/ECS must amend the SWPPP as necessary to include additional requirements, such as additional or modified BMP's, designed to correct problems or address situations in accordance with 2023 Permit Reference 6 of the NPDES Permit.

Individual Site Plans will be required by the E.C. Supervisor as deemed necessary. Refer to MnDot 1717.

A daily inspection log will be required by the E.C. Supervisor of all sediment, erosion, and materials on site (ie: chemicals, etc.). This log shall be kept current.

The E.C. Supervisor shall provide an inlet staging schedule and protection plan for the entire project. This plan and schedule shall be presented to the engineer at the pre-construction conference. Minimum requirements of the plan and schedule shall include:

- date of proposed inlet protection device installation
- protection device utilized
- estimated duration of device in operation
- schedule of subsequent devices that will be utilized for inlet protection

The contractor shall have a petroleum release plan and shall have all necessary materials on hand to implement the plan. All employees shall be trained in implementation of the plan. The MPCA shall be informed of any petroleum spills greater than 5 gallons.

#### STORM WATER POLLUTION PREVENTION PLAN NOTES:

#### Construction Practices to Minimize Storm Water Contamination

- Stockpiles should be constructed away from slopes and natural drainage ways and have sediment controls at the base prior to the initiation of stockpiling.
- Collected solid waste, sediment, asphalt and concrete millings, floating debris, paper, plastic, fabric, construction and demolition debris and other wastes must be disposed of properly and must comply with MPCA disposal requirements.
- No construction materials can be buried on site.
- Licensed sanitary waste management handler must dispose of sanitary waste.
- Fertilizers must be stored in covered locations.
- Restricted access to chemical storage areas must be provided to prevent vandalism.
- All chemicals must be stored in locked containers when not in use.
- Oil, gasoline, paint, and any hazardous substances must be properly stored, including secondary containment, to prevent spills, leaks or other discharge.
- Storage and disposal of hazardous waste must be in compliance with MPCA regulations.
- Vehicles must be monitored for leaks and preventative maintenance scheduled.
- Spill kits must be available during equipment fueling and maintenance operations.
- External washing of trucks and other construction vehicles must be limited to a defined area of the site. Runoff must be contained, and waste properly disposed of. No engine degreasing is allowed on site.
- Asphalt substances must be applied according to manufactures recommendations.
- Spray guns must be cleaned on removable surfaces such as tarpaulins.
- Contractor/Erosion Control Supervisor must make a spill response plan before the application of any chemical that may be harmful to the environment.
- All spills must be reported immediately. Spill cleanup materials must be available on site. Material shall include but not limited to brooms, mops, rags, gloves, absorbent material, sand plastic and metal containers. Spills that reach storm water conveyance systems connected to a Water of the State must be immediately reported to the MPCA State Duty Officer.
- Contractor must control weeds on the entire project site.
- Form release oil must be applied over a pallet covered with absorbent material to collect excess fluid. The absorbent material shall be replaced when saturated.
- Dust control must be provided as conditions warrant.
- If this project is not stabilized before winter conditions stop construction activities, it shall be the contractor's responsibility to ensure sediment does not reach a water of the state. A written plan of this activity shall be presented to the engineer 1 month before expected project shut down for the season occurs. This plan shall include but not be limited to:
  - date of proposed bmp employment
  - duration of bmp's employed
  - schedule of subsequent bmp's employed

Temporary and Permanent Erosion Control Practices

BMPs proposed for temporary and permanent erosion control are shown on the erosion control plan sheets and are further identified as follows:

#### Temporary Erosion Control Methods

All disturbed soil areas shall be temporarily mulched with Type 1 mulch within 7 days if the area is not being actively worked. Temporary seed mix 22-111 at a rate of 100 lbs/ac of Pure Live Seed will be used only in cases where disturbed soil areas are anticipated to remain unworked in excess of 7 days prior to placement of Type 1 mulch.

#### Permanent Erosion Control Methods

Permanent erosion control will be achieved by using Seed Mixture 25-151 at a rate of 400 lbs/ac of Pure Live Seed, Type 3 Fertilizer with a composition of 10-10-20 at a rate of 300 lbs/ac, and Hydraulic Soil Stabilizer, Type 5 at a rate of 3900 lbs/ac on all disturbed construction areas.

#### Temporary Sediment Control Methods

Silt fence and sediment control logs will be used as the primary control to prevent sediment from draining off the construction site.

Rock construction entrances shall be placed at all locations construction vehicles will be exiting the project area.

#### Unique Environmental Concerns

There are not wetlands adjacent to the project. The Mississippi River and Buffalo Creek are within one mile of the site boundary, but do not receive runoff from the site.

#### Timing of BMP Installation

Erosion and sediment control BMP's must be installed as necessary to minimize erosion from disturbed surfaces and capture sediment onsite. All BMP's must conform to 2023 Permit Reference 8 and 9 of the NPDES Permit.

#### **Erosion Prevention Practices**

The Contractor/ECS is responsible for the Erosion Prevention Practices contained in 2023 Permit Reference 8 of the NPDES Permit. The Contractor/ECS must plan for and implement appropriate construction phasing, vegetative buffer strips, horizontal slope grading and other construction practices that minimize erosion. The location of areas not to be disturbed must be delineated (marked) on the development site before work begins.

All exposed soil areas must be stabilized as soon as possible to limit soil erosion but in no case later than 14 days (7 days for sites discharging to special or impaired waters, see 2023 Permit Reference 24 of NPDES Permit) after the construction activity in that portion of the site has temporarily or permanently ceased.

The normal wetted perimeter of any temporary or permanent drainage ditch or swale that drains water from any portion of the construction site, or diverts water around the construction site, must be stabilized within 200 lineal feet from the property edge, or from the discharge into any surface water. Stabilization must be complete within 24 hours after connecting to surface water.

Pipe outlets must be provided with temporary or permanent energy dissipation within 24 hours after connection to a surface water.

#### **Sediment Control Practices**

The Contractor/ECS is responsible for the Sediment Control Practices contained in 2023 Permit Reference 9 of the NPDES Permit. Sediment Control Practices must be installed on all down gradient perimeters before any upgradient land disturbing activities begin. There shall be no unbroken slope length greater than 75 feet for slopes with a grade of 3:1 or steeper. These practices must remain in place until Permit Termination Conditions have been established in accordance with 2023 Permit Reference 13 of the NPDES Permit.

The timing of installation of Sediment Control Practices may be adjusted to accommodate short-term activities such as clearing or grubbing, or passage of vehicles. Short-term activities must be completed as quickly as possible, and the practices must be installed immediately after the activity is completed. However, the Sediment Control Practices must be installed before the next precipitation event even if the activity is not complete.

All storm drain inlets must be protected by appropriate BMP's during construction until all sources with potential for discharging to the inlet have been stabilized. Inlet protection may be removed if a specific safety concern has been identified and the procedure in 2023 Permit Reference 9.8 of the NPDES Permit is followed.

Temporary soil stockpiles must have silt fence or other effective sediment controls, and cannot be placed in surface waters, including stormwater conveyances such as curb and gutter systems, or conduit and ditches unless there is a bypass for stormwater.

Vehicle tracking of sediment from the construction site must be minimized by BMP's such as stone or wood chip pads, concrete or steel wash racks, or equivalent systems. Street sweeping with collection must be used if such BMP's are not adequate to prevent sediment from being tracked onto the street (see 2023 Permit Reference 9.12 of the NPDES Permit).

Dewatering related to the construction activity must comply with 2023 Permit Reference 10 of the NPDES Permit. Dewatering discharge that may have turbid or sediment laden discharge must be discharged to a temporary or permanent sedimentation basin on the project site whenever possible and BMP's must be implemented to prevent water containing sediment or other pollutants from being discharged to surface waters or downstream properties.

Contractor may construct temporary sedimentation basins in accordance with 2023 Permit Reference 14 of the NPDES Permit.

#### Pollution Prevention:

Each contractor on site is individually responsible for maintaining a clean and safe work site. The person responsible shall dispose of all solid waste properly and in compliance with the MPCA disposal requirements. Solid waste includes but is not limited to: collected sediment, asphalt and concrete millings, floating debris, paper, plastic, fabric, construction and demolition debris. The person responsible shall be responsible for all hazardous materials during construction. Oil, gasoline, grease, paint, and other hazardous substances must be properly stored, including secondary containment, to prevent spills, leaks and unwanted discharges. Restricted access to storage areas must be provided to prevent vandalism. Storage and disposal of hazardous waste must be in accordance with the MPCA regulations. External washing of trucks and other construction equipment is prohibited on this project site.

Concrete washout site: all liquid and solid wastes generated by concrete washout operations must be contained in a leak proof containment facility or impermeable liner. The liquid and solid wastes must not contact the ground, and there must not be runoff from the concrete washout operations or areas. Liquid and solid wastes must be disposed of properly and in compliance with the MPCA regulations. A sign must be installed adjacent to each washout facility to inform concrete equipment operators to utilize the proper facilities.

The following telephone numbers are provided for assistance to the contractors and are not necessarily comprehensive; it is the responsibility of the individual contractor to make sure of proper notification.

Poison Control (800) 222-1222 24 Hour Spill Emergency (800) 422-0798

#### <u>Payment</u>

Cost for permanent and temporary erosion and sediment control measures shown on the plans will be paid per unit bid prices. The costs to maintain and remove these devices shall be incidental to the bid items. The cost for temporary seeding, soil stabilization, or any additional temporary erosion and sediment control devices shall be paid according to MN/DOT Spec. 2573.5 or 2575.5 as applicable. All costs for documentation required by the Permit shall be incidental to other items unless a specific bid item is established.

#### Contacts


| *******       | *****  | ******        | ******       |
|---------------|--------|---------------|--------------|
| Agency        | Permit | Name          | Phone Number |
| ******        | ****** | ******        | ******       |
| MPCA          | NPDES  | Brian Green   | 507-206-2610 |
| Baxter        | City   | Trevor Walter | 218-454-5100 |
| SWPPP Design  | WSN    | Thomas Rients | 218-316-3639 |
| EC Supervisor | •      |               |              |


\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

#### Amendments to the SWPPP:

C3.01


J:\Heritage Church-49314\2024-10685\CADD\Civil\C-SW-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:13:43 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, INC





- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.
- UNLESS OTHERWISE NOTED, ALL MATERIALS, CONSTRUCTION TECHNIQUES AND TESTING SHALL CONFORM TO THE CURRENT EDITION OF THE "STANDARD SPECIFICATIONS FOR TRENCH EXCAVATION AND BACKFILL/SURFACE RESTORATION, WATERMAIN AND SERVICE LINE INSTALLATION AND SANITARY SEWER AND STORM SEWER INSTALLATION" AS PUBLISHED BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA AND THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION" AS PUBLISHED BY THE MINNESOTA DEPARTMENT OF TRANSPORTATION, CURRENT EDITION. THE CONTRACTOR SHALL BE REQUIRED TO FOLLOW ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY AND THE MINNESOTA PLUMBING CODE. THE CONTRACTOR SHALL
- THE CONTRACTOR SHALL RECEIVE THE NECESSARY PERMISSION/PERMITS FOR ALL WORK LOCATED OUTSIDE OF THE MUNICIPAL RIGHT-OF-WAY AND PROPERTY LIMITS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING INVERT LOCATIONS AND ELEVATIONS
- AT THE END OF EACH DAY, BERRYWOOD DRIVE SHALL BE CLEARED AND SWEPT OFF IF
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL AND SIGNAGE IN ANY WORK
- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS UTILITY QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-02. ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND
- PRIVATE LOCATES WILL BE DONE BY GOPHER STATE ONE CALL. ALL EROSION CONTROL MEASURES AS SHOWN ON THE EROSION CONTROL PLAN ARE TO BE IN PLACE PRIOR TO
- BITUMINOUS PAVEMENT, BUILDINGS, LIGHT POLES & BASES, ETC. NOT NOTED FOR DEMOLITION & REMOVAL DURING REMOVALS. ANY DAMAGED STRUCTURES TO REMAIN SHALL BE REPAIRED OR REPLACED AT NO COST TO THE OWNER.
- PAVEMENT SHALL BE PROTECTED AFTER REMOVALS THROUGH THE DURATION OF THE PROJECT. PAYMENT FOR SAWCUTTING WILL BE MADE ONLY ONCE. ADDITIONAL SAWCUTTING TO MAINTAIN A CLEAN SAWCUT EDGE WILL BE AT THE EXPENSE OF THE

C4.01



- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.
- UNLESS OTHERWISE NOTED, ALL MATERIALS, CONSTRUCTION TECHNIQUES AND TESTING SHALL CONFORM TO THE CURRENT EDITION OF THE "STANDARD SPECIFICATIONS FOR TRENCH EXCAVATION AND BACKFILL/SURFACE RESTORATION, WATERMAIN AND SERVICE LINE INSTALLATION AND SANITARY SEWER AND STORM SEWER INSTALLATION" AS PUBLISHED BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA AND THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION" AS PUBLISHED BY THE MINNESOTA DEPARTMENT OF TRANSPORTATION, CURRENT EDITION. THE CONTRACTOR SHALL BE REQUIRED TO FOLLOW ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY AND THE MINNESOTA PLUMBING CODE. THE CONTRACTOR SHALL REQUIRE ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY.
- THE CONTRACTOR SHALL RECEIVE THE NECESSARY PERMISSION/PERMITS FOR ALL WORK LOCATED OUTSIDE OF THE MUNICIPAL RIGHT-OF-WAY AND PROPERTY LIMITS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING INVERT LOCATIONS AND ELEVATIONS PRIOR TO BEGINNING CONSTRUCTION.
- AT THE END OF EACH DAY, BERRYWOOD DRIVE SHALL BE CLEARED AND SWEPT OFF IF NECESSARY.
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL AND SIGNAGE IN ANY WORK OR HUALING AREAS IN ACCORDANCE WITH MN MUTCD.

#### **GENERAL SITE PLAN NOTES**

- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38.2, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA".
- CONTRACTOR SHALL CALL GOPHER STATE ONE CALL PRIOR TO BEGINNING REMOVALS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER AND ENGINEER OF ANY DIFFERENCES BETWEEN THE FIELD AND
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING TRAFFIC CONTROL AND SHALL BE IN COMPLIANCE WITH THE MINNESOTA UNIFORM TRAFFIC CONTROL DEVICES MANUAL AND TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS FIELD MANUAL. THE TRAFFIC CONTROL SHALL BE APPROVED BY THE CITY PRIOR TO INSTALLATION.
- ALL CURB TO MEET MINNESOTA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR A TYPE "B612 CURB & GUTTER", UNLESS PLANS ARE MARKED OTHERWISE.
- ALL DIMENSIONS ARE TO BACK OF CURB UNLESS OTHERWISE NOTED.
- ALL CURB RADII ARE 5.0 FEET TO FACE OF CURB UNLESS OTHERWISE NOTED.


#### **IMPERVIOUS AREA TABLE**

| ITEM                      |       | AREA<br>(FT²) | IMPERVIOUS<br>(%) |
|---------------------------|-------|---------------|-------------------|
| PROPERTY AREA             | =     | 580,830       |                   |
| EXISTING IMPERVIOUS       | ARE/  | \S            |                   |
| BUILDINGS                 | =     | 66,419        | 11.449            |
| IMPERVIOUS PAVEMENT       | =     | 172,223       | 29.65%            |
| TOTAL EXISTING IMPERVIOUS | =     | 238,642       | 41.09%            |
| PROPOSED IMPERVIOUS       | S ARE | AS            |                   |
| BUILDINGS                 | =     | 66,419        | 11.449            |
| IMPERVIOUS PAVEMENT       | =     | 222,001       | 38.22%            |
| TOTAL IMPERVIOUS          | =     | 288,420       | 49.66%            |

#### PARKING CALCULATION TABLE


| EXISTING PARKING LOT                |   |     |
|-------------------------------------|---|-----|
| PARKING STALLS PROVIDED             | = | 283 |
| HANDICAP ACCESSIBLE STALLS PROVIDED | = | 12  |
| TOTAL STALLS                        | = | 295 |

| PARKING LOT ADDITION       |   |     |
|----------------------------|---|-----|
| EXISTING STALLS            | = | 244 |
| PROPOSED STALLS            | = | 147 |
| HANDICAP ACCESSIBLE STALLS | = | 14  |
| TOTAL STALLS               | = | 405 |



SCALE (IN FEET

C5.01



- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.
- UNLESS OTHERWISE NOTED, ALL MATERIALS, CONSTRUCTION TECHNIQUES AND TESTING SHALL CONFORM TO THE CURRENT EDITION OF THE "STANDARD SPECIFICATIONS FOR TRENCH EXCAVATION AND BACKFILL/SURFACE RESTORATION, WATERMAIN AND SERVICE LINE INSTALLATION AND SANITARY SEWER AND STORM SEWER INSTALLATION" AS PUBLISHED BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA AND THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION" AS PUBLISHED BY THE MINNESOTA DEPARTMENT OF TRANSPORTATION, CURRENT EDITION. THE CONTRACTOR SHALL BE REQUIRED TO FOLLOW ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY AND THE MINNESOTA PLUMBING CODE. THE CONTRACTOR SHALL REQUIRE ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY.
- THE CONTRACTOR SHALL RECEIVE THE NECESSARY PERMISSION/PERMITS FOR ALL WORK LOCATED OUTSIDE OF THE MUNICIPAL RIGHT-OF-WAY AND PROPERTY LIMITS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING INVERT LOCATIONS AND ELEVATIONS PRIOR TO BEGINNING CONSTRUCTION.
- AT THE END OF EACH DAY, BERRYWOOD DRIVE SHALL BE CLEARED AND SWEPT OFF IF NECESSARY.
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL AND SIGNAGE IN ANY WORK OR HUALING AREAS IN ACCORDANCE WITH MN MUTCD.

#### **GENERAL SITE PLAN NOTES**

- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS
  QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38.2,
  ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING
  SUBSURFACE UTILITY DATA".
- CONTRACTOR SHALL CALL GOPHER STATE ONE CALL PRIOR TO BEGINNING REMOVALS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER AND ENGINEER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING TRAFFIC CONTROL AND SHALL BE IN COMPLIANCE WITH THE MINNESOTA UNIFORM TRAFFIC CONTROL DEVICES MANUAL AND TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS FIELD MANUAL. THE TRAFFIC CONTROL SHALL BE APPROVED BY THE CITY PRIOR TO INSTALLATION.
- ALL CURB TO MEET MINNESOTA DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR A TYPE "B612 CURB & GUTTER", UNLESS PLANS ARE MARKED OTHERWISE.
- ALL DIMENSIONS ARE TO BACK OF CURB UNLESS OTHERWISE NOTED.
- ALL CURB RADII ARE 5.0 FEET TO FACE OF CURB UNLESS OTHERWISE NOTED.

#### IMPERVIOUS AREA TABLE


| IIVIPERVIOUS AREA         | I /\L | <i>,</i>      |                   |
|---------------------------|-------|---------------|-------------------|
| ITEM                      |       | AREA<br>(FT²) | IMPERVIOUS<br>(%) |
| PROPERTY AREA             | =     | 580,830       |                   |
| EXISTING IMPERVIOUS A     | RE/   | <b>NS</b>     | 1                 |
| BUILDINGS                 | =     | 66,419        | 11.44%            |
| IMPERVIOUS PAVEMENT       | =     | 172,223       | 29.65%            |
| TOTAL EXISTING IMPERVIOUS | =     | 238,642       | 41.09%            |
| PROPOSED IMPERVIOUS       | ARE   | AS            |                   |
| BUILDINGS                 | =     | 66,419        | 11.44%            |
| IMPERVIOUS PAVEMENT       | =     | 222,001       | 38.22%            |
| TOTAL IMPERVIOUS          | =     | 288,420       | 49.66%            |

#### PARKING CALCULATION TABLE


| EXISTING PARKING LOT                |   |     |
|-------------------------------------|---|-----|
| PARKING STALLS PROVIDED             | = | 283 |
| HANDICAP ACCESSIBLE STALLS PROVIDED | = | 12  |
| TOTAL STALLS                        | = | 295 |

| PARKING LOT ADDITION       |   |     |
|----------------------------|---|-----|
| EXISTING STALLS            |   | 244 |
| PROPOSED STALLS            | = | 147 |
| HANDICAP ACCESSIBLE STALLS | = | 14  |
| TOTAL STALLS               | = | 405 |

J:\Heritage Church-49314\2024-10685\CADD\Civil\C-AdditionalADAStall-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:14:52 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, IN




HERITAGE 13242 BER



- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.
- UNLESS OTHERWISE NOTED, ALL MATERIALS, CONSTRUCTION TECHNIQUES AND TESTING SHALL CONFORM TO THE CURRENT EDITION OF THE "STANDARD SPECIFICATIONS FOR TRENCH EXCAVATION AND BACKFILL/SURFACE RESTORATION, WATERMAIN AND SERVICE LINE INSTALLATION AND SANITARY SEWER AND STORM SEWER INSTALLATION" AS PUBLISHED BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA AND THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION" AS PUBLISHED BY THE MINNESOTA DEPARTMENT OF TRANSPORTATION, CURRENT EDITION. THE CONTRACTOR SHALL BE REQUIRED TO FOLLOW ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY AND THE MINNESOTA PLUMBING CODE. THE CONTRACTOR SHALL REQUIRE ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY.
- THE CONTRACTOR SHALL RECEIVE THE NECESSARY PERMISSION/PERMITS FOR ALL WORK LOCATED OUTSIDE OF THE MUNICIPAL RIGHT-OF-WAY AND PROPERTY LIMITS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING INVERT LOCATIONS AND ELEVATIONS PRIOR TO BEGINNING CONSTRUCTION.
- AT THE END OF EACH DAY, BERRYWOOD DRIVE SHALL BE CLEARED AND SWEPT OFF IF NECESSARY.
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL AND SIGNAGE IN ANY WORK OR HUALING AREAS IN ACCORDANCE WITH MN MUTCD.

#### GENERAL GRADING NOTES


- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D.
  THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE
  38-.2, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF
  EXISTING SUBSURFACE UTILITY DATA".
- ALL CONSTRUCTION SHALL CONFORM TO LOCAL, STATE, AND FEDERAL REGULATIONS INCLUDING THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT REQUIREMENTS.
- HAULING HOURS MUST BE CONFIRMED WITH THE CITY PRIOR TO BEGINNING WORK.
- SPOT ELEVATIONS SHOWN INDICATE FINISHED PAVEMENT ELEVATIONS, GUTTER FLOW LINE OF CURB GUTTER, BACK OF CURB ELEVATIONS (TC), AND FINISHED SURFACE GRADE, UNLESS OTHERWISE NOTED.
- ALL SLOPES SHALL BE GRADED TO 3:1 OR FLATTER, UNLESS OTHERWISE NOTED ON THE PLANS.
- INFILTRATION AREA SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES TO AVOID COMPACTION OF THE SOILS. IT IS RECOMMENDED THIS AREA BE FENCED OFF AND NOT UTILIZED FOR CONSTRUCTION STAGING, STOCKPILING MATERIALS, OR ANY OTHER CONSTRUCTION RELATED ACTIVITY. THE INFILTRATION AREA SHALL BE SHAPED TO FINAL GRADE AND ALL HEAVY CONSTRUCTION EQUIPMENT SHALL NOT BE ALLOWED IN THE BASIN AFTER FINAL GRADE HAS BEEN ESTABLISED.



HERITAGE CHURCH PAI

13242 BERRYWOOD DR


J:\Heritage Church-49314\2024-10685\CADD\Civil\C-GR-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:15:09 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, INC



• THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.


• UNLESS OTHERWISE NOTED, ALL MATERIALS, CONSTRUCTION TECHNIQUES AND TESTING SHALL CONFORM TO THE CURRENT EDITION OF THE "STANDARD SPECIFICATIONS FOR TRENCH EXCAVATION AND BACKFILL/SURFACE RESTORATION, WATERMAIN AND SERVICE LINE INSTALLATION AND SANITARY SEWER AND STORM SEWER INSTALLATION" AS PUBLISHED BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA AND THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION" AS PUBLISHED BY THE MINNESOTA DEPARTMENT OF TRANSPORTATION, CURRENT EDITION. THE CONTRACTOR SHALL BE REQUIRED TO FOLLOW ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY AND THE MINNESOTA PLUMBING CODE. THE CONTRACTOR SHALL REQUIRE ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY.

- THE CONTRACTOR SHALL RECEIVE THE NECESSARY PERMISSION/PERMITS FOR ALL WORK LOCATED OUTSIDE OF THE MUNICIPAL RIGHT-OF-WAY AND PROPERTY LIMITS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING INVERT LOCATIONS AND ELEVATIONS
- AT THE END OF EACH DAY, BERRYWOOD DRIVE SHALL BE CLEARED AND SWEPT OFF IF
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL AND SIGNAGE IN ANY WORK
- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-.2, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF
- ALL CONSTRUCTION SHALL CONFORM TO LOCAL, STATE, AND FEDERAL REGULATIONS INCLUDING THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPPDES)
- ALL SILT FENCE AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE PRIOR TO ANY EXCAVATION/CONSTRUCTION AND SHALL BE MAINTAINED UNTIL VIABLE TURF OR GROUND COVER HAS BEEN ESTABLISHED. MAINTENANCE AND REMOVAL OF SEDIMENT CONTROL DEVICES SHALL BE INCIDENTAL TO THE GRADING CONTRACT.
- ALL STREETS UTILIZED FOR PROJECT CONSTRUCTION MUST BE CLEANED AT THE END OF EACH DAY. A ROCK ENTRANCE TO THE SITE MUST BE PROVIDED ACCORDING TO THE DETAILS TO REDUCE TRACKING OF SEDIMENT ONTO PUBLIC STREETS. STREET SWEEPING MAY BE NECESSARY AND WILL BE CONSIDERED INCIDENTAL.
- ALL EXPOSED SOILS MUST BE STABILIZED WITHIN 14 CALENDAR DAYS OF ROUGH GRADE COMPLETION OF AFTER CONSTRUCTION TERMINATES. ALL STOCKPILES SHALL HAVE ADEQUATE SEDIMENT TRAPPING SYSTEMS INSTALLED AROUND THEM.
- ALL AREAS TO BE ESTABLISHED TO GRASS COVER SHALL RECEIVE 4" OF TOPSOIL AND SOD OR SEED. THESE AREAS SHALL BE WATERED UNTIL A HEALTHY STAND OF GRASS IS
- INLET PROTECTION SHALL BE INSTALLED AT ALL STORM SEWER INLETS WHICH HAVE A POTENTIAL TO RECEIVE RUNOFF FROM THE CONSTRUCTION SITE.
- INFILTRATION AREA SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES TO AVOID COMPACTION OF THE SOILS. IT IS RECOMMENDED THIS AREA BE FENCED OFF AND NOT UTILIZED FOR CONSTRUCTION STAGING, STOCKPILING MATERIALS, OR ANY OTHER CONSTRUCTION RELATED ACTIVITY. THE INFILTRATION AREA SHALL BE SHAPED TO FINAL GRADE AND ALL HEAVY CONSTRUCTION EQUIPMENT SHALL NOT BE
- SEE PLAN LEGEND FOR A COMPLETE LIST OF HATCHES AND SYMBOLS USED FOR




DENOTES SEDIMENT CONTROL LOGS (MNDOT SPEC. 2573.503/00062)

SURFACE DRAINAGE FLOW




SHEET NO. C7.01

J:\Heritage Church-49314\2024-10685\CADD\Civil\C-EC-2024-10685.dwg Plotted by:Thomas Rients 6/28/2024 2:15:13 PM © 2024 WIDSETH SMITH NOLTING & ASSOCIATES, INC.




- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY OWNER OF ANY DIFFERENCES BETWEEN THE FIELD AND PLAN.
- UNLESS OTHERWISE NOTED, ALL MATERIALS, CONSTRUCTION TECHNIQUES AND TESTING SHALL CONFORM TO THE CURRENT EDITION OF THE "STANDARD SPECIFICATIONS FOR TRENCH EXCAVATION AND BACKFILL/SURFACE RESTORATION, WATERMAIN AND SERVICE LINE INSTALLATION AND SANITARY SEWER AND STORM SEWER INSTALLATION" AS PUBLISHED BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA AND THE "STANDARD SPECIFICATIONS FOR CONSTRUCTION" AS PUBLISHED BY THE MINNESOTA DEPARTMENT OF TRANSPORTATION, CURRENT EDITION. THE CONTRACTOR SHALL BE REQUIRED TO FOLLOW ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY AND THE MINNESOTA PLUMBING CODE. THE CONTRACTOR SHALL REQUIRE ALL PROCEDURES AS OUTLINED BY THE LOCAL AGENCY.
- THE CONTRACTOR SHALL RECEIVE THE NECESSARY PERMISSION/PERMITS FOR ALL WORK LOCATED OUTSIDE OF THE MUNICIPAL RIGHT-OF-WAY AND PROPERTY LIMITS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING INVERT LOCATIONS AND ELEVATIONS PRIOR TO BEGINNING CONSTRUCTION.
- AT THE END OF EACH DAY, BERRYWOOD DRIVE SHALL BE CLEARED AND SWEPT OFF IF
- THE CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL AND SIGNAGE IN ANY WORK OR HUALING AREAS IN ACCORDANCE WITH MN MUTCD.
- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-.2, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF
- THE ENGINEER HAS MADE AN ATTEMPT TO SHOW ALL PUBLIC UTILITIES WITHIN THE CONSTRUCTION LIMITS OF THIS PROJECT. PUBLIC UTILITIES SHOWN ON THIS PLAN WERE DRAWN USING FIELD SURVEY INFORMATION AND MAPS PROVIDED TO THE ENGINEER BY THE UTILITY COMPANIES AS A RESULT OF A GOPHER STATE ONE CALL DESIGN LOCATE REQUEST. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THESE LOCATIONS PRIOR TO BIDDING AND CONSTRUCTING THE PROJECT.
- PRIVATE UTILITY LOCATES ARE TO BE COORDINATED BY THE CONTRACTOR. THE PRIVATE LOCATES WILL BE DONE BY GOPHER STATE ONE CALL. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EXCAVATION LOCATES AND SHALL NOTIFY ALL AFFECTED UTILITY COMPANIES AT LEAST 48-HOURS BEFORE CONSTRUCTION.
- RIM ELEVATIONS REFLECT A SUMP OF 0.05 FEET.
- STORM SEWER OF DIFFERING DIAMETERS SHALL MATCH 0.8 DIAMETER GRADE LINE ELEVATIONS AT CATCH BASIN OR MANHOLE JUNCTIONS.
- A MINIMUM OF 18 INCH VERTICAL SEPARATION SHALL BE REQUIRED AT ALL WATER MAIN CROSSINGS WITH SANITARY SEWER AND STORM SEWER.
- HDPE STORM SEWER PIPE SHALL MEET THE REQUIREMENTS OF AASHTO M294, TYPE S WITH WATERTIGHT JOINTS. PVC STORM SEWER SHALL BE SCHEDULE 40 PIPE. FLARED ENDS SHALL BE RCP WITH TRASH GUARDS AND RIP RAP.

C8.01



### **KEY TO FEATURES**

ROCK MULCH




LANDSCAPE PLANTINGS, SEE SCHEDULE


LANDSCAPE EDGING


| PLANTING SCHEDULE |                                   |                             |      |        |       |          |                       |  |
|-------------------|-----------------------------------|-----------------------------|------|--------|-------|----------|-----------------------|--|
| ABBR.             | SCIENTIFIC NAME                   | COMMON NAME                 | QTY. | SIZE   | TYPE  | SPACING  | NOTES                 |  |
| DECIDUO           | OUS TREES                         |                             |      |        |       |          |                       |  |
| QB                | QUERCUS BICOLOR 'JFS-KE12'        | AMERICAN DREAM OAK          | 3    | 6'     | B&B   | PER PLAN | 2" DBH MIN.           |  |
| QE                | QUERCUS ELLIPSOIDALIS 'BALISKIES' | MAJESTIC SKIES OAK          | 4    | 6'     | B&B   | PER PLAN | 2" DBH MIN.           |  |
| MS                | MALUS 'SUTYZAM'                   | SUGAR TYME CRABAPPLE        | 4    | 2"     | B&B   | PER PLAN | 2" DBH MIN.           |  |
| M                 | MALUS 'ADIRONDACK'                | ADIRONDACK CRABAPPLE        | 4    | 2"     | B&B   | PER PLAN | 2" DBH MIN.           |  |
| AR                | ACER RUBRUM 'ARMSTRONG'           | ARMSTRONG MAPLE             | 3    | 6'     | B&B   | PER PLAN | 2" DBH MIN.           |  |
| CONIFE            | ROUS TREES                        |                             |      |        |       |          |                       |  |
| PG                | PICEA GLAUCA DENSATA              | BLACK HILLS SPRUCE          | 3    | 6'     | B&B   | PER PLAN | 6' MIN.               |  |
| PN                | PINUS NIGRA                       | AUSTRIAN PINE               | 3    | 6'     | B&B   | PER PLAN | 6' MIN.               |  |
| DECIDUO           | OUS SHRUBS                        |                             |      |        |       |          |                       |  |
| РО                | PHYSOCARPUS OPULIFOLIUS 'ZELYel2' | RASPBERRY LEMONADE NINEBARK | 15   | 3 GAL. | CONT. | PER PLAN | 3 GAL. CONTAINER MIN. |  |
| SB                | SPIRAEA BETULIFOLIA 'TOR'         | TOR SPIREA                  | 12   | 3 GAL. | CONT. | PER PLAN | 3 GAL. CONTAINER MIN. |  |
| ВТ                | BERBERIS THUNBERGII 'BALIANNA'    | MOSCATO BARBERRY            | 15   | 3 GAL. | CONT. | PER PLAN | 3 GAL. CONTAINER MIN. |  |


#### GENERAL NOTES

- THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES, PRIVATE & PUBLIC, BEFORE COMMENCING WORK. CONTACT GOPHER STATE ONE CALL 1-800-252-1166 (OR 811). CONTRACTOR AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGE WHICH MIGHT BE CAUSED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES.
- SPREAD MULCH SO THAT IT IS NOT IN CONTACT WITH WOODY BASE OF PLANT.
- THESE NOTES ARE FOR GENERAL REFERENCE IN CONJUNCTION WITH DETAILS, ADDENDA AND CHANGE ORDERS ASSOCIATED WITH THE CONTRACT DOCUMENTS.
- LANDSCAPE CONTRACTOR SHALL COORDINATE ALL WORK WITH OTHER TRADES PRIOR TO INSTALLATION.
- LANDSCAPE CONTRACTOR SHALL BECOME FAMILIAR WITH THE LOCATION OF ALL EXISTING AND FUTURE UNDERGROUND SERVICES AND IMPROVEMENTS WHICH MAY CONFLICT WITH WORK TO BE DONE.
- FINE GRADING AND EDGING SHALL BE APPROVED PRIOR TO PLANTING OPERATIONS.
- PLANT MATERIAL SHALL NOT BE INSTALLED IN AN AREA WHICH WILL CAUSE HARM TO ADJACENT STRUCTURES. NOTIFY THE ARCHITECT SHOULD CONFLICTS ARISE.
- UNLESS OTHERWISE NOTED, FINISH GRADE OF PLANTING AREAS SHALL BE 2" BELOW ADJACENT PAVING. TAPER 3" DEPTH MULCH TOP DRESSING TO 1/2" BELOW ADJACENT PAVING (1 1/2" DEPTH) WITHIN 2" OF PAVING.
- ALL EXISTING TREES, SHRUBS, VINES AND GROUND COVERS TO REMAIN SHALL BE PROTECTED. ANY DAMAGE CAUSED BY CONTRACTOR'S WORK OR NEGLIGENCE SHALL BE REPLACED OR REPAIRED AT THE CONTRACTORS EXPENSE TO THE SATISFACTION OF THE OWNER.
- LANDSCAPE CONTRACTOR SHALL ASSURE COMPLIANCE WITH APPLICABLE CODES AND REGULATIONS GOVERNING THE WORK AND MATERIALS SUPPLIED.
- LANDSCAPE CONTRACTOR SHALL PROTECT EXISTING ROADS, CURB AND GUTTER, TRAILS, TREES, LAWNS AND SITE ELEMENTS DURING CONSTRUCTION. DAMAGE TO THESE ITEM SHALL BE REPAIRED AT NO COST TO OWNER.
- UNDERGROUND SERVICES SHALL BE INSTALLED SO THAT TRENCHES DO NOT CUT THROUGH ROOT SYSTEMS OF EXISTING TREES TO REMAIN.
- LANDSCAPE CONTRACTOR SHALL REVIEW THE SITE FOR DEFICIENCIES IN SITE CONDITIONS WHICH MIGHT NEGATIVELY AFFECT PLANT MATERIALS ESTABLISHMENT, SURVIVAL OR WARRANTY. UNDESIRABLE SITE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO BEGINNING OF WORK.
- LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR ONGOING MAINTENANCE OF NEWLY INSTALLED MATERIALS UNTIL TIME OF SUBSTANTIAL COMPLETION. REPAIR OF ACTS OF VANDALISM OR DAMAGE WHICH MAY HAVE OCCURRED PRIOR TO SUBSTANTIAL COMPLETION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- EXISTING TREES OR SIGNIFICANT SHRUB MASSING FOUND ON SITE SHALL BE PROTECTED AND SAVED UNLESS NOTED TO BE REMOVED OR ARE LOCATED IN AN AREA TO BE GRADED. QUESTIONS REGARDING EXISTING PLANT MATERIALS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO REMOVAL.
- EXISTING TREES TO REMAIN, UPON DIRECTION OF ARCHITECT, SHALL BE FERTILIZED AND PRUNED TO REMOVE DEAD WOOD, DAMAGED AND RUBBING BRANCHES.
- SYMBOLS ON PLAN DRAWING TAKE PRECEDENCE OVER SCHEDULES IF DISCREPANCIES IN QUANTITIES EXIST. DETAILS TAKE PRECEDENCE OVER NOTES.
- IT IS CONTRACTOR'S RESPONSIBILITY TO SALVAGE TREES INDICATED ON PLAN, VERIFY EXACT PLANT TYPE, KEEP MOIST AND IN GOOD CONDITION DURING CONSTRUCTION, AND REPLANT ACCORDING TO PLANTING PLAN.
- LANDSCAPE EDGING SHALL BE  $\frac{3}{16}$ "X 5  $\frac{1}{2}$ " ALUMINUM EDGING WITH MILL FINISH, MANUFACTURED BY PERMALOC CORP OR APPROVED EQUAL.
- PROVIDE HARDWOOD BARK MULCH AROUND ALL TREE PLANTINGS SHOWN TO BE PLANTED WITHIN TURF AREAS.
- ROCK MULCH SHALL MATCH SIZE AND COLOR OF EXISTING.
- LANDSCAPE GEOTEXTILE FABRIC SHALL BE MIRAFI 140NL OR APPROVED EQUAL.









#### NOTES:

- 1. SEE PLAN FOR ROCK MULCH LOCATION.
- SET ROCK MULCH 1" BELOW FINISH GRADE, TYP. SEE PLANS FOR EDGING LOCATION.
- WHERE ROCK MULCH MEETS BACK OF CONCRETE CURB, FOLLOW THIS DETAIL. SEE PLANS.



TAGE CHURCH PARKING LOT ADDITION

SCAL

TAGE CHURCH

PRATER, MN 56425

CHE

HERITAGE CH HERITAGE CH 13242 BERRY