BID PROPOSAL

CONTRACTORS NAME: D&J Pump and Well Service, LLC
CONTRACTORS LICENSE #: WD-782
(PLEASE TYPE OR PRINT)

PLEASE DO NOT RETYPE BID PROPOSAL - AN ELECTRONIC VERSION WILL BE PROVIDED UPON REQUEST.

RE-BID CITY OF BAYARD
FRESH WATER WELL #3 REHABILITATION & RE-EQUIP
2018 COLONIAS INFRASTRUCTURE FUND
NMFA PROJECT NO. 4627-CIF18
STANTEC PROJECT #227300245/181710740
BID PROPOSAL

Bidder agrees to perform all of the work in said project, described in the Specifications and shown on the Plans for the following Unit Prices.

Discrepancies between the multiplication of units of Work and Unit Prices will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum.

It is the responsibility of the Contractor to verify unit bid prices, subtotals, and totals, when submitting Bid Proposal. Stantec is not responsible for any errors occurring in this submission.

Base Bid

ITEM #	UNIT	DESCRIPTION	UNIT BID PRICE	TOTAL
1	1 L.S.	MOBILIZATION & DEMOBILIZATION WITH PUMP RIG	4,250.00 0	Dollars & Cents $ 4,250.00 -
2	1 L.S.	OPEN ROOF #12 WELLHOUSE TO RETRIEVE COLUMN PIPE & SUBMERSIBLE PUMP, CLOSE ROOF.	0	Dollars & Cents $ 2,800.00 -
3	1 L.S.	RETRIEVE EXISTING 240 LF OF 2" STEEL COLUMN PIPE & SUBMERSIBLE PUMP FROM #12 WELL. TRANSPORT TO #3 WELL SITE.	0	Dollars & Cents $ 1,275.00 -
4	1 L.S.	REMOVE EXISTING PUMP #3 WELL	0	Dollars & Cents $ 2,800.00 -
5	1 L.S.	VIDEO WELL (PROMOTE CLARITY WITH RUNNING WATER OR FLOCCULANT)	0	Dollars & Cents $ 1,000.00 -
6	1 L.S.	BRUSH WELL WITH CASING BRUSH AND BAIL SEDIMENT (PRIOR TO ACIDATION)	0	Dollars & Cents $ 3,360.00 -
7	1 L.S.	ACID/DESCALER MATERIALS	0	Dollars & Cents $ 3,250.80 -

TOTAL - THIS PAGE: $ 18,735.80 -

Base Bid

ITEM #	UNIT	DESCRIPTION	UNIT BID PRICE	TOTAL
8	1 L.S.	ACIDATION (ALLOW SOLUTION TO REMAIN IN WELL FOR 24 HOURS)	0	Dollars & Cents $ 750.00 .
9	1 L.S.	BRUSH WELL WITH CASING BRUSH AND BAIL SEDIMENT (AFTER ACIDATION)	0	Dollars & Cents $ 1,680.00 .
10	1 L.S.	NEUTRALIZE ACID IN FRAC TANK, HAUL DISCHARGE TO WASTEWATER PLANT	0	Dollars & Cents $ 975.00 .
11	1 L.S.	INSTALL PUMP AND DROP PIPE RECOVERED FROM #12 WELL INTO #3 WELL. ATTACH NEW 3/4" WATER LEVEL SOUNDING TUBE.	0	Dollars & Cents $ 975.00 .
12	1 L.S.	REMOVE CONCRETE PAD AND WELLHEAD APPURTENANCES	0	Dollars & Cents $ 1,275.00 .
13	1 L.S.	CONSTRUCT PITLESS ADAPTOR, WELL HEAD, SANITARY SEAL, AND BASE COURSE PAD (APPROXIMATELY 8 CUBIC YARDS)	0	Dollars & Cents $ 14,115.00 .
14	1 L.S.	PUMP DISCHARGE MANIFOLD INSIDE 4'X6'X6' CONCRETE VALVE VAULT WITH HINGE LOCKING COVER. PIPING MANIFOLD INCLUDES 2" D.I. PIPE (APPROX. 35 L.F.), AIR/VACUUM RELIEF VALVE, 2" SWING GATE CHECK VALVE, TURBINE FLOW METER, 3/4" TAPPING SADDLE WITH SAMPLE PORT, 300 PSI GAGE AND GATE VALVE, AND ADJUSTABLE PIPE SUPPORTS	0	Dollars & Cents $ 21,500.00 .
15	1 L.S.	CONSTRUCT 2" PVC CONNECTION TO COLLECTOR MAIN LINE AND INSTALL 2" RESTRAINED GATE VALVE	0	Dollars & Cents $ 3,250.00 .
16	1 L.S.	INSTALL TEST PUMP WITH PVC WATER LEVEL SOUNDING TUBE AND PUMP WELL FOR 30 HOURS (WELL DEVELOPMENT & PUMP TESTING)	0	Dollars & Cents $ 5,250.00 .

TOTAL - THIS PAGE: $ 49,770.00 .

Base Bid

ITEM #	UNIT	DESCRIPTION	UNIT BID PRICE	TOTAL
17	1 L.S.	DISINFECT WELL	0	Dollars & Cents $ 1125.00 .
18	1 L.S.	SITE CLEANUP (RETURN AS WAS WHEN ARRIVED)	0	Dollars & Cents $ 750.00 .
19	15 DAY	RENTAL OF (2) FRAC TANKS FOR CONTAINMENT OF DISCHARGE	0	Dollars & Cents $ 14,250.00 .
20	2 EACH	DELIVERY AND PICKUP OF (2) FRAC TANKS	0	Dollars & Cents $ 1100.00 .
21	1 L.S.	WATER TRUCK RATE: HAULING DISCHARGE FLUID TO WASTEWATER PLANT	0	Dollars & Cents $ 14400.00 .
22	1 L.S.	CONSTRUCT ELECTRICAL SERVICE AT #3 WELL SITE	0	Dollars & Cents $ 7,550.00 .
23	1 L.S.	DEMO ELECTRICAL PANELS, SURGE ARRESTOR, TRANSFORMER, PUMP STARTER & SCADA CONTROLS FROM #12 WELL SITE AND INSTALL AT #3 WELL SITE	0	Dollars & Cents $ 2850.00 .
24	1 EACH	PLUG ABANDONED WATER #12 WELL ACCORDING TO OSE AND NMED REQUIREMENTS	0	Dollars & Cents $ 5500.00 .
25	100 L.F.	6' TALL CHAIN LINK SECURITY FENCE WITH STRAND BARBED WIRE. INCLUDES 2 - 10'-0" DOUBLE SWING GATE	0	Dollars & Cents $ NA .

TOTAL - THIS PAGE: $ 47,525.00 .

TOTAL - BASE BID: $ 116,033.80 . gt 6.1875

7,179.60

$123,213.40

227300245/181710740