

City of Bay St Louis					
Construction Repairs to Sidewalks and Driveways					
Construction Cost Estimate					
Item NO.	Desription	Unit	Unit Cost	QTY	Total Cost
1	Sidewalks (4" Thick)	SY		67	\$4,783.50
2	Driveways (6" Thick)	SY		300	\$19,462.50
3	Saw cutting Asp/Concrete	INLF		400	\$2,962.50
4	2.5' x 2.5' Concrete Pad (4" Thick)	EA		30	\$9,562.50
					36,735
Notes:	All listed below are include in sy price of concrete				+ Tax unless
	SW and DW will be 3500 PSI with Fiber or wire mesh				exempt
	Remove temp rock and deliver to City Yard at St Francis St and Bookter St				
	Compact subgrade, fine grade, expansion material, forms, remove forms, backfill and dress up				