

Invoice

DATE	INVOICE #	
4/15/2022	22-0415-876	

BILL TO	
City of Beaumont Kevin Norville 50 E. 6th Street Beaumont, CA 92223	

SHIP TO			

P.O. NO.	TERMS	PROJECT	
		Rangel Park	

Item	QTY	Part No.	DESCRIPTION	RATE	AMOUNT
	1	Misc Material	Rangel Park - Power system Electrical System for Park Main Electrical power Outdoor Rated PAD Mounted 3 section Power Panel. Panel overall size - 90H x 96W X 35D Section 1 Controls Lighting and Irrigation – Irrigation controls provided by other. Automated controls with Hand -Off-Auto capability Power connection for: Field Lighting 3 contactors Parking lighting 2 contactors Section 2 Circuit Breaker Panel 4 wire 120/240 VAC 125 main CB Circuit 1,3,5 - "Back Stop" Lighting 30 amp CB 3 pole – 120% Load factor, Amp requirement 18 amps per leg Circuit 2,4,6 - "Infield" Lighting 30 amp CB 3 pole – 120% Load factor, Amp requirement 14 amps per leg Circuit 7,9,11 - "Back Stop" lighting 30 amp CB 3 pole – 120% Load factor, Amp requirement 12 amps per leg Circuit 8,10 - "Parking Lot South" lighting 40 amp CB 2 pole – 120% Load factor, Amp requirement 20 amps Circuit 12 - "Controls Power" lighting 15 amp CB 1 pole – 120% Load factor, Amp requirement 6 amps Circuit 13 - "Score Board" 15 amp CB 1 pole – 120% Load factor, Amp requirement 10 amps Circuit 15,17 - "Parking Lot North" lighting 40 amp CB 2 pole – 120% Load factor, Amp requirement 20 amps Circuit 14 - "Infield Receptacle" 15 amp CB 1 pole – 120% Load factor, Amp requirement 10 amps Circuit 14 - "Spare" 20 amp CB 1 pole – 120% Load factor, Amp requirement 15 amps Circuit 18,20- "Restroom Building" lighting 60 amp CB 2 pole – 120% Load factor, Amp requirement 46 amps Section 3 Meter Section 200 amp 4 wire 240 VAC 3 phase	46,750.00	46,750.00T

Total

Balance Due



Invoice

DATE	INVOICE#	
4/15/2022	22-0415-876	

BILL TO	SHIP TO		
City of Beaumont Cevin Norville 50 E. 6th Street Beaumont, CA 92223			

P.O. NO.	TERMS	PROJECT
		Rangel Park

Item	QTY	Part No.	DESCRIPTION	RATE	AMOUNT
			meter socket with incoming wire section bottom entry.		
			All wiring bottom entry Painting Ansi Grey		
			Total		
			Bala	nce Due	



Invoice

DATE	INVOICE#	
4/15/2022	22-0415-876	

BILL TO	
City of Beaumont Kevin Norville 550 E. 6th Street	
Beaumont, CA 92223	

P.O. NO.	TERMS	PROJECT	
		Rangel Park	

Item	QTY	Part No.	DESCRIPTION	RATE	AMOUNT
		Shipping	Shipping is FOB Factory Freight prepay and add to: Rangel Park 204 B Street Beaumont, CA 92223 Lift for mounting and setting provided by others.	0.00	0.00
		Terms 1	Terms for special expedite 50% with order 50% prior to shipment Lead-time is 10 weeks from receipt of order. Installation provided by others.	0.00	0.00
					0.00
	•				

Total \$46,750.00

Balance Due \$46,750.00