



**License#: CRC1334524**

**Proposal for Neighborhood Wall at Regal Landing**

**Scope of work:**

**Materials:** Concrete, Rebar, Blocks, Sand and Mortar, Pump for Concrete.

**Labor:**

- Tear out 51' Section and 32' of block wall and Haul off Debris.
- Dig new footing- Based on 2'x 12" with 3 #5 Rebar & Dowel @ 4'
- Tie Rebar and pour footing.
- Lay blocks- Based on 10 Courses.
- Tie Rebar for Down Cella & Top Lintel Course with 1 #5 Rebar and Pour.
- Does not include removing tree roots.

**- Total Price Labor and Materials: \$26,280**

**Total:**

Name: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

35% of payment will be made when permit is in hand. Payment in full will be made upon completion of work.