
WALLACE PARK IMPROVEMENTS



APPLICANT:

CITY OF BELLE ISLE

1600 NELA AVE, BELLE ISLE, FL 32809

DATE: JUNE, 2020 ISSUED FOR:


SITE PLAN APPROVAL

CIVICA PROJECT: 200108

	INDEX
	COVER SHEET & LOCATION MAP
	SURVEY
	ARCHITECTURE
A-1	PROPOSED SITE PLAN
A-2	EXISTING AND PROPOSED SITE IMAGES
A-3	PROPOSED BUILDING, PLANS, IMAGES
	LANDSCAPE
LA-1	LANDSCAPE PLAN
LA-2	LANDSCAPE DETAILS
	ANNEX CIVIL ENGINEERING




PROPOSED SITE 3D VIEW









PLAT OF SURVEY

LEGAL DESCRIPTION

A PORTION OF LOT 2, WALLER SUBDIVISION, ACCORDING TO THE PLAT THEREOF AS RECORDED IN PLAT BOOK 26, PAGE 105, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGIN AT THE SOUTHWEST CORNER OF SAID LOT 2, WALLER SUBDIVISION, ACCORDING TO THE PLAT THEREOF AS RECORDED IN PLAT BOOK 26, PAGE 105, PUBLIC RECORDS OF ORANGE COUNTY, FLORIDA; THENCE RUN NORTH 00 DEGREES 07 MINUTES 50 SECONDS EAST 300 FEET TO THE NORTH LINE OF SAID LOT 2, THENCE SOUTH 89 DEGREES 55 MINUTES 55 SECONDS EAST 359.92 FEET; THENCE SOUTH 04 DEGREES 13 MINUTES 30 SECONDS WEST 300.39 FEET, TO THE SOUTH LINE OF SAID LOT 2; THENCE SOUTH 90 DEGREES 00 MINUTES 00 SECONDS WEST 338.47 FEET TO THE POINT OF BEGINNING.

CONTAINS: 104,686 SQUARE FEET OR 2.4033 ACRES MORE OR LESS.

NOTES

1. BEARING STRUCTURE IS ASSUMED AND BASED ON THE MONUMENTED NORTH R/W LINE OF E WALLACE STREET, BEING S90°00'00"W (DESC).

- 2. THIS SURVEY REFLECTS ONLY MATTERS OF RECORD AS PROVIDED BY THE CLIENT OR CLIENTS REPRESENTATIVE.
- 3. THIS SURVEY WAS MADE ON THE GROUND. THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.
- 4. THIS BUILDING/LOT LIES IN ZONE "X", BASED ON FLOOD INSURANCE RATE MAP NO. 12095C0430F, COMMUNITY NO. 120179, ORANGE COUNTY, FLORIDA, EFFECTIVE: SEPTEMBER 25, 2009.
- 5. ACCORDING TO FLORIDA STATUTES, CHAPTER 472.025, A LAND SURVEYOR SHALL NOT AFFIX HIS SEAL OR NAME TO ANY PLAN OR DRAWING WHICH DEPICTS WORK WHICH HE IS NOT LICENSED TO PERFORM OR WHICH IS BEYOND HIS PROFESSION OR SPECIALTY THEREIN. THEREFORE, WE ARE UNABLE TO CERTIFY AS TO MUNICIPAL ZONING COMPLIANCE, INTERPRETATION OF ZONING CODES OR THE DETERMINATION OF VIOLATIONS THEREOF.
- 6. THIS SURVEY WAS MADE WITHOUT BENEFIT OF TITLE.
- 7. THIS SURVEY IS VALID ONLY FOR THE PARTIES TO WHOM IT IS CERTIFIED.
- 8. THIS SURVEY EXCEEDS THE ACCURACY REQUIREMENTS SET FORTH IN FLORIDA STATUTES.
- 9. ELEVATIONS BASED ON ORANGE COUNTY BENCHMARK #C698001 HAVING AN ELEVATION OF 101.033 FEET, (NAVD 88).

SE CORNER LOT 10


J.G. TYNER'S SUBDIVISION

— PB F, PG 44

FND 1 1/2" IP

NO # \$89°34'50"W 297.91' MEAS

\$90°00'00"W, 298.00' DESC



COPYRIGHT © 1986 - 2018, ACCURIGHT SURVEY


ACCURIGHT

ACCURIGHT SURVEYS OF ORLANDO INC., LB 4475

2012 E. Robinson Street, Orlando, Florida 32803 www.AccurightSurveys.net

ACCU@AccurightSurveys.net

PHONE: (407) 894-6314



CIVICA

8323 NW 12th St. Suite 106
Doral, FL 33126
tel: 305.593.9959

www.civicagroup.com AA #26001093

PROJECT:

WALLACE PARK IMPROVEMENTS

E WALLACE ST. BELLE ISLE, FL 32809

APPLICANT:

THE CITY OF BELLE ISLE



1600 NELA AVENU

CIVICA PROJECT No: 200108

ISSUED FOR:

ZONING APPROVAL

No.	DATE	REVISION	BY

DRAWN BY:	APPROVED BY: RL
DATE:	SCALE:
2020-06-20	As Shown

KEYPLAN

SEAL/SIGNATURE

ROLANDO LLANES AR - 0013160

This drawing is the property of CIVICA and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on request.

COPYRIGHT © 2020

SHEET TITLE

PROPOSED SITE PLAN

SHEET NUMBER

A-1



<u>WEST</u>



<u>EAST</u>



<u>NORTH</u>



<u>SOUTH</u>

EXISTING CONDITION 1
SCALE: N.T.S. A-1



SEAL/SIGNATURE

DRAWN BY:

DATE: 2020-06-20

KEYPLAN

SG

8323 NW 12th St. Suite 106 Doral, FL 33126 tel: 305.593.9959

www.civicagroup.com AA #26001093

PROJECT:

WALLACE PARK IMPROVEMENTS

E WALLACE ST. BELLE ISLE, FL 32809

APPLICANT:

THE CITY OF BELLE ISLE

1600 NELA AVENUE BELLE ISLE, FL 32809

CIVICA PROJECT No:

200108

ISSUED FOR:

ZONING

APPROVAL

No. DATE REVISION BY

APPROVED BY:

As Shown

ROLANDO LLANES AR - 0013160

This drawing is the property of CIVICA and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on request.


COPYRIGHT © 2020

SHEET TITLE

AERIAL VIEWS EXISTING & PROPOSED

SHEET NUMBER







NORTHEAST VIEW




TOP VIEW




NORTH VIEW

WEST VIEW








PROPOSED BUILDING - ELEVATIONS




NORTHEAST VIEW



SOUTHEAST VIEW





SEAL/SIGNATURE

2020-06-20

KEYPLAN

ROLANDO LLANES AR - 0013160

This drawing is the property of CIVICA and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on request.

COPYRIGHT © 2020

8323 NW 12th St. Suite 106

Doral, FL 33126 tel: 305.593.9959

www.civicagroup.com AA #26001093

PROJECT:

WALLACE PARK

IMPROVEMENTS

E WALLACE ST. BELLE ISLE, FL 32809

APPLICANT:

THE CITY OF BELLE ISLE

1600 NELA AVENUE BELLE ISLE, FL 32809

CIVICA PROJECT No:

200108

ISSUED FOR:

ZONING

APPROVAL

No. DATE REVISION BY


As Shown

SHEET TITLE

PROPOSED BUILDING PLANS, IMAGES

ROOF PLAN FLOOR PLAN PROPOSED BUILDING - PLANS

SHEET NUMBER



NOTES:


1. FINAL TREE LOCATION TO BE APPROVED
BY OWNER.


NOTES:

1. CONTRACTOR SHALL ASSURE PERCOLATION OF ALL
PLANTING PITS PRIOR TO INSTALLATION.

PLANTING PITS PRIOR TO INSTALLATION.


2. IN SEMI-IMPERVIOUS SOIL CONDITIONS, ROOTBALL
ELEVATION SHALL BE 2"-4" ABOVE FINISH GRADE.
COORDINATE WITH LANDSCAPE ARCHITECT PRIOR TO
SETTING ROOTBALL ELEVATIONS.






SHRUB AND GROUNDCOVER DETAIL

SCALE: NOT TO SCALE



5 TREE MULCHING IN SOD AREAS

SCALE: NOT TO SCALE




NOTE:

BENEATH ROOTBALL.


- CONTRACTOR SHALL ASSURE PERCOLATION OF ALL PLANTING
- PITS/BEDS PRIOR TO INSTALLATION.

 2. ALL SHRUBS AND GROUNDCOVER MASSES TO USE TRIANGULAR SPACING EXCEPT WHERE NOTED. REFER TO PLANT LIST FOR



TYP. GROUND COVER SPACING DETAIL

SCALE: NOT TO SCALE



6 MULCH EDGE DETAIL

SCALE: NOT TO SCALE



8323 NW 12th St. Suite 106 Doral, FL 33126 tel: 305.593.9959 www.civicagroup.com AA #26001093

PROJECT:

WALLACE PARK IMPROVEMENTS

E WALLACE ST. BELLE ISLE, FL 32809

APPLICANT:

THE CITY OF BELLE ISLE




1600 NELA AVENUE BELLE ISLE, FL 32809

CIVICA PROJECT No: 200108


ISSUED FOR:

ZONING APPROVAL



DRAWN BY:	APPROVED BY:
DPD	RL
DATE:	SCALE:

KEYPLAN



Douglas Dierlich LA0001696

This drawing is the property of CIVICA and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on request.

COPYRIGHT © 2020

SHEET TITLE

LANDSCAPE DETAILS

SHEET NUMBER

L-2

GENERAL NOTES

- 1. CONTRACTOR SHALL BE RESPONSIBLE FOR BECOMING FAMILIAR WITH DRAWINGS FOR ALL DIVISIONS OF WORK.
- 2. CONTRACTOR SHALL FAMILIARIZE HIMSELF/HERSELF WITH EXISTING SITE CONDITIONS PRIOR BIDDING WORK AND AGAIN PRIOR TO INITIATING CONSTRUCTION. ALL EXISTING SITE ROADS, PARKING LOTS, CURBS, UTILITIES, SEWERS AND OTHER ELEMENTS TO REMAIN SHALL BE FULLY PROTECTED FROM ANY DAMAGE UNLESS OTHERWISE NOTED.
- 3. THE CONTRACTOR SHALL FIELD VERIFY ALL PROJECT CONDITIONS RELATIVE TO THE DRAWINGS PRIOR TO INITIATING ANY WORK.
- 4. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS PRIOR TO COMMENCING WITH WORK. NOTIFY OWNER'S REPRESENTATIVE OF ANY DISCREPANCY BETWEEN PLANS AND ACTUAL SITE CONDITIONS. NO WORK SHALL BE DONE IN AREAS WHERE SUCH DISCREPANCIES EXIST. THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ALL NECESSARY REVISIONS DUE TO FAILURE TO GIVE SUCH NOTIFICATION.
- 5. ALL BASE INFORMATION PROVIDED BY OWNER. CONTRACTOR SHALL FIELD VERIFY ALL INFORMATION PRIOR TO BEGINNING WORK.
- 6. THE BASE MAPPING/SURVEY WAS PROVIDED BY ______. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AND REPORT ANY DISCREPENCIES TO THE OWNER'S REPRESENTATIVE PRIOR TO COMMENCING WITH WORK.
- 7. CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS PRIOR TO COMMENCING WITH WORK.
- 8. CONTRACTOR SHALL COORDINATE ACCESS AND STAGING AREAS WITH THE OWNER'S REPRESENTATIVE.
- 9. CONTRACTOR SHALL NOTIFY ALL NECESSARY UTILITY COMPANIES 48 HOURS MINIMUM PRIOR TO DIGGING FOR VERIFICATION OF ALL UNDERGROUND UTILITIES, IRRIGATION AND OTHER ELEMENTS AND COORDINATE WITH THE OWNER'S REPRESENTATIVE PRIOR TO INITIATING OPERATIONS. DRAWINGS ARE PREPARED ACCORDING TO THE BEST INFORMATION AVAILABLE AT THE TIME OF PREPARING THESE DOCUMENTS.
- 10. NOTIFY OWNER'S REPRESENTATIVE 72 HOURS IN ADVANCE OF ANY PLANNED UTILITY INTERUPTION.
- 11. CONTRACTOR SHALL COMPLY WITH STATE AND LOCAL LAWS AND REGULATIONS REGARDING NOTIFICATION OF EXISTING GAS AND OIL PIPELINE COMPANY OWNERS. EVIDENCE OF SUCH NOTICE SHALL BE FURNISHED TO THE OWNER'S REPRESENTATIVE PRIOR TO COMMENCING WITH WORK.
- 12. CONTRACTOR IS REQUIRED TO TAKE DUE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN ON THE DRAWINGS, AS WELL AS, ANY DISCOVERED DURING THE CONSTRUCTION PROCESS.
- 13. CONTRACTOR SHALL EMPLOY SKILLED PERSONNEL AND USE EQUIPMENT NECESSARY TO ENSURE THAT ALL WORK IS PROFESSIONALLY AND PROPERLY INSTALLED AND IN FULL COMPLIANCE WITH THE PLANS, SPECIFICATIONS AND DETAILS.
- 14. CONTRACTOR SHALL PROVIDE ALL NECESSARY SAFETY MEASURES DURING CONSTRUCTION OPERATIONS TO PROTECT THE PUBLIC ACCORDING TO ALL APPLICABLE CODES AND RECOGNIZED LOCAL PRACTICES.
- 15. THE CONTRACTOR SHALL COORDINATE ALL WORK AND BE RESPONSIBLE FOR ALL METHODS, MEANS, SEQUENCE AND PROCEDURE OF WORK.
- 16. CONTRACTOR SHALL COORDINATE ALL WORK WITH RELATED CONTRACTORS AND WITH THE GENERAL CONSTRUCTION OF THE PROJECT IN ORDER NOT TO IMPEDE THE PROGRESS OF THE WORK OF OTHERS OR THE CONTRACTOR'S OWN WORK.
- 18. THE LIMIT OF CONSTRUCTION LINE SHOWN DEFINES THE LIMIT OF WORK IN THIS CONTRACT. THERE MAY BE INSTANCES WHERE EROSION PROTECTION DEVICES AND UTILITY SYSTEMS EXTEND BEYOND THE PROJECT LIMITS LINE IN ORDER TO SUCCESSFULLY COMPLETE OPERATIONS AND/OR TIE INTO ADJACENT SYSTEMS.
- 19. MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES (SILT FENCE, ORANGE GEO FENCE AND/OR OTHER MEASURES) DURING CONSTRUCTION. PROVIDE ADDITIONAL MEASURES AS NECESSARY TO MINIMIZE ADVERSE IMPACTS TO THE ADJACENT WATER BODIES, SURFACES AND STORM SEWERS ACCORDING TO ALL APPLICABLE FEDERAL/STATE/LOCAL LAWS AND REGULATIONS.
- 20. REPORT ALL EXISTING DAMAGE OF EXISTING SITE IMPROVEMENTS TO OWNER'S REPRESENTATIVE PRIOR TO BEGINNING WORK. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SUBSEQUENT DAMAGE.
- 21. CONTRACTOR SHALL PROTECT, BY WHATEVER MEANS NECESSARY, THE EXISTING SITE IMPROVEMENTS TO REMAIN. ALL DAMAGED ITEMS SHALL BE REPLACED OR REPAIRED AT NO ADDITIONAL COST TO THE OWNER. NOTIFY OWNER'S REPRESENTATIVE IMMEDIATELY IF ANY DAMAGE OCCURS.
- 22. ALL AREAS WITHIN THE DRIPLINES OF EXISTING TREES SHALL REMAIN FREE OF CONSTRUCTION MATERIAL, DEBRIS, VEHICLES AND FOOT TRAFFIC AT ALL TIMES. CONTRACTOR SHALL PROVIDE TEMPORARY FENCING, BARRICADES AND/OR OTHER SUITABLE GUARDS OUTSIDE DRIP LINE (OUTSIDE PERIMETER OF BRANCHES) TO PROTECT TREES AND PLANT MATERIAL TO REMAIN. NO WORK SHALL BE PERFORMED WITHIN THE DRIPLINE OF EXISTING TREES UNLESS INDICATED. ALL WORK INDICATED TO BE PREFORMED WITHIN THE DRIPLINE OF TREES SHALL BE DONE BY HAND AND CARE SHALL BE TAKEN TO MINIMIZE DISTURBANCE TO THE TREE ROOTS.
- 23. EACH CONTRACTOR SHALL VERIFY THE CONDITION AND COMPLETENESS OF ALL WORK PERFORMED BY OTHERS IN RELATION TO HIS/HER PROJECT WORK RESPONSIBILITIES INCLUDING THE CHECKING OF EXISTING ELEVATIONS OR STRUCTURES PRIOR TO INITIATING CONSTRUCTION. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER'S REPRESENTATIVE IF ANY SITE CONDITIONS ARE INCOMLETE, MISSING OR DAMAGED.
- 24. THE CONTRACTOR SHALL KEEP ALL DRAINAGE FACILITIES AFFECTED BY HIS CONSTRUCTION OPERATIONS CLEAN AND FULLY OPERATIONAL AT ALL TIMES.
- 25. CONTRACTOR SHALL CLEAN THE WORK AREAS AT THE END OF EACH WORKING DAY. ALL MATERIALS, PRODUCTS AND EQUIPMENT SHALL BE STORED IN AN ORGANIZED FASHION.
- 26. ALL CONSTRUCTION DEBRIS AND REMOVED ITEMS SHALL BE DISPOSED OF LEGALLY OFF-SITE UNLESS OTHERWISE INDICATED ON THE DRAWINGS.

GENERAL NOTES FOR LANDSCAPE PLANTING

- 1. THE CONTRACTOR SHALL REFER TO THE LANDSCAPE PLANTING DETAILS, SPECIFICATIONS, PLANT LIST AND PLANS FOR FURTHER AND COMPLETE PLANTING INSTALLATION INSTRUCTIONS.
- 2. CONTRACTOR SHALL BE RESPONSIBLE TO REMOVE ALL EXISTING GROUND COVERS FOR ALL NEW PLANTING BEDS BY APPROVED MEANS PRIOR TO PLANTING INSTALLATION. CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ALL PORTIONS OF EXISTING PLANTING OR LAWN AREAS INDICATED TO REMAIN WHILE COMPLETING NEW PLANTING INSTALLATION WORK WITH SAME KIND OF PLANTS OR GRASS TO THE SATISFACTION OF THE OWNER AT NO ADDITIONAL COST.
- 3. THE CONTRACTOR SHALL BEAR ALL COST ASSOCIATED WITH SOIL TESTING AND SOIL AMENDMENTS AS REQUIRED AS A RESULT OF THE SOIL TESTING LABORATORY'S RECOMMENDATIONS. PRIOR TO INITIATING INSTALLATION THE CONTRACTOR SHALL PROVIDE SOIL TEST FOR AT LEAST TWO ON-SITE LOCATIONS.
- 4. ALL PLANT CONTAINER SIZES NOTED ON THE PLANT LIST ARE MINIMUM. INCREASE SIZE OF CONTAINERS IF NECESSARY TO CONFORM TO THE PLANT SIZE AND SPECIFICATIONS.
- 5. ALL TREES SHALL HAVE SIX (6') CLEAR TRUNKS UNLESS OTHERWISE NOTED ON THE PLANT LIST. ANY TREE TRUNK WITH A "V" SHAPED CROTCH WILL BE REJECTED. ALL TREE CALIPER (CAL.) SIZES NOTED ON THE PLANT LIST ARE MINIMUM. INCREASE SIZE IF NECESSARY TO CONFORM TO SPECIFIED PLANT SIZE IN THE PLANT LIST.
- 6. EROSION CONTROL FABRIC SHALL BE INSTALLED IN ALL SHRUB AND GROUND COVER PLANTING AREAS AS PER THE DETAILS AND/OR SPECIFICATIONS FOR ALL SLOPES THAT ARE GREATER THAN 3:1 (SLOPES 1' VERTICAL FOR EVERY 3' HORIZONTAL). SEE PLANS FOR LOCATIONS WHERE SLOPES ARE GREATER THAN 3:1.
- 7. SHRUB AND GROUND COVER PLANTINGS ARE TYPICALLY SHOWN ON THE PLANS IN MASS PLANTING BEDS. PLANTS SHALL BE SET IN A TRIANGULAR SPACING PATTERN (STAGGERED SPACING). PLANT CENTER TO CENTER DIMENSIONS (O.C.) ARE INDICATED IN THE PLANT LIST.
- 8. LANDSCAPE CONTRACTOR SHALL FIELD ADJUST THE LOCATION OF PLANT MATERIAL AS NECESSARY TO AVOID DAMAGE TO EXISTING TREES AND UNDERSTORY VEGETATION TO REMAIN, UNDERGROUND AND ABOVE GROUND UTILITIES AND ALL OTHER ABOVE GROUND ELEMENTS. ALL CHANGES REQUIRED SHALL BE COORDINATED WITH THE OWNER'S REPRESENTATIVE AND THE LANDSCAPE ARCHITECT PRIOR TO INITIATING ANY CHANGES.

GENERAL NOTES FOR LANDSCAPE PLANTING (cont.)

- 9. ANY SUBSTITUTIONS TO PLANT MATERIAL SIZE OR TYPE MUST BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. LANDSCAPE CONTRACTOR SHALL NOT MAKE ANY SUBSTITUTIONS OR ALTERATIONS TO THE LANDSCAPE PLANTING PLANS OR PLANT LIST & MATERIALS WITHOUT THE PRIOR APPROVAL OF THE LANDSCAPE ARCHITECT AND OWNER'S REPRESENTATIVE. ANY LANDSCAPE PLANTING INSTALLED THAT DOES NOT CONFORM TO THE PLANS, PLANT LIST AND SPECIFICATIONS SHALL BE REPLACED IMMEDIATELY TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE AND LANDSCAPE ARCHITECT.
- 10. CONTRACTOR SHALL BE RESPONSIBLE FOR HAND WATERING AS REQUIRED TO MAINTAIN AND ESTABLISH ALL PLANTING (NEW, EXISTING TO BE RELOCATED, AND EXISTING PLANTINGS TO REMAIN WHILE IRRIGATION SYSTEM IS BEING INSTALLED OR REPAIRED) TO SUPPLEMENT IRRIGATION AND RAINFALL. THE IRRIGATION SYSTEM IS DESIGNED TO MAINTAIN THE LANDSCAPE PLANTINGS AND NOT ESTABLISH THEM. THE CONTRACTOR IS RESPONSIBLE FOR HAND WATERING IN ALL PLANTING AREAS, REGARDLESS OF THE STATUS OF EXISTING OR PROPOSED IRRIGATION SYSTEMS.
- 11. CONTRACTOR SHALL RE-GRADE ALL AREAS DISTURBED BY PLANT REMOVAL, RELOCATION, AND/OR FROM INSTALLATION WORK. THE CONTRACTOR SHALL REPLACE BY EQUAL SIZE AND QUALITY ANY AND ALL EXISTING PLANT MATERIAL DISTURBED OR DAMAGED BY PLANTING REMOVAL, RELOCATION, AND/OR INSTALLATION.
- 12. EXISTING TREES OR OTHER PLANT MATERIAL INDICATED ON THE PLANS TO BE RELOCATED SHALL BE HANDLED, CARED FOR, AND MAINTAINED AS NEW PLANTINGS. THE CONTRACTOR IS RESPONSIBLE FOR ANY REQUIRED ROOT PRUNING, WRAPPING, TREE SPADING OR BALL AND BURLAPPING, ADDITIONAL SUPPLEMENTAL HAND WATERING, IRRIGATION MISTERS INSTALLED AT THE TREE CANOPY, OR ANY OTHER SOUND HORTICULTURAL PRACTICE REQUIRED TO ENSURE THE SURVIVAL OF ALL RELOCATED PLANT MATERIAL.
- 13. FOR SITE GRADING AND CONTOUR INFORMATION, EXISTING VEGETATION TO REMAIN, BUILDINGS AND OTHER SITE FEATURE LOCATIONS AND THE LOCATION OF ALL ABOVE AND BELOW GROUND UTILITIES SEE THE MOST CURRENT AND UP TO DATE ARCHITECTURAL, CIVIL, ELECTRICAL, STRUCTURAL AND MECHANICAL ENGINEERING DRAWINGS AS PROVIDED BY THE OWNER OR OWNER'S REPRESENTATIVE. FIELD LOCATE ALL UNDERGROUND UTILITIES, EXISTING VEGETATION TO REMAIN AND ANY OTHER OBSTRUCTIONS AND COORDINATE WITH OWNER'S REPRESENTATIVE PRIOR TO INITIATING ANY LANDSCAPE PLANTING OR IRRIGATION INSTALLATION WORK. LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING OR REPLACING ANY DAMAGE COMMITTED TO EXISTING OR PROPOSED ELEMENTS ABOVE OR BELOW GROUND TO ITS ORIGINAL CONDITION AND TO THE SATISFACTION OF THE OWNER AND OWNER'S REPRESENTATIVE.
- 14. LANDSCAPE CONTRACTOR SHALL FIELD STAKE THE LOCATION OF ALL PLANT MATERIAL AND EDGES OF PLANTING BEDS FOR THE REVIEW AND APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INITIATING ANY INSTALLATION OF THE LANDSCAPE PLANTINGS.
- 15. LANDSCAPE CONTRACTOR SHALL COORDINATE WORK WITH THE IRRIGATION CONTRACTOR AND ALL OTHER TRADES AS REQUIRED.
- 16. CONTRACTOR IS RESPONSIBLE FOR ALL PLANTING QUANTITIES AND TAKE-OFFS FOR PRICING/BIDDING. TOTAL QUANTITIES INDICATED ON THE PLANT LIST ARE FOR REFERENCE ONLY. INDIVIDUAL PLANT QUANTITIES SHOWN ON THE PLAN SHALL HAVE PRECEDENCE OVER PLANT LIST QUANTITIES. CONTRACTOR SHALL VERIFY QUANTITIES PRIOR TO CONSTRUCTION.
- 17. STAKE ALL BED LINES AND TREE LOCATIONS FOR THE LANDSCAPE ARCHITECT'S REVIEW PRIOR TO INSTALLATION. ALL PLANTING PROCEDURES ARE SUBJECT TO THE REVIEW OF THE LANDSCAPE ARCHITECT AND THE CONTRACTOR SHALL CORRECT ANY DEFICIENCIES FOUND AT NO ADDITIONAL COST TO THE OWNER.
- 18. SECURE PLANT MATERIAL AS SPECIFIED ON PLANS. IN THE EVENT THAT PLANT MATERIALS SPECIFIED ARE NOT AVAILABLE, CONTACT LANDSCAPE ARCHITECT FOR APPROVED SUBSTITUTIONS. NO SUBSTITUTIONS FOR PLANT MATERIALS WILL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL BY THE LANDSCAPE ARCHITECT.
- 19. VERIFY THAT ALL PLANTING PRODUCTS, PLANT MATERIAL, AND PLANT QUANTITIES DELIVERED TO THE SITE MATCH WHAT IS INDICATED ON THE PLANS AND SPECIFICATIONS.
- 20. PROTECT ALL PLANT MATERIAL DURING DELIVERY TO PREVENT DAMAGE TO ROOT BALLS, TRUNKS, BRANCHES AND THE DESICCATION OF LEAVES. PROTECT ALL PLANT MATERIAL DURING SHIPPING WITH SHADE CLOTH OR SHIP WITH ENCLOSED TRANSPORT. MAINTAIN PROTECTIONS AND HEALTH OF PLANT MATERIAL STORED ON SITE. HANDLE ALL TREES WITH NYLON STRAPS. NO CHAINS OR CABLES WILL BE ALLOWED. REMOVE UNACCEPTABLE PLANT MATERIAL IMMEDIATELY FROM THE SITE.
- 21. ALL PLANT MATERIAL SHALL BE NURSERY GROWN, WELL FORMED, TRUE TO SPECIES, HARDENED OFF WITH VIGOROUS ROOT SYSTEMS, FULL CROWN AND CANOPIES, AND FREE FROM DISEASE, PESTS AND INSECTS, AND DEFECTS SUCH AS KNOTS, SUN SCALD, WINDBURN, LEAF DIS-COLORATION, IRREGULAR BRANCHING OR INJURIES.
- 22. ALL ROOT BALLS SHALL CONFORM TO THE SIZE STANDARDS SET FORTH IN "AMERICAN STANDARDS FOR NURSERY STOCK".
- 23. ALL PLANT MATERIAL SHALL CONFORM TO STANDARDS SET FORTH IN "GRADES AND STANDARDS FOR NURSERY PLANTS" PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE, DIVISION OF PLANT INDUSTRY, GAINSVILLE, FLORIDA.
- 24. ALL PLANT MATERIAL DELIVERED TO THE SITE IS SUBJECT TO THE REVIEW OF THE LANDSCAPE ARCHITECT BEFORE, DURING AND AFTER INSTALLATION.
- 25. PROVIDE PLANT SAMPLES OR PHOTOGRAPHS OF EACH PLANT SPECIFIED TO THE LANDSCAPE ARCHITECT FOR COMPLIANCE REVIEW PRIOR TO INSTALLATION.
- 26. TEST FILL ALL TREE AND PLANTING PITS WITH WATER, PRIOR TO PLANTING, TO ASSURE PROPER SOIL PERCOLATION. PITS WHICH DO NOT ADEQUATELY DRAIN SHALL BE FURTHER EXCAVATED TO A DEPTH SUFFICIENT FOR DRAINAGE TO OCCUR AND/OR BACKFILLED WITH SUITABLE DRAINAGE GRAVEL. NO ALLOWANCES SHALL BE MADE FOR PLANT MATERIAL LOSS DUE TO IMPROPER DRAINAGE. CONTRACTOR SHALL REPLACE LOST PLANT MATERIAL WITH SAME SIZE AND SPECIES AT NO ADDITIONAL COST TO OWNER.
- 27. ALL PLANT MATERIALS, INCLUDING RELOCATED PLANT MATERIAL, SHALL BE PLANTED IN A PROFESSIONAL MANNER TYPICAL TO THE INDUSTRY STANDARDS OF THE AREA TO ASSURE COMPLETE SURVIVABILITY OF ALL INSTALLED PLANT MATERIALS AS WELL AS TO PROVIDE AN AESTHETICALLY APPROVED PROJECT. CONTRACTOR SHALL REFER TO THE PLANTING DETAILS FOR MINIMUM SIZE AND WIDTH OF PLANTING PITS AND BEDS, GUYING AND STAKING, MULCHING, AND OTHER PLANTING REQUIREMENTS.
- 28. ALL PLANTING AREAS SHALL BE WEED FREE PRIOR TO PLANTING INSTALLATION.
- 29. REMOVE ALL PLANTING AND LANDSCAPE DEBRIS FROM THE PROJECT SITE AND SWEEP AND WASH CLEAN ALL PAVED AND FINISHED SURFACES AFFECTED BY THE LANDSCAPE INSTALLATION.
- 30. NO SOIL DISTURBANCE OR COMPACTION, CONSTRUCTION MATERIALS, TRAFFIC OR BURIAL PITS ARE ALLOWED IN THE TREE PROTECTION ZONE OF EXISTING TREES.
- 31. TREE BARRICADES MUST BE INSTALLED AROUND EXISTING TREES BEFORE ANY GRADING OR CONSTRUCTION AND NOT REMOVED UNTIL AFTER FINAL ACCEPTANCE OF THE JOB.

CIVICA

8323 NW 12th St. Suite 106 Doral, FL 33126 tel: 305.593.9959 www.civicagroup.com AA #26001093

PROJECT:

WALLACE PARK IMPROVEMENTS

E WALLACE ST. BELLE ISLE, FL 32809

APPLICANT:

THE CITY OF BELLE ISLE



1600 NELA AVENUE BELLE ISLE, FL 32809

CIVICA PROJECT No: 200108

ISSUED FOR:


ZONING APPROVAI

No.	DATE	REVISION	BY

DRAWN BY:	APPROVED BY:
DPD	RL
DATE:	SCALE:
2020-06-20	As Shown

KEYPLAN

SEAL/SIGNATURE



This drawing is the property of CIVICA and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on request.


COPYRIGHT © 2020

SHEET TITLE

LANDSCAPE NOTES

SHEET NUMBER

L-3



LANDSCAPE ALONG RIGHT-OF-WAY

LENGTH ALONG ROW TREES REQUIRED:

338.5 LIN.FT.

TREES REQUIRED =

1 TREE PER 30 LIN. FT. 338.5/30 = 11.2

12 TREES REQUIRED

TREES PROVIDED = 12 TREES PROVIDED

INTERNAL LANDSCAPING REQUIREMENTS:

TOTAL AREA OF SITE

= 104,686 SQ.FT. = 2.4 ACRES

TOTAL IMPERVIOUS AREA

= 5,635 SQ.FT.

INTERIOR LANDSCAPE AREA REQUIRED

= TOTAL IMPERVIOUS AREA x 2.5%

= 5,635 SQ.FT. X .025 = 141 SQ.FT. REQUIRED

INTERIOR LANDSCAPE AREA PROVIDED

= 368 SQ.FT.

TREES REQUIRED

= 1 TREE / 100 S.F. = 1.4 TREES = 2 TREES REQUIRED

TREES PROVIDED

= 3 TREES PROVIDED

TREE PLANTING SCHEDULE

SYMBOL	QTY.	BOTANICAL/COMMON NAME	HEIGHT	SPREAD	ROOT	REMARKS	
QV	3	QUERCUS VIRGINIANA LIVE OAK	12'	6'	B&B	3" CAL. MIN.	
QV1	12	QUERCUS VIRGINIANA LIVE OAK	14'	7'	B&B	4" CAL. MIN.	

SYMBOL	QTY.	BOTANICAL/COMMON NAME	HEIGHT	SPREAD	ROOT	REMARKS
SHRUBS:						
AG	68	ARACHIS GLABRATA PERENNIAL PEANUT	6"	NA	3 GAL.	30" O.C., FULL
HP	16	HAMELIA PATENS FIREBUSH	24"	18"	3 GAL.	24" O.C., FULL
IVN	148	ILEX VOMITORIA NANA DWF. YAUPON HOLLY	24"	18"	3 GAL.	30" O.C., FULL
МС	98	MUHLENBERGIA CAPILLANS MUHLY GRASS	24"	18"	3 GAL.	30" O.C., FULL
PM	58	PODOCARPUS MACROPHYLLUS SOUTHERN YEW	30"	24"	3 GAL	FULL, WELL BRANCH
SB	340	SPARTINA BAKERI SAND CORD GRASS	24"	18"	3 GAL.	36" O.C., FULL
ZF	78	ZAMIA FRUTICOSA COONTIE	24"	18"	3 GAL.	30" O.C., FULL
SOD-MULCH:	_					
SOD	53,177 sq.ft	PASPALUM NOTATUM BAHIAGRASS				
FIELD TURF	26,600 sq.ft	CYNODON DACTYLON BERMUDA GRASS var. 419				

CIVICA

8323 NW 12th St. Suite 106 Doral, FL 33126 tel: 305.593.9959

PROJECT:

www.civicagroup.com AA #26001093

WALLACE PARK IMPROVEMENTS

E WALLACE ST. BELLE ISLE, FL 32809

APPLICANT:

THE CITY OF BELLE ISLE



1600 NELA AVENUE BELLE ISLE, FL 32809

CIVICA PROJECT No: 200108

ISSUED FOR:

ZONING APPROVAL

			-
).	DATE	REVISION	BY

DRAWN BY:	APPROVED BY:
DPD	RL
DATE:	SCALE:
2020-06-20	As Shown

KEYPLAN

SEAL/SIGNATURE

SEAL/SIGNATURE

PETER

LA-1696

STATE OF

Douglas Dierlich LA0001696

This drawing is the property of CIVICA and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on request.

COPYRIGHT © 2020

SHEET TITLE

LANDSCAPE PLAN

SHEET NUMBER


L-1

LEGAL DESCRIPTION PER ACCURIGHT SURVEYS OF ORLANDO, INC. DATED: 01/23/2018

PRELIMINARY SITE PLAN FOR CITY OF BELLE ISLE WALLACE PARK IMPROVEMENTS

CITY OF BELLE ISLE, FLORIDA

OCPA PARCEL ID# 24-23-29-8977-00-021



VICINITY MAP

UTILITY PROVIDERS

ORANGE COUNTY UTILITIES 9150 CURRY FORD ROAD ORLANDO, FL 32825 CONTACT: VICTOR GONZALEZ

(407) 836-6869, EXT. 66869

ORLANDO UTILITIES COMMISSION 6003 E. PERSHING AVENUE ORLANDO, FL 32822 CONTACT: STEVEN LOCKINGTON

(407) 434-2568

1120 S. ROGERS CIRCLE **BOCA RATON, FL 33487 CONTACT: DINO FARRUGGIO** PHONE: (561) 997-0240

POWER: DUKE ENERGY **452 E. CROWN POINT ROAD** WINTER GARDEN, FL 34787 **CONTACT: STEPHANIE OLMO** PHONE: (727) 905-3376

PROJECT TEAM

OWNER CITY OF BELLE ISLE 1600 NELA AVENUE BELLE ISLE, FL 32809

ARCHITECT: ROLANDO LLANES, AIA 8323 NW 12TH STREET-SUITE 106 DORAL, FLORIDA 33126 PHONE: (305) 593-9959 EMAIL: RLLANES@CÍVICAGROUP.COM

ENGINEER: MAJOR STACY, P.E. WINTER PARK, FL 32789 PHONE: (407) 960-5868 FAX: (866) 571-8179


EMAIL: MSTACY@APPIANFL.COM

SURVEYOR ACCURIGHT SURVEYS OF ORLANDO, INC. SURVEYOR: JAMES D. BRAY 2012 E. ROBINSON STREET ORLANDO, FL 32803

EMAIL: JBRAY@ACCURIGHTSURVEYS.NET



AERIAL MAP SCALE: 1" = 1000'



SOILS MAP SCALE: 1" = 1000'



FEMA FLOOD MAP



APPIAN ENGINEERING

2221 LEE ROAD, SUITE 27 WINTER PARK, FLORIDA 32789 (407) 960-5868

BOARD OF PROFESSIONAL ENGINEERING CERTIFICATE NO. 32174

PERMITS REGIURED						
PERMITS REQUIRED						
AGENCY	PERMIT TYPE	DATE APPLIED	DATE APPROVED	APPROVAL NO.	/3\ /4\	
CITY OF BELLE ISLE	SITE PERMIT				<u>/5\</u>	
S.J.R.W.M.D.	ERP				À	
F.D.E.P.	WATER				<u>/8\</u>	
F.D.E.P.	WASTEWATER				<u>/9\</u> _/10\	
					REV.	

SCALI	E: T = TOO	00	
\triangle			
2			
3			
4			
<u>/5</u>			
<u>/6\</u>			
77			6/23/20
<u>/8\</u>			
<u>/9\</u>			
<u>∕10\</u> REV.	DATE	DESCRIPTION	This item has been electronically signed and sealed by Luke shown on the time stamp using a digital signature.
REV.	DATE	DESCRIP HON	Printed copies of this document are not considered signed a must be verified on any electronic copies.

SHEET INDEX

EXISTING CONDITIONS

FIRE TRUCK ROUTE PLAN

EROSION CONTROL, DEMO & M.O.T. PLAN

PAVING, GRADING & DRAINAGE PLAN


COVER SHEET


C3.0 GEOMETRY PLAN


AERIAL SITE PLAN

CROSS-SECTIONS


UTILITY PLAN














4 APPIAN ENGINEERING LL

€^{OR} 6/23/20

