EXHIBIT A

STATE OF SOUTH CAROLINA)		
)	AGREEMENT FOR SERVICES AN	ΙĽ
)	CONVEYANCE OF REAL PROPERTY	
COUNTY OF BEAUFORT)		

THIS AGREEMENT FOR SERVICES AND DONATION OF REAL PROPERTY ("Agreement") is made and entered into as of the latter date of execution below by and between the TOWN OF BLUFFTON, a South Carolina municipal corporation (the "Town"), BEAUFORT COUNTY, a political subdivision of the State of South Carolina (the "County"), and SOUTHEASTERN PROPERTY DEVELOPMENT, LLC and its subsidiaries BC BUCKWALTER, LLC and BUCKWALTER PLACE ASSOCIATION, INC. (collectively "SEDA"). The Town, District, and SEDA may from time to time be referred to individually as a "Party" and collectively as the "Parties."

RECITALS:

WHEREAS, the Town of Bluffton Town Council ("Town Council") initially approved the Buckwalter Place Master Plan ("BP Master Plan") via majority vote on July 17, 2007, which is associated with real property located within the Town of Bluffton's jurisdiction. The BP Master Plan shows a right-of-way connecting Innovation Drive and Discovery Drive within Buckwalter Place ("Connector Road"); and,

WHEREAS, Buckwalter Place Association, Inc. currently owns the real property which contains the future right-of-way for the Connector Road consisting of approximately 25.36-acres, more or less, and identified as Beaufort County Tax Map No. R610 022 000 1101 0000, identified as Parcel G on the Plat in "Exhibit A" attached hereto and incorporated herein by reference; collectively hereinafter the "Parent Parcel"; and,

WHEREAS, the County, to address the transportation needs for the developing area adopted Transportation Impact Fees ("*Impact Fees*"), described in more detail herein, where said fees shall be used for specific projects including the Connector Road; and,

WHEREAS, the County and the Town entered into an agreement for the use of Impact Fees....

WHEREAS, the Parties agree that the purpose of this Agreement is to permit the Parties to formalize the agreed upon responsibilities, covenants and obligations of each Party to fulfill the obligations established in the BP Master Plan to construct the Connector Road and complete the Project in a timely manner.

Now, Therefore, for and in consideration of the mutual promises, undertakings and covenants set forth herein, the receipt and sufficiency of which are hereby acknowledged and affirmed, the Parties hereto agree as follows:

- **I. RECITALS INCORPORATED**. The foregoing recitals are hereby incorporated as though fully set forth herein.
- **II. THE PROJECT DEFINED.** The Parties agree that for purposes of this Agreement, the "*Project*" is defined as the construction of the Connector Road on and across the Parent Parcel as approved in the BP Master Plan and as further shown and detailed in the Exhibits attached hereto.

III. PROJECT BACKGROUND.

a. Buckwalter Place. The Town of Bluffton Town Council initially approved the Buckwalter Place Master Plan via majority vote on July 17, 2007, which was last revised in April 2019 and as fully provided for in "Exhibit B", attached hereto and incorporated herein by reference. The initial Master Plan and its subsequent amendments show the Connector Road connecting the development to the northern development, initially known as Parcel C4 and now known as Washington Square. The developer of Washington Square constructed the portion of the Connector Road up to the shared property line with Buckwalter Place when installing its infrastructure. The portion of the Connector Road within Buckwalter Place, beginning at the intersection of Innovation Drive and Discovery Drive and ending at its intersection with the existing portion constructed by Washington Square, has yet to be constructed.

SEDA obtained a Development Permit (DP-02-16-009495) from the Town on January 6, 2022, for the construction of the Connector Road, described in more detail in "**Exhibit C**", attached hereto and incorporated herein by reference.

b. Connector Road Property and Existing Roads. The general location of the Connector Road right-of-way is shown in the "Wetland Earthwork Plans for Connector Road to Parcel 4" provided in "Exhibit D", attached hereto and incorporated herein by reference.

SEDA also owns a portion of two rights-of-way which intersect with the Connector Road known as Innovation Drive and Discovery Drive consisting of consisting of approximately 3-acres, more or less, and identified as Beaufort County Tax Map No. R610-029-000-1720-0000 (the "Existing Roads") as shown on the Plat attached as "Exhibit E", attached hereto and incorporated herein by reference.

- c. Beaufort County Impact Fees. The County approved a Transportation Impact Fee Ordinance and its corresponding Support Study with Ordinance 2023/08 on March 13, 2023. Pursuant to Beaufort County Code Section 82-34 "Accounts and Expenditures", the Transportation Impact Fees may only be expended as follows:
 - i. Beaufort County Code Section 82-34(b)(1) states that "expenditure of development impact fees shall be made only for the category of system improvements, and within or for the benefit of the service area, for which the development impact fee was imposed as shown by the relevant capital improvements plan and as authorized in the State Development Impact Fee Act".
 - ii. Beaufort County Code Section 82-87 includes Table 82-87b: Road Facility Project South of the Broad River of the Impact Fee Ordinance, which identifies Buckwalter Parkway Access Management as a Capital Improvement Project. To identify transportation needs for this area, the County approved an updated Buckwalter Parkway Access Management Plan via Ordinance 2022/07 on February 28, 2022, and Town Council subsequently adopted the Plan via Resolution on March 8, 2022. The Access Management Plan, Figure 3B (Exhibit A) identifies the Connector Road as a Cross Access Connection. Therefore, the Connector Road is a qualified and approved project for which Transportation Impact Fees may be expended.

- **IV. TERM AND SCHEDULE.** The Parties agree that SEDA shall commence construction of Connector Road no later than ______, 2025, and the Project shall be completed no later than ______, 2026. The Project shall be considered completed when SEDA obtains a certification of completion from ______ stating the work was completed and is in compliance with all State and local laws, regulations and requirements.
- V. PROJECT WORK. The Parties acknowledge and agree that SEDA shall be solely responsible for all work related to the Project including, but not limited to, obtaining permits and approvals, site preparation, construction of Connector Road, and all other services and actions associated with and necessary to complete the Project.

VI. PROJECT COST AND PAYMENT.

- a. *Project Cost.* SEDA has provided a breakdown of the costs associated with the Project, with a total cost of One Million Two Hundred Thousand (\$1,200,000) Dollars; the details and breakdown of costs are fully shown in "**Exhibit F**", attached hereto and incorporated herein by reference; collectively hereinafter referred to as the "*Project Cost*". SEDA shall be solely responsible for the initial costs associated with the Project and shall be reimbursed for a portion of the Project Cost as established in this Agreement.
- b. *Project Cost Reimbursement Amount*. The Parties acknowledge and agree to the Project Cost, and to those terms and conditions contained in this Agreement that may affect the amount associated with the Project Cost. The Parties agree to each individually be solely responsible for a third (1/3) of the Project Cost in an amount not to exceed Four Hundred Thousand (\$400,000) Dollars except for any additional costs that are endured pursuant to the terms of this Agreement, specifically to include any Overage Costs as established in this Agreement.
- c. Request for Payment. Following completion of the Project, whereby completion has occurred once the final approvals have been provided to SEDA by ______, SEDA shall provide separate written requests to the Town and to the County for payment of the Party's portion of the Project Costs. The required written request shall be made pursuant to Section X of this Agreement. The written request required in this Section shall include a complete breakdown of the total Project Cost.
- d. *Project Cost Overages*. The Parties acknowledge and agree that cost overages may occur as the Project progresses due to unexpected cost inflation, unforeseen circumstances and environmental project delays. The Parties agree to cost overages in an amount not to exceed ten (10%) percent of the Project Cost shown in Exhibit F. If cost overages exceed ten (10%) percent of the Project Cost, then SEDA shall provide the Town and the County a written explanation of said overages prior to the expenses be incurred and shall obtain approval from the Town and County prior to incurring the expenses. Failure by SEDA to obtain said prior approval may result in the Town or the County not reimbursing SEDA for the overages. The Parties agree to each individually be solely responsible for a third (1/3) of any cost overages resulting from the terms and conditions in this section.
- e. *Review of Project Cost.* Following a written request from SEDA pursuant to Section III(c), the Town and County shall have ten (10) business days to review the Project Cost breakdown and

provide a written request to SEDA for additional information or details associated with any or all of the Project Cost. SEDA must provide a written response to the aforementioned inquiry within ten (10) business days, failure to provide said response shall result in an automatic amendment to any cost dispute to the benefit of the Town or County.

f. Payment by Parties. Pursuant to Section III(a) of this Agreement, SEDA shall initially be responsible for the total cost of the Project. The Parties acknowledge and agree that SEDA is not required to pay any other Party any amount of funds for the Project Cost.

The Town and County shall provide payment to SEDA for its portion of the Project Cost within Forty-Five (45) days from either: 1) the date of the written request required in Section III(c), or 2) following completion of a review of the Project Cost established in Section III(d); whichever date comes later.

- i. Form of Payment. The Parties acknowledge and agree that the Town and County shall remit payment to SEDA in the form of a written check and mailed to the address provided for in Section X of this Agreement.
- VII. CONVEYANCE OF RIGHT-OF-WAY. The Parties acknowledge and agree that in order to allow the use of Impact Fees for the construction of the Connector Road, the right-of-way must be a public road which requires its transfer to a public entity. As the Project may impact the Existing Roads which may utilize Impact Fees, the Existing Roads should also be public roads owned by a public entity. Therefore, SEDA, specifically Buckwalter Place Association, Inc., agrees to convey a limited warranty deed to the Town prior to the start of construction, for a nominal consideration in the amount of Ten and 00/100 (\$10.00) Dollars and exclusive of any development rights, the Connector Road and the Existing Roads pursuant to a separate Donation Agreement and approval by Resolution of Town Council. The Town shall be responsible for the cost of the necessary subdivision plat to create the Connector Road right-of-way and submit application for review and approval.

VIII. RECORDS AND REPORTS.

- a. Record Retention, Reports and Access. The Parties shall maintain all records and reports connected with this Agreement and the Project for a period of at least four (4) years following the Effective Date. During the aforementioned retention period or at anytime during a term of this Agreement, the Town or County may request access to any and all records associated with this Agreement or the Project; and SEDA shall provide requested records within ten (10) business days from the date of receipt of the written request.
- b. Accounting Report. SEDA acknowledges and understands that the funds associated with this Agreement are public monies and shall be used only for the purposes stated in this Agreement. SEDA agrees to comply with any and all requests from the Town or the County regarding accounting reports including, but not limited to, breakdown of Project Cost, payments to vendors, payments to contractors or payments for licenses or permits. Failure to provide the requested documents may result in the Town or County denying payment of the reimbursement for the Project Cost.

- IX. TERMINATION. Any Party terminate this Agreement with or without cause, thirty (30) calendar days prior to commencement of construction of the Connector Road with a written notice to all other Parties. If thirty (30) calendar days prior to construction is initiated, then Town or the County terminate this Agreement, then SEDA shall be reimbursed for any expended funds that were included in the Project Cost. If SEDA terminates this Agreement at anytime, the Town nor the County shall be responsible for any costs associated with the Project nor required to provide any payments to SEDA for any Project Cost.
- X. NOTICES. Whenever notice is required or permitted under the terms of this Agreement, it shall be in writing and personally delivered or sent postage or delivery charges prepaid by either (a) United States mail, certified, return receipt requested, in which case notice shall be deemed given on the certified date of delivery or rejection of delivery, or (b) by any national express delivery service which provides evidence of delivery. All notices shall be addressed to the following address (or at such other address as may hereafter be substituted by notice in writing thereof):

The County:	Beaufort County Attn: Mike Moore, Administrator 100 Ribaut Road Beaufort, SC 29902 Phone: 843.255.2000 Email: Mmoore@bcgov.net	The Town:	Town of Bluffton Attn: Stephen Steese, <i>Town Manager</i> 1 Town Center Court Hilton Head Island, SC29928 Phone: 843-341-4600 Email: marco@hiltonheadislandsc.gov
With Copy to:	Beaufort County Attorney Attn: Brian Hulbert 100 Ribaut Road Beaufort, SC 29902 Phone: 843.255.2055 Email: brian.hulbert@bcgov.net	With Copy to:	Finger, Melnick, Brooks & LaBruce, P.A. Attn: Terry L. Finger, Esq. P.O. Box 24005 Hilton Head Island, SC 29925 Phone: 843.681.7000 Emal: tfinger@fingerlaw.com
To SEDA:	Southeastern Property Development, LLC Attn: Ph. Em.	To SEDA:	BC Buckwalter, LLC Attn: Ph Em
To SEDA	Buckwalter Place Association, Inc. Attn: Ph. Em.		

- XI. COMPLIANCE WITH LAWS. In execution of this Agreement, SEDA certifies and agrees that it is and shall continue to conduct all activities, construction and business in compliance with all applicable federal, state, and local laws, regulations and ordinances and to obtain and maintain all appropriate permits and consents. The terms of this Section shall survive termination of this Agreement. Failure to comply with this Section and/or failure to construct the Connector Road in compliance with the applicable laws and regulations may result in partial or full denial of reimbursement by either the Town or the County, or both.
 - a. Conflict of Interest. SEDA shall comply with all applicable conflict of interest laws, ordinances and regulations now in effect or hereafter to be enacted during the term of this Agreement. SEDA warrants that as of the Effective Date it is not aware of any facts that create a conflict of interest. If SEDA hereafter becomes aware of any facts that may reasonably be construed to create a conflict of interest, SEDA shall immediately inform the Town and County, and disclose all relevant facts in writing. Failure to comply with this Section shall be deemed a breach of the Agreement and may result in the immediate termination of the Agreement.
- XII. INDEMNIFICATION. SEDA shall, at its cost and expense, protect, defend, indemnify and hold harmless the Town and County, its directors, officers, employees, and agents, from and against any and all demands, liabilities, causes of action, costs and expenses (including attorney's fees), claims, judgments, or awards of damages, arising out of or in any way resulting from the acts or omissions of SEDA, its directors, officers, employees, or agents, relating in any way to SEDA's performance under this Agreement.
- **XIII. ASSIGNMENT.** The Parties understand and agree that SEDA may neither assign nor transfer any rights or obligations under this Agreement without the prior written consent of the Town and County a fully executed Assignment Agreement, approved by the Parties who executed and approved this original Agreement.
- **XIV. NON-DISCRIMINATION.** The Parties certifies that in the performance of this Agreement, no Paty will not discriminate any person, client, or subcontractor on account of race, color, sex, age, religion, handicap, or national origin. It is the policy of the Town to comply with Title VI of the 1964 Civil Rights Act (Title VI) and its related statutes. To this end, the Town gives notice to all vendors or businesses that the Town assures full compliance with Title VI and its related statues in all programs, activities, and contracts. It is the policy of the Town that no person shall be excluded from participation in, denied the benefit of, or subjected to discrimination under any of its programs, activities, or contracts based on race, color, national origin, age, sex, disability, religion, or language. Pursuant to Title VI requirements, any entity that enters into a contract or agreement with the Town including, but not limited to vendors or businesses, may not discriminate based on race, color, national origin, age, sex, disability, religion, or language.

XV. MISCELLANEOUS.


a. *Relationship of the Parties*. Notwithstanding any provision hereof, for the purposes of this Agreement each Party is an independent party and nothing contained in this Agreement shall be construed as creating any agency, partnership, franchise, business opportunity, joint venture, or any other type of agency relationship. The Parties acknowledge, understand and


- agree that this Agreement does not create a fiduciary relationship between the Parties nor does it create any obligations unless contained in the terms of this Agreement.
- b. *Construction of Agreement*. Each Party acknowledges that it has participated in the negotiation and drafting of this Agreement. No provision of this Agreement shall be construed against or interpreted to the disadvantage of any Party hereto or thereto by any court by reason of such Party having or being deemed to have structured, dictated, or drafted any provision in the Agreement.
- c. Sole Agreement, Merger, and Amendments. This Agreement contains all of the terms and conditions agreed to between the Parties and supersedes all prior agreements, and there are no oral agreements relating to the transaction covered hereby. All other discussions, proposals, agreements or offers are merged into this Agreement. This Agreement cannot be amended, altered, changed or modified unless each such alteration, amendment, change or modification shall have been set forth in writing in its entirety and signed and delivered by each Party.
- d. *Counterparts*. This Agreement may be executed in one or more counterparts, all of which taken together shall constitute one and the same instrument.
- e. *Good Faith.* The Parties shall act in good faith in performing and discharging their respective duties and obligations hereunder. Any provision requiring the approval of either Party shall not be unreasonably withheld. The Parties shall execute and deliver such other instruments and documents as reasonably may be necessary to implement and effectuate the terms of this Agreement.
- f. Waiver. No provision, condition or covenant of this Agreement shall be waived by either Party hereto except by a written instrument delivered to the other Party and signed by the Party consenting thereto. If the Town fails to enforce any provision of this Agreement, that failure does not waive the provision or Town's right to enforce it.
- g. Successors and Assigns. All provisions of this Agreement shall be binding on and inure to the benefit of each Party and each Party's respective heirs, executors, legal representatives, successors, successors in title and assigns.
- h. *Time of the Essence*. Time is of the essence of this Agreement, although a request for additional time should not be unreasonably withheld when the additional time is needed by a Party to receive the approval and authority required by either local or state law.
- i. *Captions*. The section headings appearing in this Agreement are for convenience of reference only and are not intended to any extent for the purpose, to limit or define the test of any section or any subsection hereof.
- j. Severability. If any provision of this Agreement is held to be illegal, invalid or unenforceable, then this Agreement shall be construed and enforced as if such illegal, invalid or unenforceable provision had never comprised a part of this Agreement, and the remaining provisions of this Agreement shall remain in full force and effect and shall not be affected by the illegal, invalid or unenforceable provision or by its severance from this Agreement.

k. *Applicable Law.* This Agreement has been made in the State of South Carolina, and shall be interpreted in accordance with South Carolina law, and any enforcement of this Agreement shall be brought in the State of South Carolina.

IN WITNESS WHEREOF, the Parties hereto have affixed their signatures hereto on the Effective Date.

Town of Bluffton: WITNESSES:	
	Stephen Steese
	Town Manager
D 4 4 4	
Beaufort County: WITNESSES:	
	Michael Moore
	County Administrator
Southeastern Property Development, LLC: WITNESSES:	
	<u> </u>
BC Buckwalter, LLC: WITNESSES:	
Buckwalter Place Association, Inc.: WITNESSES:	











BUCKWALTER PLACE COMMERCE PARK MASTER PLAN

BLUFFTON, SOUTH CAROLINA
APRIL 2019





TOWN OF BLUFFTON FINAL PLAN APPROVAL

APPLICATION NO.: DP-02-16-009495
APPLICATION TYPE: Development Plan

ISSUE DATE: 01/06/2022 APPROVAL DATE: 07/13/2016 EXPIRATION DATE: 07/13/2018

PARCEL NO.: R610 029 000 0786 0000

PROPERTY ADDRESS: 27 DISCOVERY DR, BLUFFTON

SC 29910

ZONING DISTRICT: Planned Unit Development

APPLICANT: Carolina Engineering Consultants, Inc.

OWNER: Phil Madhere

BC Buckwalter LLC

DESCRIPTION: This approval is granted for a Development Plan for a Kroger and mixed use development located on the approx. 39 acres in the Buckwalter Place development. The project scope includes a Kroge grocery store, retail, restaurants, 124 multi family units, fuel center and a park. This approval is based on Site Development Plans prepared by Thomas and Hutton engineers, dated 5/13/2016 and Landscape Plan prepared by Wittmer, Jones Keefer dated June 30, 2016.

STATUS: DEVELOPMENT PLAN AMENDMENTAPPROVED 2/14/2017 based on Thomas & Hutton Engineer date stamped plans last modified January 10, 2017. AND Wittmer, Jones, Keefer dated July 22, 2016.

05/19/2020: An application for a Development Plan Amendment for construction of the TCL Culinary Institution has been submitted for review. Comments will be reviewed at the May 27 meeting of the DRC. STATUS UPDATE: Re-submittal to address parking for the project is required Awaiting re-submittal. STATUS 08/13/2020: Re-submittal application materials received. Comments will be provided by 8/21/2020.

STATUS 08/27/2020: Re-submittal to address comments received. The Amendment is approved with the following CONDITIONS OF APPROVAL:

STATUS 12/20/21: The Connector Road to Parcel 4 was on the agenda for the 12-20-21 DRC meeting an was subsequently approved without comments.

A shared parking agreement, recorded with Beaufort County, to provide parking for the TCL Culinary Institute will be required prior to the issuance of the Certificate of Occupancy for the building.

Jehry

12/21/2021

TOWN OF BLUFFTON APPROVAL SIGNATURE

DATE

The Applicant must schedule and host a Pre-Construction Meeting with Town Staff, the design engineer, the site general contractor, and any other necessary personnel involved in the horizontal construction. After the this meeting is conducted, the Applicant will be provided a Conditional Notice to Proceed authorizing the installation of tree protection fencing and erosion control devices. Upon installation of such fencing and devices, the Applicant must schedule Pre-Clearing and Stormwater Inspections of the completed work. Once approved by the Town, the Applicant will be provided a Notice to Proceed authorizing the commencement of horizontal construction as depicted in this Final Plan Approval.

WETLAND EARTHWORK PLANS FOR CONNECTOR ROAD TO PARCEL 4 BLUFFTON, SOUTH CAROLINA

PREPARED FOR:

BC BUCKWALTER, LLC

2473 PERIMETER PARKWAY BUILDING 100, SUITE 370, AUGUSTA,
GA 30909

TM# R610-022-000-1101-0000

J-25125.0004


NOVEMBER 18, 2021

PREPARED BY:

WETLAND EARTHWORK
CONNECTOR ROAD TO PARCEL 4
VERTICAL DATUM: NAVD 88







	Sheet List Table						
Sheet Number	Sheet Title						
CO	COVER SHEET						
G1.1	GENERAL NOTES AND SHEET INDEX						
G2.1	EXISTING CONDITIONS PLAN						
C1.1	LAYOUT PLAN						
C2.1	GRADING & DRAINAGE PLAN						
C3.2	GRADING & DRAINAGE DETAILS						
EC1.1	ES & PC NOTES						
EC1.2	ES & PC NOTES						
EC2.1	ES & PC PLAN - INITIAL PHASE						
EC3.1	ES & PC PLAN - INTERMEDIATE PHASE						
EC4.1	ES & PC PLAN - STABILIZATION PHASE						
EC5.1	ES & PC DETAILS						

	REVISION HISTORY		
REV. NO.	REVISION	BY	DATE

	SUBMITTAL HISTORY	
TOWN OF BLUFFTON		11/18/2021
	SUBMITTED TO	DATE





p.912.234.5300


	AE	<u>BBRE</u>	EVIATIONS		
HDPE	HIGH DENSITY POLYETHYLENE	FR	FRAME	RCP	REINFORCED CONCRETE PIPE
вот	воттом	GB	GRADE BREAK	RJP	RESTRAINED JOINT PIPE
BFS	BEGIN FULL SUPER	GI	GRATE INLET	R/W	RIGHT-OF-WAY
BNC	BEGIN NORMAL CROWN	GV	GATE VALVE	RC	REVERSE CROWN
BNS	BEGIN NORMAL SHOULDER	INV	INVERT ELEVATION	SD	STORM DRAINAGE
BV	BUTTERFLY VALVE	JB	JUNCTION BOX	SDMH	STORM DRAINAGE MANHOLE
СІ	CURB INLET	LF	LINEAR FEET	SF	SQUARE FEET
cv	CHECK VALVE	LC	LEVEL CROWN	ss	SANITARY SEWER
СРР	CORRUGATED PLASTIC PIPE	LSM	LOW SHOULDER MATCH	тс	TOP OF CONCRETE
DIP	DUCTILE IRON PIPE	MAX	MAXIMUM	TG	TOP OF GRAVEL
EL	ELEVATION	MIN	MINIMUM	ТР	TOP OF PAVEMENT
EFS	END FULL SUPER	мн	MANHOLE	sw	TOP OF SIDEWALK
ENC	END NORMAL CROWN	ос	ON CENTER	TYP	TYPICAL
ENS	END NORMAL SHOULDER	PC	POINT OF CURVE	w	WATER
EOA	END OF ALIGNMENT	РН	POST HYDRANT	W/	WITH
FG	FINISH GRADE	РТ	POINT OF TANGENT	wv	WATER VALVE
FH	FIRE HYDRANT	PVC	POLYVINYL CHLORIDE	YI	YARD INLET
FM	FORCE MAIN (SANITARY SEWER)	PV	PLUG VALVE		
		I	1	1 1	1

	WATER LEGE	<u>ND</u>
DESCRIPTION	EXISTING	PROPOSED
WATER MAIN	10"W -	
SINGLE SERVICE LATERAL		
DOUBLE SERVICE LATERAL	<u> </u>	>
VALVE AND BOX	\otimes	€
FIRE HYDRANT W/VALVE & BOX	\otimes - \Diamond -	₩•
POST HYDRANT) H	>
REDUCER		•
BACKFLOW PREVENTOR		
CROSS	I <u></u> I	1_1
TEE	<u> </u>	1-1
90° BEND - HORIZONTAL		_
45° BEND - HORIZONTAL	/	/1
22-½° BEND - HORIZONTAL	/	/
II-¼° BEND - HORIZONTAL	1	/ 1
BEND - VERTICAL		11
CAP		l

	SEWER LEGEN	<u>ND</u>
DESCRIPTION	EXISTING	PROPOSED
GRAVITY PIPE	ss	
SINGLE SERVICE LATERAL		
DOUBLE SERVICE LATERAL		—
MANHOLE		•
CLEANOUT	○ ₁	• +
FORCEMAIN -	IO"FM IO"FM	IO"FM IO"FM _
VALVE AND BOX	\otimes	Θ
FLUSH HYDRANT))
REDUCER		•
BACKFLOW PREVENTOR		
CROSS	_	I <u></u> I
TEE	1-1	ı ⁻ ı
90° BEND - HORIZONTAL	_	_
45° BEND - HORIZONTAL	/	/
22-½° BEND - HORIZONTAL	/	/
II-¼° BEND - HORIZONTAL	1	1
BEND - VERTICAL		11
PLUG		

HATCH LEGEND				
SUITABLE ROAD FILL				
WETLAND	* * * * * * * * * * * * * * * * * * *			
PRESERVED WETLAND BUFFER				

DR	DRAINAGE LEGEND							
DESCRIPTION	EXISTING	PROPOSED						
PIPE								
DITCH								
CURB INLET	0	•						
GRATE INLET								
JUNCTION BOX	0	•						
OUTLET STRUCTURE								



INDEX

SCALE: I" = 500'

GENERAL NOTES

- I. BOUNDARY AND TOPOGRAPHIC INFORMATION PROVIDED BY THOMAS AND HUTTON. ALL TOPOGRAPHIC INFORMATION IS BASED ON AVAILABLE LIDAR DATA USING NAVD88 VERTICAL DATUM. COORDINATES ARE BASED ON THE SOUTH CAROLINA STATE PLANE COORDINATE SYSTEM OF NAD 1983. VERIFY CHANGES IN ELEVATIONS IN ROADBEDS AND OTHER AREAS RESULTING FROM CONTRACTOR CLEARING AND STRIPPING.
- 2. SEE SURVEY CONTROL PLAN FOR BENCHMARKS. HORIZONTAL AND VERTICAL CONTROL SHOWN IN THESE PLANS ARE TO BE USED FOR ALL LAYOUT AND RECORD DATA FOR THIS PROJECT. IF DISCREPANCIES ARE FOUND CONTACT THOMAS AND HUTTON BEFORE PROCEEDING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ESTABLISH SUPPLEMENTAL CONTROL WITHIN THE PROJECT AS NEEDED. CONTRACTOR IS TO VERIFY ACCURACY OF ANY TEMPORARY BENCHMARKS SHOWN PRIOR TO UTILIZING THEM FOR CONSTRUCTION.
- 3. THE EXISTING UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UPON AVAILABLE INFORMATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF ALL UTILITIES ENCOUNTERED DURING CONSTRUCTION, CONTRACTOR SHALL COORDINATE ALL WORK WITH THE OWNER AND UTILITY COMPANIES. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY WITH ANY DISCREPANCIES AND TAKE STEPS TO PROTECT THE LINE(S) AND ENSURE CONTINUED SERVICE. DAMAGE CAUSED TO EXISTING UTILITIES BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST. ADDITIONALLY, THE CONTRACTOR SHALL CONFIRM THE CONNECTION POINTS OF NEW UTILITIES TO EXISTING UTILITIES PRIOR TO BEGINNING NEW CONSTRUCTION.
- 4. CONTRACTOR SHALL VERIFY EXISTING UTILITY ELEVATIONS AND INVERTS BEFORE STARTING WORK. THE CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY WITH DISCREPANCIES AND AWAIT WRITTEN RESPONSE FROM ENGINEER PRIOR TO PROCEEDING WITH INSTALLATION. EXISTING FRAMES, WITHIN DISTURBED LIMITS, SHALL BE ADJUSTED TO PROPOSED GRADES.
- 5. SHOULD PIPE, FITTINGS, AND OTHER MATERIALS BE NEEDED IN ADDITION TO THAT SHOWN ON THE DRAWINGS BECAUSE PIPELINE WAS NOT INSTALLED TO THE ALIGNMENT AND PROFILE SHOWN, THEN THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING THOSE NECESSARY MATERIALS AND PROVIDING THE EQUIPMENT AND LABOR TO INSTALL THEM TO MEET THE DESIGN INTENT OF THE WATER MAIN AT NO ADDITIONAL COST TO THE
- 6. THE CONTRACTOR SHALL NOTIFY THE OWNER AND THE ENGINEER 48 HOURS IN ADVANCE OF ALL REQUIRED TESTS AND OBSERVATIONS.
- 7. ALL WATER USED FOR CONSTRUCTION SHALL BE METERED THROUGH AN ACCEPTABLE BACK FLOW
- PREVENTION DEVICE AND FIRE HYDRANT METER.

 8. REFER TO EROSION CONTROL SHEETS FOR NOTES REGARDING EROSION AND SEDIMENTATION CONTROL.
- 9. ALL SIGNAGE AND STRIPING SHALL BE COMPLETED PER SCDOT STANDARDS.
- IO. ALL TRAFFIC CONTROL SIGNS AND PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE MANUAL ON "UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AND "SOUTH CAROLINA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" BOTH CURRENT EDITIONS.
- II. ALL MATERIALS AND ACCESSORIES SHALL, UNLESS OTHERWISE DIRECTED, BE UNLOADED AND STORED WHERE THEY WILL BE PROTECTED AND WILL NOT BE HAZARDOUS TO TRAFFIC. THEY SHALL, AT ALL TIMES, BE HANDLED WITH CARE TO AVOID DAMAGE. THE INTERIOR OF ALL PIPES, FITTINGS, AND OTHER ACCESSORIES SHALL BE KEPT FREE FROM DIRT AND FOREIGN MATTER AT ALL TIMES. CLEAN THE INTERIOR OF ALL PIPES BY BRUSHING, SWABBING OR WASHING OUT BEFORE LAYING.
- 12. CONTRACTOR SHALL FLUSH ALL INLETS AND PIPE AT THE COMPLETION OF CONSTRUCTION TO REMOVE SILT AND DEBRIS. THE CLEANING AND FLUSHING OF INLETS AND PIPE (EXISTING AND PROPOSED) SHALL BE CONSIDERED PART OF THE COST FOR PIPE ON THE PROJECT. ALL DRAINAGE SYSTEMS TO WHICH PIPES ARE TO BE CONNECTED SHALL BE FLUSHED.
- 13. BACK FILL NECESSARY FOR THE CONSTRUCTION OF THIS PROJECT SHALL BE PROVIDED BY THE CONTRACTOR FROM ONSITE EXCAVATION SHOWN ON PLANS, OR SOURCES DEVELOPED BY THE CONTRACTOR AND CONFORMING TO THE CONTRACT SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR EXCAVATION, HAULING AND PLACING THE FILL AS SHOWN ON THE PLANS. GEOTECHNICAL CONSULTANT SHALL DETERMINE IF FILL MATERIALS ARE SUITABLE FOR FILL AREAS.
- 14. ALL ITEMS WHICH MUST BE REMOVED BY THE CONTRACTOR DURING CONSTRUCTION, INCLUDING EARTHWORK MATERIAL, AND WHICH ARE NOT SHOWN TO BE PAID FOR OTHERWISE, ARE TO BE REMOVED WITHOUT ADDITIONAL PAYMENT.

- 15. CONTRACTOR SHALL PROTECT OR RESET ALL EXISTING MARKERS AND PROPERTY CORNERS PRIOR TO FINAL PAYMENT. ALL REQUIRED MARKERS SHALL BE INSTALLED BY REGISTERED SURVEYOR IN THE STATE OF
- 16. CONTRACTOR TO REMOVE ALL EROSION AND SEDIMENTATION CONTROL DEVICES PRIOR TO FINAL PAYMENT. COSTS FOR REMOVAL OF THESE DEVICES SHALL BE INCLUDED IN THE CORRESPONDING LINE ITEM COST ON THE BID FORM.
- I7. ALL DAMAGE CAUSED BY CONSTRUCTION IS TO BE REPLACED AT THE CONTRACTOR'S EXPENSE.
 I8. IT IS THE OBLIGATION OF THE CONTRACTOR TO MAKE THEIR OWN INTERPRETATION OF ALL SURFACE AND SUBSURFACE DATA AVAILABLE AS TO THE NATURE AND EXTENT OF THE MATERIALS TO BE EXCAVATED. WASTED, GRADED AND COMPACTED. THE INFORMATION SHOWN ON THESE PLANS IN NO WAY GUARANTEES THE AMOUNT OR NATURE OF THE MATERIALS TO BE ENCOUNTERED.
- 19. THE CONTRACTOR SHALL NOT BEGIN CONSTRUCTION UNTIL THE PROPER PERMITS HAVE BEEN OBTAINED.
- 20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PHASING OF CONSTRUCTION AND THE COORDINATION, SEQUENCING AND SUPERVISION OF CONSTRUCTION ACTIVITIES. ANY AND ALL COSTS ASSOCIATED WITH PROJECT PHASING WILL BE BORNE IN FULL BY THE CONTRACTOR. NO SEPARATE PAYMENT WILL BE MADE FOR ITEMS, MATERIALS OR PERSONNEL NOT SPECIFICALLY LISTED ON THE BID FORM.
- 21. CONTRACTOR SHALL COORDINATE WITH AN OWNER DESIGNATED GEOTECHNICAL CONSULTANT TO ENSURE FILL PLACED IS SUITABLE FOR ROADWAY CONSTRUCTION AND IS PLACED IN LIFTS AS DEEMED APPROPRIATE BY THE GEOTECHNICAL ENGINEER.
- 22. EACH EXISTING ROAD WILL BE CLEANED UP AND RESTORED DAILY. COORDINATE WITH OWNER IF ROADWAY
- 23. FRESHWATER WETLANDS EXIST IN THE PROJECT SITE. CONTRACTOR IS RESPONSIBLE FOR ADHERING TO ALL WETLAND AND WETLAND LINE BUFFERS THROUGHOUT CONSTRUCTION. CONTRACTOR SHALL OBTAIN A COPY OF WETLAND ARMY CORPS PERMIT #2001-IG-I22 AND COMPLY WITH ALL REQUIREMENTS LISTED WITHIN WHEN PERFORMING WORK.
- 24. CONTRACTOR SHALL GRADE AREAS TO DRAIN FOR POSITIVE FLOW PRIOR TO FINAL ACCEPTANCE.

BEAUFORT JASPER WATER AND SEWER AUTHORITY

PALMETTO ELECTRIC COOPERATIVE, INC.

ACCESS CANNOT BE MAINTAINED PRIOR TO PROCEEDING WITH BLOCKAGE.

UTILITIES: WATER AND SEWER

6 SNAKE ROAD

843-987-9250

843-208-5512

843-815-1676

OKATIE, SC 29909

ONE COOPERATIVE WAY

HARDEEVILLE, SC 29927

TELEPHONE AND CABLE

5 BUCK ISLAND ROAD

BLUFFTON, SC 29910

HARGRAY COMMUNICATIONS

- 25. THE TOWN OF BLUFFTON STORMWATER DIVISION SHALL BE NOTIFIED AT LEAST 24 HOURS PRIOR TO ANY DEWATERING ACTIVITIES.
- 26. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS AND LICENSES, AS REQUIRED BY BEAUFORT COUNTY AND/OR THE TOWN OF BLUFFTON ORDINANCES.
- 27. CONTRACTOR SHALL NOTIFY OWNER 45 DAYS IN ADVANCE, PRIOR TO BLOCKAGE OF EXISTING ROADWAY, TO ALLOW AMPLE TIME FOR ANY NOTIFICATIONS TO OTHERS.

GENERAL INFORMATION

PREPARED FOR:

BC BUCKWALTER, LLC

2473 PERIMETER PARKWAY, BUILDING 100

AUGUSTA, GA 30909

ZONING: BUCKWALTER PUD

SURVEYOR: THOMAS & HUTTON
50 PARK OF COMMERCE WAY
SAVANNAH, GA 31405


(912) 234-5300


COUNTY:

BEAUFORT COUNTY

TOWN OF BLUFFTON

THOMAS & HUTTON
50 PARK OF COMMERCE WAY
SAVANNAH, GA 31405
(912) 234-5300





THOMAS THOTTON Deark of Commerce Way


50 Park of Commerc Savannah, GA 31405 • 9


ROAD TO PARCEL 4

CONNECTOR ROAI GENERAL NOTES A


JOB NO: J-25125.000DATE: II/I8/202I
DRAWN: HAC
DESIGNED: HAC
REVIEWED: NBL
APPROVED: NBL
SCALE: AS SHOWN


G1.1


































THOMAS

THOMAS

LOTA

So Park of Commerce Way

shindh, GA 31405 • 912.234.53

OAD TO PARCEL 4

CONNECTOR ROAD TO F
GRADING & DRAINAGE

JOB NO: J-25125.0004
DATE: II/I8/202I
DRAWN: HAC
DESIGNED: HAC
REVIEWED: NBL
APPROVED: NBL
SCALE: NTS

C3.2

B. DESCRIPTION OF CONSTRUCTION ACTIVITY

WORK CONSISTS OF CLEARING, GRADING, EXCAVATION, DRAINAGE IMPROVEMENTS, GRASSING, AND ROADS.

C. RUNOFF DATA

C.1. SOIL CLASSIFICATIONS: SYMBOL / NAME C/D / BLADEN C.2. LAND USE(S): COMMERCIAL D. RECEIVING WATERS OKATIE RIVER

E. CLOSEST RECEIVING WATERS: **COLLETON RIVER** F. ULTIMATE RECEIVING WATERS: G. FLOOD

G.1. FEMA FLOOD ZONE(S):

II. CONTROL MEASURES

1. EROSION AND SEDIMENT CONTROLS

G.2. FEMA FLOOD INSURANCE MAP(S):

PRIOR TO START OF CONSTRUCTION, ALL EXTERIOR SILT FENCE WILL BE INSTALLED AS SHOWN ON THE PLANS.

ZONE C

4500250085D

1.1. CLEARING

1.1.1. AS CLEARING IS COMPLETED, ADDITIONAL SILT FENCE WILL BE INSTALLED WHERE NECESSARY, SUCH AS POINTS WHERE FLOWS BECOME CHANNELIZED, AND OTHER POINTS WHERE EXCESSIVE RUNOFF VELOCITIES MAY OCCUR.

1.1.2. INSTALL CONSTRUCTION ENTRANCES / EXITS BEFORE BEGINNING CLEARING 1.1.3. CONSTRUCTION DELAYS IN ANY ONE AREA GREATER THAN 14 DAYS PRIOR TO START OF ROUGH GRADING WILL MANDATE STABILIZATION PROCEDURES. ACCEPTABLE METHODS OF STABILIZATION INCLUDE MULCHING AND TEMPORARY SEEDING

DISTURBANCE. RETAIN AND PROTECT TREES TO ENHANCE FUTURE LANDSCAPING EFFORTS AND REDUCE RAINDROP IMPACT.

1.1.5. INSTALL ALL SEDIMENT CONTROL PRACTICES PRIOR TO ANY UP-SLOPE SOIL DISTURBING ACTIVITIES.

1.1.4. MAINTAIN EXISTING VEGETATION WHENEVER POSSIBLE AND MINIMIZE THE AREA OF

1.1.6. PHASE CONSTRUCTION ACTIVITIES TO MINIMIZE THE AREAS DISTURBED AT ONE TIME. THIS WILL ALSO ALLOW COMPLETED AREAS TO BE STABILIZED AND RE-VEGETATED BEFORE DISTURBING ADJACENT SITES. THE NEED FOR TEMPORARY EROSION CONTROL MEASURES MAY BE AVOIDED BY COMPLETING A PHASE AND INSTALLING PERMANENT EROSION

CONTROL MEASURES WHEN THE FINAL GRADE IS ATTAINED 1.1.7. MAINTAIN AND PROTECT ALL NATURAL WATERWAYS. RETAIN AT LEAST A 35-FOOT UNDISTURBED BUFFER OF NATURAL VEGETATION ALONG ALL WATERWAYS TO FILTER OUT SEDIMENT AND OTHER POLLUTANTS. MAINTAIN A 45-FOOT UNDISTURBED BUFFER AROUND SENSITIVE WATERS.

1.1.8. INSTALL SILT FENCE (OR BIO ROLLS/ROCK SOCK PRODUCTS) ON THE DOWN-SLOPE PERIMETER OF ALL DISTURBED AREAS PRIOR TO ANY SOIL DISTURBING ACTIVITIES (INCLUDING CLEARING AND GRUBBING). SILT FENCE CAN TREAT A MAXIMUM OF 100 SQUARE FEET PER LINEAL FOOT OF FENCE. INSTALL SILT FENCE IN SHORTER REACHES ON THE CONTOUR WITH EACH END TURNED UP-SLOPE . SWALES AND SHORELAND AREAS SHOULD ALSO BE PROTECTED WITH SILT FENCE, BIO ROLLS, OR ROCK SOCKS.

1.1.9. IN AREAS OF CONCENTRATED FLOW INSTALL STRAW BALE CHECKS, ROCK CHECK DAMS, TRIANGULAR DIKES, BIO ROLL BLANKETS, OR ROCK SOCKS TO SLOW RUNOFF AND TRAP

1.1.10. USE TEMPORARY SLOPE DRAINS OR ROCK CHUTES TO MOVE WATER DOWN STEEP SLOPES.

1.1.11. CONSTRUCT SEDIMENT BASINS FOR DRAINAGE AREAS GREATER THAN 10 ACRES

1.2. ROUGH GRADING

1.2.1. ALL EXISTING CONTROLS WILL BE MAINTAINED DURING ROUGH GRADING, DELAYS OF GREATER THAN 14 DAYS PRIOR TO START OF NEXT ACTIVITY WILL MANDATE STABILIZATION PROCEDURES. ACCEPTABLE METHODS OF STABILIZATION INCLUDE MULCHING AND

1.2.2. ALL AREAS NOT SUBJECT TO FURTHER CONSTRUCTION (DRAINAGE, SANITARY SEWER, ROADS, WATER DISTRIBUTION SYSTEMS, OR STORM WATER FACILITIES) SHALL BE GRASSED WITH A PERMANENT COVER.

1.2.3. COVER ANY STOCK PILED TOPSOIL WITH PLASTIC (OR OTHER IMPERVIOUS COVERING) OR USE A TEMPORARY SEED MIX. USE STOCKPILED TOPSOIL AS EARTHEN BERMS TO SERVE AS TEMPORARY SEDIMENT BASINS.

1.3. DRAINAGE

1.3.1. ALL EXISTING CONTROLS WILL BE MAINTAINED DURING DRAINAGE INSTALLATION. 13.2 CONSTRUCTION DRAINAGE WILL BE ROUTED THROUGH LAKES, WHICH WILL ACT AS

SEDIMENT BASINS OR OTHER ACCEPTABLE SEDIMENT BASINS/TRAPS. 1.3.3. STORM DRAIN INLET PROTECTION AS SHOWN ON DETAIL SHEET SHALL BE INSTALLED ON ALL CURB INLETS, STORM DRAIN MANHOLES, JUNCTION BOXES, AND GRATE INLETS.

SEQUENCE WILL MANDATE STABILIZATION PROCEDURES. ACCEPTABLE METHODS OF STABILIZATION INCLUDE MULCHING AND TEMPORARY SEEDING.

1.3.4. DELAYS OF GREATER THAN 14 DAYS PRIOR TO START OF THE NEXT CONSTRUCTION

1.3.5. ALL STORM LINES NOT IN STREETS OR OTHER PAVED AREAS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL.

1.4. WASTE DISTRIBUTION SYSTEM INSTALLATION

1.4.1. ALL EXISTING CONTROLS WILL BE MAINTAINED DURING INSTALLATION OF THE WATER

DISTRIBUTION SYSTEM 1.4.2. DELAYS OF GREATER THAN 14 DAYS PRIOR TO START OF NEXT ACTIVITY WILL MANDATE STABILIZATION PROCEDURES. ACCEPTABLE METHODS OF STABILIZATION INCLUDE

1.5. WASTEWATER COLLECTION SYSTEM INSTALLATION

MULCHING AND TEMPORARY SEEDING

MULCHING AND TEMPORARY SEEDING.

1.5.2. DELAYS OF GREATER THAN 14 DAYS PRIOR TO START OF NEXT ACTIVITY WILL MANDATE STABILIZATION PROCEDURES. ACCEPTABLE METHODS OF STABILIZATION INCLUDE

1.6. CONSTRUCTION OF ROADS

1.6.1. ALL EXISTING CONTROLS WILL BE MAINTAINED DURING ROAD CONSTRUCTION. 1.6.2. DELAYS OF GREATER THAN 14 DAYS PRIOR TO START OF NEXT ACTIVITY WILL MANDATE STABILIZATION PROCEDURES. ACCEPTABLE METHODS OF STABILIZATION INCLUDE MULCHING AND TEMPORARY SEEDING.

1.7. GRASSING

1.7.1. ALL EXISTING CONTROLS WILL BE MAINTAINED UNTIL GRASSING IS ESTABLISHED 1.7.2. ANY AREAS THAT ERODE OR WHERE GRASS DOES NOT ESTABLISH ITSELF SHALL BE RE-GRADED AND RE-GRASSED

STORM WATER MANAGEMENT

RUNOFF FROM THIS PROJECT WILL DISCHARGE INTO A STORM WATER MANAGEMENT SYSTEM. TREATMENT WILL OCCUR IN STORM WATER DETENTION PONDS.

OTHER CONTROLS

3.1. WASTE DISPOSAL

3.1.1. NO SOLID MATERIALS, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED TO ANY

HUMAN HEALTH, WELFARE OR SAFETY, OR TO ANIMALS OR PLANT LIFE.

RECEIVING WATERS 3.1.2. OFFSITE VEHICLE TRACKING OF SEDIMENTS AND THE GENERATION OF DUST SHALL BE

MINIMIZED. 3.1.3. THIS PLAN SHALL COMPLY WITH STATE AND/OR LOCAL WASTE DISPOSAL, SANITARY SEWER

OR SEPTIC SYSTEM REGULATIONS 3.1.4. DUST CONTROL ON DISTURBED AREAS - CONTROLLING SURFACE AND AIR MOVEMENT OF DUST ON CONSTRUCTION SITE AND HAUL ROUTES. THE PURPOSE OF THE MEASURE IS TO REDUCE THE PRESENCE OF AIRBORNE SUBSTANCES, WHICH MAY BE HARMFUL OR INJURIOUS TO

III. MAINTENANCE

MAINTENANCE PROGRAM

1.1. THE SITE SUPERINTENDENT, OR HIS/HER REPRESENTATIVE, SHALL MAKE VISUAL INSPECTIONS OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREAS (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER HEAVY RAINFALL EVENT TO INSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY.

1.2. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. ALL DRAINAGE SWALES, POCKETS, DEPRESSION, LOW LINES, AND OUTLET DITCHES SHALL DRAIN EFFECTIVELY AT ALL TIMES. SETTLEMENT OR WASHING THAT MAY OCCUR SHALL BE REPAIRED BY THE CONTRACTOR. SEDIMENT WILL BE REMOVED FROM BEHIND THE SEDIMENT FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE. THE SEDIMENT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN AN EFFECTIVE BARRIER. MAINTAIN THE CONSTRUCTION EXIT IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE SITE. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED. WASHED. OR TACKED ONTO PUBLIC ROADWAYS. RESEED AND MULCH AREA WHERE SEEDING EMERGENCE IS POOR, OR WHERE EROSION OCCURS. PROTECT FROM TRAFFIC AS MUCH AS POSSIBLE. INSPECT ALL MULCHES PERIODICALLY, AND AFTER RAINSTORMS TO CHECK FOR EROSION, DISLOCATION OR FAILURE. IF WASHOUT OCCURS, REPAIR THE SLOPE GRADE, RESEED AND REINSTALL MULCH. FOLLOW THE CONSTRUCTION SEQUENCE THROUGHOUT THE PROJECT DEVELOPMENT. WHEN CHANGES IN CONSTRUCTION ACTIVITIES ARE NEEDED, AMEND THE SEQUENCE SCHEDULE IN ADVANCE TO MAINTAIN MANAGEMENT CONTROL IF MAJOR CHANGES ARE NECESSARY SEND A COPY OF THE MODIFIED SCHEDULE TO THE ENGINEER, SEDIMENT AND EROSION CONTROL MEASURES WILL REMAIN IN PLACE AND BE MAINTAINED UNTIL THE DISTURBED AREAS ARE

SILT FENCE

SILT FENCES WILL BE MONITORED DURING CONSTRUCTION. ANY SILT FENCE WHICH IS NOT FUNCTIONING PROPERLY WILL BE PROMPTLY REPAIRED. CLEAN OUT THE SILT FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE OR REPLACE WITH FUNCTIONAL SILT FENCE WITHIN 24 HOURS. USE OF HOSES AND WATER TO FLUSH THE SEDIMENT INTO THE STORM INLETS IS UNACCEPTABLE.

3. SEDIMENTATION BASINS

SEDIMENTATION BASINS WHICH ARE AT 50% USED CAPACITY OR APPROACHING SUCH CAPACITY SHALL BE RE-EXCAVATED TO ORIGINAL DIMENSIONS AND THE SILT PROPERLY DISPOSED OF.

4. SEDIMENT LOGS/ROLLS SEDIMENT LOGS/ROLLS OR OTHER CONTROL MEASURES WHICH BEGIN TO DISINTEGRATE OR

FUNCTION INEFFECTIVELY SHALL BE PROMPTLY REPLACED.

5. VEGETATION COVER

ANY VEGETATION COVER SERVING TO STABILIZE DISTURBED SOILS WHICH IS ITSELF DISTURBED SHALL IMMEDIATELY BE REPLACED.

6. CONSTRUCTION ENTRANCE

MAINTAIN ROCK CONSTRUCTION ENTRANCE AND CLEAN ADJACENT ROADS OF ANY MUD TRACKED ONTO THEM.

1. QUALIFIED PERSONNEL WILL INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE, AREAS VII. EROSION, SEDIMENTATION & POLLUTION CONTROL NOTES FINALLY STABILIZED, STRUCTURAL CONTROL MEASURES, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE AT LEAST ONCE EVERY SEVEN CALENDAR DAYS. WHERE SITES HAVE BEEN FINALLY STABILIZED SUCH INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH DURING THE WARRANTY PERIOD.

2. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE. THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT TRACKING.

3. A WRITTEN REPORT SUMMARIZING THE SCOPE OF THE INSPECTION, NAME(S) AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION. THE DATE(S) OF THE INSPECTION. WEATHER INFORMATION FOR THE PERIOD SINCE THE LAST INSPECTION (OR SINCE COMMENCEMENT OF CONSTRUCTION ACTIVITY) INCLUDING A BEST ESTIMATE OF THE BEGINNING OF FACH STORM EVENT, DURATION OF EACH STORM EVENT, APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM EVENT (IN INCHES) AND WHETHER ANY DISCHARGES OCCURRED, LOCATION(S) OF DISCHARGES OF SEDIMENT OR OTHER POLLUTANTS FROM THE SITE, LOCATION(S) OF BMP'S THAT NEED MAINTENANCE, LOCATION(S) OF BMP'S THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION, LOCATION(S) WHERE ADDITIONAL BMP'S ARE NEEDED THAT DID NOT EXIST AT THE TIME OF INSPECTION AND ANY CORRECTIVE ACTION REQUIRED INCLUDING ANY CHANGES TO SWPPP NECESSARY AND IMPLEMENTATION DATES.

4. THE REPORT SHALL BE MAINTAINED AT LEAST THREE YEARS FROM THE DATE THE SITE IS FINALLY STABILIZED. THE REPORT MUST BE SIGNED AND SHALL CONTAIN A CERTIFICATION THAT THE FACILITY IS IN COMPLIANCE WITH THE STORM WATER POLLUTION PREVENTION PLAN AND THE NPDES PERMIT REFERENCED ABOVE. THE CONTRACTOR SHALL MAINTAIN THIS REPORT. THE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND OWNER.

1.5.1. ALL EXISTING CONTROLS WILL BE MAINTAINED DURING INSTALLATION OF THE WASTEWATER V. LONG TERM MAINTENANCE OF DRAINAGE AND STORM WATER MANAGEMENT SYSTEM

THE ROADS AND DRAINAGE SYSTEM WILL BE OWNED AND MAINTAINED BY BC BUCKWALTER LLC,

VI. SC DHEC STANDARD NOTES

1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO GRASSING / HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.

2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED

2.1. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE. 2.2. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.

3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF SITE INSPECTIONS IDENTIFY BMP'S THAT ARE DAMAGED OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE BEFORE THE NEXT STORM EVENT WHENEVER PRACTICAL

4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL

11. THE CONTRACTOR SHALL FLUSH ALL INLETS AND PIPE AT THE COMPLETION OF CONSTRUCTION TO

STORMWATER POLLUTION PREVENTION PLAN

FROSION DURING UTILITY CONSTRUCTION ALL DISTURBED AREAS SHALL BE CLEANED GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL. COVER. AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED INTO ANY WATERS OF THE STATE.

5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL FROSION AND/OR OFFSITE SEDIMENTATION, ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND

THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO THE PAVED ROADWAY FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT AS MAY BE REQUIRED.

RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION, INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 AND SCR100000.

TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.

9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN NOT BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND

10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

11. A COPY OF THE SWPPP, INSPECTION RECORDS AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.

INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.

13. MINIMIZE SOIL COMPACTION IN AREAS NOT UNDER PAVEMENTS AND /OR STRUCTURES AND. UNLESS INFEASIBLE, PRESERVE TOPSOIL

14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUAL OR BETTER TREATMENT PRIOR TO DISCHARGE.

15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG. ETC.).

16. THE FOLLOWING DISCHARGES ARE PROHIBITED:

AS SOON AS REASONABLY POSSIBLE.

16.1. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL

16.2. WASTEWATER FROM WASHOUT AND CLEANOUT OF OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;

16.3. FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND 16.4. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.

17 AFTER CONSTRUCTION ACTIVITIES BEGIN INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF

REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF PERMIT SCR100000 AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED

THESE PERFORMANCE STANDARDS APPLY TO ALL SITES.

AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS

19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE. THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

THE IMPLEMENTATION OF THESE EROSION SEDIMENT CONTROL (ESC) PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.

2. THE ESC FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO INSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS

THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS, DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.

THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.

THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A MAJOR STORM EVENT.

6. AT NO TIME SHALL MORE THAN ONE FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING AND PRIOR TO FINAL INSPECTION. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE DOWNSTREAM SYSTEM.

STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

8. BEFORE COMMENCING ANY LAND DISTURBING ACTIVITY, THE EXISTING STORM WATER INLET(S) THAT RECEIVING RUNOFF FROM THE PROPOSED WORK AREA SHALL BE PROTECTED. THE TEMPORARY INLET PROTECTION MUST REMAIN IN PLACE UNTIL THE CONSTRUCTION ACTIVITY IS COMPLETED, THE STREET HAS BEEN SWEPT AND ANY EXPOSED SOILS ARE STABILIZED. THE CONTRACTOR IS ALSO RESPONSIBLE FOR REMOVING ANY TEMPORARY INLET PROTECTION INSTALLED: AFTER ALL DISTURBED AREAS ARE STABILIZED. TEMPORARY PROTECTION OF THE INLETS MAY BE ACCOMPLISHED BY ONE OR MORE OF THE FOLLOWING:

8.1. USE OF GRAVEL BAGS TO FILTER THE SEDIMENT FROM ANY RUNOFF. TO MAKE A GRAVEL BAG, USE A BAG MADE OF GEOTEXTILE FABRIC (NOT BURLAP) AND FILL WITH EITHER 3/4 INCH ROCK OR 1/4 INCH PEA GRAVEL

8.2. USE OF SEDIMENT LOGS TO FILTER THE SEDIMENT FROM ANY RUNOFF (AVAILABLE THROUGH LOCAL EROSION CONTROL SUPPLIERS). 8.3. USE OF ABOVE OR UNDER-GRATE FILTER BAGS OR DEVICES TO FILTER THE SEDIMENT FROM ANY RUNOFF (AVAILABLE THROUGH EROSION CONTROL SUPPLIERS).

WATER MAY NOT BE DISCHARGED IN A MANNER THAT CAUSES EROSION, SEDIMENTATION, OR FLOODING ON THE SITE. ON DOWNSTREAM PROPERTIES. IN THE RECEIVING CHANNELS, OR IN ANY STORM WATER INLET. WHEN SITE DEWATERING, WATER PUMPED FROM THE SITE, INCLUDING

9.1. TEMPORARY SEDIMENTATION BASINS 9.2. SEDIMENT FILTERING BAGS

TRENCHES, SHALL BE TREATED BY ONE OF THE FOLLOWING:

10. THE CONTRACTOR SHALL VERIFY THE SIZE AND LOCATION OF ALL EXISTING UTILITIES. EXISTING UTILITIES ARE ALL UTILITIES THAT EXIST ON THE PROJECT IN AN ORIGINAL. RELOCATED OR NEWLY INSTALLED POSITION. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGED UNDERGROUND OR OVERHEAD FACILITIES, EVEN IF THE UTILITY IS NOT SHOWN ON THE SITE DEVELOPMENT PLANS. THE CONTRACTOR SHALL CONTACT THE LOCAL UTILITIES PROTECTION CENTER TO COORDINATE THE MARKING OF EXISTING UTILITY LINES A MINIMUM OF 96 HOURS PRIOR TO COMMENCEMENT OF ANY WORK.

3.10. FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS

3.7. PAVEMENT WASH WATERS WHERE SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS

HAVE NOT OCCURRED (UNLESS ALL SPILLED MATERIAL HAS BEEN REMOVED) AND WHERE

THE FOLLOWING NON-STORMWATER DISCHARGES MUST BE PROTECTED FROM CAUSING

MATERIALS SUCH AS SOLVENTS 3.11. UNCONTAMINATED EXCAVATION DEWATERING 3.12. LANDSCAPE IRRIGATION

CONSTRUCTION WASTES: DEMOLITION RUBBLE, PACKAGING MATERIALS, SCRAP BUILDING

3.13. DECHLORINATED SWIMMING POOL DISCHARGES.

3.9. UNCONTAMINATED GROUND WATER OR SPRING WATER

4.1. SELECT A DESIGNATED WASTE COLLECTION AREA 4.2. PROVIDE LIDS FOR WASTE CONTAINERS

4.3. WHEN POSSIBLE LOCATE CONTAINERS IN COVERED AREA 4.4. MAINTAIN CONSISTENT REMOVAL SCHEDULE FOR WASTE

PESTICIDES: REDUCE THE AMOUNT OF PESTICIDES AVAILABLE FOR CONTACT WITH STORM WATER.

5.1. STORE IN A DRY COVERED AREA

5.2. INSTALL CURBS OR DIKES AROUND STORAGE AREA TO PROTECT AGAINST SPILLS 5.3. STRICTLY FOLLOW RECOMMENDED APPLICATION RATES

6. FERTILIZERS AND DETERGENTS: REDUCE THE AMOUNT OF FERTILIZERS AND DETERGENTS AVAILABLE FOR CONTACT WITH STORM WATER.

6.1. LIMIT APPLICATION OF FERTILIZERS TO THE MINIMUM NEEDED 6.2. APPLY MORE FREQUENTLY BUT AT LOWER APPLICATION RATES

REMOVE SILT AND DEBRIS. THE CLEANING AND FLUSHING OF INLETS AND PIPE (EXISTING AND PROPOSED) SHALL BE CONSIDERED PART OF THE COST FOR THE PROJECT.

12. EGRESS FROM THE SITE SHALL BE CONTROLLED SUCH THAT VEHICLES LEAVING THE SITE MUST

14 FROSION CONTROL MEASURES ARE THE MINIMUM REQUIRED. THE CONTRACTOR SHALL PROVIDE

CONSTRUCTION IN ORDER TO PREVENT EROSION AND CONTROL SEDIMENT. EROSION AND

15. THE DATA, TOGETHER WITH ALL OTHER INFORMATION SHOWN ON THESE PLANS, OR IN ANY WAY

UPON FIELD INVESTIGATIONS AND IS BELIEVED TO BE INDICATIVE OF ACTUAL CONDITIONS.

16 CONTRACTOR SHALL MAINTAIN SITE ON A DAILY BASIS TO PROVIDE FOR POSITIVE DRAINAGE

17. SITE DRAINAGE SHALL BE ESTABLISHED TO PREVENT ANY PONDED WATER CONDITIONS WITHIN

18. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF

19.1. AGRICULTURAL LIME SHALL BE APPLIED AT THE RATE SHOWN IN THE SEEDING SECTION

SPECIFICATIONS OF THE SOUTH CAROLINA DEPARTMENT OF AGRICULTURE.

ADDITIONAL CONTROL MEASURES AS DICTATED BY ACTUAL FIELD CONDITIONS AT THE TIME OF

SEDIMENT CONTROL MEASURES WILL REMAIN IN PLACE AND BE MAINTAINED UNTIL THE ENTIRE

PROJECT IS TERMINATED OR SUSPENDED FOR AND INDEFINITE LENGTH OF TIME, ALL DISTURBED

INDICATED THEREBY, WHETHER BY DRAWINGS OR NOTES, OR IN ANY OTHER MANNER, IS BASED

HOWEVER, THE SAME IS SHOWN AS INFORMATION ONLY, IS NOT GUARANTEED AND DOES NOT BIND

CONTRACTOR, AT HIS COST, SHALL GRADE SITE AND PROVIDE NECESSARY TEMPORARY DRAINAGE

EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH,

UNLESS SOIL TESTS INDICATE OTHERWISE. GRADED AREAS REQUIRE LIME APPLICATION. IF

ADDITIONAL LIME IS NOT REQUIRED. AGRICULTURAL LIME APPLICATION SHALL BE WITHIN THE

STRAW SHALL BE APPLIED AT THE RATE OF TWO TONS PER ACRE. DRY HAY SHALL BE APPLIED

LIME IS APPLIED WITHIN SIX MONTHS OF PLANTING PERMANENT PERENNIAL VEGETATION.

MULCHING IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCH APPLIED TO

SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. SELECT THE MULCHING MATERIAL FROM THE

20.1. DRY STRAW OR DRY HAY OF GOOD QUALITY AND FREE OF WEED SEEDS CAN BE USED. DRY

20.2. WOOD CELLULOSE MULCH OR WOOD PULP FIBER SHALL BE USED WITH HYDRAULIC SEEDING.

20.3. ONE THOUSAND POUNDS OF WOOD CELLULOSE OR WOOD PULP FIBER, WHICH INCLUDES A

20.5. PINE STRAW OR PINE BARK SHALL BE APPLIED AT A THICKNESS OF 3 INCHES FOR BEDDING

20.6. WHEN USING TEMPORARY EROSION CONTROL BLANKETS OR BLACK SOD, MULCH IS NOT

20.7. ON SLOPES GREATER THAN 10 FEET IN LENGTH AND 4:1 OR STEEPER, USE THE FOLLOWING

• 3:1 SLOPES OR STEEPER: - WOOD OR STRAW BLANKET WITH NET ON BOTH SIDES

1. PETROLEUM PRODUCTS: INCLUDING OIL, GASOLINE, LUBRICANTS AND ASPHALTIC SUBSTANCES.

1.1. HAVE EQUIPMENT TO CONTAIN AND CLEAN UP PETROLEUM SPILLS IN FUEL STORAGE AREAS

EROSION CONTROL BLANKETS THAT HAVE BEEN PROPERLY ANCHORED TO THE SLOPE

• 4:1 SLOPES OR FLATTER: - WOOD OR STRAW MULCH BLANKET WITH NET ON ONE SIDE

• 2:1 SLOPES OR STEEPER: - STRAW/COCONUT BLANKET OR HIGH VELOCITY WOOD BLANKET

TACKIFIER, SHALL BE USED WITH HYDRAULIC SEEDING ON SLOPES 3/4:1 OR STEEPER.

20.4. SERICEA LESPEDEZA HAY CONTAINING MATURE SEED SHALL BE APPLIED AT A RATE OF 3 TONS

PURPOSES. OTHER SUITABLE MATERIALS IN SUFFICIENT QUANTITY MAY BE USED WHERE

ORNAMENTALS OR OTHER GROUND COVERS ARE PLANTED. THIS IS NOT APPROPRIATE FOR

APPLIED (AT THE RATE INDICATED ABOVE) AFTER HYDRAULIC SEEDING.

ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS:

OR ON MAINTENANCE AND FUELING VEHICLES

2. SPILLS: PREVENTION AND RESPONSE.

2.3.3. STOP THE SOURCE

2.3.4. CONTAIN THE SPILL

POLLUTION OR EROSION:

3.2. FIRE HYDRANT FLUSHINGS

NON-STORM WATER DISCHARGES

1.2. STORE IN COVERED AREAS PROTECTED WITH DIKES

2.1. STORE AND HANDLE MATERIALS TO PREVENT SPILLS

2.3. REDUCE STORM WATER CONTACT IF SPILL OCCURS

3.1. DISCHARGES FROM FIRE-FIGHTING ACTIVITIES

WATER USED TO CONTROL DUST

DETERGENTS ARE NOT USED

2.3.1. CLEANUP PROCEDURES SHOULD BE CLEARLY POSTED.

2.3.2. CLEANUP MATERIALS SHOULD BE READILY AVAILABLE

2.2. TIGHTLY SEALED CONTAINERS, NEAT AND SECURE STACKING, ETC.

3.3. WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED

3.5. POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHINGS

3.8. UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE

3.6. ROUTINE EXTERNAL BUILDING WASH DOWN THAT DOES NOT USE DETERGENTS

13. SCHEDULE CONSTRUCTION ACTIVITIES TO MINIMIZE THE EXPOSED AREA AND DURATION OF EXPOSURE. IN SCHEDULING, TAKE INTO ACCOUNT THE SEASON AND THE WEATHER FORECAST.

TRAVERSE CONSTRUCTION EXITS TO REMOVE MUD FROM TIRES.

AREAS SHALL BE PLANTED WITH PERMANENT VEGETATION.

SWALES TO INSURE STORM WATER DOES NOT POND ON SITE.

THE CONSTRUCTION AREA AND TO FACILITATE STORM WATER DISCHARGE.

THOMAS & HUTTON, OR THE OWNER IN ANY WAY.

LAND DISTURBING ACTIVITIES.

FOLLOWING AND APPLY AS INDICATED:

AT THE RATE OF 2 1/2 TONS PER ACRE.

19. LIME RATES AND ANALYSIS:

REQUIRED

VIII. HOUSEKEEPING

20. MULCHING:

6.3. LIMIT USE OF DETERGENTS ON-SITE 6.4. DO NOT DISCHARGE WASH WATER INTO STORM WATER SYSTEM

6.5. MAINTAIN STRUCTURAL AND VEGETATIVE BMP'S

6.6. APPLY ACCORDING TO SOIL TEST RECOMMENDATIONS PRIOR TO SEEDING.

IX. GRASSING NOTES

ALL SOD SHALL BE NURSERY GROWN AS CLASSIFIED IN THE ASPS GSS. MACHINE CUT SOD AT A UNIFORM THICKENS OF 3/4" WITHIN A TOLERANCE OF 1/4", EXCLUDING TOP GROWTH AND THATCH EACH INDIVIDUAL SOD PIECE SHALL BE STRONG ENOUGH TO SUPPORT ITS OWN WEIGHT WHEN LIFTED BY THE ENDS. BROKEN PODS. IRREGULARLY SHAPED PIECES. AND TORN OR UNEVEN ENDS WILL BE REJECTED. WOOD PEGS AND / OR WIRE STAPLES SHALL REPLACE SOD WITH AN EQUAL SOD COMPOSITION AS THAT WHICH IS EXISTING. IF NO SOD TYPE EXIST. THEN THE FOLLOWING SC COMPOSITION SHALL BE USED.

SODDING SCHEDULE:

LAY SOD FROM MAY 1 TO SEPTEMBER 15 FOR SPRING PLANTING AND FROM SEPTEMBER 15 TO NOVEMBER 1 FOR FALL PLANTING.

ALL SEED SHALL CONFORM TO ALL STATE LAWS AND TO ALL REQUIREMENTS AND REGULATIONS OF THE SOUTH CAROLINA DEPARTMENT OF AGRICULTURE. THE SEVERAL VARIETIES OF SEED SHALL BE INDIVIDUALLY PACKAGED OR BAGGED, AND TAGGED TO SHOW NAME OF SEED, NET WEIGHT, ORIGIN, GERMINATION, LOT NUMBER, AND OTHER INFORMATION REQUIRED BY THE DEPARTMENT OF AGRICULTURE.

3.1. PENNISETUM GLAUCIUM (BROWNTOP MILLET): TESTING 98 PERCENT PURITY AND 85 PERCENT

3.3. DOMESTIC ITALIAN RYE: TESTING 98 PERCENT PURITY AND 90 PERCENT GERMINATION.

GERMINATION. 3.2. BERMUDA COMMON: TESTING 98 PERCENT PURITY AND 85 PERCENT GERMINATION.

4. MISCELLANEOUS:

4.1. PERMANENT SEEDING SHALL COVER ALL DISTURBED AREA NOT TO BE COVERED BY LANDSCAPE PLANTING BEDS, STRUCTURE, OR PAVEMENT.

4.2. SEED ALL DISTURBED AREAS WITHIN SEVEN DAYS OF FINAL GRADING AND TEMPORARY SEED/MULCH ALL AREAS THAT WILL BE LEFT INACTIVE FOR MORE THAN FOURTEEN (14) DAYS

4.3. ALL PERMANENT GRASS PLANTINGS SHALL BE MULCHED 4.4. CENTIPEDE SOD CAN BE USED AS PERMANENT COVER ANYTIME EXCEPT JUNE THRU OCTOBER

4.5. IF GRASSING OCCURS DURING A MONTH REQUIRING TEMPORARY COVER, THE CONTRACTOR SHALL APPLY PERMANENT COVER (IN ADDITION TO THE TEMPORARY COVER) AT THE APPROPRIAT TIME AT NO NO ADDITIONAL COST. THE CONTRACTOR MUST ACHIEVE A STRAND OF PERMANENT GRASS WITH AT LEAST 95% COVER. BARE SPOTS CAN NOT BE MORE THAN 1 INCH SQUARE IN ANY

IT SHALL BE APPLIED AT A RATE OF 500 POUNDS PER ACRE. DRY STRAW OR DRY HAY SHALL BE X. PERMANENT STABILIZATION

NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC. AND CONCENTRATED RUNOFF UNTIL THE VEGETATION IS WELL ESTABLISHED. NECESSARY, AREAS MUST BE RE-WORKED AND RE-STABILIZED IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY ,OR TOPSOIL EROSION IS EVIDENT. ONE OR MORE OF THE FOLLOWING MAY APPLY TO THE SITE.

AREA WITH MATURE, HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.

4.1. SEEDED AREAS

4.2. SODDED AREAS FOR SODDED AREAS, PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOD

FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS A 90% COVER OF THE DISTURBED

4.3. PERMANENT MULCH

FOR MULCHED AREAS, PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL.

FOR AREAS STABILIZED WITH RIPRAP, PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIPRAP HAVE AN APPROPRIATE BACKING OF AN APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIPRAP.

4.5. DITCHES, CHANNELS, AND SWALES

ROOTS INTO THE APPROVED MULCH MATERIAL.

FOR OPEN CHANNELS, PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH MATURE VEGETATION AT LEAST THREE INCHES IN HEIGHT, WITH WELL-GRADED RIPRAP LINING OR WITH ANOTHER NON-EROSIVE LINING CAPABLE OF WITHSTANDING THE ANTICIPATED FLOW VELOCITIES AND FLOW DEPTHS WITHOUT RELIANCE ON CHECK DAMS TO SLOW FLOW. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE LINING, UNDERCUTTING OF THE BANKS, OR DOWN CUTTING OF THE CHANNEL.

XI. FERTILIZER REQUIREMENTS

TEMPORARY SEEDING FERTILIZER

APPLY A MINIMUM OF 500 LBS PER ACRE OF A COMPLETE 10-10-10 FERTILIZER (11.5 POUNDS PER 1000 SQUARE FEET) OR EQUIVALENT DURING TEMPORARY SEEDING OF GRASSES UNLESS A SOIL TEST INDICATES A DIFFERENT REQUIREMENT. INCORPORATE FERTILIZER AND LIME (IF LISED) INTO THE TOP 4-6 INCHES OF THE SOIL BY DISKING OR OTHER MEANS WHERE CONDITIONS ALLOW. LIME IS NOT REQUIRED FOR TEMPORARY SEEDING UNLESS A SOIL TEST SHOWS THAT THE SOIL PH IS BELOW 5.0. IT IS DESIRABLE TO APPLY LIME DURING THE TEMPORARY SEEDING OPERATION TO BENEFIT THE LONG-TERM PERMANENT SEEDING. APPLY A MINIMUM OF 1.5 TONS OF LIME / ACRE (70LBS. / 1000 SQ. FT.).

2. PERMANENT SEEDING FERTILIZER

APPLY A MINIMUM OF 1000 LBS PER ACRE OF A COMPLETE 10-10-10 FERTILIZER (23 POUNDS PER 1000 SQUARE FEET) OR EQUIVALENT DURING PERMANENT SEEDING OF GRADES UNLESS A SOIL TEST INDICATES A DIFFERENT REQUIREMENT. INCORPORATE FERTILIZER AND LIME (IF USED) INTO THE TOP 4-6 INCHES OF THE SOIL BY DISKING OR OTHER MEANS WHERE CONDITIONS ALLOW. DO NOT MIX THE LIME AND THE FERTILIZER PRIOR TO THE FIELD APPLICATION. UNLESS A SPECIFIC SOIL TEST INDICATES OTHERWISE, APPLY 1 & 1/2 TONS OF GROUND COARSE TEXTURED

XII. SWPP PREPARER CERTIFICATION

AGRICULTURAL LIMESTONE PER ACRE (70 LBS. / 1000 SQ.FT.).

I HAVE PLACED MY SIGNATURE AND SEAL ON THE DESIGN DOCUMENTS SUBMITTED SIGNIFYING THAT I ACCEPT RESPONSIBILITY FOR THE DESIGN OF THE SYSTEM. FURTHER, I CERTIFY TO THE BEST OF MY KNOWLEDGE AND BELIEF THAT THE DESIGN IS CONSISTENT WITH THE REQUIREMENTS OF TITLE 48, CHAPTER 14 OF THE CODE OF LAWS OF SC, 1976 AS AMENDED, PURSUANT TO REGULATION 72-300 ET SEQ. (IF APPLICABLE), AND IN ACCORDANCE WITH THE TERMS AND CONDITIONS OF SCR100000.





 \propto ⋖ ட 0 ပ \triangleleft ட დ

Ш

11/18/2021 DRAWN: HAC DESIGNED: HAC REVIEWED: NBL APPROVED: NBL

CALE: N/A

STORMWATER POLLUTION PREVENTION PLAN

TEMPORARY SEEDING - COASTAL

SPECIES	LBS/AC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC
	SANDY, DROUGHTY SITES												
BROWNTOP MILLET	40					1		1					
RYE, GRAIN	56												
RYEGRASS	50												
			·	WELL DF	RAINED, C	LAYEY/LO	DAMEY SIT	ES				·	·
BROWNTOP MILLET	40												
JAPANESE MILLET	40												
RYE, GRAIN	56												
OATS	75												
RYEGRASS	50												

SPECIES	LBS/AC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
	•	1	!	'	SANDY, D	ROUGHT	Y SITES	· ·	,	•	'		<u>'</u>
BROWNTOP MILLET	10			_									
BAHIAGRASS	40												
BROWNTOP MILLET	10												
BAHIAGRASS	30												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
ATLANTIC COASTAL	15												
PANICGRASS	PLS												
BROWNTOP MILLET	10												
SWITCHGRASS	8												
(ALAMO)	PLS												
LITTLE BLUESTEM	4												
SERICEA LESPEDEZA	20												
BROWNTOP MILLET	10												
WEEPING LOVEGRASS	8			_									
				WELL	DRAINED,	CLAYEY/L	OAMEY SI	TES			I		
BROWNTOP MILLET	10												
BAHIAGRASS	40												
RYE, GRAIN	10												
BAHIAGRASS	40												
CLOVER, CRIMSON (ANNUAL)	5												
BROWNTOP MILLET	10												
BAHIAGRASS	30												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
BERMUDA, COMMON	10												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
BERMUDA, COMMON	12												
KOBE LESPEDEZA (ANNUAL)	10												
BROWNTOP MILLET	10												
BAHIAGRASS	20												
BERMUDA, COMMON	6												
SERICEA LESPEDEZA	40												
BROWNTOP MILLET	10												
SWITCHGRASS	8												
LITTLE BLUESTEM	PLS												
INDIANGRASS	3												

DESCRIPTION	NTROL LEGEND
<u>DESCRIPTION</u>	PLAN SYMBOL
SILT FENCE	
CLEARING LIMITS	—— cl ——— cl ——
DIVERSION DIKE	⇒DD⇒
DIVERSION BERM	⇒DB⇒
TEMPORARY DIVERSION	⇒TD⇒
PERMANENT DIVERSION	—→ PD—→
SUBSURFACE DRAIN	(<u>-</u> :ssd(<u>-</u> :
VEGETATED CHANNEL	الله ^ش علاله الماله شعر الماله الما
RIP RAP LINED CHANNEL	
ECB OR TRM LINED CHANNEL	
PAVED CHANNEL	PC 📺
TREE PROTECTION	
SURFACE ROUGHENING	or LG
TOP SOILING	
TEMPORARY SEEDING	TS
PERMANENT SEEDING	PS
MULCHING	M

EDOCION CONTDOL I ECEND

EROSION CONT	PLAN SYMBOL
EROSION CONTROL BLANKET OR TURF REINFORCEMENT MAT	
FLEXIBLE GROWTH MATRIX	FGM
BONDED FIBER MATRIX	BFM
SODDING	so
SLOPED SODDING	
STAKED SOD	
STAKED SOD AROUND INLET	OR OR
RIPRAP	
OUTLET PROTECTION - RIP RAP	
OUTLET PROTECTION - ECB OR TRM	
DUST CONTROL	DC
POLYACRYLAMIDE (PAM)	PAM
SEDIMENT BASIN	
SEDIMENT BASIN WITH SKIMMER	
SEDIMENT TRAP	
ROCK SEDIMENT DIKE	
SEDIMENT TUBE	

EROSION CONTROL LEGEND

DESCRIPTION	PLAN SYMBOL
ROCK CHECK DAM	OR OR
POROUS BAFFLES	
STABILIZED CONSTRUCTION ENTRANCE	
CONCRETE WASHOUT	
STORM DRAIN INLET PROTECTION - TYPE A FILTER FABRIC	A
STORM DRAIN INLET PROTECTION - TYPE A SEDIMENT TUBE	A
STORM DRAIN INLET PROTECTION - TYPE B HARDWARE FABRIC AND STONE	B
STORM DRAIN INLET PROTECTION - TYPE C BLOCK AND GRAVEL	:C:
STORM DRAIN INLET PROTECTION - TYPE D RIGID INLET FILTER	
STORM DRAIN INLET PROTECTION - TYPE E SURFACE COURSE CURB INLET FILTER	E
STORM DRAIN INLET PROTECTION - TYPE F INLET TUBE	F
STORM DRAIN INLET PROTECTION - TYPE G IMPERVIOUS AREA	G
STORM DRAIN INLET PROTECTION - CATCH BASIN INSERT	I
PIPE SLOPE DRAINS	
TEMPORARY STREAM CROSSING	
LEVEL SPREADER	

LIST OF ACRONYMS FOR SEDIMENT AND EROSION CONTROL AASHTO AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS

ACRYLAMIDE POLYMER BONDED FIBER MATRIX BEST MANAGEMENT PRACTICE(S) CFS CUBIC FEET PER SECOND CORRUGATED METAL PIPE

DEPARTMENT OF HEATH AND ENVIRONMENTAL CONTROL ECB EROSION CONTROL BLANKET

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY EROSION PREVENTION AND SEDIMENTATION CONTROL FDA UNITED STATES FOOD AND DRUG ADMINISTRATION

FLEXIBLE GROWTH MATRIX HDPE HIGH DENSITY POLYETHYLENE

MUNICIPAL SEPARATE STORM SEWER SYSTEM MATERIAL SAFETY DATA SHEETS

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM NPDES POLYACRYLAMIDE OR POLYMER REINFORCED CONCRETE PIPE

SOIL CONSERVATION SERVICE STORMWATER POLLUTION PREVENTION PROGRAM

TURF REINFORCEMENT MAT VEGETATED FILTER STRIP

	CONSTRUCTION SEQUENCE							
	CONSTRUCTION ACTIVITY	SCHEDULE CONSIDERATION						
INITIAL PHASE								
1 OBTAIN COPIES OF ALL PLAN APPROVALS AND OTHER APPLICABLE PERMITS.		CONTRACTOR TO HAVE ONSITE AT ALL TIMES DURING CONSTRUCTION.						
2	FLAG THE WORK LIMITS AND BARRICADE TREES AND MARK BUFFER AREAS FOR PROTECTION.	HAVE LOCAL REGULATORY AGENCY INSPECT TREE BARRICADES.						
3	HOLD PRE CONSTRUCTION CONFERENCE AT LEAST ONE WEEK PRIOR TO STARTING CONSTRUCTION.	REVIEW TREE PROTECTION (BARRICADE) WITH OWNER AND LOCAL REGULATORY AGENCY. TAKE PICTURES OF ALL PROTECTED TREES AND LOCATIONS WHERE SITE WORK TIES INTO EXISTING TO DOCUMENT PREDEVELOPMENT PROCEDURES.						
4	INSTALL CONSTRUCTION ACCESS AND LAY DOWN AREAS	STABILIZE BARE AREAS IMMEDIATELY AND INSTALL CONSTRUCTION EXITS / ENTRANCES.						
5	CONSTRUCT SEDIMENT FENCES	INSTALL SEDIMENT FENCES AFTER CONSTRUCTION SITE IS ACCESSED.						
6	CONSTRUCT OUTLET PROTECTION. INSTALL SKIMMER.	INSTALL PRINCIPAL BASINS AFTER SEDIMENT FENCES IS INSTALLED.						
7	ESTABLISH RUNOFF CONTROL - DIVERSIONS, PERIMETER DIKES, WATER BARS, AND OUTLET PROTECTION.	INSTALL PRINCIPAL SEDIMENT TRAPS AND BEFORE LAND GRADING. INSTALL ADDITIONAL RUNOFF-CONTROL MEASURES DURING GRADING.						
8	LAND CLEARING AND GRADING-SITE PREPARATION CUTTING, FILLING AND GRADING, SEDIMENTATION TRAPS, BARRIERS, DIVERSIONS, DRAINS, SURFACE ROUGHENING.	BEGIN MAJOR CLEARING AND GRADING AFTER PRINCIPAL SEDIMENT AND KEY RUNOFF-CONTROL MEASURES ARE INSTALLED. CLEAR BORROW AND DISPOSAL AREAS ONLY AS NEEDED. INSTALL ADDITIONAL CONTROL MEASURES AS GRADING PROGRESSES. MARK TREES AND BUFFER AREAS FOR PRESERVATION.						
CONSTRUCTION PHASE								
1	RUNOFF CONVEYANCE SYSTEM- INSTALL STORM DRAINS, STABILIZE BANKS, CHANNELS, INSTALL INLET AND OUTLET PROTECTION, SLOPE DRAINS.	WHERE NECESSARY, STABILIZE BANKS AS EARLY AS POSSIBLE. INSTALL PRINCIPAL RUNOFF CONVEYANCE SYSTEM WITH RUNOFF- CONTROL MEASURES. INSTALL REMAINDER OF SYSTEM AFTER GRADING.						
2	INSTALL WASTEWATER COLLECTION, WATER DISTRIBUTION, AND STORM DRAINAGE SYSTEMS	APPLY TEMPORARY OR PERMANENT STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS WHERE WORK IS DELAYED OR COMPLETE.						

3	SURFACE STABILIZATION-TEMPORARY AND PERMANENT SEEDING, MULCHING, SODDING, RIP RAP.	APPLY TEMPORARY OR PERMANENT STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS WHERE WORK IS DELAYED OR COMPLETE.						
	STABILIZATION PHASE							
4	BUILDING CONSTRUCTION- BUILDINGS UTILITIES, ROADS, ETC.	INSTALL NECESSARY EROSION AND SEDIMENTATION CONTROL PRACTICES AS WORK TAKES PLACE.						
5	LANDSCAPING AND FINAL STABILIZATION - TOPSOILING, TREES AND SHRUBS, PERMANENT	LAST CONSTRUCTION PHASESTABILIZE ALL OPEN AREAS, INCLUDING BORROW AND SPOIL AREAS. REMOVE AND						

SEEDING, MULCHING, SODDING, RIP RAP. REMOVE STABILIZE ALL TEMPORARY CONTROL MEASURES.

SKIMMER.





	MILLE	TO CHANA	Sun	A THE	2 1133 11111	uun Siri	MA	
	(Z	onsuma			00)	


PARCI NOTES \triangleleft BUCKW,


ಹ

DATE: II/I8/202I
DRAWN: HAC
DESIGNED: HAC REVIEWED: NBL APPROVED: NBL SCALE: N/A










BLANKET

SECTION A-A



STAIR-STEP GRADING

LAND GRADING TECHNIQUES

NOT TO SCALE

DUST CONTROL ON

DISTURBED AREAS

DEFINITION Controlling surface and air movement of dust on land-disturbing activities.



- · Prevent the movement of dust from exposed soil surfaces.
- · Prevent the movement of airborne substances that may be harmful to health.

INSTALLATION

- · Apply according to approved plan, if shown. · Mulch disturbed areas and tackify with resins such as asphalt, Curasol or Terratack according to manufacturer's recommenda-
- · Stabilize disturbed areas with temporary or permanent vegetation.
- Irrigate disturbed areas until surface is wet.
- · Cover surfaces with crushed stone or gravel.

- · Apply calcium chloride at a rate to keep surfaces moist.
- · Apply spray-on adhesives to mineral soils (not muck soils) as described in Table 1.


Table 1. Spray-On Adhesive Application

Requirements								
Adhesive	Water Dilution	Nozzle Type	Application (Gal./Acre)					
Anionic asphalt emulsion	7:1*	Coarse spray	1,200					
Latex emulsion	12.5:1 *	Fine spray	235					
Resin-in- water emulsion	4:1*	Fine spray	300					

*Use manufacturer's recommendations when available.

DUST CONTROL MEASURES

NOT TO SCALE



WHEN AND WHERE TO USE IT

STABILIZED CONSTRUCTION ENTRANCES SHOULD BE USED AT ALL POINTS WHERE TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE AND MOVING DIRECTLY ONTO A PUBLIC ROAD.

IMPORTANT CONSIDERATIONS:

IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFFSITE. WASHDOWN FACILITIES SHALL BE REQUIRED AS DIRECTED BY SCDHEC AS NEEDED. WASHDOWN AREAS IN GENERAL MUST BE ESTABLISHED WITH CRUSHED GRAVEL AND DRAIN INTO A SEDIMENT TRAP OR SEDIMENT BASIN.

CONSTRUCTION ENTRANCES SHOULD BE USED IN CONJUNCTION WITH THE STABILIZATION OF CONSTRUCTION ROADS TO REDUCE THE AMOUNT OF MUD PICKED UP BY VEHICLES.

REMOVE ALL VEGETATION AND ANY OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA.

DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM STONES TO A SEDIMENT TRAP OR BASIN.

INSTALL A NON-WOVEN GEOTEXTILE FABRIC PRIOR TO PLACING ANY STONE.

INSTALL A CULVERT PIPE ACROSS THE ENTRANCE WHEN NEEDED TO PROVIDE POSITIVE DRAINAGE.

THE ENTRANCE SHALL CONSIST OF 1-INCH TO 3-INCH D50 STONE PLACED AT A MINIMUM DEPTH OF 6-INCHES. MINIMUM DIMENSIONS OF THE ENTRANCE SHALL BE 24-FEET WIDE BY 100-FEET LONG, AND MAY BE MODIFIED AS NECESSARY TO ACCOMMODATE

THE EDGES OF THE ENTRANCE SHALL BE TAPERED OUT TOWARDS THE ROAD TO PREVENT TRACKING OF MUD AT THE EDGE OF THE ENTRANCE.

CHECK FOR MUD AND SEDIMENT BUILDUP AND PAD INTEGRITY. MAKE DAILY INSPECTIONS DURING PERIODS OF WET WEATHER. MAINTENANCE IS REQUIRED MORE FREQUENTLY IN WET WEATHER CONDITIONS. RESHAPE THE STONE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.

WASH OR REPLACE STONES AS NEEDED. THE STONE IN THE ENTRANCE SHOULD BE WASHED OR REPLACED WHENEVER THE ENTRANCE FAILS TO REDUCE MUD BEING CARRIED OFF-SITE BY VEHICLES.


FREQUENT WASHING WILL EXTEND THE USEFUL LIFE OF STONE.


IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. FLUSHING SHOULD ONLY BE USED WHEN THE WATER CAN BE DISCHARGED TO A SEDIMENT TRAP OR BASIN. REPAIR ANY BROKEN PAVEMENT IMMEDIATELY.




STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE







V-SHAPED TRENCH DETAIL

FLAT-BOTTOM TRENCH DETAIL

WHEN AND WHERE TO USE IT: SILT FENCE IS APPLICABLE IN AREAS:

WHERE THE MAXIMUM SHEET OR OVERLAND FLOW PATH LENGTH TO THE FENCE IS 100-FEET. WHERE THE MAXIMUM SLOPE STEEPNESS (NORMAL [PERPENDICULAR] TO FENCE LINE) IS 2H:1V. THAT DO NOT RECEIVE CONCENTRATED FLOWS GREATER THAN 0.5 CFS.

DO NOT PLACE SILT FENCE ACROSS CHANNELS OR USE IT AS A VELOCITY CONTROL BMP

STEEL POSTS

USE 48-INCH LONG STEEL POSTS THAT MEET THE FOLLOWING MINIMUM PHYSICAL REQUIREMENTS:

COMPOSED OF HIGH STRENGTH STEEL WITH MINIMUM YIELD STRENGTH OF 50,000 PSI. HAVE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND NOMINAL "T" LENGTH OF 1.48-INCHES. WEIGH 1.25 POUNDS PER FOOT (± 8%).

HAVE A SOIL STABILIZATION PLATE WITH A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES ATTACHED TO THE STEEL POSTS. PAINTED WITH A WATER BASED BAKED ENAMEL PAINT.

USE STEEL POSTS WITH A MINIMUM LENGTH OF 4-FEET, WEIGHING 1.25 POUNDS PER LINEAR FOOT (± 8%) WITH PROJECTIONS TO AID IN FASTENING THE FABRIC. EXCEPT WHEN HEAVY CLAY SOILS ARE PRESENT ON SITE, STEEL POSTS WILL HAVE A METAL SOIL STABILIZATION PLATE WELDED NEAR THE BOTTOM SUCH THAT WHEN THE POST IS DRIVEN TO THE PROPER DEPTH, THE PLATE WILL BE

BELOW THE GROUND LEVEL FOR ADDED STABILITY. THE SOIL PLATES SHOULD HAVE THE FOLLOWING CHARACTERISTICS:

BE COMPOSED OF MINIMUM 15 GAUGE STEEL. HAVE A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES.

CUT TO A MINIMUM WIDTH OF 36 INCHES.

COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS COMPOSED OF AT LEAST 85% BY WEIGHT OF POLYOLEFINS,


POLYESTERS, OR POLYAMIDES. FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS RETAIN DIMENSIONAL STABILITY RELATIVE TO EACH OTHER. FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL PROPERTIES AFTER INSTALLATION. FREE OF DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR FILTERING PROPERTIES.


USE ONLY FABRIC APPEARING ON SCDOT APPROVAL SHEET #34 MEETING THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE SCDOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

EXCAVATE A TRENCH APPROXIMATELY 6-INCHES WIDE AND 6-INCHES DEEP WHEN PLACING FABRIC BY HAND. PLACE 12-INCHES OF GEOTEXTILE FABRIC INTO THE 6-INCH DEEP TRENCH, EXTENDING THE REMAINING 6-INCHES TOWARDS THE UPSLOPE SIDE OF THE TRENCH. BACKFILL THE TRENCH WITH SOIL OR GRAVEL AND COMPACT. BURY 12-INCHES OF FABRIC INTO THE GROUND WHEN PNEUMATICALLY INSTALLING SILT FENCE WITH A SLICING METHOD. PURCHASE FABRIC IN CONTINUOUS ROLLS AND CUT TO THE LENGTH OF THE BARRIER TO AVOID JOINTS. WHEN JOINTS ARE NECESSARY, WRAPPED THE FABRIC TOGETHER AT A SUPPORT POST WITH BOTH ENDS FASTENED TO THE POST, WITH A 6-INCH MINIMUM OVERLAP. INSTALL POSTS TO A MINIMUM DEPTH OF 24-INCHES. INSTALL POSTS A MINIMUM OF 1- TO 2- INCHES ABOVE THE FABRIC, WITH NO MORE THAN 3-FEET OF THE POST ABOVE THE GROUND. SPACE POSTS TO MAXIMUM 6-FEET CENTERS. ATTACH FABRIC TO WOOD POSTS USING STAPLES MADE OF HEAVY-DUTY WIRE AT LEAST 1-1/2-INCH LONG, SPACED A MAXIMUM OF 6-INCHES APART. STAPLE A 2-INCH WIDE LATHE OVER THE FILTER FABRIC TO SECURELY FASTEN IT TO THE UPSLOPE SIDE OF WOODEN POSTS. ATTACH FABRIC TO THE STEEL POSTS USING HEAVY-DUTY PLASTIC TIES THAT ARE EVENLY SPACED AND PLACED IN A MANNER TO PREVENT SAGGING OR TEARING OF THE FABRIC. IN CALL CASES, TIES SHOULD BE AFFIXED IN NO LESS THAN 4 PLACES. INSTALL THE FABRIC A MINIMUM OF 24-INCHES ABOVE THE GROUND. WHEN NECESSARY, THE HEIGHT OF THE FENCE ABOVE GROUND MAY BE GREATER THAN 24-INCHES. IN TIDAL AREAS, EXTRA SILT FENCE HEIGHT MAY BE REQUIRED. THE POST HEIGHT WILL BE TWICE THE EXPOSED POST HEIGHT. POST SPACING WILL REMAIN THE SAME AND EXTRA HEIGHT FABRIC WILL BE 4-, 5-, OR 6-FEET TALL. LOCATE SILT FENCE CHECKS EVERY 100 FEET MAXIMUM AND AT LOW POINTS. INSTALL THE FENCE PERPENDICULAR TO THE DIRECTION OF FLOW AND PLACE THE FENCE THE PROPER DISTANCE FROM THE TOE OF STEEP SLOPES TO PROVIDE SEDIMENT STORAGE AND ACCESS FOR MAINTENANCE AND


CHECK FOR SEDIMENT BUILDUP AND FENCE INTEGRITY. CHECK WHERE RUNOFF HAS ERODED A CHANNEL BENEATH THE FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED BY FENCE OVERTOPPING. IF THE FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE SECTION OF FENCE IMMEDIATELY. REMOVE SEDIMENT ACCUMULATED ALONG THE FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE, ESPECIALLY IF HEAVY RAINS ARE EXPECTED. REMOVE TRAPPED SEDIMENT FROM THE SITE OR STABILIZE IT ON SITE. REMOVE SILT FENCE WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED OR

AFTER TEMPORARY BEST MANAGEMENT PRACTICES (BMPS) ARE NO LONGER NEEDED. PERMANENTLY STABILIZE DISTURBED AREAS RESULTING










 \simeq ⋖ ட

Ш **_** Ø \cong \circ S

BUCK

11/18/2021 DRAWN: HAC ESIGNED: HAC REVIEWED: NBL

APPROVED: NBL CALE: NTS



Book133/Page151

