

RESOLUTION NO. 2026-1962

WHEREAS, the City of Boaz, Alabama awarded Boaz Street Paving Project: Fiscal Year 2026, City of Boaz Project No. 2025-06-129, City of Boaz Bid No. 2025-12-132 to Rogers Group, Inc. as Resolution No. 2026-1939 on February 9, 2026 in the amount of \$1,122,000.00.

WHEREAS, the City has since requested additional work be included in the project, described in the attached, as Change Order 1.

THEREFORE, BE IT RESOLVED by the Mayor and Council of the City of Boaz that Change Order 1 be awarded to Rogers Group, Inc. in the amount of \$78,987.34 to be paid from the 2023 A Bond Account.

APPROVED AND ADOPTED THIS 11TH DAY OF MAY, 2026.

Tim Walker
Mayor

ATTEST:

Beth Stephens
City Clerk/Treasurer

CITY OF BOAZ

DATE:

May 11, 2026

Authority for additions, alterations and omissions on construction work under contract:

CONTRACT/PROJECT NO:

2025-06-129

Boaz Street Paving Project: Fiscal Year 2026

CHANGE ORDER NO.:

1

TOTAL CONTRACT AMOUNT:

\$1,122,000.00

THIS CHANGE ORDER AMOUNT:

\$78,987.34

REVISED CONTRACT AMOUNT:

\$1,200,987.34

CONTRACT TIME:

50 Working Days

THIS CHANGE ORDER:

5 Working Days

REVISED CONTRACT TIME:

55 Working Days

DESCRIPTION:

1. Additional milling, paving and gutter installation at fire station on E Mann Ave.
2. Repair of existing pipe cavity on McVile Rd.
3. Gutter repair on McVile Rd.
4. Addition of W Royal Ave, W Elrod Ave & northern section of Cherokee St to pavement resurfacing list.
5. Brown St patching of cuts made by Boaz Water & Sewer (BWS).*
6. Main St patching, striping, markings & sidewalk repair of cuts made by BWS.*
7. Darnell St pipe replacement.
8. Gutter retrofits on Darnell St & Williams St (1).

**To be billed to BWS*

COST:

1. Additional milling and paving at fire station on E Mann Ave.

Additional Milling & Paving at Fire Station					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
214A000	STRUCTURE EXCAVATION	Cu Yd	\$ 17.00	15.00	\$ 255.00
424A360	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D	Ton	\$ 101.00	17.69	\$ 1,787.14
623A001	CONCRETE GUTTER (VALLEY)	Lin Ft	\$ 46.00	150.00	\$ 6,900.00
SUBTOTAL					\$ 8,942.14

2. Repair of existing pipe cavity on McVile Rd.

Repair of Existing Pipe Cavity on McVile Rd					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
210A000	UNCLASSIFIED EXCAVATION	Cu Yd	\$ 40.00	17.00	\$ 680.00
305B077	CRUSHED AGGREGATE, SECTION 825, FOR MISCELLANEOUS USE	Ton	\$ 42.00	25.86	\$ 1,086.12
SUBTOTAL					\$ 1,766.12

3. Gutter repair on McVile Rd.

Gutter Repair on McVile Rd					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
206D002	REMOVING CURB AND GUTTER	Lin Ft	\$ 10.00	20.00	\$ 200.00
623C003	COMBINATION CURB & GUTTER, TYPE C (MODIFIED)	Lin Ft	\$ 32.00	20.00	\$ 640.00
SUBTOTAL					\$ 840.00

4. Addition of W Royal Ave, W Elrod Ave & northern section of Cherokee St to pavement resurfacing list.

Addition of W Elrod, W Royal Ave & Cherokee St					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
424A360	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D	Ton	\$ 101.00	256.51	\$ 25,907.51
703A002	TRAFFIC CONTROL MARKINGS, CLASS 2, TYPE A	Sq Ft	\$ 8.00	24.00	\$ 192.00
SUBTOTAL					\$ 26,099.51

5. Brown St patching of cuts made by Boaz Water & Sewer (BWS).

Brown St Patching					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
424A360	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D	Ton	\$ 101.00	2.41	\$ 243.80
SUBTOTAL					\$ 243.80*

*To be billed to BWS.

6. Main St patching, striping & sidewalk repair of cuts made by BWS.

Main St Patching*					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
424A360	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D	Ton	\$ 101.00	4.25	\$ 429.46
618A001	CONCRETE SIDEWALK, 6" THICK	Sq Yd	\$ 475.00	8.00	\$ 3,800.00
701A235	SOLID YELLOW, CLASS 2, TYPE A TRAFFIC STRIPE	Mile	\$ 5,000.00	0.004	\$ 20.00
701G249	SOLID WHITE, CLASS 2, TYPE A TRAFFIC STRIPE	Lin Ft	\$ 5.25	15.00	\$ 78.75
SUBTOTAL					\$ 4,328.21*

**To be billed to BWS.*

7. Darnell St pipe replacement.

Darnell St Pipe Replacement					
Item No.	Item Description	Unit	Bid Price	Quantity	Amount
206D000	REMOVING PIPE	Lin Ft	\$ 27.00	116.00	\$ 3,132.00
305B077	CRUSHED AGGREGATE, SECTION 825, FOR MISCELLANEOUS USE	Ton	\$ 42.00	76.24	\$ 3,202.08
424A360	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D	Ton	\$ 101.00	12.00	\$ 1,212.00
-	24" RCP	Lin Ft	\$ 150.00	112.00	\$ 16,800.00
SUBTOTAL					\$ 24,346.08

8. Gutter retrofits on Darnell St & Williams St (1).


Gutter Repairs					
ITEM NO	DESCRIPTION	Unit	Bid Price	Quantity	Amount
DARNELL ST					
206D002	REMOVING CURB AND GUTTER	Lin Ft	\$ 10.00	43	\$ 430.00
214A000	STRUCTURE EXCAVATION	Cu Yd	\$ 17.00	5.56	\$ 94.44
623A001	CONCRETE GUTTER (VALLEY)	Lin Ft	\$ 46.00	135	\$ 6,210.00
WILLIAMS ST (1)					
206D002	REMOVING CURB AND GUTTER	Lin Ft	\$ 10.00	43	\$ 430.00
214A000	STRUCTURE EXCAVATION	Cu Yd	\$ 17.00	4.30	\$ 73.04
623A001	CONCRETE GUTTER (VALLEY)	Lin Ft	\$ 46.00	96	\$ 4,416.00
623C003	COMBINATION CURB & GUTTER, TYPE C (MODIFIED)	Lin Ft	\$ 32.00	24	\$ 768.00
SUBTOTAL					\$ 12,421.48

GRAND TOTAL \$ 78,987.34

REASON:

1. As requested by City for firetruck turning paths.
 2. Cavity around existing pipe was discovered during planned pipe replacement. Additional excavation and backfill were required to fill cavity area.
 3. As requested by City.
 4. Construction traffic at ballfields is no longer in immediate future so resurfacing work was added by stakeholders at Pre-Construction conference.
 5. As requested by City/BWS.
 6. As requested by BWS.
 7. Existing voids were discovered around existing crossdrains during Darnell St paving work so Engineer recommended replacement.
 8. Topographic survey was not available during design phase and installed gutter was steeper than preferred due to existing gutter flowlines and surface elevations.
-

RECOMMENDED:



Katie Warren, P.E.
Project Manager
Volkert, Inc

ACCEPTED:

David South
General Manager
Rogers Group, Inc.

APPROVED:

Tim Walker
Mayor, City of Boaz