800 – 6th Street N.W.
New Prague, MN 55071
Office: (952) 758-9445
Fax: (952) 758-9661

Quotation

To: Breezy Point, MN

Attn: Joe Zierden

Date: 03/28/2024
From: Ben Sollin
Phone: (612) 803-2701
Email: Ben@qfsi.net

Re: Irrigation Pump Station- Vertical Turbine Replacement Pump

Please see quote below per your request.

Irrigation LS: Vertical Turbine Replacement Pump-
This will consist of supplying and installing a new "Simflo" vertical turbine pump to directly replace your existing pump at your irrigation station.

Item	Description	Qty	Ext. Price	
1	"Simflo" OLS-SM10M-5, 6 inch, 5 Stage Vertical Turbine, Bare Pump to Include: - 6" J-Type Threaded Column - Standard Strainer Basket - 1-1/4" Line-shaft, 10" Stickup - 6" Discharge Flange - Packing Gland Seal Assembly - Standard Base/Foundation Plate - Re-Use Existing Motor - QFS Delivery & Install	1	$29,792.00	*Simflo Stock*

Total Installed Price: **$29,792.00** *Plus tax, if any*

Terms:
Quotation is valid for 30 days. Based upon Quality Flow Systems Standard Terms and Conditions of Sale; copy provided upon request.

Proposed Delivery Schedule:
Delivery: 4-6 weeks after approval.

Thank you for this opportunity to be of service to you. If you have any questions please don't hesitate to call.
612-803-2701

Sincerely,

Ben Sollin
Ben Sollin