PRELIMINARY MINOR SUBDIVISION

AP 158 LOTS 20 & 25 **MASSASOIT AVENUE EXTENSION BRISTOL, RHODE ISLAND**

APPLICANT/OWNER:

NCD DEVELOPERS, INC. C/O MICHAEL FONSECA 370 METACOM AVENUE BRISTOL, RI 02809




PRINCIPE COMPANY, INC.

ENGINEERING DIVISION

TIVERTON, RHODE ISLAND 02878 401.816.5385 INFO@PRINCIPEENGINEERING.COM WWW.PRINCIPEENGINEERING.COM

> AUGUST 17, 2017 REVISED: 12/12/17 1/3/18 1/19/18





LOCUS MAP NOT TO SCALE

LIST OF DRAWINGS

- COVER SHEET EXISTING SURVEY
- SITE DEVELOPMENT LAYOUT
- DRAINAGE AND GRADING ROADWAY PLAN AND PROFILE
- CONSTRUCTION DETAILS
 CONSTRUCTION DETAILS
- CONSTRUCTION DETAILS
 CONSTRUCTION DETAILS

PLANNING BOARD NOTE:

IN LIEU OF HAVING A DEAD END STREET THE PLANNING BOARD APPROVED THE CONNECTION OF ABILIO DRIVE ON JAN. 11, 2018 FOR SAFETY REASONS. DO TO SITE CONSTRAINTS THE ONE INCH WATER QUALITY RUNOFF HAS BEEN MITIGATED AS REQUESTED BY THE PLANNING BOARD WITH THE USE OF A STONE DRAINAGE INFILTRATION SWALE AND CORRESPONDING CALCULATIONS AS SHOWN ON SHEET

SOILS ON THE SITE CONSIST ENTIRELY OF SOIL TYPE CeC - CANTON AND CHARLTON-FINE SANDY LOAMS, VERY ROCKY 3-8% SLOPES

THE SITE IS LOCATED IN ZONE X (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOOD PLAIN) AS SHOWN ON FLOOD INSURANCE RATE MAP COMMUNITY PANEL NUMBER 44001C0014H MAP REVISED ON JULY 7,

REFERENCE:

EXISTING CONDITIONS PLAN MASSASOIT AVENUE EXTENTION ASSESSOR'S PLAT 158, LOTS 20 AND 25 SITUATED AT MASSASOIT AVENUE IN BRISTOL, RHODE ISLAND PREPARED BY STEPHEN M. MURGO SR. DATED DEC. 6th.


SURVEY & TOPOGRAPHIC PLAN AP 158 LOT 20-28, 53 & 54 MASSASOIT AVENUE BRISTOL, RHODE ISLAND FOR ADRIANO ANDRADE 225 WOOD STREET BRISTOL, RHODE ISLAND 02809 PREPARED BY WATERMAN ENGINEERING DATED APRIL 26, 2005


ZONING CRITERIA


MINIMUM LOT AREA
MINIMUM LOT WIDTH
MINIMUM LOT FRONTAGE
*MINIMUM FRONT YARD SETBACK
*MINIMUM SIDE YARD SETBACK
*MINIMUM REAR YARD SETBACK
*MINIMUM REAR YARD SETBACK
MAXIMUM LOT BUILDING COVERAGE
MAXIMUM BUILDING HEIGHT


15.000 S.F. WITH TOWN SEWER & WATER


Comer lot: A comer lot will have more than one front lot line, all of which shall meet the front yard setback. The yard setback of one of the rear lot lines may be reduced to side yard setback requirements.














LEGEND & ABBREVIATIONS

NIF	- NOW OR FORMERLY		- PROPERTY LINE
A.P.	- ASSESSORS PLAT		- ZONING SETBACK LINE
S.F.	- SQUARE FEET		- EXISTING CONTOUR
AC.	- ACRES		- STONE WALL
#	- PLUS OR MINUS	— x —	- FENCE
STY	- STORY	—— S ——	- SEWER LINE
W/F	- WOOD FRAMED	—— D ——	- DRAIN LINE
SHP	- STATE HIGHWAY PLAT	—— w ——	- WATER LINE
RET.	- RETAINING WALL	<u> — с —</u>	- GAS LINE
PED.	- PEDESTRIAN	——Е——	- ELECTRIC LINE
(FND.)	- FOUND	(S)	- SANITARY SEWER MANHOLE
RIHB	- RI HIGHWAY BOUND	III	- CATCH BASIN
PK NAIL	- MASONRY NAIL	0	- STORM DRAIN MANHOLE
FE.	- FLARED END	(C)	- WATER GATE
RCP	- REINFORCED CONCRETE PIPE	®	- GAS VALVE
CLF	- CHAIN LINK FENCE	(E)	- ELECTRIC MANHOLE
INV.	- INVERT		- CONCRETE BOUND
x 10.80	- SPOT GRADE		- DRILL HOLE
		0	- IRON PIPE
		•	- GRANITE BOUND WITH DRILL HOLE TO BE S.
	ZONING CRIT	ERIA	

R-20SP ZONING

15,000 S.F. WITH TOWN SEWER & WATER

Corner lot: A corner lot will have more than one front lot line, all of which shall meet the front yard setback. The yard setback of one of the rear lot lines may be reduced to side yard setback requirements.

ROADWAY PLAN AND PROFILE



DATE: 8/17/17

PRINCIPE COMPANY, INC. ENGINEERING DIVISION PO BOX 298 TIVERTON, RI 02878 401.816.5385 WWW.PRINCIPEENGINEERING.COM

REVISIONS

1.	DATE	DRWN	CHKD	ı
	12/12/17	TJP	TJP	1
	1/3/18	TJP	TJP	ı
	1/19/18	TJP	TJP	1
_				l
				ł
				l
1				1

PRELIMINARY MINOR SUBDIVISION AP 158 LOTS 20 & 25 MASSASOIT AVENUE EXTENSION BRISTOL, RHODE ISLAND

SCALE: AS NOTED SHEET NO: 5 of 9 DRAWN BY: TJP DESIGN BY: TJP CHECKED BY: TJP

PROJECT NO.: LDP 17-36

APPLICANT/OWNER: NCD DEVELOPERS, INC. 370 METACOM AVENUE BRISTOL, RI 02809

GENERAL NOTES:

1. THE STATE OF RHODE ISLAND STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, 2004 EDITION, AND THE RHODE ISLAND STANDARD DETAILS ARE MADE A PART HEREOF AS FULLY AND COMPLETELY AS IT ATTACHED HERETO. THE 2004 STANDARD SPECIFICATIONS MAY BE OBTAINED AT THE RHODE ISLAND DEPARTMENT OF TRANSPORTATION WEB PAGE. THESE SPECIFICATIONS ARE MADE A PART HEREOF AS FULLY AND COMPLETELY AS IF ATTACHED HERETO.

2. ALL REQUIRED SITE IMPROVEMENTS SHALL BE INSPECTED BY THE TOWN ENGINEER TO ENSURE SATISFACTORY COMPLETION. IN NO CASE SHALL THE INSTALLATION OF ANY IMPROVEMENTS BE STATRED UNTIL PRIOR NOTIFICATION IS GIVEN TO THE TOWN ENGINEER. AT LEAST A 48—HOUR NOTICE SHALL BE GIVEN TO THE TOWN ENGINEER PRIOR TO ANY SUCH START OF CONSTRUCTION. A FINAL INSPECTION OF ALL SITE IMPROVEMENTS, UTILITIES AND GRADING WILL BE MADE TO DETERMINE WHETHER THE WORK IS SATISFACTORY AND IN SUBSTANTIAL

- 3. LOCATION AND DEPTH OF EXISTING UTILITIES ARE APPROXIMATE AND HAVE BEEN PLOTTED FROM THE BEST AVAILABLE INFORMATION. THE CONTRACTOR SHALL CHECK AND VERIFY LOCATIONS OF ALL EXISTING UTILITIES BOTH UNDERGROUND AND OVERHEAD. ANY DAMAGE TO EXISTING UTILITIES AS SHOWN OR NOT SHOWN ON THE PLANS SHALL BE THE CONTRACTOR'S RESPONSIBILITY. COSTS OF SUCH DAMAGE SHALL BE BORNE BY THE CONTRACTOR. NO EXCAVATION SHALL BE DONE UNTIL ALL INVOLVED UTILITY COMPANIES ARE NOTIFIED 48—HOURS IN ADVANCE. THE CONTRACTOR SHALL BE RESPONSIBLE TO NOTIFY DIG-SAFE (1—800—344—7233) A MINIMUM OF 48 WORKING HOURS, EXCLUDING WEEKENDS AND HOLIDAYS, PRIOR TO THE START OF ANY EXCAVATION AND/OR BLASTING WORK. THE NAME OF THE COMPANY PERFORMING THE EXCAVATION AND/OR BLASTING WORK MUST BE SUPPLIED TO DIG-SAFE, IF IT IS DIFFERENT FROM THE CALLER.
- 4. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO OBTAIN ANY AND ALL PERMITS REQUIRED BY, BUT NOT LIMITED TO, THE STATE OF RHODE ISLAND, THE FEDERAL GOVERNMENT. THE TOWN OF BRISTOL AND ALL INDIVIDUAL UTILITY COMPANIES PRIOR TO COMMENCING ANY WORK.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING AND MAINTAINING ALL TEMPORARY SEDIMENTATION AND EROSION CONTROLS.
- 7. ALL MATERIAL FOR FILL SHALL BE CLEAN AND FREE OF MATTER WHICH COULD POLLUTE ANY DOWN STREAM WATERCOURSE.
- 9. FILL MATERIAL SHALL BE COMPACTED IN ONE FOOT (MAXIMUM) LIFTS TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED IN ACCORDANCE WITH ASTM D-1557 (MODIFIED PROCTOR TEST).

STORM DRAINAGE SYSTEM MAINTENANCE PLAN:

THE FOLLOWING LIST OF MAINTENANCE TASKS AND FREQUENCIES MUST BE ADHERED TO IN ORDER TO INSURE A SUCCESSFUL LONG TERM OPERATION OF THE STORM DRAINAGE SYSTEM.

- DURING CONSTRUCTION ACTIVITIES ALL EROSION CONTROLS ON THE SITE SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN TWENTY FOUR (24) HOURS AFTER AN EVENT WHICH GENERATES AT LEAST 0.25 INCHES OF RAIN IN A TWENTY FOUR (24) HOUR PERIOD.
- 2. SEDIMENTS SHALL BE REMOVED FROM THE ALL BASINS IMMEDIATELY AFTER SITE STABILIZATION.
- 3. ALL TRASH, LITTER AND OTHER DEBRIS SHALL BE REMOVED FROM ALL STORM WATER INLET AND OUTLET STRUCTURES A MINIMUM OF TWICE PER YEAR. THESE STRUCTURES SHALL ALSO BE INSPECTED TWICE PER YEAR. INSPECTIONS SHALL BE PERFORMED SEVERAL TIMES WITHIN THE FIRST SIX MONTHS OF OPERATION.
- SPECTIONS OF ALL CATCH BASINS SHALL OCCUR ON AN ANNUAL BASIS TO CHECK FOR DEBRIS REMOVAL (SEDIMENT AND HYDROCARBONS) AND STRUCTURAL INTEGRITY OR DAMAGE. SUCH DEFICIENCIES SHALL BE CORRECTED IMMEDIATELY.
- 5. REPAIRS OR REPLACEMENT OF INLET/OUTLET STRUCTURES OR ANY ELEMENT OF THE FACILITY SHALL BE DONE WITHIN THIRTY (30) DAYS OF DEFICIENCY REPORTS. IF AN EMBERGENCY SITUATION IS IMMINENT THEN REPAR/REPLACEMENT SHALL BE DONE IMMEDIATELY TO AVERT FAILURE OR DANGER TO NEARBY RESIDENTS.
- 6. MAKE REPAIRS IMMEDIATELY USING APPROPRIATE STONE SIZES. DO NOT PLACE STONES ABOVE FINISHED GRADE,
- 7. ALL REMOVED SEDIMENTS AND DEBRIS SHALL BE DISPOSED OF OFF SITE IN IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS.
- 8. ALL OUTLET STRUCTURES AND OUTFLOW CHANNELS WILL BE INSPECTED ANNUALLY. INSPECTIONS WILL BE ACCOMPLISHED SEVERAL THES DURING THE FIRST SIX MONTHS OF OPERATION, ESPECIALLY AFTER RAINFALL EVENTS TO CHECK FOR CLOGGING OR, CONVERSELY, TOO RAPID OF A RELEASE.
- REPAIRS OR REPLACEMENT OF INLET/OUTLET STRUCTURES, RIP—RAP CHANNELS, FENCES, OR OTHER ELEMENTS OF THE FACILITY WILL BE DONE WITHIN 30 DAYS OF DEFICIENCY REPORTS. IF AN EMERGENCY SITUATION IS IMMINENT THEN REPAIR/REPLACEMENT MUST BE DONE IMMEDIATELY TO AVERT FAILURE OR DANGER TO NEARBY RESIDENTS.
- 10. ALL SEDIMENT GENERATED DURING CONSTRUCTION AND AS A RESULT OF MAINTENANCE OF THE DRAINAGE SYSTEM MUST BE DISPOSED OF PROPERLY. SEDIMENT SHALL NOT BE DISPOSED OF IN OR NEAR STATE OR FEDERAL REGULATED WATERS.
- 11. RECORDS OF THE FIRST TWO YEARS OF MAINTENANCE FOLLOWING CONSTRUCTION SHALL BE SUBMITTED TO RIDEM DIVISION OF WATER RESOURCES. MAINTENANCE RECORDS FOR SUBSEQUENT YEARS SHALL BE KEPT ON FILE AND SUBMITTED TO RIDEM, DIMISION OF WATER RESOURCES, UPON REQUEST.
- 12. Grasses shall be planted around and within the detention basin immediately following construction to stabilize slopes and prevent erosion. Trees and shrubs are not to be planted on basin slopes.
- 13. All drainage structures are to be inspected at least three times in
- the first six months of operation. Evidence of clogging or rapid release
- of flow shall be remedied immediately.
- 14. Side slopes, embankments, and the upper stages of all detention basins are to be mowed at least three times per growing season, to prevent unwanted growth, and to maintain the capacity and integrity of the facilities. Mowing should include the removal of woody growth, which

- 15. The grassed areas of all basins are to be inspected at least twice a year to check for erosion problems. Areas subject to erosion problems shall be re-seeded immediately to stabilize any exposed soils. Where pools of stagnant water are observed in a detention basin, the deficiency shall be corrected immediately. This will prevent the formation of a nuisance habitat for insects.
- 16. Trash, litter and other debris are to be removed from all stormwater facilities at least twice a year to prevent blockage of inlet and outlet structures, and hence failure of the structure. Where the amounts of debris found are large, a careful inspection of all adjacent inlet and outlet structures shall be undertaken to identify any damage that may have occurred. Litter shall be removed from the detention basin prior to mowing operations.
- 17. If a blockage occurs to a basin outlet, it may necessary to drain the basin in order to effect a repair. All water that is drained from the basin shall be adequately filtered to remove suspended solids prior to
- 18. All catch basins shall be inspected at least twice a year for debris and the presence of potential pollutants. Catch basins and manholes shall be inspected twice a year for structural integrity. 19. Maintenance of the stormwater system during the construction process shall be the responsibility of the contractor.
- 20. On completion of construction maintenance of the stormwater system shall become the responsibility of the Town of Bristol.

EROSION CONTROL AND SOIL STABILIZATION PROGRAM:

DENUDED SLOPES SHALL NOT BE LEFT EXPOSED FOR EXCESSIVE PERIODS OF E. SUCH AS THE INACTIVE WINTER SEASONS.

- 2. TEMPORARY TREATMENTS SHALL CONSIST OF A HAY, STRAW, FIBER MULCH OR PROTECTIVE COVERS SUCH AS A MAT OR RIBER LINING (BURLAP, JUTE, FIBERGLASS NETTING, EXCELSIOR BLANKETS). THEY SHALL BE INCORPORATED INTO THE WORK AS WARRANIED OR AS ORDERED BY THE ENGINEER.
- 3. HAY OR STRAW APPLICATIONS SHOULD BE IN THE AMOUNT OF 2000
- 4. ALL HAY BALES OR TEMPORARY PROTECTION SHALL REMAIN IN-PLACE UNTIL AN ACCEPTABLE STAND OF GRASS OR APPROVED GROUND COVER IS ESTABLISHED.
- 5. THE TOPSOIL SHALL HAVE A SANDY LOAM TEXTURE RELATIVELY FREE OF SUBSOIL MATERIAL, STONES, ROOTS, LUMPS OF SOIL, TREE LIMBS, TRASH OR CONSTRUCTION DEBRIS AND SHALL CONFORM WITH RHODE ISLAND STANDARD SPECIFICATION M.20.01.
- 6. THE SEED MIX SHALL BE INOCULATED WITHIN 24-HOURS BEFORE MIXING AND PLANTING, WITH APPROPRIATE INOCULUM FOR EACH VARIETY.
- THE DESIGN MIX UTILIZED IN ALL DISTURBED AREAS TO BE SEEDED SHALL COMPRISED OF THE FOLLOWING: % BY WEIGHT SEEDING DATE TYPE CREEPING RED FESCUE APRIL 1 - JUNE 15 AUGUST 15 - OCTOBER
- APPLICATION RATE 100 LBS/ACRE LIMING AND FERTILIZING AS REQUIRED TO COMPLIMENT OR UPGRADE EXISTING CONDITIONS.
- 8. THE CONTRACTOR MUST REPAIR AND/OR RESEED ANY AREAS THAT DO NOT DEVELOP WITHIN THE PERIOD OF ONE YEAR, AND SHALL DO SO AT NO ADDITIONAL EXPENSE.
- 9. THE NORMAL ACCEPTABLE SEASONAL SEEDING DATES ARE APRIL 1ST THROUGH OCTOBER 15TH.
- 10. STABILIZATION OF ONE FORM OR ANOTHER AS DESCRIBED ABOVE SHALL BE ACHIEVED WITHIN FIFTEEN (15) DAYS OF FINAL GRADING.
- STOCKPILES OF TOPSOIL AND EARTH MATERIALS SHALL NOT BE LOCATED R WATERWAYS. THEY SHALL HAVE SIDE SLOPES NO GREATER THAN THIRT PERCENT (30%) AND STOCKPILE SHALL ALSO BE SEEDED AND/OR STABILIZED.
- ON BOTH STEEP AND LONG SLOPES, CONSIDERATION SHOULD BE GIVEN TO MINIOR OR "TRACKING" TO TACK DOWN MULCH APPLICATIONS.
- 13. TREES TO BE RETAINED SHALL BE FENCED OR ROPED OFF TO PROTECT THEM FROM CONSTRUCTION EQUIPMENT.
- 15. ALL PROPOSED PLANTINGS MUST BE MAINTAINED BY THE PROPERTY OWNER TO ENSURE SURVIVAL.
- 16. SHOULD ANY OR ALL OF THE PROPOSED PLANTS FAIL TO SURVIVE AT LEAST ONE (1) FULL GROWING SEASON FROM THE TIME THEY HAVE BEEN PLANTED, THE OWNER SHALL BE FULLY RESPONSIBLE FOR REPLACING AND MAINTAINING THE SAME PLANT SPECIES FOR ONE (1) ADDITIONAL GROWING
- 17. ALL DISTURBED AREAS MUST BE SEEDED OR PLANTED WITHIN THE CONSTRUCTION SEASON.
- 18. TEMPORARY SEEDING MUST BE DONE WITHIN ONE (1) MONTH AFTER DISTURBANCE.

MAINTENANCE RESPONSIBILITY

THE APPLICANT IS RESPONIBLE FOR THE MAINTENANCE OF ALL DRAINAGE STRUCTURES.

SEDIMENTATION CONTROL PROGRAM:

- 1. EXTREME CARE SHALL BE EXERCISED SO AS TO PREVENT ANY UNSUITABLE MATERIAL FROM ENTERING DOWNSTREAM WATERCOURSES AND STORMWATER DRAINAGE SYSTEMS.
- 3. SEDIMENTATION CONTROL DEVICES SHALL BE INSPECTED CLOSELY AND MAINTAINED PROMPTLY AFTER EACH RAINFALL 4. CARE SHALL BE TAKEN SO AS NOT TO PLACE "REMOVED SEDIMENTS" WITHIN THE PATH OF EXISTING, NEWLY CREATED (BOTH TEMPORARY AND PERMANENT) OR PROPOSED WATERCOURSES OR THOSE AREAS SUBJECTED TO STORMWATER FLOWAGE.
- 5. ADDITIONAL HAYBALES OR SANDBAGS SHALL BE LOCATED AS CONDITIONS WARRANT OR AS DIRECTED BY THE ENGINEER.
- 6. SEDIMENTATION TRAPS SHALL BE PROVIDED AT ALL DRAINAGE STRUCTURES DURING CONSTRUCTION.
- 7. EROSION AND SEDIMENTATION CONTROLS SHALL BE INSTALLED AT THE SITE PRIOR TO THE START OF CONSTRUCTION AND BE PROPERLY MAINTAINED UNTIL ALL DISTURBED AREAS ARE STABILIZED INCLUDING:
- A) THE INSTALLATION OF A CONTINUOUS LINE OF STAKED HAYBALES IN ALL LOCATIONS SHOWN ON THE APPROVED SITE PLANS AND WHERE OTHERWISE NECESSARY TO PREVENT SEDIMENTS FROM ENTERING DOWNSTREAM WATERCOURSES AND STORMWATER DRAINAGE SYSTEMS.
- DOWNS IRLAM WAILERCOURSES AND STORMWAILER DRAINAGE SYSTEMS.


 B) ALL DISTURBED AREAS ARE TO BE PERMANENTLY STABILIZED WITH APPROVED GROUND COVER PRIOR TO THE COMPLETION OF THE PROJECT. AREAS EXPOSED FOR EXTENDED PERIODS ARE TO BE COMPLETELY COVERED WITH SPREAD HAY MULCH.

 CATCH BASINS WILL BE PROTECTED WITH HAYBALE FILTERS THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED. SUMPS ARE TO BE CLEANED IMMEDIATELY FOLLOWING INSTALLATION OF PERMANENT PAVEMENT.
- D) OUTFALLS ARE TO BE PROTECTED BY HAYBALE FILTERS UNTIL DISTURBED AREAS ARE PERMANENTLY STABILIZED WITH APPROVED GROUND COVER. ALL CONTROL MEASURES WILL BE MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.
- 8. THE LIMITS OF ALL CLEARING, GRADING AND DISTURBANCE SHALL BE KEPT TO A MINIMUM WITHIN THE PROPOSED AREA OF CONSTRUCTION. ALL AREAS OUTSIDE OF THE LIMITS OF DISTURBANCE SHALL REMAIN TOTALLY UNDISTURBED.
- UPON COMPLETION OF CONSTRUCTION OF SITE IMPROVEMENTS AND THE STORMWATER DRAINAGE SYSTEM, ALL CATCH BASINS AND STORM DRAIN PIPING SHALL BE CLEANED OF SEDIMENT. DETENTION BASINS SHALL BE CLEANED OF SEDIMENT TO THE DESIGN GRADES INDICATED
- 10. AT NO TIME DURING CONSTRUCTION SHALL THE SUBGRADE OF THE SITE BE SUCH THAT SURFACE RUNOFF WILL BE PERMITTED TO DIRECTLY ENTER ANY DRAINAGE STRUCTURE. A TEMPORARY DEPRESSED AREA AROUND THE STRUCTURE SHALL BE INCORPORATED AS A SEDMENTATION TRAP. THE MOUTH OF THE TRAP SHALL BE LINED WITH HAYBALES AROUND THE COMPLETE PERMIETER DURING ALL PRELIMINARY STAGES, THE TOP OF THE STRUCTURE SHALL ALWAYS BE HIGHER THAN THE SUBGRADE.
- 12. ALL COMPONENTS OF THE DRAINAGE SYSTEM MUST BE CLEANED OF SEDIMENT BY THE APPLICANT OR HIS REPRESENTATIVE IMMEDIATELY AFTER CONSTRUCTION IS COMPLETED.
- 13. INSPECT TEMPORARY DIVERSIONS AND THEIR COMPONENTS ONCE A WEEK AND AFTER EVERY RAINFALL DAMAGE CAUSED BY CONSTRUCTION TRAFFIC OR OTHER ACTIVITY SHOULD BE REPAIRED BEFORE THE END OF EACH WORKING DAY. A SEDMENTATION TRAP. THE MOUTH OF THE TRAP SHALL BE LINED WITH HAYBALES AROUND THE COMPLETE PERIMETER. DURING ALL PRELIMINARY STAGES, THE TOP OF THE STRUCTURE SHALL ALWAYS BE HIGHER THAN THE SUBGRADE.
- CHECK DAMS SHALL BE INSTALLED EVERY 300 FEET FOR SLOPES OF 1% OR LESS, EVERY 200 FEET FOR SLOPES OF 2% EVERY 150 FEET FOR SLOPES OF 3% TO 5%, AND EVERY 100 FEET FOR SLOPES OF 5% OR GREATER.
- SEDIMENTS SHOULD BE REMOVED FROM THE CHECK DAM WHEN IT REACHES —HALF THE DAM HEIGHT.


CATCH BASIN AND WATER QUALITY INLET TANK

- SEDIMENTATION CONTROL AND MAINTENANCE: 1. AT NO TIME DURING CONSTRUCTION SHALL THE SUBGRADE OF THE SITE BE SUCH THAT SURFACE RUNOFF WILL BE PERMITTED TO DIRECTLY ENTER ANY DRAINAGE STRUCTURE. A TEMPORARY DEPRESSED AREA AROUND THE MOUTH OF THE TRAP SHALL BE INCORPORATED AS A SEDIMENTATION TRAP. THE MOUTH OF THE TRAP SHALL BE LINED WITH STRAW BALES AROUND THE COMPLETE PERMITTER. DURING ALL PRELIMINARY STAGES, THE TOP OF THE STRUCTURE SHALL ALWAYS BE HIGHER THAN THE SUBGRADE.
- STRAW BALE EROSION CHECKS SHALL BE MAINTAINED AROUND ALL RUCTURES UNTIL ALL UPGRADIENT DISTURBED AREAS ARE STABILIZED BY

I. SET POSTS MINIMUM DEPTH OF 12" AND EXCAVATE A 6"x6" TRENCH UPSLOPE ALONG THE LINE OF POSTS. 2. STAPLE WIRE FENCING TO THE POSTS. 3. ATTACH THE FILTER FABRIC TO THE WIRE FENCE AND EXTEND IT TO THE TRENCH. BACKFILL AND COMPACT THE EXCAVATED SOIL. SILT FENCE BARRIER DETAIL



10' MINIMUM WIDTH OF FLARED END SECTION SECTION + 6 FT. , 111111. [083<u>505650650</u>6508800 SECTION B-B




SECTION A-A 5' MINIMUM WIDTH

CLASS OF RIP—RAP AND BEDDING TO BE SPECIFIED IN CONTRACT DOCUMENTS.
 DIMENSIONS MAY BE MODIFIED BY ENGINEER TO MEET FIELD CONDITIONS
 JUNLESS OTHERMISE SPECIFIED, DUMPED RIP—RAP SHALL BE USED.

ROCK FILL RIP-RAP @ FLARED END SECTIONS NOT TO SCALE

RIP-RAP TABLE


M02.02.4 = 8" - 95 / 100%4" - 0 / 25% 2½" - 0 / 5%




4" MIN.-

CONSTRUCTION ENTRANCE

RIP-RAP_STABILIZATION PAD @ CONSTRUCTION ENTRANCE





INSTALLATION

REMOVE DRAIN GRATE

INSERT SILTSACK

REPLACE GRATE TO HOLD SILTSACK IN POSITION

REMOVE FILLED SILTSACKS

CLEAN AND REUSE

AS MANUFACTURED BY ACF ENVIRONENTAL OR APPROVED EQUAL

> SILT SACK DETAIL NOT TO SCALE

CONSTRUCTION DETAILS-1



PRINCIPE COMPANY, INC. ENGINEERING DIVISION

PISAN ESTABLISHED IN 1981 PO BOX 298
TIVERTON, RI 02878
401.816.5385
WWW.PRINCIPEENGINEERING.COM


REVISIONS PRELIMINARY MINOR SUBDIVISION DATE DRWN CHKD AP 158 LOTS 20 & 25 1/3/18 TJP TJP AND 2 1/19/18 TJP TJP MASSASOIT AVENUE EXTENSION BRISTOL, RHODE ISLAND


SCALE: AS NOTED	SHEET NO	SHEET NO: 6 OF 9				
DRAWN BY: TJP	DESIGN BY: TJP	CHECKED BY: TJP				
DATE: 8/17/17	PROJECT	NO.: LDP 17-36				

APPLICANT/OWNER:

NCD DEVELOPERS, INC. C/O MICHAEL FONSECA 370 METACOM AVENUE BRISTOL, RI 02809

tiO	wner:		Aico	Processes	art A - Soll F	uation For rofile Des		Applicati	on Number_			
	cation:				AP 155	LOD .	0.75	Mass	14800T .4V	- BREW	<u> </u>	
	t Hole:			22/17								
l Evalua ather	tor:		Etuds 7.	Phonest	70,A			Number: Yes D N	D-4075			
_			curdanes			Re-Dox		Yes LI N	ime:			
H <u>OR-</u> brizon	Depth	Dst	Topo	Metrix	Re-Dox Feetures	Ab. S.		Testure	Structure	Consistence	Spil Outegory	
HTM.	D-18											
C.	u-71	" 4	5	16412 5/4	7.54.4	C-n	1-p	SL	O, MA	FL	ő	
			,									
	X						-		- a - 0	-7		
H 06-		Horizon	oundaries	55/10	blors	Pa-l	Dax	_			Soil	
brizon	Depth	Dat	Topo	Matrix	Pe-Dox Features	Ab. S	Contr.	Teture	Structure	Consistence	Category	
hm	0-20											
C	20°-96	٠ ٩	2	1042574	2544	C-M	-p	SL	U, ags	TR	රි	
								P			* - 1	
1.											6 1	
										,	×	
		*					F*					
Comment of the	Soil Class			epth <u>72</u> "	Impervious/L	imiting Laye	r Depth	7 <u>2 " (og)</u> GV 16 '' (og) GV	V Seepage Depth V Seepage Depth	HUME SHAT	48 (og)	
rrments;			V 1 -					5 5				
			16-1 =	- 24" Le	iNF.	Cel	. (CA			er Fine:		





WATER GATE VALVE/SERVICE CURB STOP

PROFILE VIEW

APPLICANT/OWNER:

NCD DEVELOPERS, INC. C/O MICHAEL FONSECA

370 METACOM AVENUE BRISTOL, RI 02809

(13) Street Trees.
Where existing tree growth is determined by the Planning Board or Technical
Review Committee (TRC) to be insufficient, the Planning Board or TRC shall
require the applicant to plant street trees along both sides of all new streets within
developments or along the existing streets abutting the development in accordance
with the approved landscape plan. Street trees shall be appropriate for the terrain,
soil and climatic conditions encountered in the development, and in accordance
with the following standards:

cation - Street trees shall be planted within street rights-of-way along


(a) Location — Street trees shall be planted within street rights—of—way along both sides of the street.

(b) Spacing — Trees shall be planted at distances of not less than thirty (30) feet nor more than fifty (50) feet apart along each side of the street powement. At street corners, trees shall not be planted within twentyfive (25) feet of the intersecting right—of—way lines.


(c) Type — Trees shall be of nursery stock grown under local climatic conditions and of a type as recommended by the Bristal Conservation Commission and opproved by the Planning Board. Species which have been introduced to this region by way of Bristol are preferred, (see town approved planting list).

CONSTRUCTION DETAILS-2

PROJECT NO.: LDP 17-36



DATE: 8/17/17



WELL DRAINED SHELL IMPERVIOUS SOIL CORE WELL DRAINED 1 EXTEND IMPERVIOUS CORE 3'
BELOW EXISTING GRADE WHERI
BASIN RISES ABOVE EXISTING
GRADE

- NOTES.

 1. IMPERVIOUS SOIL CORE TO BE PROVIDED FOR ALL DETENTION POND

 1. IMPERVIOUS SOIL CORE TO BE CONSTRUCTED OF MATERIAL

 2. IMPERVIOUS SOIL CORE TO BE CONSTRUCTED OF MATERIAL

 2. CONSISTING OF SILT ON \$\circ{2}\Oldow{O}\sigma_{\text{o}}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{TE}\text{O}\text{O}\text{TE}\text{O}\text{O}\text{TE}\text{TE}\text{O}\text{TE}\text{O}\text{TE}\text{TE}\text{O}\text{TE}\text{TE}\text{O}\text{TE}\text{TE}\text{TE}\text{TE}\text{TE}\text{O}\text{TE}
- INCLUDES, BUT NOT LIMITED TO, MAINS.

 11. THE IMPERVIOUS CORE SHALL BE KEPT FREE FROM STANDING WATER DURING THE BACKFILL OPERATION.


 12. ALL EMBANKMENTS TO BE DESIGNED BY A GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION. ALL EMBANKMENT INSTALLATIONS TO BE SUPERVISED BY A GEOTECHNICAL ENGINEER.


Detention Pond Earthen Embankment

NOT TO SCALE


DRAINAGE AND UTILITY NOTES:

- 1. UTILITY LOCATION VERIFICATION IS TO INCLUDE TEST HOLES AS NEEDED
- 2. WATER MAINS AND APPURTENANCES, INCLUDING SERVICE CONNECTIONS SHALL BE INSTALLED IN CONFORMITY WITH THE SPECIFICATIONS OF THE BRISTOL COUNTY WATER AUTHORITY.
- 3. THE CONTRACTOR IS REQUIRED TO SCHEDULE AND COORDINATE WATER SERVICE INSTALLATIONS, SHUT DOWNS AND DISRUPTIONS WHICH AFFECT THE SITE AND SITE ADJACENT USERS WITH THE LOCAL WATER AUTHORITY AND THE LOCAL FIRE DEPARTMENT.
- 4. UNDERGROUND UTILITIES, ELECTRIC, TELEPHONE, FIRE ALARM CABLE, TELEVISION AND GAS SERVICES SHALL BE INSTALLED PER THE REQUIREMENTS OF THE APPLICABLE SITE UTILITY PROVIDER
- 5. METALLIC WARNING TAPE SHALL BE INSTALLED 12" ABOVE ALL STORM DRAIN AND OTHER UTILITIES.
- 6. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO MAINTAIN THE INTEGRITY OF ALL EXISTING UTILITIES, STRUCTURES AND ABUTTING PROPERTIES. THE COST OF ANY REPAIR OR REPLACEMENT OF DAMAGED ITEMS SHALL BE BORNE BY THE CONTRACTOR.






Low Flow Outlet



APPLICANT/OWNER:

NCD DEVELOPERS, INC. C/O MICHAEL FONSECA 370 METACOM AVENUE BRISTOL, RI 02809

CONSTRUCTION DETAILS-3



PRINCIPE COMPANY, INC.


ESTABLISHED IN 1981

ENGINEERING DIVISION TIVERTON, RI 02878 401.816.5385 WWW.PRINCIPEENGINEERING.COM

REVISIONS PRELIMINARY MINOR SUBDIVISION No. DATE DRWN CHKD AP 158 LOTS 20 & 25 1 1/3/18 TJP TJP AND 2 1/19/18 TJP TJP **MASSASOIT AVENUE EXTENSION**

BRISTOL, RHODE ISLAND

SCALE: AS NOTED		SHEET NO	D: 8 OF 9
DRAWN BY: TJP	DESIGN B	Y: TJP	CHECKED BY: TJP
DATE: 8/17/17		PROJECT	NO.: LDP 17-36



DATE: 8/17/17

BRISTOL, RI 02809

PROJECT NO.: I DP 17-36