

PROVIDE ENCLOSURE FOR EQUIPMENT. MAINTAIN ALL SERVICE CLEARANCES. ENCLOSURE SHALL BE PERFORATED TO ALLOW PROPER AIRFLOW. THE ENCLOSURE PANELS SHALL TERMINATE 12" ABOVE GRADE TO ALLOW AIRFLOW.

