



MOISTURE SURVEY RESULTS				
ROOF SECTION	APPROX. SIZE (SF)	NUMBER OF WET AREAS	APPROX. WET AREAS (SF)	PERCENTAGE WET
ROOF 'A'	1,775	1	1,775	100%
ROOF 'B'	2,657	-	-	-
ROOF 'C'	378	-	-	-
ROOF 'D'	890	-	-	-
TOTAL	5,700	1	1,775	31%

LEGEND	
	WET INSULATION
	MANSARD ROOF

- GENERAL NOTES:**
- 1.) IT IS THE ROOFING CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE THEMSELVES WITH ALL DETAILS INVOLVED IN THE ROOFING CONTRACT.
 - 2.) ALL DRAWINGS ARE GRAPHIC REPRESENTATION OF APPROXIMATE LOCATIONS OF EXISTING AND NEW MATERIALS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL EXISTING CONDITIONS PRIOR TO COMMENCEMENT OF WORK.
 - 3.) THE ROOFING CONTRACTOR TO PROTECT ALL ADJACENT SURFACES NOT SCHEDULED FOR WORK AND TO REPAIR ANY DAMAGED AREAS AS A RESULT OF CONTRACTOR WORK AT NO ADDITIONAL COST TO THE OWNER.
 - 4.) THE ROOFING CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN WATER TIGHTNESS AND PROVIDE PROTECTION AT ANY/ALL OPENINGS IN THE ROOF LEFT AT THE END OF EACH CONSTRUCTION DAY.
 - 5.) CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, CONDITIONS AND QUANTITIES.

SYMBOL LEGEND	
	CURB
	PLUMBING VENT
	PITCH POCKET
	SKYLIGHT
	VENT
	ROOF DRAIN
	OVERFLOW SCUPPER
	GOOSE VENT
	SLEEPER
	ROOF HATCH
NOTE: PENETRATIONS ARE APPROXIMATE IN SIZE AND LOCATION TO BE USED AS REFERENCE POINTS ONLY	

- EXISTING ROOF CORE SAMPLES:**
- TEST CUT #1
- LIGHTWEIGHT CONCRETE/ STEEL DECK
 - 4.5 ISO INSULATION - 3 LAYERS
 - 1/2" GYPSUM (WET)
 - .060 TPO
- TEST CUT #2
- LIGHTWEIGHT CONCRETE/ STEEL DECK
 - 4.5 ISO INSULATION - 3 LAYERS
 - 1/2" GYPSUM (WET)
 - .060 TPO
- TEST CUT #3
- STEEL DECK
 - PLYWOOD
 - .060 TPO



ROGERS FREE LIBRARY

525 Hope Street
Bristol, RI 02809

SCALE: AS NOTED
DATE: 10/26/2024
PROJ. #:
DRAWN BY:

ROOF PLAN

A-101