	TREE LEGEND			
SYMBOL	BOTANICAL / COMMON NAME	SIZE	QUANTITY	TRI
TREES				INI
Control of the second	ACER RUBRUM 'ARMSTRONG' ARMSTRONG MAPLE	2" cal. min.	17	17
	CARPINUS BETULUS 'FASTIGIATA' PYRAMIDAL EUROPEAN HORNBEAM	2" cal. min.	4	4
	LIRIODENDRON TULIPERA 'JFS-OZ' EMERALD CITY TULIP TREE	2" cal. min.	3	3
and the second	THUJA PLICATA 'HOGAN' WESTERN RED CEDAR	6' HT min.	5	5
52 - 52 - 52 - 52 - 52 - 52 - 52 - 52 -	TILIA CORDATA 'CORZAM' CORINTHIAN LINDEN	2" cal. min.	4	4
	•	OTAL T	REE UNITS	33
SHRUBS				
※	LIGUSTRUM JAPONICUM 'TEXANUM' WAX PRIVET	5 GAL.	38	
\bigcirc	MAHONIA REPENS CREEPING OREGON GRAPE	2 GAL.	12	
Δ	MYRICA CALIFORNICA PACIFIC WAX MYRTLE	5 <i>G</i> AL.	27	
0	PRUNUS LAUROCERASUS 'OTTO LUYKEN' OTTO LUYKEN'S LAUREL	5 GAL.	52	
⊗	VIBURNUM DAVIDII DAVID VIBURNUM	2 GAL.	24	
SROUNDCOYE	ER	l .	I	
	ARCTOSTAPHYLOS UVA URSI 'MASS.' MASSACHUSETTS KINIICKINNICK	I GAL.	30" O.C.	
	RUBUS CALYCINOIDES CREEPING RASPBERRY	I GAL.	30" O.C.	
	LAWN (SEED OR SOD) PER OWNER		1	

TREE UNIT SUMMARY			
SITE AREA	.93± AC		
REQUIRED TREE UNITS / ACRE	20		
TOTAL REQUIRED TREE UNITS	19		
EXISTING TREE UNITS RETAINED	0		
TREE UNITS PROPOSED TO PLANT	33		
TREE UNITS PROVIDED	33		

DRAWN: CB	CHECKED:		
SCALE: " = 20'-0"	DATE: 11.03.23		
JOB #: 23-1837			
ISSUED FOR: PLR			
REVISIONS:			
\triangle			
<u> </u>			
<u> </u>			
<u></u>			
£			

IRRIGATION NOTE

ALL LANDSCAPE AREAS SHALL BE HAND WATERED OR IRRIGATED WITH AN AUTOMATIC DRIP AND/OR SPRAY IRRIGATION SYSTEM. REFER TO CIVIL ENGINEERING PLANS FOR WATER SOURCE.

REFER TO SHEET PD FOR LANDSCAPE DETAILS AND NOTES REFER TO SHEET ID FOR IRRIGATION DETAILS AND NOTES.

PLANTING	NOTES
_	

- 16. THE CONTRACTOR SHALL ENSURE THAT ALL EXCAVATED PLANTING PITS HAVE POSITIVE DRAINAGE. PLANT PITS ALL BOUNDARIES, EASEMENTS, UTILITIES AND LEGAL ENCUMBRANCES TO BE CONFIRMED WITH OWNER PRIOR TO BEGINNING WORK. PROPERTY LINES AND SURVEY INFORMATION PROVIDED BY PLS ENGINEERING
- 2. IN NO WAY IS THIS PLAN TO BE INTERPRETED TO EXCEED THE LEGAL BOUNDARIES OF THE OWNER'S REAL
- 3. THE LANDSCAPE DESIGNER ASSUMES NO RESPONSIBILITY FOR THE LOCATION OF BOUNDARIES, UTILITIES AND WETLANDS.
- 4. THIS PLAN SHALL BE INSTALLED TO MEET ALL APPLICABLE CITY, COUNTY, STATE AND FEDERAL CODES. 5. THIS PLAN SHALL BE CONSIDERED PRELIMINARY UNTIL APPROVED BY ALL GOVERNING AGENCIES.
- IMPLEMENTATION OF THIS PLAN SHALL NOT PROCEED UNTIL ISSUANCE OF ALL RELATED PERMITS.
- 6. PLANT QUANTITIES ARE FOR INFORMATION ONLY. IN CASE OF ANY DISCREPANCY, THE PLAN SHALL GOVERN. ALL WORK IS TO BE PERFORMED BY LICENSED CONTRACTORS AND EXPERIENCED WORKERS.
- 8. THE CONTRACTOR IS TO VERIFY THE LOCATION OF EXISTING UNDERGROUND UTILITIES AND STRUCTURES PRIOR TO PERFORMING ANY EXCAVATION. CONTRACTOR SHALL REPAIR ANY DAMAGE TO UTILITIES CAUSED BY THE
- 9. ALL PLANT MATERIALS SHALL MATCH SPECIFICATIONS PER SPECIES AND SHALL COMPLY WITH ANSI Z60.1 'STANDARD FOR NURSERY STOCK'.
- 10. THE CONTRACTOR SHALL ADHERE TO THE WASHINGTON ASSOCIATION OF NURSERYMEN'S GUIDELINES FOR PLANTING PRACTICES.

SITE AREA 48 HOURS PRIOR TO ANY EXCAVATION.

- THE CONTRACTOR SHALL REPAIR ANY DAMAGE TO EXISTING ELEMENTS ON AND OFF SITE, RESULTING FROM THE
- CONTRACTOR'S WORK. 12. THE CONTRACTOR IS RESPONSIBLE FOR THE VIABILITY OF ALL PLANT MATERIAL FOR 2 YEARS AFTER COMPLETION OF PLANTING. DISEASED, DYING, OR DEAD PLANT MATERIAL SHALL BE REPLACED BY THE

CONTRACTOR DURING THE TWO YEAR PERIOD AND MAINTAINED FOR AN ADDITIONAL 2 YEAR PERIOD. \mid 13. \mid IMMEDIATELY UPON BID AWARD, CONTRACTOR SHALL SECURE THE PLANT MATERIALS AS \mid SPECIFIED FROM

- AVAILABLE SOURCES. IN THE EVENT THAT PLANT MATERIALS ARE NOT AVAILABLE, CONTACT LANDSCAPE ARCHITECT FOR APPROVED SUBSTITUTIONS. NO SUBSTITUTION FOR PLANT MATERIAL WILL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT.
- 14. TOP DRESS ALL SHRUB AND GROUND COVER AREAS (NOT LAWN) WITH 3" OF FIR BARK MULCH. SUBMIT SAMPLE TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO CONSTRUCTION.
- | 15. TREE LOCATIONS MAY BE ADJUSTED IN THE FIELD TO SUIT SITE REQUIREMENTS AS DIRECTED BY THE LANDSCAPE ARCHITECT.

- FULLY FLOODED WITH WATER SHALL DRAIN WITHIN (12) HOURS OF FILLING.
- 17. FINISH GRADE SHALL BE SET TO ALLOW POSITIVE DRAINAGE
- 18. ROTOTILL 2" OF COMPOST INTO ALL PLANTED AREAS. 19. INCORPORATE PEAT INTO THE ROOT ZONE OF RHODODENDRONS, AZALEAS AND OTHER ACID LOVING PLANTS.
- 20. INCORPORATE 10-20-20 FERTILIZER INTO THE ROOT ZONE OF ALL NEW PLANTINGS.
- 21. RONSTAR, OR APPROVED EQUAL, PREEMERGENT HERBICIDE TO BE APPLIED TO ALL PLANTED AREAS PER MANUFACTURERS INSTRUCTIONS.
- 22. EXISTING VEGETATION TO BE SPRAYED WITH ROUNDUP, OR APPROVED EQUAL, PER MANUFACTURERS INSTRUCTIONS. SUFFICIENT TIME SHALL BE GIVEN TO ALLOW EXISTING MATERIAL TO DIE. REMOVE EXISTING 27. THE PROPERTY OWNER IS RESPONSIBLE FOR MAINTAINING TURF PLANTED WITHIN THE RIGHT OF WAY.
- 23. CROWN LAWN AREAS AND GRADE TO PROVIDE POSITIVE DRAINAGE.
- 24. ROLL LAWN AREA TO INSURE PROPER COMPACTION TO MINIMIZE SETTLING. CONTRACTOR'S WORK, AT NO ADDITIONAL COST TO THE OWNER. CONTACT ALL UTILITY PROVIDERS SERVING THE 25. AMEND SOIL IN LAWN AREAS WITH 80 LBS. OF DOLOMITE LIME AND 40 LBS. OF IO-20-20 SLOW RELEASE
 - FERTILIZER OR EQUIVALENT. PROVIDE A 3" LAYER OF SANDY LOAM TOPSOIL FOR LAWN AND BED AREA. 26. SEED LAWN AREAS WITH GRASS SEED MANUFACTURER'S RECOMMENDATIONS. COVER SEED WITH FINE MULCH APPLIED WITH ROLLER OR HYDROSEED.
 - 27. THE PROPERTY OWNER IS RESPONSIBLE FOR MAINTAINING TURF PLANTED WITHIN THE RIGHT OF WAY. 28. PLANT MATERIAL SHALL BE PLANTED W/ ROOT CROWN I" ABOVE FINISHED GRADE TO ALLOW POSITIVE
 - DRAINAGE AWAY FROM CROWN. 29. STAKE ALL TREES OVER 6 FT. IN HEIGHT PER DETAILS ON THIS SHEET.
 - 30. REFER TO DETAILS FOR ADDITIONAL INFORMATION. 31. ALL PLANTING SHALL BE HAND WATERED OR IRRIGATED BY AN AUTOMATIC UNDERGROUND SPRINKLER SYSTEM.
 - 32. ALL PLANT MATERIALS FURNISHED ARE TO BE HEALTHY, UNIFORMLY BRANCHED AND WITH WELL DEVELOPED FIBROUS ROOT SYSTEMS. 33. ALL PLANT MATERIALS FURNISHED ARE TO BE FREE FROM DEAD OR BROKEN BRANCHES, LICHENS, SCARS,
 - BROKEN BARK OR WOUNDS. ALL PLANT MATERIALS WILL BE INSECT, WEED, AND DISEASE FREE ACCORDING TO THE REQUIREMENTS OF THE WASHINGTON STATE DEPARTMENT OF AGRICULTURE FOR NURSERY PLANT MATERIALS SOLD FOR WHOLESALE OR RETAIL. ALL PRUNING WOUNDS MUST BE WELL HEALED WITH NO
 - EVIDENCE OF DECAY. 34. FIELD CONFIRM ALL SITE CONDITIONS, AREAS AND SIZES PRIOR TO BIDDING \$ CONSTRUCTION. DO NOT SCALE FROM PLANS.

Planning Solutions, Inc Creating Solution to Complex Issue. 4400 NE 77th Avenue Suite 275 VANCOUVER, WA 9866

VOICE: 360-750-9000 FAX: 360-713-61

www.planningsolutionsinc.co