



SHEET NOTES

- CONTRACTOR MAY STAGE WITHIN LIMITS OF DEMOLITION.
- REMOVE ALL SITE COMPONENTS AND RECYCLE COMPONENTS AS REQUIRED IN THE SPECIFICATIONS.
- GENERAL DEMOLITION PERMIT SHALL BE SECURED BY THE CONTRACTOR.

- SAWOUT STRAIGHT LINES IN SIDEWALK, AS NECESSARY
- CONTRACTOR IS RESPONSIBLE TO CONTROL DUST AND MUD THE DEMOL INON PERIOD, AND DURING TRANSPORTATION OF DEMOL INDO DEBIS, ALL STREET SURFACE OUTSIDE THE CONSTRUCTION ZONE MUST BE KEPT CLEAN.
- DARK LINEWORK DEPICTS ITEMS WITHIN THE DEMOLITION / WORK LIMITS TO BE DEMOLISHED.
- 11. REFERENCE LANDSCAPE PLANS FOR TREE DEMOLITION.

SHEET LEGEND

DEMOLITION TO OCCUR AS PART OF BYBEE ROAD REALIGNMENT

♦ DEMOLITION KEY NOTES

- 23 REMOVE ASPHALT PAVEMENT
- 26 REMOVE UTILITY POLE AND GUY WIRE

- 29 REMOVE EXISTING SIGN

- DECOMMISSION SEPTIC TANK AND REMOVE ASSOCIATED INFRASTRUCTURE

- "40 PROTECT EXISTING MONUMENT
- 41 PROTECT EXISTING CULVERT



VANCOUVER WASHINGTON TEMPLE
THE CHURCH OF JESUS CHRIST OF LATTER-DAY SAINTS
1819 SE PROFEE DAY
CAMAS, WA 98607

AUGUST 2024 SITE PLAN REVIEW C1.0