Ad Hoc Committee to Study Depot Hill Bluff Pathway

Interim Report to City Council 23-October-2025


Agenda

- Summary of Current Situation
- History of Events and Studies of Depot Hill Bluff
 - Geological
 - Drainage
- Value of the pathway
- Options for Restoring a Pathway
- Current Situation
 - Pathway from Saxon to Oakland
 - Pathway from Central to Saxon

Current Situation - BLUF

- The unabated erosion of the Depot Hill bluff has resulted in failure and loss of the Grand Avenue pathway in two locations:
 - Between Oakland and Hollister (significant damage)
 - Between Saxon and Oakland (failure to edge of fencing, pathway temporarily closed)
- The Ad Hoc Committee studied options going forward
 - Inadequate storm drainage needs to be addressed
 - Pathway re-routing is possible

Overview of the Bluff



Photographs of Bluff Failures

Photo Credit: Snapshot taken from video shot on 19 April 2017, provided by Misha Bunch. Original video can be seen on Youtube at https://youtube/Yebbel/Pik






Oakland to Hollister section



Saxon to Oakland section

Timeline of Events and Studies



Value of the Pathway

- We don't have any hard data but here are the Committee's observations:
 - The pathway is a popular spot for both tourists and City residents
 - Estimate of 200 300 pedestrians per day on average
 - Some reduction in traffic after the bluff collapse between Oakland and Hollister in 2017
 - Significant increase in traffic during Covid 19 still remains substantial
 - Tourist traffic is still robust

Options for Re-storing the Bluff Pathway

- Do nothing
- 2. Move pathway onto the city's easement:
 - a. Improve drainage at Saxon Avenue & 302 Grand
 - b. Install pathway on the city's easement (8 houses)
 - c. Move fence to edge of pathway
 - d. Add simple retention system over the latest landslide (between 304 and 308 Grand)
- 3. Add reinforcement to the bluff at the top to protect the marine layer
- 4. Implement full Depot Hill drainage plan
- 5. Install a protective seawall

Options for Re-establishing the Bluff Pathway (1 of 2)

Option	Cost	Risks	Est.	Notes
			Life	
1.Do Nothing	Minor	Utilities would be damaged Potential risk to life Unpredictable erosion	0	Needs better barrier at each end of the pathway Utilities need to be addressed
2.Move pathway onto easement	\$	May only last a year or two	6	Drainage needs to be addressed to improve the life of the new pathway Utilities need to be addressed
Rein force Bluff	\$\$\$	Formation underneath will fail`		Requires study

Options for Re-establishing the Bluff Pathway

Option	Cost	Risks	Est. Life	Notes
4.Implement full drainage	Current estimate is \$2.4 M	May not solve the long term problem	TBD	Based on Study in 2008 where cost was \$800k
5.Install protectiv e seawall	\$\$\$\$	Coastal Commission approval	Long	Not likely to get CCC approval

Committee's Conclusion

- The Committee determined the only feasible solution is to move the pathway inland approx. 10 feet
 - Quickest and easiest solution
 - Least expensive option
 - Probably gets 5+ years out of the existing pathway
- Rough Estimate of City's Costs

Item	Cost Estimate (\$k)	Notes
Pathway Design	\$50.0	Based on SSA Landscape Architects Estimate
Netting Retention System	\$29.8	Based on Granite Construction Estimate
Pathway Materials	\$50.0	WAG
Labor	\$0.0	Assuming its feasible the work would be done by RAKC

Next Steps - simplified


- Fix the drainage outlet at the end of Saxon Avenue (complete)
- Get a landscape designer to create the pathway plans (see Appendix for quotes from SSA)
- Get approval from Public Works for these plans and the plans for the netting
- Order material and set a date for RACK to do the work
- Complete the pathway and the retention system
- Inspection by PW
- Open pathway to public

Appendix


References

- 1. Effects of the Santa Cruz Harbor on coastal processes of northern Monterey Bay, California, Griggs, G.B. and Johnson, R.E., 1976
- 2. Coastline Erosion: Santa Cruz County, Griggs, G.B. and Johnson, R.E., 1979
- 3. Geological Investigation, Depot Hill Geologic Hazard Abatement District, Rogers E. Johnson and Associates, April 2000
- 4. **Study of Depot Hill Storm Drainage, Harris & Associates, May 2007 (note: a map of proposed drainage system for Depot Hill with cost estimate provided in May 2008)
- 5. Depot Hill Drainline Installation, Haro & Kasunich, January 2010
- 6. **Limited Geological Investigation of coastal bluff failure Grand Avenue near intersection with Oakland Avenue and Hollister Avenue, Capitola, Zinn Geology, May 2017
- 7. **Limited Geological Investigation of coastal bluff failure Grand Avenue footpath near Intersection with Oakland Avenue and Saxon Avenue, Capitola, Pacific Crest Engineering Inc., June 2023
- 8. **Updated Geological Investigation of coastal bluff failure Grand Avenue footpath near Intersection with Oakland Avenue and Saxon Avenue, Capitola, Pacific Crest Engineering Inc., April 2025
- ** completed for the City of Capitola, Public Works Department

Netting Retention Concept



Similar concept installed on Bluff at Sacramento



Proposed Initial Study Work by SSATotal Estimate \$11,893

PHASE ONE -CONCEPTUAL DESIGN

- 1. Attend a kick-off meeting with the CLIENT to review the program and goals.
- Collect and review all available existing conditions and design information including City of Capitola design standards.
- 3. Initiate land surveyor to proceed with topographic survey
- 4. Prepare a base file in AutoCAD format
- 5. Prepare initial conceptual site plan to include the following program elements
 - a. Pathway location, configuration and material selections
 - b. Preliminary grades
 - Location of safety fence, previously designed and installed by community
- Present Conceptual Site Plan to CLIENT in one meeting.
- 7. Update Conceptual Site Plan based on CLIENT comments.
- Publish Final Conceptual Site Plan to CLIENT
- Coordinate and liaise with CLIENT via phone conference and emails.

Conceptual Design Phase Deliverables:

- Preliminary Conceptual Site Plan
- 2. Final Conceptual Site Plan
- One (1) project kick-off meeting with CLIENT
- 4. One (1) presentation meeting with CLIENT