

GLIDDEN

ROOFING CORPORATION

Town of Casco

To: Anthony Ward

From: Bill Cashman-Glidden Roofing

Date: August 3, 2026

Price: \$105,100.00 100% Completion

RE: 940 Meadow RD Casco Maine

Scope:

Owens Corning Duration Architectural Shingles- Color:

Install 8" Aluminum drip edge on all eaves & rakes- Color- White

Install Owens Corning Rhino Ice and Water Shield- Complete Roof

Install Synthetic underlayment- N/A

Install Owens Corning starter strips on all eaves

Install Owens Corning Pro edge & Ridge Vent on Ridge System

Install 6 nails per Shingle for 160 MPH wind rating

Install new .060 EPDM Roof System on High Flat Roof Area

Magnet property once job is completed

Tarp walls and grounds, Strip old shingles and haul away debris. Inspect all roof decking once shingles are stripped. Ice and Water Shield complete roof. Replace any roof boots around plumbing pipes.

ACCEPTED _____

DATE _____

William Cashman

