



P.O. Box 427 / 300 Bryan St. South Hill, VA 23970
O: 434-447-7331 / F: 434-447-5892 / E-Mail: dtanner@barkerconst.com

ESTIMATE

July 30, 2024

To: Town of Chase City
319 N. Main St.
Chase City, VA 23924

Attn: Mr. Timothy Bohannon

The following is a detailed outline of our proposed scope of work for the removal and replacement of road culvert that has failed on Ogburn St.

SCOPE OF WORK:

- Mark Designated Work Area w/ VA811 72 Hours Prior to Excavation
- Mobilization of Equipment
- Construct Temporary Cofferdam & Divert Water for Culvert Replacement
- Excavate & Remove Existing Road Culvert (Protect 6" Water Main & 2" Water Service Line in Work Area)
- Haul Existing Pipe / Unsuitable Soils Off-Site
- Grade Subbase for (2) New Culverts
- Furnish & Install VA #21A for Culvert Subbase
- Furnish & Install (2) 48" x 19'6" VDOT Grade Double Wall Polypropylene Culvert Pipe
- Furnish, Install & Compact VA #21A Stone Material for Backfill of New Culvert Pipes
- Compact VA #21A Stone Material w Vibratory Trench Compactor
- Form, Pour & Finish VDOT EW-7 for Inlet of Culverts w/ 10' Wing Walls
- Furnish & Install (2) Loads of Class A1 Rip/Rap Stone Material for Outlet Protection
- Fine Grade VA #21A Stone Material for Asphalt Base & Saw Cut Existing Asphalt for Tie-Ins
- Furnish, Place & Compact 3" of Asphalt Pavement on Roadway (18' x 60' Area)

ESTIMATE :\$57,445.00

We appreciate the opportunity to serve the Town of Chase City with its improvement needs. Please, for any questions or scheduling do not hesitate to give us a call anytime. We look forward to hearing from you and your project!

Best Regards,

Jamie A. Barker

Jamie A. Barker
President

J.A. Barker Construction, Inc.

Smiley's Construction, LLC

7877 Hwy One, South Hill, VA 23970

Office# 434-689-2344 or Jamie Smiley cell# 434-447-9286

Proposal and Acceptance 7/24/24

Submitted To: Town of Chase City
Attn: Tim

Job Name: Replace double 48" pipes – Repair Road
Location: Ogburn St.

Work Description

Labor, Equipment & Materials:

NOTE: Town to handle traffic control – shut down street

NOTE: If fill is not suitable, Town to supply suitable fill material

Sawcut asphalt, remove, excavate

Demo 2) 48" culverts damaged from storm

Dispose of old pipe, supply and install 120'

New HP 48" culvert – Double 60'

Cover and compact, Armor Outlet end with Geo Fabric

Suitable Rip Rap cover. Fill sand bags and place sand bags across branch

Set up pumps, Pump around while building

Concrete Wing Wall 8' tall on a 3' x 3' footing with 10' wings to include rebar in wall, 1' thick

Back fill wall with bill from Town Shop Yard, compact, place fabric and Rip Rap on Inlet side as needed
(Smiley's will haul RR)

Topsoil cover

Seed and straw mat, repave street over 1' Crush & Run compacted

Pavement Patch 4" x 25' x 20'

Remove sand bags and pumps

Date of Plan: TBD - to be scheduled upon approval

WE PROPOSE HEREBY TO FURNISH MATERIAL AND LABOR COMPLETE IN ACCORDANCE WITH ABOVE SPECIFICATIONS FOR THE SUM OF **\$78,750**

PAYMENT TO BE MADE AS FOLLOWS: Upon Completion Of Job

ACCEPTANCE OF PROPOSAL

AUTHORIZED SIGNATURE

Jamie Smiley

DATE OF ACCEPTANCE _____

DATE 7/24/24

PRICE GRADING & PAVING, LLC

5495 BASKERVILLE RD
 BASKERVILLE, VA 23915

Estimate

Date	Estimate #
7/24/2024	Proposal

Name / Address
Town of Chase City

Project

Description	Rate	Total
Proposal for Ogburn St Washout Demo old pipe and replace with two runs of HD (grey) 48" x 60'. Pour headway with 10' wings at invert and rip rap outvert. Compact red dirt fill to sub-grade Compact 8" of 21's stone. Lay 2" of asphalt over existing road dimension	80,000.00	80,000.00
Total		\$80,000.00