

CITY OF CHIPLEY

STAFF REPORT

SUBJECT: Request for a Development Order and a Variance – Corner of Watts Avenue and 7th Street – Serene Life Beer Garden

MEETING DATE

Thursday, January 29, 2026

PREPARED BY

Tamara Donjuan, Planning & Zoning Officer

SUMMARY

This will approve a Development Order and Variance for alcoholic beverages for Serene Life Beer Garden. This property requires Planning and Zoning and City Council approval due to the property being located in the Corridor Development District and a Variance for Alcoholic beverages. The property is located at Watts Avenue, Parcel ID:00000000-00-1328-0001, .28 acreage.

The proposed development will be an entertainment establishment and has been reviewed by the City's planning firm Kimley Horn and meets all standards for uses allowed, density and intensity, and design standards for Chapter 44 – Zoning, ARTICLE VI – District Regulations, Section 44-163- Corridor development district (CDD). The CDD shall consist of where the majority of commercial development has occurred in the past, and where such uses are planned to occur in the future. The purpose of the CDD is to provide higher standards for redevelopment of deteriorating and/or unattractive structures and signs. The purpose also includes providing more stringent standards for new development so that such development aesthetically blends with the small city character of Chipley.

A variance has been requested to allow alcoholic beverage sales for the property located at the corner of 7th Street and Watts Avenue, Parcel ID: 00-1328-0001. The property is located less than 500 feet of any residence.

Chapter 4, Alcoholic Beverages, Article II.-Establishments, Sec. 4-29 Location restricted; proximity to churches, public parks, residential dwellings, and schools; distance locations for bottle clubs, private clubs, and entertainment establishments; restrictions for established businesses. *1. Distance from dwelling or residence.* a. It shall be unlawful to sell beer, wine, or other alcoholic or intoxicating beverages for consumption on the premises within 500 feet of any residence, which distance shall be measured by measuring a radius from the main public entrance of the place or establishment. If any portion of a parcel of land used as a dwelling or residence lies within such radius, then the new establishment shall be deemed to be within such distance.

Notice of the public hearing was mailed on January 8, 2026, by certified mail to fourteen (14) property owners located within 300 feet of the property requesting the variance, located on Watts Avenue, Parcel ID:00000000-00-1328-0001, .28 acreage. Of the fourteen (14) notices mailed, twelve (12) property owners have signed and returned the certified mail receipts..

According to Fema's National Flood Hazard Layer (NFHL) data maps approximately 100% of the property is in Flood Zone "X", which is an area of minimal flood hazard.

Granting the development to include a variance will be in harmony with the general intent and purpose of the Code and that such development to include a variance will not be injurious to the surrounding area. The variance granted is the minimum that will make possible the reasonable use of the new development as an entertainment establishment.

The City Council will meet February 10, 2026, at 5:00 p.m. to review the recommendation.

RECOMMENDATION

City Staff recommends approval of the development order and variance for alcoholic beverages to promote the growth and success of the downtown area with offering additional entertainment to our community.

ATTACHMENTS

1. Development Packet
2. Variance Request

DATE: 1/23/2025

TO: Patrice Tanner, City Administrator, City of Chipley

CC: Tamara Donjuan, Code Enforcement/Planning and Zoning Officer, City of Chipley

FROM: Hadley Peterson, Community Planner

PROJECT: Chipley IPO 25-01 Development Review 02

Development Order Application

Kimley-Horn performed a development review for the proposed Serene Life Beer Garden development. The property is located at the corner of Watts Avenue and 7th St, Chipley, Florida and is in the Commercial zoning district. The purpose of the review is to identify whether the proposed development is consistent with Part II of the City of Chipley Code of Ordinances. Deficiencies of the applications are indicated in red throughout this memo based on the application materials provided.

Additional submissions were made for this project, prompting a review of the following application types:

- Land Use Compliance Certificate Application;
- Application for Certificate of Appropriateness;
- Variance Request for the Sale of Alcohol in Proximity to Residential;
- Sign Application; and
- Application for Concurrency Review.

The applicant provided a re-submission addressing all deficiencies in November 2025.

Development Order Application Review

Chapter 36 – Subdivisions, [Article III. - Plat, Plan Approval Procedure](#), Sec. 36-52. - Submittal of general site plans and data.

The proposed plat design and development plans shall be reviewed and approved by the zoning commission in two stages. In the first stage, the subdivider is required to submit only general site plans and data which shall include, but not be limited to, the following:

(1) Topographic data. The topographic data shall include existing conditions as follows:

- Boundary lines, street lines and block lines.* Bearing and distances; easements; locations, widths and purposes.

Sufficient: *Provided in Plan Set: 1A*

Streets on and adjacent to tract. Names and right-of-way widths and locations; types; width and elevation of surfacing; any legally established centerline elevations; walks, curbs, and gutters, etc.

Sufficient: *Provided in Plan Set: 1A and 2A*

- b. *Utilities on and adjacent to the tract.* Locations, sizes and invert elevations of sanitary, storm and combined sewers; locations and sizes of water mains; locations of gas lines, fire hydrants, electrical and telephone poles, and streetlights; if water mains or sewers are not on or adjacent to the tract, indicate the direction and distance to the site of nearest ones, showing invert elevations of sewers.

Sufficient: *Provided in Plan Set: 3B*

- c. *Ground elevation on the tract.* Based upon a datum plane approved by the city clerk, for land that slopes approximately less than two percent, show spot elevations at all breaks in grade, along all drainage channels or swales, and at selected points not more than 100 feet apart in all directions; for land that slopes approximately more than two percent, either show contours with an interval of not more than five feet if ground slope is regular and such information is sufficient for planning purposes, or show contours with intervals of not more than two feet if necessary because of irregular land or the need for more detailed data for preparing plans and construction drawings.

Sufficient: *Provided in Plan Set: 1A and 3A, Topo Map Attachment*

- d. *Title and certificates.* Present land tract designation according to official records in the office of the appropriate recorder; title under which the proposed subdivision is to be recorded, with names and addresses of owners, notation stating acreage, scale, north arrow, datum, benchmarks, certification of a registered civil engineer or surveyor, and date of survey.

Sufficient: *Provided in DO Forms Attachment; Plan Set: Cover, 2A*

- (2) The following data may be required of the applicant by the zoning commission, contingent upon special conditions of the site and/or proposal:

- a. Subsurface conditions on the tract, when required by the zoning commission. Location and results of tests made to ascertain subsurface soil, rock and groundwater conditions; depth to groundwater unless test pits are dry at a depth of five feet; location and results of soil percolation tests if individual sewage systems are proposed.

Conditional: *This subsection may be required by zoning commission and is provided in document Maps: Soil Map Attachment.*

Other conditions on the tract. Watercourses, marshes, rock outcrops, wooded areas, isolated preservable trees one foot or more in diameter, houses, barns, shacks and other significant features.

Conditional: *This subsection may be required by zoning commission and no watercourses, marshes, rock outcrops, wooded areas, or isolated are reported in the provided documentation.*

- b. Other conditions on adjacent lands. Approximate direction and gradient of ground slope, including any embankments or retaining walls, character and location of buildings, railroads, power lines, towers and other nearby nonresidential land uses or adverse influences; owners of adjacent unplatted land; for adjacent platted land, refer to the subdivision plat by name, recordation data, and number and show approximate percentage built up, typical lot size and dwelling type.

Conditional: *This subsection may be required by zoning commission and conditions of adjacent lands are not included in the provided documentation.*

- c. Photographs, when required by the zoning commission. Location of cameras, direction of views, and key numbers.

Sufficient: *Photograph examples of the intended use of the proposed development are included in the applicant submission.*

- d. Zoning on and adjacent to the tract. Proposed public improvements; highways or other major improvements planned by public authorities for future construction on or near the tract.

Conditional: *This subsection may be required by zoning commission and is not provided within the submitted Plan Site.*

- e. Key plan showing the location of the tract.

Sufficient: *This subsection may be required by zoning commission and therefore it is important to note that this is provided in Plan Site: Cover.*

Specifications, Minimum Standards | Chapter 36 – Subdivisions, [Article IV, Specifications, Minimum Standards](#)

Sec. 36-93. - Suitability of land.

- (a) The zoning commission shall not approve the subdivision of land if, from investigation conducted by state or county health authorities, it is determined that in the interest of the public, the site is not suitable for platting and development purposes of the kind proposed.

Sufficient: *There is no evidence to suggest that the proposed site is unsuitable for the proposed development.*

- (b) Land that is subject to flooding conditions as determined by the state department of health and land that is determined by the zoning commission to be topographically unsuitable shall not be platted for residential occupancy, nor for such other use as may endanger health, life or property, or aggravate erosion or flood conditions.

Sufficient: *There is no evidence to suggest that the proposed site is particularly sensitive to flooding based on the elevations depicted in the Topo Map Attachment. The site is not located in a flood zone as identified by the FEMA Flood Zone Map Service Center.*

Fire Prevention and Protection | Chapter 16

Sec. 16-10. - Review of fire protection plans.

- (a) When plans are submitted to the city for approval of proposed subdivisions, mobile home parks, multifamily dwellings, recreation or vehicle parks, commercial buildings or other structural developments, the fire chief or the fire chief's designee shall review the proposed fire protection provisions in accordance with recognized practices. All buildings shall be conspicuously marked with identifying address numbers of not less than three inches in height on all new or existing structures.

Sufficient: *All necessary spaces—including the bathrooms, nano brewery and cooler— have been adequately accounted for in the fire flow calculations.*

- (b) The following hydrant specifications are considered minimal, and the fire chief or the fire chief's designee may require a higher level of fire protection for specific developments:
 - (1) All fire hydrants shall conform to the following:
 - a. Hydrants shall be accessible at all times, with hose connections readily available.
 - b. Parking shall not be permitted within 15 feet of any hydrant or post indicator valve.
 - c. Hydrants shall be painted for high visibility.
 - d. Hydrants shall be set with the lowest hose connection at least 18 inches above the finished grade.
 - e. All hydrants shall have at least one 4½-inch outlet and one 2½-inch outlet.
 - (2) Fire hydrants in single-family subdivisions shall be spaced at a distance of not more than 500 vehicular travel feet between hydrants.
 - (3) Fire hydrants in industrial, commercial or multifamily developments, mobile home parks, recreational structures for public congregations, and other high-value sites shall be spaced at a distance of not more than 300 vehicular travel feet between hydrants.

Sufficient: *The fire hydrants located on the corners of Watts and Main Street; as well as Watts and Martin Luther King St, are both within 300 feet of the corners of the property.*

Land Use Compliance | Chapter 44 – Zoning, [Article VI – District Regulations](#), Sec. 44-151. - Commercial land use classification.

- (1) Commercial: The purpose of commercial land use is to provide the community and region with commercial uses to encourage compact development of integrated commercial centers and districts, to serve the traveling public with highway commercial areas, and to provide adequate areas for commercial development and redevelopment in order to support economic development within the city.

Sufficient: *The beer garden achieves the purpose of Commercial by providing and integrating for an appropriate commercial development that supports the economic development of the city that serves the traveling public.*

- (2) Intensity: Maximum lot coverage of 85 percent of total gross acreage of a parcel, including buildings and impervious surfaces.

Sufficient: *The proposed site intensity is 34%.*

- a. Uses: Commercial land uses include:
1. retail sales and services;
 2. business and professional offices;
 3. commercial lodgings;
 4. wholesale trade and services;
 5. places of worship;
 6. neighborhood commercial uses; and
 7. public utilities.

Neighborhood commercial land uses may be required by the city council in transitional areas.

Sufficient: *The beer garden, with proposed brewery, achieves the purpose of Commercial by fulfilling a retail service.*

- (3) Requirements:

- a. Maximum lot coverage: 85 percent.

Sufficient: *The proposed site intensity is 34% and the impervious surface ratio is 40%.*

- b. Building setback:
1. Front: 27 feet.

Sufficient: *The proposed front setback exceeds the required 25 feet.*

2. Side: W Side 10 feet; E side 18 feet.

Sufficient: *The proposed site exceeds the West side 10 feet setback; and the 7.5 feet East side setback.*

3. Rear: 5 feet.

Sufficient: *The proposed rear setback is 5 feet.*

Chapter 4 – Alcoholic Beverages, Article II. – Establishments, Sec, 4-29. – Location restricted; proximity to churches, public parks, residential dwellings, and schools; distance locations for bottle clubs, private clubs, and entertainment establishments; restrictions for established businesses.##

#

- (1) Distance from dwelling or residence.

- a. It shall be unlawful to sell beer, wine, or other alcoholic or intoxicating beverages for consumption on the premises within 500 feet of any residence, which distance shall be measured by measuring a radius from the main public entrance of the place or establishment. If any portion of a parcel of land used as a dwelling or residence lies within such radius, then the new establishment shall be deemed to be within such distance.

- (2) Distance from schools. Nothing herein shall amend, alter, affect, or reduce F.S. § 562.45(2) as it pertains to the sale of alcoholic or intoxicating beverages in relational distance to public or private schools. For measurement purposes, the distance shall be measured by measuring a radius from the main public entrance of the place or establishment. If any portion of a parcel of land used as a school lies within such radius, then the new establishment shall be deemed to be within such distance.

- (3) Distance locations for bottle clubs, private clubs, and entertainment establishments. It is unlawful for any licensed alcoholic beverage bottle club, private club, or entertainment establishment to operate, barter, sell, give away, exchange or otherwise dispose of in the nature of a gift or exchange alcoholic and intoxicating liquors for consumption on the premises where sold, bartered, exchanged, given away or disposed of within 1,000 feet of any church, public park, residence or school. The distance shall be determined by measuring a radius from the main public entrance of the place or establishment. If any portion of a parcel of land in use as a church, public park, residence or school facility lies within such radius, then the church, public park, residence or school shall be deemed to be within such distance. This provision shall not apply to brewpubs, micro-breweries, micro-distilleries, micro-wineries or event venues.

Sufficient: *The subject site is within 500 feet of residential and has submitted a variance application for the sale of alcohol. Properties within 300 feet of the subject site have received notice from the City of Chipley for the variance requested for these criteria.*

Concurrency Review Requirements

Chapter 14 - Environmental and Natural resources, Article VIII. – Stormwater Management, Sec. 14-189. - Stormwater management requirements.

The following local design criteria shall be used in the city:

(1) Performance standards.

- a. Discharge. A storm event of 24-hour duration and 25-year return frequency shall be used in computing allowable off-site discharge. Off-site discharge shall be limited to pre-development levels or the first one inch of rainfall, whichever is less, unless an engineering analysis using professionally accepted methodologies demonstrates that a differing discharge rate should be used. In requiring a lesser rate of discharge, the burden of analysis shall be the responsibility of the city. In requesting a larger rate of discharge, the burden of analysis shall be the responsibility of the developer.
- b. Stormwater facilities. All development shall provide stormwater facilities that provide retention, or detention with filtration, of the runoff from the first one inch of rainfall; or as an option for projects with drainage areas less than 100 acres, provide for the retention, or detention with filtration, of the first one-half inch of runoff.

(2) Design standards.

- a. The design standards required by the state shall be used in the design and construction of stormwater management facilities.
- b. Dredging, clearing of vegetation, deepening, widening, straightening, stabilizing or otherwise altering natural waters shall be minimized.
- c. Natural surface waters shall not be used as sediment traps during or after development.
- d. A vegetated buffer of at least 30 feet shall be retained or created along the shores, banks or edges of all manmade or natural surface waters.

Sufficient: *The proposed stormwater facilities successfully offsets the 3,771 square feet of impervious area based on the data submitted in the: Calcs – Stormwater Management Attachment document.*

Chapter 28 – Planning, Article III. – Concurrency Management, Sec. 28-53 – Concurrency Review

(a) *Evaluation.*

(1) *Roads.*

- a. *Generally.* The evaluation for roads shall compare the existing level of service standards to the adopted level of service standards established by the city's comprehensive plan for the impacted roads. The level of service shall be determined for conditions on the existing roads, to include any committed or funded improvements to those roads, meeting the minimum requirements for concurrency set forth below.

Sufficient: *The development is not expected to significantly impact the surrounding roadway network.*

- b. *Submittals.* The applicant for a development permit shall submit to the city, along with the application for a development permit, the following information:

- 1. The legal description of the development site;

Sufficient: *A legal description of the proposed development site is provided in: DO Forms – Attachment.*

The street address of the development site, if applicable;

Sufficient: *A street address of the proposed development site is provided in: DO Forms – Attachment.*

2. A written statement indicating the nature and extent of proposed development.

Sufficient: *A written statement is provided in: DO Forms – Attachment.*

c. *Transportation study.*

1. *Application meeting.* An application meeting between the city and the applicant is required. The purpose of this meeting will be to review the methodology and procedure, and to determine the study area and study period. This will usually be a p.m. peak hour analysis, however, other time periods may require analysis. The transportation study shall be signed and sealed by a registered professional engineer.

Sufficient: *The development is not expected to significantly impact the surrounding roadway network. No meeting is necessary.*

2. *Define study area.* The study area is defined as the primary impact area affected by traffic associated with the site. A radius around the site will be established based on the average trip length associated with the land use, as set forth in the trip characteristics for that land use as approved by the city. The primary impact area will be approved by the city at the application meeting.

Sufficient: *The development is not expected to significantly impact the surrounding roadway network. No meeting is necessary.*

3. *Existing conditions.* The following existing conditions shall be provided based on the application review:

- (i) Existing peak hour traffic volumes and level of service on all collectors and arterials within the study area.

Sufficient: *The development is not expected to significantly impact the surrounding roadway network.*

- (ii) Existing turning movement volumes at the impacted intersection and intersection level of service.

Sufficient: *The development is not expected to significantly impact nearby intersections.*

Sources of data.

- (i) The above required data shall be no older than the previous calendar year. Volumes shall be adjusted to reflect annual conditions using current Florida Department of Transportation (FDOT) seasonal adjustment factors for the city or other adjustment factors approved by the city.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

The above required level of service for roadways shall be determined in accordance with the adopted level of service of the city given in the traffic circulation element of the city's comprehensive plan.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

- (ii) The above required intersection capacities shall be based on the most recent edition of the Highway Capacity Manual, Special Report 209.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

- 4. *Projection of future roadway traffic.* Roadway volumes shall be projected for each development phase including the year of the project completion. Volumes can be determined using one of the following procedures:

- (i) Multiplying existing volumes by the annual growth factor provided by the city. Traffic generated by any major project approved since the traffic counts shall be included as background traffic.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

- (ii) Multiplying existing volumes by an annual growth factor developed by the applicant and approved by the city. Traffic generated by any major project approved since the traffic counts were conducted shall be included as background traffic.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

- (iii) Using projections from an area modeling effort.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

- (iv) Methodology regarding projection of intersection turn movements and level of service shall be established at the application conference.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network.*

5. *Projection of traffic generation.* The following procedures and information shall be provided:

- (i) To determine project traffic generation, the trip characteristics table shall be used, or trip rates may be obtained from studies of comparable sites in the city or standards adopted by the city, and are subject to the approval of the city.

Sufficient: *Trip rates were obtained from the ITE Trip Generation Manual (11th Edition).*

- (ii) Identify all land use codes, amount of development and trip rates.

Sufficient: *The trip generation was revised in the resubmitted study.*

- (iii) Any proposed reduction factors for internal capture of trips between land uses of a mixed-use project or for passerby trips shall be provided by the applicant at the application/methodology meeting and approved by the city.

Sufficient: *Internal capture is not applicable to this site development.*

6. *Projection of traffic distribution/assignment.* Project traffic distribution shall be based on reasonable and acceptable industry assumptions and methodologies as applied to the individual site conditions to be approved by the city in the application meeting.

Sufficient: *A distribution of generated trips was provided in the resubmitted study. Generated trips are not expected to significantly impact the surrounding roadway network.*

7. *Transportation system management strategies.* A discussion of any proposed transportation system management strategies shall be included in the study.

Sufficient: *Generated trips are not expected to significantly impact the surrounding roadway network, and therefore no discussion of transportation management strategies is required.*

(2) *Potable water.*

a. *Submittals.* The applicant for a development permit shall submit, along with the application for a development permit, proof that sufficient capacity exists as demonstrated by one of the following:

- 1. If the service provider is other than an on-site potable water well, documentation will be required from the provider that the project is within its service area and that it has the capacity to serve the project as proposed, at or above the adopted level of service. If the ability of a provider to serve a proposed project is contingent upon planned facility expansion, details regarding such planned improvements shall also be submitted. Prior to the issuance of a development order by the city, the applicant may be required to provide evidence of a contract with the service provider, indicating the provider's commitment and ability to serve the proposed project;

Sufficient: *The subject site is within the potable water service area as confirmed by a notarized affidavit.*

2. Permits issued by the Northwest Florida Water Management District for a potable water well to serve the development;

Conditional: *Northwest Florida Water Management District permits are required to be provided to the City upon issuance.*

3. A notarized statement or affidavit that there is an existing functioning potable water well on the site.

Sufficient: *A notarized affidavit signed by Sherry Snell was provided, declaring sufficient water supply and utilities on site.*

(3) *Wastewater.*

- a. **Submittals.** The applicant for a development permit shall submit, along with the application for a development permit, proof that sufficient capacity exists as demonstrated by one of the following:

1. If the proposed service provider is other than an on-site septic system, documentation will be required from the provider that the project is within its service area and that it has the capacity to serve the project as proposed, at or above the adopted level of service. If the ability of a provider to serve a proposed project is contingent upon planned facility expansion, details regarding such planned improvements shall also be submitted. Prior to the issuance of a final development order by the city, the applicant may be required to provide evidence of a contract with the service provider indicating the provider's commitment and ability to serve the proposed project;

Sufficient: *A notarized affidavit signed by Sherry Snell was provided, declaring all needed utilities shall be provided by the City.*

2. All applicable state health department permits for an on-site septic system, pursuant to F.A.C. 64E-6, are obtained; or

Conditional: *It is noted that the proposed development will be provided sanitary sewer service by the City.*

3. Proof the city impact fees for the provision of a wastewater system have been paid.

Conditional: *City impact fees or payment for sanitary sewer service for the proposed development are required to be paid prior to building permit.*

(4) *Drainage.*

- a. **Submittals.** The applicant for a development permit shall submit, along with the application for the development permit, proof that sufficient capacity exists as demonstrated by one of the following:

4. All applicable department of environmental protection (DEP) permits for stormwater management systems;

Sufficient: *A DEP permit of “SELF-CERTIFICATION FOR A STORMWATER MANAGEMENT SYSTEM IN UPLANDS SERVING LESS THAN 10 ACRES OF TOTAL PROJECT AREA AND LESS THAN 2 ACRES OF IMPERVIOUS SURFACES,” was successfully submitted and complies with necessary stormwater management systems.*

5. All applicable department of transportation (DOT) permits for drainage connections, pursuant to F.A.C. 14-86 are obtained; and/or

Conditional: *FDOT permits for drainage connections are required to be provided to the City upon issuance.*

6. All applicable Northwest Florida Water Management District (NFWFMD) permits, pursuant to F.S. §§ [373.451 through 373.4595](#) (the Surface Water Improvement SWIM Act) are obtained.

Conditional: *NFWFMD permits are required to be provided to the City upon issuance.*

(5) *Solid waste.*

- a. *Submittals.* The applicant for a development permit shall submit, along with the application for the development permit, proof that sufficient capacity exists as demonstrated by one of the following:
 1. Documentation will be required from the provider that the project is within its service area and that it has the capacity to serve the project as proposed, at or above the adopted level of service. If the ability of a provider to serve a proposed project is contingent upon planned facility expansion, details regarding such planned improvements shall also be submitted.

Sufficient: *A notarized affidavit signed by Sherry Snell was provided, declaring all needed utilities shall be provided by the City.*

2. Prior to the issuance of a development order by the city, the applicant may be required to provide evidence of a contract with the service provider, indicating the provider's commitment and ability to serve the proposed project; or

Sufficient: *A notarized affidavit signed by Sherry Snell was provided, declaring all needed utilities shall be provided by the City.*

- (6) *Recreation and open space; city-wide presumption of available capacity.* Based upon the data and analysis contained in the city's comprehensive plan, adequate capacity exists for the estimated demand for park and open space facilities. Therefore, a presumption of available capacity for all development shall be rendered by the city for the period beginning September 1, 1991, through the submission of the first concurrency management system annual report. At such time, the available capacity for park and open space shall be re-assessed, and a determination made as to whether the presumption of available capacity is to be continued.

Sufficient: *This requirement is not applicable to the proposed development.*

Sign Application Review Requirements

Sign Application and Permit Requirements | Chapter 30 – Signs.

NOTE: Two signs are included in the application materials. No details about where both signs will be located is provided. There is only one sign allowed along frontage more than 300 feet.

Sec. 30-9. - Design, construction and location standards.

(a) *Compliance with building and electrical codes required.* All permanent signs, and the illumination thereof, shall be designed, constructed and maintained in conformity with applicable provisions of the building and electrical codes adopted by the city.

(b) *Illumination standards.*

(1) Sign lighting may not be designed or located to cause confusion with traffic lights.

Sufficient: *The illuminated sign does not appear to be designed in any way to cause confusion with traffic lights.*

(2) Illumination by floodlights or spotlights is permissible so long as none of the light emitted shines directly onto an adjoining property or into the eyes of motorists or pedestrians using or entering public streets.

Sufficient: *The illuminated sign does not appear to be designed in any way that would emit excessive light onto adjoining properties, motorists or passing pedestrians.*

(3) Illuminated signs shall not have lighting mechanisms that project more than 18 inches perpendicularly from any surface of the sign over public space.

Sufficient: *The illuminated sign's dimensions indicate that it will not project more than 18 inches perpendicularly over public space.*

(c) *Placement standards.*

(1) *Near street and/or driveway intersections.* No sign shall be erected within a visibility triangle in such a manner as to materially impede vision between a height of two feet and ten feet above grade. The clear visibility triangle shall be formed by connecting a point on each street centerline, to be located at the distance from the intersection of the street centerlines indicated below, and a third line connecting the two points. The clear visibility triangle distance from the intersection of the street centerlines for the various road classifications shall be as follows: (depicted in Table 30-2: Visibility Triangle Distance From Intersection of Street Centerlines)

Sufficient: *The proposed sign does not impede a visibility triangle and is compliance with the set standards, according to Plan Sheet 4.*

- (2) *In right-of-way.* Supports for signs or sign structure shall not be placed in or upon a public right-of-way or public easement, except under the terms of a lease between the owner of the easement or right-of-way and the owner of the sign.

Sufficient: *The proposed sign does not intersect any public right-of-way or public easement, according to Plan Sheet 4.*

- (3) *Over right-of-way.* No ground sign shall project over a public right-of-way.

Sufficient: *The proposed sign does project over public any right-of-way, according to Plan Sheet 4.*

- (4) *Blocking exits, fire escapes, etc.* No sign or sign structure shall be erected that impedes use of any fire escape, emergency exit or standpipe.

Sufficient: *The proposed sign does not impede any use of fire escape, emergency exit or standpipe, according to Plan Sheet 4.*

- (d) *Clearance standards.*

- (1) *Over pedestrian ways.* All signs over pedestrian ways shall provide a minimum of nine feet of clearance.

Sufficient: *The proposed sign does not intersect any pedestrian ways, according to Plan Sheet 4.*

- (2) *Over vehicular ways.* All signs over vehicular ways shall provide a minimum of 13 feet, six inches of clearance.

Sufficient: *The proposed sign does not intersect any vehicular ways, according to Plan Sheet 4.*

- (e) *Relationship to building features.* A building sign shall not extend beyond any edge of the surface to which it is attached nor disrupt a major architectural feature of the building.

Sufficient: *Both renderings of the signs is not depicted to disrupt any major architectural features or extend beyond the edge of the surface to which it is attached.*

- (f) *Maximum projection.* A building sign may project no more than four feet perpendicularly from the surface to which it is attached.

Sufficient: *The proposed sign does not project from the surface, according to Plan Sheet 4.*

- (g) *Maximum window coverage.* The combined area of permanent and temporary signs placed on or behind windows shall not exceed 25 percent of the total window area at the same floor level on the side of the building or unit upon which the signs are displayed.

Sufficient: *The proposed sign is not depicted as a window sign or in a way where the sign obstructs windows.*

- (h) *Format for multiple-occupancy complexes.* Building signs for multiple-occupancy complexes constructed or remodeled after the effective date of the ordinance from which this chapter is derived shall conform to an approved sign format. The sign format shall be included as a submittal for authorization to erect such a sign and shall be maintained on file in the planning and zoning department. The format shall be presented in a plan or sketch, together with written specifications in sufficient detail to enable the city building official to authorize signs based on the specifications. At a minimum, the sign format shall specify the types of signs and dimensions (not to exceed the size limits contained in this chapter) which will be permitted to each occupant within the complex. The sign format shall also contain common design elements, such as placement, color, shape or style of lettering, which lend a unified appearance to the signs of the occupants within the complex. The sign format may only be modified with the approval of the director upon submission of a revised plan and specifications detailing the revised format.

Sufficient: *The proposed development is not a multiple-occupancy complex or similar development.*

- (i) *Signs required to be certified by a state-registered engineer.* The following signs shall be designed and certified by a state-registered engineer:

- (1) Building signs that project perpendicularly from the surface to which it is attached and that are more than 24 square feet in area.
- (2) Ground signs of more than eight feet in height and 48 square feet in area.

Sufficient: *The proposed sign is 40 square feet in area and does not exceed 8 feet in height, according to Plan Sheet 4.*

Variance Application Requirements

Article XI – Variances

Pursuant to Sec. 44-289 the applicant submitted a variance application on January 20, 2026. This was reviewed against the requirements listed in Sec. 44-290. All application requirements have been met by the applicant and the City.

Pursuant to Sec. 44-290, the petition for a variance to the land development code shall be evaluated based on the below determinations:

- (1) That the proposed variation does not constitute a change in the districts shown on the zoning map;

No zoning district will be changed with this variance.

(2) That the proposed variation will not significantly increase congestion in the public streets nor impair the public safety;

There will be no increased congestion or public safety concerns with this variance.

(3) That the proposed variation will not impair the established values of property in the surrounding area;

Property values will not be impaired by this variance.

(4) That special conditions and circumstances exist which are peculiar to the land, structure or building involved and which are not applicable to other lands, structures or buildings in the same zoning district;

The special condition of the building of the subject development is that is a non-alcoholic brewery. The City of Chipley Land Development Code does not provide requirements for or exceptions to the code as it relates to non-alcoholic breweries. There are no other non-alcoholic breweries within the same zoning district.

(5) That the special conditions and circumstances do not result from the actions of the applicant;

It is not due to the actions of the applicant that non-alcoholic breweries are not addressed in the Code.

(6) That granting the variance requested will not confer on the applicant any special privilege that is denied by the Code to other lands, buildings or structures in the same zoning district;

No special privileges will be granted to this applicant. There are other parcels within the zoning district that sell alcoholic and non-alcoholic beverages like beer, wine, and kombucha.

(7) That literal interpretation of the provisions of the Code would deprive the applicant of rights commonly enjoyed by others in the same zoning district under the terms of the Code and would work unnecessary and undue hardship on the applicant;

The Code prohibits alcohol sales within 500 feet of residential but does not consider non-alcoholic beverage sales as part of brewpub establishment. There are other parcels within the zoning district that have alcoholic and non-alcoholic beverage sales.

(8) That the variance granted is the minimum variance that will make possible the reasonable use of the land, building or structure;

This variance will allow for alcoholic beverage sales for beverages with less than 0.5% alcohol content.

(9) That the grant of the variance will be in harmony with the general intent and purpose of the Code and that such variance will not be injurious to the area involved or otherwise detrimental to the public welfare.

The use of a non-alcoholic and under 0.5% alcoholic beverage “brewpub” aligns with the intent and purpose of the City’s Code.

City of Chipley Development Order

File No. _____

Fees Paid \$ _____

Name of Owner: ANTHONY THOMPSON

Phone #: (931) 378-2723

Address: 4731 WHITEWATER LN, CRESTVIEW, FL 32539

Name of Developer/Contractor: AGENT/ENGINEER ELISSA PETTIS, TRI STATE COMPANIES LLC

Address: 834 KIRKLAND ROAD, CHIPLEY, FL 32428

Phone #: (850) 420-9922

Type of Development: COMMERCIAL

Parcel Size: 0.36 AC

Location of Development: SOUTHWEST OF WATTS AVE AND 7TH ST INTERSECTION

Land Use Designation: COMMERCIAL

Sq. Ft. of Building SEE ATTACHED

Site Plan Required? Yes ☒ No ☐

Stormwater Permit Required? Yes ☒ No ☐

City Utilities Needed? Potable Water ☒ Waste Water ☒ Natural Gas ☐ Garbage ☒

Attachments to Order: 1. _____ 2. _____

3. _____ 4. _____

Date of Planning & Zoning Commission Approval: _____

Date of City Council Approval: _____

Contingencies/Conditions of Approval: _____

The City Council hereby authorizes the development of land within the City of Chipley, Florida, as specified herein. Any development undertaken pursuant to this order shall be in strict conformance with the application for development approval and site plans) as approved by the City.

Signature – City Administrator _____

Date _____

Attest _____

Date _____

Owner/Developer/Contractor: _____


AGENT/ENGINEER: ANTHONY THOMPSON

SEAL

ZONING CHANGE OR VARIANCE REQUEST

FEE: \$

Any applicant requesting a particular service specified herein shall make formal application to the City and shall pay the appropriate fee. No portion of the appropriate fee shall be refunded whether the request is withdrawn by the applicant or denied or granted by the City of Chipley.

Date 12/15/2025 Applicant's Name: Anthony W. Thompson

Phone 931-378-2723 Address: 0000 Watts Avenue, Chipley, FL 32428

Parcel ID: 00000000-00-1328-0001

Present Zoning Category of Property: Commercial

Requested Zoning of Property: _____

Property is: Developed _____ Undeveloped ☒

ADDRESS OR DESCRIPTION OF PROPERTY TO BE CONSIDERED: Lots 11 and 12,
less the West 33 feet of Lot 12 in the City of Chipley

TYPE OF REQUEST: Zoning Change () Variance ☒

REASON FOR REQUEST: In order to sell alcohol due to
proximity to residential.

SUPPORTING DOCUMENT(S): _____

Anthony W. Thompson
Signature of Applicant

12/15/2025
Date

CITY STAFF USE ONLY

Is the proposed zoning change consistent with the Comprehensive Plan? () Yes () No

Are proposed development plans consistent with the Comprehensive Plan? () Yes () No

Are proposed development plans compatible with the surrounding community? () Yes () No

Certified copy of property deed attached? () Yes () No

Legal Advertisement for public hearing scheduled for: _____

Map prepared: _____

Site Visit Performed: _____

Staff Summary Prepared: _____

APPLICATION REVIEWED BY: _____



Our goal is to have a nano brewery that produces small batches of non-alcoholic beer with a very small, craft-scale brewing operation focused on making alcohol-free or non-alcoholic (0.1%-0.5%) beer with an emphasis on experimentation, quality, and local or niche markets.

Here's a clear breakdown:

A nano brewery is the smallest category of commercial brewery.

- Produces very small batches (often 1–5 barrels per batch, sometimes even less)
- Typically run by one person or a small team
- Often experimental, flexible, and craft-focused
- We will sell directly to the consumer by means of a taproom

Non-alcoholic (NA) beer generally means:

0.0%–0.5% ABV (depending on country regulations)

Our nano brewery may use one or more of these methods:

- Restricted fermentation – stopping yeast early so alcohol doesn't form
- Special yeast strains – produce flavor without much alcohol

A nano NA brewery focuses specifically on brewing beer that:

- Tastes like traditional beer
- Has little to no alcohol
- Appeals to people who want the beer experience without intoxication

A nano non-alcoholic brewery typically:

- Produces small, seasonal, or experimental batches
- Focuses on craft quality, not mass production
- Creates distinct flavors (IPAs, stouts, sours, botanical beers)
- Serves a growing market of:
 - Health-conscious consumers
 - Designated drivers
 - Athletes
 - People avoiding alcohol for personal or cultural reasons

What Makes it Unique

A nano brewery produces small batches of non-alcoholic beer. It is a tiny craft brewery that specializes in alcohol-free beer, made in limited quantities with a focus on taste, creativity, and quality rather than volume. We will also work with a local distributor to provide an array of non-alcoholic beers and other beverages such as:

- Non-alcoholic IPA – hoppy, bitter, citrus-forward
- Non-alcoholic Stout – dark, roasted, coffee or chocolate notes
- Non-alcoholic Wheat Beer – light, smooth, slightly fruity
- Hop Water – carbonated water infused with hops (0.0% ABV)
- Kombucha (often ≤0.5% ABV, fermented tea)
- Sparkling botanical drinks (herbs, flowers, spices)
- Craft sodas (ginger beer, root beer, cola)
- Cold brew coffee
- Iced tea or herbal tea
- Fruit-based mocktails
- Energy drinks or functional drinks (electrolytes, adaptogens)

What is a Beer Garden?

A beer garden is an outdoor space where people can enjoy beer and food in a relaxed setting.

- **Social atmosphere:** Beer gardens are often lively and energetic, creating a social atmosphere where people can relax and connect with friends, family or make new acquaintances.
- **Variety of beers:** Beer gardens usually offer a selection of different beers, allowing patrons to try new types and flavors.
- **Casual vibe:** Beer gardens typically have a relaxed, casual vibe, making them a great place to unwind and forget about daily stressors.

Weekly Event idea

- Host events: Run/walk club
- Yoga (stretch and sip)
- pop up art shows
- Songwriter session
- Community Grill Night
- Beer Garden Book Club
- Daddy Daycare time
- DJ Sunset Session
- Art Affair featuring poets, musicians and artists

Monthly Event idea

- Yappy Hour- Dog Friendly, local shelter partnership

-Beer Club Meet up Night

-Movie Night

-Youth Craft Fair

-Fish Fry Fourth Friday

-Battle of the Grill with Kids as the judge

APPLICATION FOR CERTIFICATE OF APPROPRIATENESS

Name: ANTHONY THOMPSON

Address: 4731 WHITEWATER LN

Phone #: (931) 378-2723

CRESTVIEW, FL 32539

Address of property to be improved: SOUTHWEST OF WATTS AVE AND 7TH ST INTERSECTION


List of improvements including materials to be used, paint colors, and other details which will alter the current appearance of the structure or property.

PLEASE REFER TO THE GRAPHICS ATTACHMENT AS WELL AS THE PLANS FOR MATERIALS

AND TYPES OF STRUCTURES.

Note: Include a site plan showing location of proposed construction if the improvement is not on the existing structure.

I, ELISSA PETTIS
(name of applicant) TRI STATE COMPANIES LLC certify that the information submitted truly reflects all improvements which will be made on the property. Should any changes be desired, I will notify the City of Chipley. I acknowledge that penalties can be the result of varying from the plans or description submitted and approved.

Signed: 

Date: 4/25/2025

AGENT FOR APPLICANT, ANTHONY THOMPSON

Action: Approved

Not Approved

Comments: _____

Signature/Title/Authority



City of Chipley

Land Use Compliance Certificate



Fee Amount \$ _____

Verification provided for (Owner's Name): ANTHONY THOMPSON

Project Site Address: TBD (SOUTHWEST OF 7TH ST & WATTS AVE INTERSECTION)

Phone Number: (931) 378-2723

Contractor Name/Address AGENT/ENGINEER, ELISSA PETTIS, TRI STATE COMPANIES LLC
834 KIRKLAND ROAD, CHIPLEY, FL 32428

Contractor Phone #: (850) 420-9922 Parcel I.D. Number: 00000000-00-1328-001

City of Chipley Future Land Use Designation


Low Density Residential	☐	Neighborhood Commercial	☐
Medium Density Residential	☐	Historic Commercial	☐
High Density Residential	☐	Industrial	☐
Historic	☐	Recreational	☐
Commercial	☒	Public/Semi Public/Educational	☐

Flood Zone: ☐ Yes ☒ No Zone Type ZONE X: AREA OF MINIMAL FLOOD HAZARD

Scope of work (Please provide details of all work): _____

THE PROPOSED PROJECT CONSISTS OF SITE DEVELOPMENT INCLUDING INSTALLATION OF WATER AND SEWER UTILITIES,
STORMWATER MANAGEMENT INCLUDING GRADING (EARTHWORK), CONCRETE SIDEWALK, ADA SPACES AND
BUILDING PAD (BAR AREA), GRAVEL PARKING AND LOADING/FOOD TRUCK SPACE, PRE-FABRICATED RESTROOMS, OFFICE AND
STORAGE, GRASSED (OR TURF) PICNIC AREA AND LOUNGE #1, ELEVATED DECK FOR STAGE AND LOUNGE #2.
ADDITIONALLY, THE SITE WILL BE FENCED AND LANDSCAPED.

A site inspection has been performed on the above development site within the City of Chipley, Florida. It is hereby verified that all site development standards meet the City's land use, zoning and comprehensive planning requirements.


Applicant

AGENT FOR APPLICANT,
ANTHONY THOMPSON

4/25/2025
Date

City Official Verifying Compliance

Date

Notice to Applicant: This certificate must be presented to the Washington County Building Official and is requisite to issuance of a "Certificate of Occupancy" for your construction project.

City of Chipley

Sign Application & Permit

Date: 4/25/2025

Permit #: _____

Applicant's Name: ANTHONY THOMPSON

Business Name: SERENE LIFE BEER GARDEN Phone #: (931) 378-2723

Address of Sign: TBD (SOUTHWEST OF 7TH ST & WATTS AVE INTERSECTION)

Name & Address of Sign Contractor: TBD

Permit Fee: _____

.....
Please provide the following information:

1. Type of Sign(s): _____ Ground Sign ☒ Building Sign _____ Outdoor Advertising (Billboard)
2. Scale drawing and dimensions of sign.
 - a. Ground Signs & Outdoor Advertising Signs: provide site plan showing location of sign, distances from existing buildings, intersections, driveway connections and property lines. (Outdoor advertising signs require D.O.T. permit application).
 - b. Building Signs: provide drawing of building showing elevation and location of sign.
3. Type of Illumination: SEE
4. Land Use Designation: COMMERCIAL
5. Number of Existing Signs on Property: 0

The City of Chipley hereby authorizes placement of the above referenced signage. Any deviation to construction or location which are not reflected in this document will result in revocation of permit.

Signature: City Administrator or
Code Enforcement Officer

Date

Signature: [Signature]
Owner/Contractor

4/25/2025

Date

AGENT FOR
APPLICANT

CITY OF CHIPLEY
APPLICATION FOR CONCURRENCY REVIEW

Applicant: ANTHONY THOMPSON Date: 4/25/2025
Address: 4731 WHITEWATER LN, CRESTVIEW, FL32539 Phone: (931) 378-2723
Project Name: SERENE LIFE BEER GARDEN Address: TBD (S WEST OF 7TH & WATTS INTERSECTION)
Contact Person: ELISSA PETTIS, TRI STATE COMPANIES LLC Phone: (850) 420-9922

(Use additional sheets if necessary)

1. Provide estimated water usage in gallons per person per day plus total usage per day, month, and annually.
2. Provide estimated sanitary sewer usage in gallons per person per day plus total usage per day, month, and year.
3. Provide estimated solid waste generation in pounds. Provide list of types of waste generated by establishment.
4. Provide storm water management plan.
 - a. Include all permits from applicable state and federal agencies.
5. Provide estimated traffic volume at peak hours.
 - a. Include a written statement indicating the nature and extent of proposed development.

*****NOTE:** Certain types of development are exempt from some portions of the concurrency review; however, some may have greater requirements than those requested above. Call the planning department at city hall if you have any questions concerning your requirements.

Approved by: _____ Date: _____
(City Official)

Certificate of Concurrency" valid for only one year following submission of information.



City of Chipley

1442 Jackson Avenue
P.O. Box 1007
Chipley, Florida 32428
(850) 638-6350



AFFIDAVIT

STATE OF Florida
COUNTY OF Washington

BEFORE ME, a Notary Public in and for the said County and State, this day personally appeared Patrice Tanner, City of Chipley City Administrator, who, being by me duly sworn, deposes and says:

1. I am the City Administrator for the City of Chipley identified as the Utility Provider of the property located at Parcel ID: 00-1328-0001, Chipley, FL 32428.
2. I hereby depose and state that all necessary utilities for the construction, development, and operation of the property are presently available to the boundaries of the property. This includes, but is not limited to, water supply and sanitary sewer.
3. I further affirm that this affidavit is true and correct to the best of my knowledge and belief.

AFFIANT'S SIGNATURE:

Patrice A. Tanner

City of Chipley by Patrice Tanner, City Administrator

Sworn to (or affirmed) and subscribed before me by means of

☒ physical presence ☐ online notarization

this 10 day of Nov., 2025.

Sherry Snell


Notary Public Signature

Sherry Snell

Printed Name of Notary Public

My Commission Expires:

(Seal)



NOTICE OF PUBLIC HEARING

The Planning & Zoning Commission of the City of Chipley, FL will conduct a public hearing at the City Hall Council Chambers located at 1442 Jackson Ave, Chipley, FL and via Zoom, on Thursday, January 29, 2026, at 3:00 p.m. CST. The purpose of this hearing is to review and consider the following request:

1. Request for Development Order to include a Variance – Serene Life Beer Garden. The property is located at the corner of Watts Avenue & 7th Street, Parcel ID: 00000000-00-1328-0001.
2. Request for a Variance – WJHFL, LLC - 966 Lera Lane. Parcel ID: 00000000-00-2258-0140.

You are invited to a Zoom webinar!

When: January 29, 2026 03:00 PM Central Time (US and Canada)

Topic: Planning & Zoning Commission Meeting

Join from PC, Mac, iPad, or Android: <https://us02web.zoom.us/j/85241464711>

Phone one-tap:

+16469313860,,85241464711# US +13017158592,,85241464711# US (Washington DC)

Join via audio:

+1 646 931 3860 US +1 301 715 8592 US (Washington DC) +1 305 224 1968 US +1 309 205 3325 US +1 312 626 6799 US (Chicago) +1 646 558 8656 US (New York) +1 386 347 5053 US +1 507 473 4847 US +1 564 217 2000 US +1 669 444 9171 US +1 669 900 9128 US (San Jose) +1 689 278 1000 US +1 719 359 4580 US +1 253 205 0468 US +1 253 215 8782 US (Tacoma) +1 346 248 7799 US (Houston) +1 360 209 5623 US

Webinar ID: 852 4146 4711

All citizens and interested parties are encouraged to attend the public hearing in person or via zoom. Any inquiries regarding the public hearings or any person requiring special accommodation due to disability or physical impairment, including speech or hearing impairments, should contact the City Hall at 850-638-6350 at least five (5) business days prior to the hearing.

Patrice Tanner
City Administrator



City of Chipley

1442 Jackson Avenue
P.O. Box 1007
Chipley, Florida 32428
(850) 638-6350



NOTICE OF PUBLIC HEARING

December 29, 2025

Dear Citizen:

The City of Chipley Planning & Zoning Commission will conduct a public hearing on January 29, 2026 at 3:00 p.m., City Hall Council Chambers. The purpose of this hearing is to review and consider the following request:

Serene Life Beer Garden is requesting approval of a development order that includes a variance to permit the sale of alcoholic beverages within 500 feet of a residential property.

Property Location: The corner of Watts Avenue and 7th Street
Parcel ID #: 00-1328-0001

City Code Chapter 4 – Alcoholic Beverages
Article II – Establishments

(1) Distance from dwelling or residence.

- a. It shall be unlawful to sell beer, wine, or other alcoholic or intoxicating beverages for consumption on the premises within 500 feet of any residence, which distance shall be measured by measuring a radius from the main public entrance of the place or establishment. If any portion of a parcel of land used as a dwelling or residence lies within such radius, then the new establishment shall be deemed to be within such distance.

In accordance with City Code of Ordinances Chapter 44, Article XI, property owners located within 300 feet of said location are to be notified.

The City Council will review the development order and variance at their meeting to be held on February 13, 2026 at 5:00 p.m., City Hall Council Chambers.

If you have any questions or need additional information regarding this request, please contact City Hall prior to the public hearing at (850) 638-6350.

Sincerely,

Patrice A. Tanner
City Administrator

CITY OF CHIPLEY AFFIDAVIT OF MAILING

January 15, 2026

Re: Notice of Public Hearing for the Planning and Zoning Commission, on January 29, 2026, at 3:00 pm., and Notice of Public Hearing for City Council on February 13, 2026, at 5:00 pm both located at 1442 Jackson Avenue, Chipley, FL 32428, in the city's chambers,

I, Sherry Snell, designated and employed by the City of Chipley, Florida, did mail the notice of a public hearing to the following:

See Exhibit A, on December 29, 2025.



Employee Signature




Date

Sworn to and subscribed before me this 15 day of January, 2026, by Sherry Snell, who is personally known by me.



Signature of Notary Public



CALVERLY JOHN, REHBERG MONICA C
% MONICA REHBERG
746 3RD ST
CHIPLEY, FL 32428

CITY OF CHIPLEY
PO BOX 1007
CHIPLEY, FL 32428

COOPER JIMMIE L
PO BOX 66
CHIPLEY, FL 32428

COOPER Z REGINALD, COOPER JIMMIE
PO BOX 34
CHIPLEY, FL 32428

CURLETT SUSANNA
781 MAIN ST
CHIPLEY, FL 32428

HADDOCK RONDA M, HADDOCK DAN
774 MAIN ST
CHIPLEY, FL 32428

HARRELL DONALD R, HARRELL SHARC
1660 COY DR
CHIPLEY, FL 32428

HARRELL RENA
1660 COY DR
CHIPLEY, FL 32428

HITCHCOCK DAVID A, HITCHCOCK TII
2540 DOGWOOD DR
COTTONDALE, FL 32431

J CORB LLC
912 HWY 277
CHIPLEY, FL 32428

JOHNS LOWELL THOMAS JR & ETAL, JC
448 CUTCHINS MILL RD
CHIPLEY, FL 32428

MASLOW ROBERT, MASLOW MICHELI
2380 EARLS CT
LOS ANGELES, CA 90077

NELSON WAYNE, NELSON BETTY
669 7TH ST
CHIPLEY, FL 32428

PEDRAJA LEANNE G
PO BOX 472
CHIPLEY, FL 32428

THOMPSON ANTHONY, THOMPSON A
4731 WHITEWATER LN
CRESTVIEW, FL 32539

TREADWELL ADAM, PIGGLY WIGGLY AI
1140 MONTGOMERY HWY
DOTHAN, AL 36305

TREADWELL ADAM
1140 MONTGOMERY HWY
DOTHAN, AL 36305



City of Chipley

1442 Jackson Avenue
P.O. Box 1007
Chipley, Florida 32428
(850) 638-6350



NOTICE OF PUBLIC HEARING (Updated City Council Meeting Date)

January 20, 2026

Dear Citizen:

The City of Chipley Planning & Zoning Commission will conduct a public hearing on January 29, 2026, at 3:00 p.m., City Hall Council Chambers. The purpose of this hearing is to review and consider the following request:

Serene Life Beer Garden is requesting approval of a development order that includes a variance to permit the sale of alcoholic beverages within 500 feet of a residential property.

Property Location: The corner of Watts Avenue and 7th Street
Parcel ID #: 00-1328-0001

City Code Chapter 4 – Alcoholic Beverages
Article II – Establishments

(1) Distance from dwelling or residence.

- a. It shall be unlawful to sell beer, wine, or other alcoholic or intoxicating beverages for consumption on the premises within 500 feet of any residence, which distance shall be measured by measuring a radius from the main public entrance of the place or establishment. If any portion of a parcel of land used as a dwelling or residence lies within such radius, then the new establishment shall be deemed to be within such distance.

In accordance with City Code of Ordinances Chapter 44, Article XI, property owners located within 300 feet of said location are to be notified.

The City Council will review the development order and variance at their meeting to be held on February 10, 2026, at 5:00 p.m., City Hall Council Chambers.

If you have any questions or need additional information regarding this request, please contact City Hall prior to the public hearing at (850) 638-6350.

Sincerely,

Patrice A. Tanner
City Administrator


**CITY OF CHIPLEY
AFFIDAVIT OF MAILING**

January 20, 2026

Re: Notice of Public Hearing for the Planning and Zoning Commission, on January 29, 2026, at 3:00 pm., and Notice of Public Hearing for City Council on February 10, 2026, at 5:00 pm both located at 1442 Jackson Avenue, Chipley, FL 32428, in the city's chambers,

I, Tamara Donjuan, designated and employed by the City of Chipley, Florida, did mail the notice of public hearing to the following:

See Exhibit A,



Employee Signature

1/20/26

Date

Sworn to and subscribed before me this 20th day of Jan, 2026, by
Tamara Donjuan, who is personally known by me.



Signature of Notary Public




Exhibit A

CALVERLY JOHN, REHBERG MONICA C
% MONICA REHBERG
746 3RD ST
CHIPLEY, FL 32428

CITY OF CHIPLEY
PO BOX 1007
CHIPLEY, FL 32428

COOPER JIMMIE L
PO BOX 66
CHIPLEY, FL 32428

COOPER Z REGINALD, COOPER JIMMIE
PO BOX 34
CHIPLEY, FL 32428

CURLETT SUSANNA
781 MAIN ST
CHIPLEY, FL 32428

HADDOCK RONDA M, HADDOCK DAN
774 MAIN ST
CHIPLEY, FL 32428

HARRELL DONALD R, HARRELL SHARC
1660 COY DR
CHIPLEY, FL 32428

HARRELL RENA
1660 COY DR
CHIPLEY, FL 32428

HITCHCOCK DAVID A, HITCHCOCK TII
2540 DOGWOOD DR
COTTONDALE, FL 32431

J CORB LLC
912 HWY 277
CHIPLEY, FL 32428

JOHNS LOWELL THOMAS JR & ETAL, JC
448 CUTCHINS MILL RD
CHIPLEY, FL 32428

MASLOW ROBERT, MASLOW MICHELI
2380 EARLS CT
LOS ANGELES, CA 90077

NELSON WAYNE, NELSON BETTY
669 7TH ST
CHIPLEY, FL 32428

PEDRAJA LEANNE G
PO BOX 472
CHIPLEY, FL 32428

THOMPSON ANTHONY, THOMPSON A
4731 WHITEWATER LN
CRESTVIEW, FL 32539

TREADWELL ADAM, PIGGLY WIGGLY A
1140 MONTGOMERY HWY
DOTHAN, AL 36305

TREADWELL ADAM
1140 MONTGOMERY HWY
DOTHAN, AL 36305

SITE PLAN REVIEW REQUIREMENT CHECKLIST

1. Legal description of subject parcel. -SEE PLANS – SHEET: 1A
2. Site location map. -SEE PLANS – SHEET: COVER
3. Topography map. -SEE MAPS – TOPO MAP ATTACHMENT
4. Generalized soil types and map, if available. -SEE MAPS – SOIL MAP ATTACHMENT
5. Type & location of existing vegetation & tree grouping. -SEE PLANS – SHEET: 4A
6. Location, names, widths of existing & proposed streets, driveways and dumpsters.
-SEE PLANS – SHEETS: 1A AND 2A
7. Dimensions/location of all buildings/structures. -SEE PLANS – SHEET: 2A AND SEE GRAPHICS ATTACH
8. Gross floor area of all buildings. -SEE PLANS – SITE DATA SUMMARY ON SHEET 2A
9. Exact number of dwelling units by number of bedrooms. -N/A
10. Total number of residential units by acre. -N/A
11. Dimensions of all yard setbacks and open spaces.
-SEE PLANS – SITE SUMMARY DATA SHEET ON SHEET 2A
12. Location of recreation areas, if any. -N/A
13. Drainage concept. -SEE PLANS – SHEET: 3A
14. Site percentage & square footage covered by building structures.
-SEE PLANS – SITE SUMMARY DATA SHEET ON SHEET 2A
15. Site percentage & square footage covered by paving.
-SEE PLANS – SITE SUMMARY DATA SHEET ON SHEET 2A
16. Site percentage & square footage covered by open space.
-SEE PLANS – SITE SUMMARY DATA TABLE ON SHEET 2A
17. Sediment control measures. -SEE PLANS – SHEET: 1B
18. Fire flow calculations. -SEE CALCS – FIRE FLOW ATTACHMENT
19. Preliminary site plan submittals must contain the following stormwater management information:
 - A. Graphic definition of the drainage areas with each area's:
 1. approximate surface area indicated
-SEE PLANS – SITE SUMMARY DATA TABLE ON SHEET 2A
 2. approximate coefficient of imperviousness -SEE CALCS – SWMF CALCS ATTACH
 3. approximate points of water collection -SEE PLANS – SHEET 3A
 - B. Definition of the type of stormwater management system proposed, along with the location and approximate dimensions and/or size of the facilities. -SEE CALCS – SWMF CALCS ATTACH
 - C. Approximate stormwater management design calculations.
-SEE CALCS – SWMF CALCS ATTACH
20. A grading & drainage plan; stormwater management analysis/design Calculations must be signed & sealed by a registered Florida engineer. -SEE CALCS: SWMF CALCS ATTACHMENT & PLANS: SHEET 3A
21. A landscape plan. -SEE PLANS – SHEET: 4A
22. Exact location of all public easements. -SEE PLANS – SHEET 1A

Development Statement on Public Easements

This project does not include any public easements. However, the adjacent rights-of-ways that abut the property are recognized as public access areas. These rights-of-ways will remain accessible.

23. Utility services & connection points; fire hydrant locations.
-SEE MAPS – EXIST UTILITIES MAP ATTACH & PLANS – SHEET: 3B
24. Architectural elevations of all buildings and structures. -SEE GRAPHICS – ARCH ELEVATIONS
25. Size, type and location of street graphics.
-SEE GRAPHICS ATTACHMENT AND PLANS – SHEET: 4A
26. Size, location and intensity of exterior lighting devices and a statement that lighting will meet City of Chipley codes. -SEE PLANS – SHEET: 4A
27. If phasing is planned, a development timetable is required. PLEASE SEE BELOW.


Phasing Plan

(Each phase will commence within 60 days after the completion of the prior phase.)

- A. Phase 1: Foundation Setup**
 - I. Install cooler and nano brewery containers**
 - II. Construct restrooms**
 - III. Build stage for events and entertainment**
- B. Phase 2: Main Serving & Bar Area**
 - I. Establish primary bar and serving station**
 - II. Ensure plumbing, electrical, and seating arrangements**
 - III. Develop customer flow and optimize layout**
- C. Phase 3: Lounge Areas & Landscaping**
 - I. Create relaxation lounges for guests**
 - II. Implement landscaping features for aesthetics and ambiance**
 - III. Final touch-ups and enhancements for seamless operation**

28. A sedimentation plan. -SEE PLAN – SHEETS: SWPPP(1), SWPPP(2) AND SHEET 1B

Name	
NR3	
Patient Number	
LP 29002	
Exam by	
AJC	
Treatment by	
EAP	
Appropriately	
TCS	
Signature	
CVR	



GENERAL NOTES

	GEN
	COPY TO FILE:
_____	TCS
_____	Aqueduct
_____	EAP
_____	Paid by
_____	A/C
_____	Name Of
LP 23 002	
_____	Paid To File
_____	Date

11. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PRESERVE OR RELOCATE ALL BENCHMARKS (VERTICAL CONTROL) AS NEEDED DURING CONSTRUCTION. ALL PUBLIC OR PRIVATE CORNER

26. THE CONTRACTOR SHALL ADJUST ALL VALVE BOX AND MANHOLE CASTINGS TO MATCH FINAL SURFACE ELEVATIONS.

27. AS-BUILTS ARE THE RESPONSIBILITY OF THE CONTRACTOR. IF THE AS-BUILT SURVEY INDICATES AN AREA OF INCOMPLETE OR UNACCEPTABLE WORK, THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING THE NECESSARY REPAIRS. AS DIRECTED BY THE ENGINEER, OR OWNER. CONTRACTOR WILL BE REQUIRED TO PROVIDE UPDATED AS-BUILTS TO DEMONSTRATE COMPLIANCE WITH THE PLANS AND PERMITS. ALL FINAL AS-BUILT SURVEYS ARE REQUIRED TO BE CERTIFIED BY A FLORIDA REGISTERED PROFESSIONAL SURVEYOR.

UTILITY NOTES:

1. THE LOCATION SHOWN FOR EXISTING UNDERGROUND UTILITIES IS APPROXIMATE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK IN EACH AREA. THE CONTRACTOR AGREES TO BE COMPLETELY RESPONSIBLE FOR ALL DAMAGES WHICH MIGHT OCCUR BY HIS/HER FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES.
2. UTILITY OWNERS SHALL BE NOTIFIED AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION SO THAT THE UTILITY OWNER CAN SPOT VERIFY AND/OR EXPOSE THEIR UTILITIES.
3. CENTURYLINK WILL COMPLETE ALL WORK DURING THE HOURS OF 7:30 AM - 4:30 PM, MONDAY THRU FRIDAY. NO NIGHT OR WEEKEND WORK.
4. ALL CABLE DAMAGE MUST BE REPORTED TO THE CENTURYLINK REPAIR SERVICE DEPARTMENT AT 611 FROM A LAND LINE OR 877-737-2478 IF USING A CELL PHONE.
5. CONTRACTOR IS TO USE CAUTION WHEN WORKING IN OR AROUND AREAS OF OVERHEAD TRANSMISSION LINES AND UNDERGROUND UTILITIES.
6. UTILITIES ARE TO REMAIN AND BE PROTECTED DURING CONSTRUCTION. NECESSARY REPAIRS SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS AND SHALL BE TO THE SATISFACTION OF THE UTILITY OWNERS.

LAYOUT NOTES:

1. THE ELEVATIONS AS SHOWN HEREON ARE REFERENCED TO NORTH AMERICAN VERTICAL DATUM (1988).
2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT LOCATION OF EXISTING UTILITIES AND TO DETERMINE IF OTHER UTILITIES WILL BE ENCOUNTERED DURING THE COURSE OF THE WORK AND TAKE ALL NECESSARY STEPS TO PROVIDE FOR UTILITY PROTECTION.
3. REFERENCE BENCHMARKS EXISTS ON THIS PROPERTY AS SHOWN HEREON.
4. CONTRACTOR SHALL CONTACT THE ENGINEER IMMEDIATELY REGARDING ANY APPARENT CONFLICTS IN THE PROPOSED IMPROVEMENTS ENCOUNTERED DURING THE COURSE OF CONSTRUCTION.

STORMWATER SYSTEM MAINTENANCE:

1. CONTRACTOR SHALL STAGE AND TIME CONSTRUCTION TO MINIMIZE THE SIZE OF EXPOSED SOIL AREAS AND THE TIME BETWEEN EXPOSING THE SOIL AREA AND FINISHING THE SOIL AREA.
2. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR PERFORMING A TASK TO PROVIDE EROSION CONTROL UNLESS ANOTHER PARTY HAS BEEN PREVIOUSLY SPECIFIED AS RESPONSIBLE FOR THE EROSION CONTROL ASSOCIATED WITH THAT TASK. IN THE EVENT ANOTHER PARTY IS RESPONSIBLE FOR EROSION CONTROL, THE CONTRACTOR SHALL STILL BE RESPONSIBLE FOR COORDINATION WITH THE PARTY RESPONSIBLE. IN THE EVENT THAT DAMAGE TO THE CONSTRUCTED ITEM ARE DUE TO LACK OF EROSION CONTROL, THE CONTRACTOR SHALL REPAIR OR REPLACE THE ITEM AT NO CHARGE TO THE OWNER.
3. THE CONTRACTOR IS TO PROVIDE EROSION CONTROL/SEDIMENTATION BARRIER HAY BALES, SILT FENCE, TURBIDITY BARRIER, OR AS SPECIFIED IN THE CONSTRUCTION DRAWINGS) TO PREVENT SILTATION OF ADJACENT PROPERTY, STREETS, STORM SEWERS, WATERWAYS, AND WETLAND OR JURISDICTIONAL AREAS. IF, IN THE OPINION OF THE ENGINEER, AND/OR REGULATORY AUTHORITIES, EXCESSIVE QUANTITIES OF MATERIAL ARE TRANSPORTED OFF-SITE BY EROSION OR STORMWATER RUNOFF, THE CONTRACTOR SHALL IMPROVE CONDITIONS TO THE SATISFACTION OF THE ENGINEER AND/OR AUTHORITIES AT NO ADDITIONAL COST TO THE OWNER. IN NO CASE SHALL CONSTRUCTION COMMENCE PRIOR TO INSTALLATION OF EROSION CONTROL/SEDIMENTATION BARRIER.
4. ALL EXPOSED CORNERS AND EDGES OF CONCRETE ARE TO BE CHAMFERED 3/4".
5. CONSTRUCTION OF THE ROADWAY AND DRAINAGE SYSTEMS SHALL CONFORM TO THE MOST RECENT FOOT ROAD AND BRIDGE MANUAL AND SUPPLEMENTS.

EROSION CONTROL NOTES:

1. EROSION PROTECTION: SOIL EROSION SEDIMENTATION MUST BE CONTROLLED AND RETAINED ON SITE DURING CONSTRUCTION. THEREFORE, EROSION PROTECTION, SUCH AS STAKED BALED HAY AND SILT FENCE BARRIERS, MUST BE INSTALLED PRIOR TO START OF CONSTRUCTION.
2. SILT FENCE BARRIER SHALL BE INSTALLED AS SHOWN ON PLANS, AND IN ALL AREAS SUBJECT TO SOIL EROSION SEDIMENTATION.
3. SOO ALL SLOPES 3:1 OR STEEPER
4. CONTRACTOR SHALL RETAIN ALL SOIL EROSION SEDIMENTATION ON-SITE.
5. ALL DISTURBED AREAS NOT SPECIFICALLY SHOWN TO BE SODDED SHALL BE GRASSED AND MULCHED. THE GRASS SEED SHALL BE 20 PARTS BERMUDA AND 80 PARTS PENSACOLA BAHIA APPLICATION SHALL BE 100 POUNDS PER ACRE. IF CONSTRUCTION OCCURS DURING THE MONTHS OF OCTOBER THROUGH JANUARY, SEEDING SHALL BE 50 PARTS WINTER RYE AND 50 PARTS PENSACOLA BAHIA AT 100 POUNDS PER ACRE. SEEDING AREAS SHALL BE FERTILIZED WITH 8-8-8 NPK DRY FERTILIZER AT THE RATE OF 800 POUNDS PER ACRE.
6. ALL AREAS TO BE GRASSED AND MULCHED SHALL HAVE A MINIMUM OF ONE INCH OF TOPSOIL DISTRIBUTED PRIOR TO SEEDING.
7. FUNCTIONAL EROSION AND SILTATION CONTROLS SHALL BE INSTALLED AS NEEDED THROUGHOUT THE CLEARED AREAS AND AS SHOWN ON THE CONSTRUCTION PLANS IMMEDIATELY SUBSEQUENT TO ESTABLISHED ROUGH GRADE.
8. ALL EROSION CONTROL STRUCTURES SHALL BE IN PLACE BEFORE DEMOLITION BEGINS.
9. CONSTRUCT FILTER FENCES, HAY BALES AND TREE BARRICADES.
10. STRIP THE TOP SOIL AND STOCK PILE FOR USE IN LANDSCAPED AREAS.


TSC

TRI-STATE Companies, Inc.
624 Island Road
P.O. Box 992
Chipley, Florida 32428
Phone 905-651-1122 Fax 905-651-1122
E-Mail: info@tsc.com Website: www.tsc.com

GENERAL NOTES

SERENE LIFE BEER GARDEN
CHIPLEY, WASHINGTON CO., FLORIDA

Notes	



TRI-STATE Companies, Inc.
601 Grand Road
P.O. Box 1000
Auburn, Alabama 36801
Phone 205-836-1922 Fax 205-836-1923
E-Mail: tsc@tri-state.com

GENERAL NOTES

SERENE LIFE BEER GARDEN
CHIPLEY, WASHINGTON CO., FLORIDA

Project No.	1000000000
Revision	1
Drawn By	LP/23002
Check By	ALC
Approved By	EAP
Scale	TCS

GEN(3)

11. INSTALL UTILITIES AND DRAINAGE PIPES PROTECTING INLETS WITH STAKED HAY BALES OR FILTER FENCE TO PREVENT SEDIMENT FROM ENTERING THE DRAINAGE SYSTEMS. CONSTRUCT STORMWATER MANAGEMENT CONTROL STRUCTURES (FILTRATION, RATE CONTROL, ETC.)
 12. CONSTRUCT DRAINAGE, PARKING AND OTHER IMPROVEMENTS AS SHOWN ON THE PLANS; MAINTAIN SEDIMENTATION, EROSION AND TREE PROTECTION MEASURES.
 13. FINAL GRADE THE SITE AND LANDSCAPE AS PER PLANS AND SPECIFICATIONS, STABILIZING ALL DISTURBED AREAS.
 14. NO HEAVY EQUIPMENT IN NATURAL AREAS. ALL PLANTING TO BE DONE BY HAND.
 15. ALL DISTURBED AREAS SHALL BE SATISFACTORILY STABILIZED, UNLESS OTHERWISE SPECIFIED. SOD SHALL BE PROVIDED IN THE FOLLOWING AREAS:
 - a. ALL SLOPES 3:1 AND STEEPER.
 - b. ENTIRE AREA BETWEEN SIDEWALKS AND BACK OF CURB.
 - c. INTERIOR SLOPES OF PONDS AND SWALES, AND IN A TWO-FOOT WIDE STRIP ALONG THE TOP OF BANK OF ALL PONDS AND SWALES.
 - d. IN A TWO-FOOT WIDE STRIP ALONG ALL BUILDINGS, STRUCTURES, ROADS WHERE NO SIDEWALKS RUN PARALLEL AND OUTER EDGES OF ALL SIDEWALKS. OTHER AREAS MAY BE SEEDED AND MULCH, UNLESS OTHERWISE SPECIFIED. CONTRACTOR SHALL MAINTAIN GRASSSED UNTIL PLANTS HAVE TAKEN ROOT AND THE AREA IS SATISFACTORILY STABILIZED.
- CONSTRUCTION SEQUENCE:
1. CONTRACTOR WILL BE RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION CONFERENCE WITH THE WALTON COUNTY, UTILITY COMPANIES, ENGINEER AND ALL OTHER PARTIES REQUIRED FOR COMMENCEMENT OF PROJECT. THIS MEETING SHALL TAKE PLACE PRIOR TO COMMENCEMENT OF ANY PROJECT RELATED ACTIVITIES. AT THIS TIME PRIOR TO CONSTRUCTION THE PERMIT MUST BE POSTED WITHOUT NAILING TO ANY TREE ON SITE.
 2. THE CONTRACTOR SHALL ENSURE THAT A FOREMAN OR SUPERVISOR WHO HAS BEEN CERTIFIED UNDER FLORIDA STORMWATER, EROSION, AND SEDIMENTATION CONTROL INSPECTOR TRAINING PROGRAM IS AVAILABLE IN PERSON OR BY TELEPHONE AT ALL TIMES DURING CONSTRUCTION ACTIVITIES. CONSTRUCTION SHALL NOT COMMENCE UNTIL INFORMATION (NAME AND PHONE NUMBER) OF CERTIFIED STORMWATER EROSION AND SEDIMENTATION CONTROL INSPECTOR HAS BEEN PROVIDED TO THE COUNTY AT THE PRE-CONSTRUCTION MEETING.
 3. PRIOR TO CLEARING, A SILT FENCE BACKED WITH 4" HOG WIRE FENCE (TRENCHED 8 INCHES DEEP AND BACKFILLED ON THE UPHILL SIDE), SHALL BE INSTALLED AS SHOWN ON THE PLANS. SILT FENCE MUST NOT BE TRENCHED WITHIN THE CPZ OF ANY TREES TO BE PROTECTED. EROSION CONTROL SHOWN ON PLANS IS REQUIRED. ADDITIONAL SEDIMENT AND EROSION CONTROL MEASURES MAY BE REQUIRED DURING ANY PHASE OF THE DEVELOPMENT. AT THE DISCRETION OF THE CITY INSPECTOR, THE CITY INSPECTOR MAY REQUIRE ADDITIONAL MEASURES TO PREVENT ADDITIONAL EROSION. CONTRACTOR SHALL PROVIDE OUTLET PROTECTIONS FOR SEDIMENTS THAT MAY LEAVE THE SITE. CONTRACTOR WILL BE RESPONSIBLE FOR CLEANING THE SITE AFTER CONSTRUCTION. CONTRACTOR CAN USE ADDITIONAL ALTERNATIVE TO PREVENT SEDIMENTS FROM LEAVING THE SITE. CONTRACTOR WILL BE RESPONSIBLE FOR ANY OFFSITE IMPACTS. DO NOT BEGIN CONSTRUCTION UNTIL EROSION CONTROL DEVICES HAVE BEEN INSPECTED AND APPROVED BY THE LOCAL PERMITTING AUTHORITY.
 4. DURING THE CLEARING, GRUBBING AND SITE GRADING STAGES, AREAS THAT ARE DISTURBED MORE THAN 7 DAYS SHALL BE STABILIZED WITH RYE GRASS APPLIED AT MANUFACTURER'S RECOMMENDATIONS. AFTER SEEDING, EACH AREA SHALL BE MULCHED WITH 4,000 POUNDS OF STRAW PER ACRE. ALL EXPOSED SLOPES THAT ARE EQUAL TO OR GREATER THAN 5% AN EROSION BLANKET SHALL BE UTILIZED UNTIL THE AREA ACHIEVES FINAL STABILIZATION. TO LIMIT THE AMOUNT OF EROSION ON SITE CONTRACTOR SHALL CLEAR SITE AS NEEDED DURING CONSTRUCTION. CONTRACTOR SHALL USE CARE WHEN CUTTING GRADES FOR THE WALL AND SWALE. CONTRACTOR SHALL ALSO PREPARE DIVERSION BERMS AS NEEDED.
5. ALL SEDIMENT IS TO BE CAPTURED ON THE PROJECT SITE. ANY SEDIMENT ESCAPING THE PROJECT SITE WILL BE REQUIRED TO BE REMOVED AND RESTORED INCLUDING THE TRACKING OF SOIL ON STREETS.
 6. CONSTRUCT UTILITIES AND OTHER IMPROVEMENTS IN ACCORDANCE WITH THE APPROVED DRAWINGS.
 7. TEMPORARY SEEDING SHALL BE RYE GRASS APPLIED AT MANUFACTURER'S RECOMMENDATIONS TO ANY DISTURBED AREAS THAT ARE INACTIVE MORE THAN 7 DAYS. SOD SHALL BE USED TO STABILIZE THE STORMWATER DISCHARGE SWALE. FILTER FABRIC SHALL BE PLACED UNDER STORMWATER DISCHARGE SWALE OUTFALL. SOD STRIPS IN SWALES AND WATERWAYS SHALL BE LAID PERPENDICULAR TO THE DIRECTION OF FLOW. SOD SHALL BE PEGGED OR STAPLED TO RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD.
 8. DAILY SWEEPING WILL BE REQUIRED ON THE PROPERTY AND IMMEDIATELY AFTER STORM EVENTS TO PREVENT TRACKING OF SEDIMENT ONTO STREETS AND RIGHT-OF-WAY.
 9. REMOVE ALL SEDIMENT/EROSION CONTROL DEVICES. REMOVE AND DISTRIBUTE ANY REMAINING SEDIMENT ONCE FULLY STABILIZED. ASSURE THAT DISTRIBUTED SEDIMENT WILL NOT BE REDISTRIBUTED. ANY EXCESS DIRT SHALL BE DISPOSED OF IN A MANNER OFF SITE THAT WILL NOT CAUSE ANY EROSION OR SEDIMENT ISSUES. CONTRACTOR WILL ALSO INSPECT STRUCTURES FOR SEDIMENT. ANY SEDIMENT SHALL BE FLUSHED FROM THE CONVEYANCE SYSTEM.
 10. CONTRACTOR SHALL GUARANTEE ALL WORK FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE BY THE OWNER.
 11. EACH CONTRACTOR SHALL CARRY ON HIS WORK AND ADHERE TO THE PROGRESS SCHEDULE DURING ALL DISPUTES OR DISAGREEMENTS WITH THE OWNER. NO WORK SHALL BE DELAYED OR POSTPONED PENDING RESOLUTION OF ANY DISPUTES OR DISAGREEMENTS.
 12. KEEP EXISTING PAVEMENT AS SHOWN, AND SAW CUT WHERE NEEDED FOR DRAINAGE PIPE CROSSINGS.
 13. TWO WEEKS PRIOR TO FINAL INSPECTION, THE CONTRACTOR SHALL HAVE A WALK THROUGH WITH THE ENGINEER, AND OWNER AND A PUNCH LIST SHALL BE PREPARED. ONCE ALL PUNCH LIST ITEMS ARE ADDRESSED TO SATISFY THE ENVIRONMENTAL PERMIT, THE CONTRACTOR SHALL ALSO SCHEDULE A WALK THROUGH WITH THE OWNER, ARCHITECT, ENGINEER AND COUNTY UPON COMPLETION.
 14. CONTRACTOR SHALL PROVIDE THE ENGINEER WITH MINIMUM OF SIX (6) COPIES OF A SIGNED AND SEALED AS-BUILT SURVEY TO VERIFY THE INSTALLATION OF ALL INFRASTRUCTURE, STORMWATER CONVEYANCES, AND LANDSCAPE IMPROVEMENTS ACCORDING TO COUNTY ENVIRONMENTAL PERMITS.

STORMWATER POLLUTION PREVENTION PLAN:

1. SITE DESCRIPTION: COMMERCIAL DEVELOPMENT
A. CONSTRUCTION ACTIVITY: CONSTRUCTION OF SITE IMPROVEMENTS INCLUDING INSTALLATION OF MAJOR UTILITIES AND STORMWATER FACILITIES.
B.

C. TOTAL PROJECT AREA: 0.28 ACRES
TOTAL SOIL AREA TO BE DISTURBED: SEE SW MANAGEMENT REPORT FOR SPECIFICS RELATED TO AREA OF DISTURBANCE, COEFFICIENTS,
D. RUNOFF COEFFICIENTS BEFORE AND AFTER CONSTRUCTION: SEE SW MANAGEMENT REPORT
DESCRIPTION OF SOIL OR QUALITY OF DISCHARGE: SEE SW MANAGEMENT REPORT

E. FOR LOCATIONS OF DRAINAGE AREAS AND OUTFALLS: SEE SW MANAGEMENT REPORT
NAME OF RECEIVING WATERS: N/A
WETLAND AREA: NO DISTURBANCE TO WETLANDS ARE ANTICIPATED

2. CONTROLS:
NARRATIVE - SEQUENCE OF SOIL DISTURBING ACTIVITIES AND IMPLEMENTATION OF CONTROLS
THE SOIL DISTURBING ACTIVITIES FOR THIS PROJECT ARE AS FOLLOWS: ONLY UPON PROPER PLACEMENT OF ALL EROSION CONTROLS CAN SOIL DISTURBING ACTIVITIES TAKE PLACE. HAY BALES AND SILT FENCE WILL BE USED LATERALLY AT SPECIFIED INTERVALS. HAY BALES SHALL BE USED TO PREVENT SEDIMENTATION FROM ESCAPING PROJECT LIMITS.

2A. EROSION AND SEDIMENT CONTROLS:
(1) STABILIZATION PRACTICES:
X PERMANENT SODDING
X TEMPORARY GRASSING
X PERMANENT PLANTING, SODDING, OR SEEDING
X TEMPORARY MULCHING
X ARTIFICIAL COVERING
X BUFFER ZONES
X PRESERVATION OF NATURAL RESOURCES

2B. STRUCTURAL PRACTICES:
X SAND BAGGING
X SILT FENCES
X HAY BALES
X BERMS
X DIVERSION, INTERCEPTOR, OR PERIMETER DITCHES
X PIPE SLOPE DRAINS
X FLUMES
X ROCK BEDDING AT CONSTRUCTION EXIT
X TIMBER BEDDING AT CONSTRUCTION EXIT
X DITCH LINER

2C. DESCRIPTION OF STORMWATER MANAGEMENT: SEE SW MANAGEMENT REPORT

2D. OTHER CONTROLS:
(1) WASTE DISPOSAL: NO CONSTRUCTION WASTE MATERIAL WILL BE BURIED ON SITE
(2) OFF-SITE VEHICLE TRACKING:
X Haul roads dampened for dust control
X Loaded haul trucks to be covered with tarpaulin
X Excess dirt on road removed daily
X Stabilized construction entrance
(3) SANITARY WASTE: N/A
(4) FERTILIZERS AND PESTICIDES: FERTILIZERS AND/OR PESTICIDES SHALL BE APPLIED ACCORDING TO MANUFACTURERS
RECOMMENDATIONS BY A LICENSED OR CERTIFIED APPLICATOR AS DIRECTED BY THE PROJECT ENGINEER.
(5) NON-STORMWATER DISCHARGE (INCLUDING SPILL REPORTING): NO NON-STORMWATER DISCHARGES ARE ANTICIPATED.

2E. APPROVED STATE, LOCAL PLANS, OR STORMWATER PERMITS:

3. MAINTENANCE:
ALL OF THE CONTROLS SHALL BE MAINTAINED AT ALL TIMES. IF A REPAIR IS NECESSARY, IT WILL BE DONE AT THE EARLIEST DATE POSSIBLE. BUT NO LATER THAN (7) CALENDAR DAYS AFTER THE SURROUNDING EXPOSED AREA HAS DRIED SUFFICIENTLY TO PREVENT FURTHER DAMAGE FROM HEAVY EQUIPMENT.

4. INSPECTION:
ALL CONTROLS SHALL BE INSPECTED WEEKLY BY THE CONTRACTOR AS WELL AS AFTER 0.25" OR MORE OF RAIN. AN INSPECTION AND MAINTENANCE REPORT WILL BE MADE PER EACH INSPECTION. BASED ON INSPECTION RESULTS THE CONTROLS SHALL BE REVISED PER THE INSPECTION REPORTS.

A. THE CONTRACTOR SHALL INITIATE REPAIRS WITHIN 24 HOURS OF INSPECTION THAT INDICATE ITEMS ARE NOT IN GOOD WORKING ORDER. TO COMPLY, THE CONTRACTOR SHALL INSTALL AND MAINTAIN RAIN GAGES AND DAILY RAINFALL RECORDS. WHERE SITES HAVE BEEN PERMANENTLY STABILIZED, INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH. THE CONTRACTOR SHALL ALSO INSPECT AND CERTIFY THAT CONTROLS INSTALLED IN THE FIELD AGREE WITH THE LATEST STORMWATER POLLUTION PREVENTION PLAN.

B. IF INSPECTIONS INDICATE THAT THE INSTALLED STABILIZATION AND STRUCTURAL PRACTICES ARE NOT SUFFICIENT TO MINIMIZE EROSION, RETAIN SEDIMENT, AND PREVENT DISCHARGING POLLUTANTS, THE CONTRACTOR SHALL PROVIDE ADDITIONAL MEASURES, AS NEEDED.

C. RECORDS OF THE INSPECTION AND THE CONSTRUCTION PERMIT MUST BE MAINTAINED AT THE CONSTRUCTION SITE AND BE READILY AVAILABLE FOR INSPECTION.

5. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING COVERAGE UNDER THE GENERAL PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES PRIOR TO START OF CONSTRUCTION OR ANY DISTURBANCE OF LAND GREATER THAN ONE ACRE. THE CONTRACTOR WILL FORWARD A COPY OF THE PERMIT AND WILL PROVIDE 24 HOUR NOTIFICATION TO THE CITY AT 800.233.5100 PRIOR TO COMMENCEMENT OF WORK. ALL REQUIRED ELEMENTS OF THE STORMWATER POLLUTION PREVENTION PLAN MUST BE IN PLACE PRIOR TO COMMENCEMENT OF CONSTRUCTION. FAILURE TO COMPLY COULD RESULT IN CODE ENFORCEMENT ACTION AND FINES.

STORMWATER POLLUTION PREVENTION PLAN SERENE LIFE BEER GARDEN CHIPLEY, WASHINGTON CO, FLORIDA



TRI-STATE Companies, Inc.
914 Island Road
Chipley, Florida 32428
Phone: 904-634-1972 Email: tri-state@tri-state.com
H-447610-001-001-001 Document No. 11-20060002

Issue	
Rev	
MTB	
Project/Utility	LP23002
Drawn by	AGC
Checked by	EAP
Approved by	TCS
SWPPP	


TS&E

TRI-STATE Companies, Inc.
 614 Island Road, Suite 300B
 Palm Beach, FL 33480
 Phone: 561-833-7522 Fax: 561-833-7523
 A Longtime Division Since 1958

**STORMWATER POLLUTION PREVENTION
 PLAN
 SERENE LIFE BEER GARDEN
 CHIPLEY, WASHINGTON CO., FLORIDA**

SWPPP(2)


Project	
Client	TS&E
Inspector	LP23002
Drawn By	ALC
Reviewed By	EAP
Approved	TCS



TEMPORARY DIVERSION DAM
 SEE




BALES BACKED BY FENCE
 SEE




**PROTECTION AROUND INLETS
 OR SIMILAR STRUCTURES**
 SEE




TYPE IV SILT FENCE
 SEE




SILT FENCE APPLICATIONS
 SEE




BALES BACKED BY FENCE
 SEE



**TEMPORARY GRAVEL
 CONSTRUCTION ENTRANCE**
 SEE



SALT FENCE
 SEE



**RECOMMENDED SPACING FOR TYPE I AND TYPE II
 HAY BALE BARRIERS AND TYPE IV SILT FENCES**
 SEE


TSC

TRI-STATE Companies, Inc.
 824 Island Road, Chipley, Florida 32429
 Phone 904-631-1722 Fax 904-631-1723
 www.tri-state.com

EXISTING CONDITIONS
 SERENE LIFE BEER GARDEN
 CHIPLEY, WASHINGTON CO., FLORIDA

LEGAL DESCRIPTION:
 LOTS 11 AND 12, LESS THE WEST 33 FEET OF LOT 12, IN THE CITY OF
 CHIPLEY, EAST OF AND ABUTTING SIXTH ST AND IN SW 1/4 OF NE 1/4 OF
 SECTION, TOWNSHIP 4 NORTH, RANGE 13 WEST, ACCORDING TO THE
 MAP OF CHIPLEY, LESS AND EXCEPT LOTS 13 IN OR BOOK 88E,
 PAGE 283.

WATTS AVENUE
20' RIGHT-OF-WAY
 CERTIFIED TO:
 SUSANNA GURLEY




- ABBREVIATION DESCRIPTION**
- AL - ALLEY
 - AR - ARROW
 - BL - BLOCK
 - BR - BRIDGE
 - CA - CANAL
 - CD - CROWN
 - CH - CHURCH
 - CL - CLOTHES
 - CM - CEMENT
 - CO - COAST
 - CR - CREEK
 - CS - COUNTRY
 - CU - CULVERT
 - CV - CANYON
 - DC - DITCH
 - DE - DECK
 - DI - DIKE
 - DL - DRAINAGE
 - DM - DAM
 - DN - DOWN
 - DO - DOCK
 - DP - DRAINAGE
 - DR - DRIVE
 - DS - DRAINAGE
 - DT - DITCH
 - DU - DRAINAGE
 - EA - EARTH
 - EB - EARTH
 - EC - EARTH
 - ED - EARTH
 - EE - EARTH
 - EF - EARTH
 - EG - EARTH
 - EH - EARTH
 - EI - EARTH
 - EJ - EARTH
 - EK - EARTH
 - EL - EARTH
 - EM - EARTH
 - EN - EARTH
 - EO - EARTH
 - EP - EARTH
 - EQ - EARTH
 - ER - EARTH
 - ES - EARTH
 - ET - EARTH
 - EU - EARTH
 - EV - EARTH
 - EW - EARTH
 - EX - EARTH
 - EY - EARTH
 - EZ - EARTH
 - FA - FARM
 - FB - FARM
 - FC - FARM
 - FD - FARM
 - FE - FARM
 - FF - FARM
 - FG - FARM
 - FH - FARM
 - FI - FARM
 - FJ - FARM
 - FK - FARM
 - FL - FARM
 - FM - FARM
 - FN - FARM
 - FO - FARM
 - FP - FARM
 - FQ - FARM
 - FR - FARM
 - FS - FARM
 - FT - FARM
 - FU - FARM
 - FV - FARM
 - FW - FARM
 - FX - FARM
 - FY - FARM
 - FZ - FARM
 - GA - GARDEN
 - GB - GARDEN
 - GC - GARDEN
 - GD - GARDEN
 - GE - GARDEN
 - GF - GARDEN
 - GG - GARDEN
 - GH - GARDEN
 - GI - GARDEN
 - GJ - GARDEN
 - GK - GARDEN
 - GL - GARDEN
 - GM - GARDEN
 - GN - GARDEN
 - GO - GARDEN
 - GP - GARDEN
 - GQ - GARDEN
 - GR - GARDEN
 - GS - GARDEN
 - GT - GARDEN
 - GU - GARDEN
 - GV - GARDEN
 - GW - GARDEN
 - GX - GARDEN
 - GY - GARDEN
 - GZ - GARDEN
 - HA - HALL
 - HB - HALL
 - HC - HALL
 - HD - HALL
 - HE - HALL
 - HF - HALL
 - HG - HALL
 - HH - HALL
 - HI - HALL
 - HJ - HALL
 - HK - HALL
 - HL - HALL
 - HM - HALL
 - HN - HALL
 - HO - HALL
 - HP - HALL
 - HQ - HALL
 - HR - HALL
 - HS - HALL
 - HT - HALL
 - HU - HALL
 - HV - HALL
 - HW - HALL
 - HX - HALL
 - HY - HALL
 - HZ - HALL
 - IA - ISLAND
 - IB - ISLAND
 - IC - ISLAND
 - ID - ISLAND
 - IE - ISLAND
 - IF - ISLAND
 - IG - ISLAND
 - IH - ISLAND
 - II - ISLAND
 - IJ - ISLAND
 - IK - ISLAND
 - IL - ISLAND
 - IM - ISLAND
 - IN - ISLAND
 - IO - ISLAND
 - IP - ISLAND
 - IQ - ISLAND
 - IR - ISLAND
 - IS - ISLAND
 - IT - ISLAND
 - IU - ISLAND
 - IV - ISLAND
 - IW - ISLAND
 - IX - ISLAND
 - IY - ISLAND
 - IZ - ISLAND
 - JA - JAIL
 - JB - JAIL
 - JC - JAIL
 - JD - JAIL
 - JE - JAIL
 - JF - JAIL
 - JG - JAIL
 - JH - JAIL
 - JI - JAIL
 - JJ - JAIL
 - JK - JAIL
 - JL - JAIL
 - JM - JAIL
 - JN - JAIL
 - JO - JAIL
 - JP - JAIL
 - JQ - JAIL
 - JR - JAIL
 - JS - JAIL
 - JT - JAIL
 - JU - JAIL
 - JV - JAIL
 - JW - JAIL
 - JX - JAIL
 - JY - JAIL
 - JZ - JAIL
 - KA - KAYAK
 - KB - KAYAK
 - KC - KAYAK
 - KD - KAYAK
 - KE - KAYAK
 - KF - KAYAK
 - KG - KAYAK
 - KH - KAYAK
 - KI - KAYAK
 - KJ - KAYAK
 - KK - KAYAK
 - KL - KAYAK
 - KM - KAYAK
 - KN - KAYAK
 - KO - KAYAK
 - KP - KAYAK
 - KQ - KAYAK
 - KR - KAYAK
 - KS - KAYAK
 - KT - KAYAK
 - KU - KAYAK
 - KV - KAYAK
 - KW - KAYAK
 - KX - KAYAK
 - KY - KAYAK
 - KZ - KAYAK
 - LA - LAKE
 - LB - LAKE
 - LC - LAKE
 - LD - LAKE
 - LE - LAKE
 - LF - LAKE
 - LG - LAKE
 - LH - LAKE
 - LI - LAKE
 - LJ - LAKE
 - LK - LAKE
 - LL - LAKE
 - LM - LAKE
 - LN - LAKE
 - LO - LAKE
 - LP - LAKE
 - LQ - LAKE
 - LR - LAKE
 - LS - LAKE
 - LT - LAKE
 - LU - LAKE
 - LV - LAKE
 - LW - LAKE
 - LX - LAKE
 - LY - LAKE
 - LZ - LAKE
 - MA - MALL
 - MB - MALL
 - MC - MALL
 - MD - MALL
 - ME - MALL
 - MF - MALL
 - MG - MALL
 - MH - MALL
 - MI - MALL
 - MJ - MALL
 - MK - MALL
 - ML - MALL
 - MM - MALL
 - MN - MALL
 - MO - MALL
 - MP - MALL
 - MQ - MALL
 - MR - MALL
 - MS - MALL
 - MT - MALL
 - MU - MALL
 - MV - MALL
 - MW - MALL
 - MX - MALL
 - MY - MALL
 - MZ - MALL
 - NA - NATURE
 - NB - NATURE
 - NC - NATURE
 - ND - NATURE
 - NE - NATURE
 - NF - NATURE
 - NG - NATURE
 - NH - NATURE
 - NI - NATURE
 - NJ - NATURE
 - NK - NATURE
 - NL - NATURE
 - NM - NATURE
 - NN - NATURE
 - NO - NATURE
 - NP - NATURE
 - NQ - NATURE
 - NR - NATURE
 - NS - NATURE
 - NT - NATURE
 - NU - NATURE
 - NV - NATURE
 - NW - NATURE
 - NX - NATURE
 - NY - NATURE
 - NZ - NATURE
 - OA - OAK
 - OB - OAK
 - OC - OAK
 - OD - OAK
 - OE - OAK
 - OF - OAK
 - OG - OAK
 - OH - OAK
 - OI - OAK
 - OJ - OAK
 - OK - OAK
 - OL - OAK
 - OM - OAK
 - ON - OAK
 - OO - OAK
 - OP - OAK
 - OQ - OAK
 - OR - OAK
 - OS - OAK
 - OT - OAK
 - OU - OAK
 - OV - OAK
 - OW - OAK
 - OX - OAK
 - OY - OAK
 - OZ - OAK
 - PA - PARK
 - PB - PARK
 - PC - PARK
 - PD - PARK
 - PE - PARK
 - PF - PARK
 - PG - PARK
 - PH - PARK
 - PI - PARK
 - PJ - PARK
 - PK - PARK
 - PL - PARK
 - PM - PARK
 - PN - PARK
 - PO - PARK
 - PP - PARK
 - PQ - PARK
 - PR - PARK
 - PS - PARK
 - PT - PARK
 - PU - PARK
 - PV - PARK
 - PW - PARK
 - PX - PARK
 - PY - PARK
 - PZ - PARK
 - QA - QUARTER
 - QB - QUARTER
 - QC - QUARTER
 - QD - QUARTER
 - QE - QUARTER
 - QF - QUARTER
 - QG - QUARTER
 - QH - QUARTER
 - QI - QUARTER
 - QJ - QUARTER
 - QK - QUARTER
 - QL - QUARTER
 - QM - QUARTER
 - QN - QUARTER
 - QO - QUARTER
 - QP - QUARTER
 - QQ - QUARTER
 - QR - QUARTER
 - QS - QUARTER
 - QT - QUARTER
 - QU - QUARTER
 - QV - QUARTER
 - QW - QUARTER
 - QX - QUARTER
 - QY - QUARTER
 - QZ - QUARTER
 - RA - RAILROAD
 - RB - RAILROAD
 - RC - RAILROAD
 - RD - RAILROAD
 - RE - RAILROAD
 - RF - RAILROAD
 - RG - RAILROAD
 - RH - RAILROAD
 - RI - RAILROAD
 - RJ - RAILROAD
 - RK - RAILROAD
 - RL - RAILROAD
 - RM - RAILROAD
 - RN - RAILROAD
 - RO - RAILROAD
 - RP - RAILROAD
 - RQ - RAILROAD
 - RR - RAILROAD
 - RS - RAILROAD
 - RT - RAILROAD
 - RU - RAILROAD
 - RV - RAILROAD
 - RW - RAILROAD
 - RX - RAILROAD
 - RY - RAILROAD
 - RZ - RAILROAD
 - SA - SAND
 - SB - SAND
 - SC - SAND
 - SD - SAND
 - SE - SAND
 - SF - SAND
 - SG - SAND
 - SH - SAND
 - SI - SAND
 - SJ - SAND
 - SK - SAND
 - SL - SAND
 - SM - SAND
 - SN - SAND
 - SO - SAND
 - SP - SAND
 - SQ - SAND
 - SR - SAND
 - SS - SAND
 - ST - SAND
 - SU - SAND
 - SV - SAND
 - SW - SAND
 - SX - SAND
 - SY - SAND
 - SZ - SAND
 - TA - TANK
 - TB - TANK
 - TC - TANK
 - TD - TANK
 - TE - TANK
 - TF - TANK
 - TG - TANK
 - TH - TANK
 - TI - TANK
 - TJ - TANK
 - TK - TANK
 - TL - TANK
 - TM - TANK
 - TN - TANK
 - TO - TANK
 - TP - TANK
 - TQ - TANK
 - TR - TANK
 - TS - TANK
 - TT - TANK
 - TU - TANK
 - TV - TANK
 - TW - TANK
 - TX - TANK
 - TY - TANK
 - TZ - TANK
 - UA - UMBEL
 - UB - UMBEL
 - UC - UMBEL
 - UD - UMBEL
 - UE - UMBEL
 - UF - UMBEL
 - UG - UMBEL
 - UH - UMBEL
 - UI - UMBEL
 - UJ - UMBEL
 - UK - UMBEL
 - UL - UMBEL
 - UM - UMBEL
 - UN - UMBEL
 - UO - UMBEL
 - UP - UMBEL
 - UQ - UMBEL
 - UR - UMBEL
 - US - UMBEL
 - UT - UMBEL
 - UU - UMBEL
 - UV - UMBEL
 - UW - UMBEL
 - UX - UMBEL
 - UY - UMBEL
 - UZ - UMBEL
 - VA - VALLEY
 - VB - VALLEY
 - VC - VALLEY
 - VD - VALLEY
 - VE - VALLEY
 - VF - VALLEY
 - VG - VALLEY
 - VH - VALLEY
 - VI - VALLEY
 - VJ - VALLEY
 - VK - VALLEY
 - VL - VALLEY
 - VM - VALLEY
 - VN - VALLEY
 - VO - VALLEY
 - VP - VALLEY
 - VQ - VALLEY
 - VR - VALLEY
 - VS - VALLEY
 - VT - VALLEY
 - VU - VALLEY
 - VV - VALLEY
 - VW - VALLEY
 - VX - VALLEY
 - VY - VALLEY
 - VZ - VALLEY
 - WA - WALL
 - WB - WALL
 - WC - WALL
 - WD - WALL
 - WE - WALL
 - WF - WALL
 - WG - WALL
 - WH - WALL
 - WI - WALL
 - WJ - WALL
 - WK - WALL
 - WL - WALL
 - WM - WALL
 - WN - WALL
 - WO - WALL
 - WP - WALL
 - WQ - WALL
 - WR - WALL
 - WS - WALL
 - WT - WALL
 - WU - WALL
 - WV - WALL
 - WW - WALL
 - WX - WALL
 - WY - WALL
 - WZ - WALL
 - XA - X-ROAD
 - XB - X-ROAD
 - XC - X-ROAD
 - XD - X-ROAD
 - XE - X-ROAD
 - XF - X-ROAD
 - YG - YARD
 - YH - YARD
 - YI - YARD
 - YJ - YARD
 - YK - YARD
 - YL - YARD
 - YM - YARD
 - YN - YARD
 - YO - YARD
 - YP - YARD
 - YQ - YARD
 - YR - YARD
 - YS - YARD
 - YT - YARD
 - YU - YARD
 - YV - YARD
 - YW - YARD
 - YX - YARD
 - YY - YARD
 - YZ - YARD
 - ZA - ZONE
 - ZB - ZONE
 - ZC - ZONE
 - ZD - ZONE
 - ZE - ZONE
 - ZF - ZONE
 - ZG - ZONE
 - ZH - ZONE
 - ZI - ZONE
 - ZJ - ZONE
 - ZK - ZONE
 - ZL - ZONE
 - ZM - ZONE
 - ZN - ZONE
 - ZO - ZONE
 - ZP - ZONE
 - ZQ - ZONE
 - ZR - ZONE
 - ZS - ZONE
 - ZT - ZONE
 - ZU - ZONE
 - ZV - ZONE
 - ZW - ZONE
 - ZX - ZONE
 - ZY - ZONE
 - ZZ - ZONE

SURVEY NOTES
 CONCRETE WALL CROSSING PROPERTY LINE
 ON WESTERN SIDE OF PROPERTY.
 AS-BUILT CROSSING PROPERTY LINE
 ON NORTHERLY AND SOUTHERLY SIDE OF
 THE PROPERTY.


COMMUNITY NUMBER: 12025
 PANEL: 0070 SUFFIX: C
 L.R.M. DATE: N/A
 FLOOD ZONE: X
 FIELD WORK: 5/1/2024
 PROPERTY ADDRESS:
 781 MAIN STREET
 CHIPLEY, FL 32428
 SURVEY NUMBER: 83 562
 CLIENT FILE NUMBER: N/A

**LOCATION
 OF EXIST
 HYDRANT**






DEMO & EROSION CONTROL PLAN

[illegible]

SITE DATA SUMMARY

PARCEL ID: 00000000-00-1328-0001
 PROJECT AREA: 0.36 AC / 15,778.5 SF
 (INCLUDING 0.185 AC / 8,058 SF OFFSITE)
 FUTURE LAND USE: COMMERCIAL
 FLOOD ZONE: ZONE X
 BUILDING SETBACKS/BUFFERS:
 REQUIRED 25'
 PROVIDED 27'
 FRONT 5'
 REAR 10'
 W SIDE 10'
 E SIDE 18'
 SITE INTENSITY:
 ALLOWED = 35%
 PROVIDED = 34%
 PARKING SPACES:
 REQUIRED - 1 SPACE PER 4 SEATS * 60 SEATS = 15 SPACES
 PROVIDED = 15 SPACES
 SEAT TOTAL
 BAR: 18 SEATS
 LOUNGE #1: 2 SEATS
 LOUNGE #2: 4 SEATS
 STAGE: 20 SEATS
 PICNIC: 16 SEATS
 FLOOR AREA RATIO:
 PROVIDED = 1.580 SF / [0.46 AC x (1 AC/43,560 SF)] = 0.10
 BUILDING TOTAL
 BATH: 253 SF
 BAR: 928 SF
 OFFICE: 300 SF
 STORAGE: 200 SF
 IMPERVIOUS SURFACE RATIO:
 ALLOWED = 85%
 PROVIDED = 42%
 8'0" IMP SURFACE / 23,758 SF PROJECT AREA = 0.337
 OR 34%
 OPEN SPACE (PERMEABLE AREA):
 15,771 SF OPEN SPACE / 23,758 SF PROJECT AREA = 0.66
 OR 66%



PROPOSED SITE PLAN

CHIPLEY, WASHINGTON CO., FLORIDA

TSL


TRI-STATE Companies, Inc.
 134 West 10th Street, Suite 200
 Oklahoma City, Oklahoma 73102
 (405) 233-1111 FAX (405) 233-1112
 11/20/2017 10:24:22 AM 11/20/2017 10:24:22 AM

DRAINAGE PLAN
 SERENE LIFE BEER GARDEN SERENE
 CHIPLEY, WASHINGTON CO., FLORIDA

Notes

1" = 20'
 LP23502
 AGC
 EAP
 TCS

3A




TSL

TRI-STATE Companies, Inc.
 134 Wharf Road
 Chipley, FL 32429
 904.857.2800
 www.tri-state.com

UTILITY PLAN SERENE LIFE BEER GARDEN CHIPLEY, WASHINGTON CO., FLORIDA


Scale
 1" = 20'
 Project No.
 LP23072
 Date
 1/2/20
 Author
 AGC
 Checker
 BAP
 Approver
 TCS
 Date
 3/8



LANDSCAPING & LIGHTNING PLAN

CHIPLEY, WASHINGTON CO., FLORIDA

Name
1" = 20'
Patient Number
LP23002
Dobson Rd
AGC
Revised by
EAP
Approved by
TCS
Sheet Number
4A



**TRAFFIC ANALYSIS
SERENE LIFE BEER GARDEN
CITY OF CHIPLEY DEVELOPMENT ORDER**

INTRODUCTION

The following is a traffic concurrency analysis of the proposed construction of a new nano brewery/beer garden development located on the south side of Watts Avenue, just SW of the Watts Avenue and 7th Street intersection in Chipley, Washington County, Florida. The property is currently undeveloped. The proposed development of the site will consist of 1,580 SF of brewery, seating and associated improvements.

TRIPS GENERATED

For the proposed use, the projected number of PM peak hour trips generated is determined using the Institute of Transportation Engineers publication *Trip Generation*, 11th Edition. The total number of PM Peak Hour trips generated is calculated using the average rate for the peak hour of adjacent street traffic (one hour between 4:00 and 6:00 PM), as shown in the table below.

ITE TRIP CODE	PROPOSED DEVELOPMENT	PROPOSED IMPACT (X) per 1,000 SF GFA	TRIP GENERA TION EQN / AVG RATE	PM PEAK HOUR TRIPS (T)	ENTERING (66%)	EXITING (34%)
271	Brewery Tap Room	$X = 1580/1000$ $= 1.58$	$T = 9.83X$	15.53	11	5

Total PM Peak Hour Trips (T) = $9.83(1.58) = 15.53 = 16$

PROJECT TRAFFIC DISTRIBUTION

The entering and exiting ratios shown for the Brewery Tap Room ITE code #271 are 66% and 34%, respectively. There is a total of approximately 11 trips which will enter the development during the PM peak hour, and 5 trips that will exit the development.

CONCLUSION

The proposed development will generate 16 new PM peak hour trips. Based on the trip distribution, it is not anticipated that segments of roadways will be impacted prior to all Washington County concurrency requirements being met.

SERENE LIFE BEER GARDEN
ERP STORMWATER CALCULATIONS
TSC PROJECT #24002
PREPARED FOR: ANTHONY THOMPSON

This spreadsheet is intended to be used in conjunction with the Environmental Resources Permit Applicant's Handbook Volume 2 published by the Department of Environmental Protection and the Northwest Florida Water Management District. All referenced figures and equations can be found within Chapter 13 of this handbook.

Step 1- Determine Vr

Project Area = 0.46 acres
(0.36 AC Site / 0.10 AC Offsite) 19,854 ft²

Seasonal High GWTElevation (ft) = 96.50

Hydrologic Soil Group (HSG): B
Soil Type: Loamy Sand

PRE-CONDITION

Description	Area (ft ²)	Curve Number (CN)
Impervious	0	98
Semi-impervious	0	76
Stormwater Pond	0	98
Pervious	19,854	45
Sum =	19,854	

Pre-Condition Weighted Composite Curve Number (CN) = 45

POST-CONDITION

Calculate the Composite Runoff Coefficient (C), Required Treatment Depth and Composite Curve Number (CN)

Description	Area (ft ²)	C value	Weighted Area (ft ²)	Curve Number (CN)
Impervious	3,771	0.95	3,582	98
Semi-impervious	3,765	0.7	2,635	76
Stormwater Pond	1,838	0.3	551	100
Pervious	10,481	0.3	3,144	30
Sum =	19,854		9,913	

Weighted Runoff Coefficient (C) = 0.5
Therefore, required depth of treatment (inches) per ERP = 0.5
Required depth of treatment (inches) per County = 1.0
Weighted Composite Curve Number (CN) = 58

Vr = Treatment Volume Required by ERP or County (whichever is greater)

Vr = 827 ft³

SERENE LIFE BEER GARDEN
 ERP STORMWATER CALCULATIONS
 TSC PROJECT #24002
 PREPARED FOR: ANTHONY THOMPSON

Step 2 - Determine Vp and Check for Lateral Analysis

Pond Data:					
Stage (ft)	Area (ft ²)	Volume (ft ³)	Cumulative Volume (ft ³)	Description	
97.00	65	0.00	0.00	Bottom of Pond	
98.00	320	192.50	192.50		
99.00	705	512.50	705.00		
99.25	480	148.09	853.09	Approximate Treatment Elevation	
100.00	1,214	959.50	1664.50		
101.00	1,838	1526.00	3190.50	Top of Pond	

Total Volume provided is 3,190.5 ft³. The required volume 827 ft³ is achieved between the 99.0' and 100.0' contour, therefore interpolating to find height of treatment:

$$h_1 = \frac{(ELEV_A - ELEV_B) \times (V_T - V_B)}{(V_A - V_B)} + ELEV_B$$

ELEV _A =	100.00	ft
ELEV _B =	99.00	ft
V _T =	827.25	ft ³
V _A =	1,664.50	ft ³
V _B =	705.00	ft ³
h _T =	99.13	ft

*ELEV_A is the upper boundary of the contour range in which treatment volume is achieved and ELEV_B is the lower boundary. V_A and V_B are the respective cumulative volumes provided at those elevations.

Height of treatment is 16.00', therefore solving for the treatment depth, h_v:

$$h_v = \text{Height of Treatment} - \text{Pond Bottom}$$

$$h_v = 1.13 \text{ ft}$$

Height of water required to saturate the soil, h_u (from Eq 13-4):

$$h_u = \left(\frac{f}{1-h_b} \right)$$

$$f = \text{fillable porosity (0.20 for Silty/Slightly Silty Sands and 0.30 for Fine Sands)}$$

$$= \frac{0.2}{0.2}$$

$$h_b = \text{height of basin above bottom of SHGWT} =$$

$$h_u = 0.3 \text{ ft}$$

SERENE LIFE BEER GARDEN
ERP STORMWATER CALCULATIONS
TSC PROJECT #24002
PREPARED FOR: ANTHONY THOMPSON

Section 13.3.3 of the handbook (Volume 2) states that there are two conditions under which recovery of the treatment volume will occur entirely through vertical flow conditions. Checking these conditions:

Condition 1: Height of treatment volume, $h_v \leq h_u$

Condition met?

Total volume of water required to saturate the soil below the basin, V_u (Eq. 13-3):

$$V_u = (A_b)(h_b)(f)$$

$$A_b = \text{pond bottom area} =$$

$$V_u =$$

$$320 \text{ ft}^2$$

$$1.13$$

Condition 2: Treatment volume, $V_r \leq V_u$

Condition met?

If either of these conditions are met, then only vertical analysis is required. However, if both conditional checks result in "No", then lateral analysis will be required.

SERENE LIFE BEER GARDEN
ERP STORMWATER CALCULATIONS
TSC PROJECT #24002
PREPARED FOR: ANTHONY THOMPSON

Step 3- Infiltration and Recovery Time

Since the infiltration rate was obtained through a DRI, the resulting rate is considered an unsaturated infiltration rate.

So $K_{vU} = 12$ ft/day

The design infiltration rate is the unsaturated rate with an applied factor of safety (Eq. 13-1).

So $I_d = K_{vU}/FS$
 $FS = 2$
 $I_d = 6$ ft/day

The time to saturate the soil mass below the basin, T_{SAT} (Eq. 13-2):

$T_{SAT} = \frac{(r)(h_b)}{I_d}$
 $f = 0.2$
 $h_b = 1.50$ ft.
 So $T_{SAT} = 0.05$ days

The required lateral treatment volume, $V_{TLateral}$ is the remaining volume after the soil below the basin has become saturated.

So $V_{TLateral} = V_T - V_U$
 $V_{TLateral} = 731.25$ ft³

Interpolating between the 99' and 100' contour to determine the lateral treatment elevation, $h_{TLateral}$:

$h_{TLateral} = (ELEV_A - ELEV_b) \times \frac{(V_{TLateral} - V_b)}{(V_A - V_b)} + ELEV_b$
 *ELEV_A is the upper boundary of the contour range in which lateral treatment volume is achieved and ELEV_b is the lower boundary. V_A and V_b are the respective cumulative volumes provided at those elevations.

ELEV_A = 100.00 ft
 ELEV_b = 99.00 ft
 $V_{TLateral} = 731.25$ ft³
 $V_A = 1,664.50$ ft³
 $V_b = 705.00$ ft³
 $h_{TLateral} = 99.03$ ft

SERENE LIFE BEER GARDEN
ERP STORMWATER CALCULATIONS
TSC PROJECT #24002
PREPARED FOR: ANTHONY THOMPSON

Step 4- Determination of P_y and F_x :

At time $t = t_{\text{del}}, h_c$ (height of water in basin above the initial groundwater level) is equal to h_b

So $h_c = 1.50 \text{ ft.}$

F

The height of water in the basin at the start of saturated lateral flow, h_2 is found by:

$$h_2 = h_{\text{lateral}} - \text{bottom of basin}$$

$$h_2 = 1.03 \text{ ft}$$

According to Equation 13-8, the height of water in the basin above the initial groundwater level at the start of saturated lateral flow, H_1 is found by:

$$H_1 = h_2 + h_b$$

$$H_1 = 2.53 \text{ ft.}$$

According to Eqn. 13-6, P_y (dimensionless parameter representing percent of water level decline below a maximum level) is found by:

$$P_y = h_c/H_1$$

$$P_y = 0.593505155$$

Calculating F_x (dimensionless parameter representing physical and hydraulic characteristics of the retention basin and effective aquifer system) from Figure 13-7:

Pond Dimensions:

$$\text{Length (L)} = 62 \text{ ft.}$$

$$\text{Width (W)} = 36 \text{ ft.}$$

So $L/W = 1.722222222$

*Consulting Figure 13-5, 13-6, 13-7, or 13-8, $F_x = 1.2$ *depending on fillable porosity, f

As there is no confining layer near the bottom of the basin, it can be assume 50 ft.

SERENE LIFE BEER GARDEN
ERP STORMWATER CALCULATIONS
TSC PROJECT #24002
PREPARED FOR: ANTHONY THOMPSON

So the average saturated thickness, D , is given by: (Eq. 13-7)

$$D = H + (h_d/2)$$

$$D = \boxed{50.75 \text{ ft.}}$$

The time to recover the remaining treatment volume under lateral saturated flow conditions, t is found using Eq. 13-9:

$$t = \frac{w^2}{(4)(K_H)(D)(F_x)}$$

$$\begin{aligned} K_H &= \boxed{12 \text{ ft./day}} \\ w &= \boxed{36 \text{ ft.}} \\ D &= \boxed{50.75 \text{ ft.}} \\ F_x &= \boxed{1.2} \end{aligned}$$

* K_H is to be provided by Geotechnical Engineer. If this value is not available, K_{H1} should be used to remain conservative.

So $t = \boxed{0.369458128 \text{ days}}$

The total time of recovery in the basin is calculated as follows:

$$T_{\text{total}} = T_{\text{SAT}} + t$$

$$\begin{aligned} T_{\text{SAT}} &= \quad \quad \quad 0.05 \text{ days} \\ t &= \quad \quad \quad 0.369458128 \text{ days} \\ \text{So } T_{\text{total}} &= \boxed{0.419458128 \text{ days}} \\ &= \boxed{10.06699507 \text{ hours}} \end{aligned}$$

Therefore, the time required to recover the treatment volume is less than the required 72 hours and the design is sufficient.

**SERENE LIFE BEER GARDEN
FIRE FLOW CALCULATIONS**

Building Foot Print Length = 24 Width = 24 Sq. Ft. = 576

Total Sq. Ft. = 576

*Add height for
each floor

Ceiling Height = 12

Cu. Ft. = 6,912

*Note: take 1/2 of
pitched roof height

Attic Height =

Cu. Ft. = -

Additional space
(porch, etc.)

Length

Width

Height

Cu. Ft. = -

Total Cu. Ft. = 6,912

Total Cu. Ft. = 6,912 OHC = 3 Gallons = 2,304

Note Occupancy Hazard Classification number is 7 for dwellings, small office complexes and similar constructed facilities. Refer to NFPA 1142 for other types of structures.

Gallons = 2,304 CCN = 1 Gallons = 2,304

Note Type II Construction .75. Ex: Cinderblock, approved non-combustible material.
Type III Construction 1.0. Ex: Brick veneer, approved non-combustible material etc.
Type V Construction 1.5. **Dwellings max 1.0 CCN per NFPA 1142**

Gallons = 2,304 Exp = 1 Gallons = 2,304.00

Note Any structure within 50' of burn structure is considered an exposure and requires total gallons to be multiplied by 1.5. **DO NOT** add .5 for each additional exposures.

Total Gallons Required	GPM
Up to 2,499 Gallons	250 GPM
2,500 to 9,999 Gallons	500 GPM
10,000 to 19,999 Gallons	750 GPM
20,000 or more	1000 GPM

Total GPM for NFPA 1142 250

In accordance with NFPA 1403, an additional water supply in the amount of 50% of total required fire flow must be available to handle unforeseen situations.

Gallons = 2,304 at 250 GPM for about 9 Minutes

2,304 Gallons x 1.5 = 3,456
NFPA 1403
requirement

SERENE LIFE BEER GARDEN

EXISTING UTILITIES MAP

77

EXISTING
FIRE
HYDRANT

EXISTING
WATER
MAIN

EXISTING
SANITARY
SEWER

Legend

- EXISTING SANITARY SEWER
- EXISTING WATER MAIN

Office Pk Dr

Watts Ave

Watts Ave

7th St



100 ft

Google Earth

Image 2/25/2005

