



Always a Better Plan

100 Camelot Drive  
Fond du Lac, WI 54935  
920-926-9800  
excelengineer.com

PROJECT INFORMATION

PROPOSED BUILDING ADDITION TO:  
**KUNES FOX VALLEY RV**  
2615 WEST AMERICAN DRIVE • TOWN OF CLAYTON, WI

PROFESSIONAL SEAL

PRELIMINARY DATES

NOV. 6, 2023

NOT FOR CONSTRUCTION

JOB NUMBER

230322300

SHEET NUMBER

A1.1

FIRST FLOOR PLAN

GENERAL NOTES

- ALL INTERIOR DIMS. ARE FROM FACE-OF-STUD TO FACE-OF-STUD.
- ALL INTERIOR WALLS TO BE 3 5/8" OR 6" METAL STUDS @ 16" O.C. (SEE FLOOR PLAN FOR SIZE) W/ 5/8" GYPSUM BOARD BOTH SIDES - EXTEND TO BOTTOM CHORD OF TRUSSES.
- PROVIDE 3 1/2" SOUND BATT INSULATION AROUND PERIMETER OF OFFICE WALLS.
- PROVIDE WOOD BLOCKING FOR ANY FURNISHINGS BY OWNER. (VERIFY LOCATIONS)
- SEE SHEET A4 FOR TYPICAL CONTROL JOINT DETAILS.
- SEE SHEET A5 FOR TYPICAL GUARD POST DETAILS.
- ALL CABINETS AND COUNTERTOPS TO HAVE PLASTIC LAMINATE FRONTS AND TOPS.

SALES & SERVICE COUNTERS

IN RETAIL STORES WHERE COUNTERS HAVE CASH REGISTERS AND ARE PROVIDED FOR SALES OR DISTRIBUTION OF GOODS OR SERVICES TO THE PUBLIC, AT LEAST ONE OF EACH TYPE SHALL HAVE A PORTION OF THE COUNTER WHICH IS AT LEAST 36" IN LENGTH WITH A MAXIMUM HEIGHT OF 36" ABOVE THE FINISH FLOOR. COUNTER SHALL BE ON AN ACCESSIBLE ROUTE COMPLYING WITH A.D.A. GUIDELINE 4.3.

SYMBOLS LEGEND

- 1 - INTERIOR WALL TYPES  
- SEE A4 FOR EXTERIOR WALL TYPES
- EXIT SIGNAGE
- FIRE EXTINGUISHER  
- SEE A5 SHEETS
- FIRE EXTINGUISHER w/ CABINET  
- SEE A5 SHEETS
- GUARD POST/GOAL POST DESIGNATION  
- SEE SHEET A5 FOR DETAILS
- EXISTING WALL TO REMAIN
- STUD WALL
- C.M.U. WALL
- EXISTING DOOR TO REMAIN
- NEW DOOR
- EXISTING AREA - NO SCOPE OF WORK

