





W:\PROJECTS\0906\09240497\CADD\Civil3D\Plan\_Sheets\02\_Survey\_Control.dwg, 02\_Survey\_Control.dwg, Plot Date: 7/10/2024 3:30 PM, xrefs: (x-mcm ex clayton-parcels (2)), lammers\_shop\_comps.dwg

HORIZONTAL CONTROL POINTS			
POINT #	NORTHING	EASTING	DESCRIPTION
1	548358.63	796828.11	MAG NAIL
2	546823.44	796809.32	MAG NAIL
4	546390.54	795241.69	MAG NAIL
9	546977.66	794228.10	MAG NAIL
13	547185.52	792606.32	MAG SPIKE
42	546870.68	796691.06	MAG NAIL
43	547609.61	796618.89	MAG NAIL
48	547606.19	796625.47	MAG NAIL
49	547605.18	796119.51	MAG NAIL
50	546926.45	796127.99	3/4" REBAR

VERTICAL BENCHMARK CONTROL		
POINT #	ELEVATION	DESCRIPTION
6	823.39	MAG NAIL IN TREE
7	825.41	MAG NAIL IN TREE
8	827.98	MAG NAIL IN TREE
27	883.14	HYDRANT TAG BOLT
28	864.90	HYDRANT TAG BOLT
29	868.31	HYDRANT TAG BOLT
30	857.21	HYDRANT TAG BOLT
31	844.69	HYDRANT TAG BOLT
32	845.69	HYDRANT TAG BOLT
33	837.69	HYDRANT TAG BOLT
34	834.40	HYDRANT TAG BOLT
35	832.17	HYDRANT TAG BOLT
36	829.37	HYDRANT TAG BOLT
37	828.03	HYDRANT TAG BOLT
38	828.10	HYDRANT TAG BOLT
39	826.35	HYDRANT TAG BOLT
40	826.54	HYDRANT TAG BOLT
41	824.74	HYDRANT TAG BOLT



**NOTE:**  
 PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL VERIFY PROPOSED SITE GRADES BY FIELD CHECKING TWO (2) BENCHMARKS AND A MINIMUM OF ONE (1) SITE FEATURE AS SHOWN ON THESE PLANS. THE CONTRACTOR SHALL ALSO VERIFY HORIZONTAL CONTROL BY FIELD CHECKING SEVERAL CONTROL POINTS AND SHALL IMMEDIATELY NOTIFY MCM MAHON OF ANY DISCREPANCIES.

**VERTICAL DATUM:**  
 ELEVATIONS ARE REFERENCED TO NGS DATA:  
 CONTROL POINT NAME: 4J53  
 POINT ID: DE7567 NAVD 88 DATUM  
 BY GPS OBSERVATION TO ELEVATION = 828.05 (2012 ADJUSTMENT)  
 LEVEL LOOP PER FIELD BOOK 1511 PAGES 30-31 & DIGITAL LEVEL LOOP.  
 REFERENCED TO MCM PROJECT C0023-09-2000286.06  
 FIELD BOOK 1511 PAGES 47-50

**HORIZONTAL DATUM:**  
 COORDINATES ARE REFERENCED TO THE WISCONSIN COUNTY COORDINATE SYSTEM AS PUBLISHED FOR WINNEBAGO COUNTY NAD83 (91)

**MCM MAHON**  
 ENGINEERS ARCHITECTS  
 MCM MAHON ASSOCIATES, INC.  
 1445 MCM MAHON DRIVE NEENAH, WI 54956  
 Mailing: P.O. BOX 1025 NEENAH, WI 54957-1025  
 PH 920.751.4200 FX 920.751.4284 MCMGRP.COM



MCM Mahon Associates, Inc. provides of firm; all instruments of service are prepared by MCM Mahon Associates, Inc. The MCM Mahon Associates, Inc. shall be held responsible for the accuracy of the information contained herein. MCM Mahon Associates, Inc. shall not be held responsible for any use of or reliance on the information contained herein without the prior written consent of MCM Mahon Associates, Inc.

NO.	DATE	REVISION

**TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION**  
**TOWN OF CLAYTON, WINNEBAGO COUNTY, WI**  
**SURVEY CONTROL**

DESIGNED BTH	DRAWN RRS
PROJECT NO. L0906-09-24-00497	
DATE JUNE 2024	
SHEET NO. <b>02</b>	

bhomblin, w:\PROJECTS\0906\092400497\CADD\Civil3D\Plan Sheets\Existing Conditions and demo plan.dwg, 03 existing site & demolition plan, Plot Date: 7/10/2024, 3:30 PM, xrefs: (x=exist topo trident holdings, x=all points trident holdings, x=exist shade/rident holdings, lomers slope\_comp.dwg)



- NOTES:
1. REMOVE TREES, BRUSH.
  2. REMOVE & SALVAGE 10 TREES FOR REPLANTING (SEE LANDSCAPING PLAN).
  3. RELOCATE BURIED UTILITIES. COORDINATE WITH APPROPRIATE UTILITY.
  4. EXCAVATION AREA. STRIP/STOCKPILE TOPSOIL AREA (18,000SF APPROX).
  5. REMOVE CONCRETE.
  6. SAWCUT ASPHALT (BUTT EDGE).
  7. REMOVE GRAVEL DRIVEWAY (AFTER CONSTRUCTION IS COMPLETE).
  8. SALVAGE WALL PACK (SEE PHOTOMETRIC PLAN).
  9. REMOVE EXISTING LANDSCAPING BED.
  10. REMOVE ASPHALT.

**McMAHON**  
ENGINEERS ARCHITECTS

McMAHON ASSOCIATES, INC.  
1445 McMAHON DRIVE NEENAH, WI 54956  
Mailing: P.O. BOX 1025 NEENAH, WI 54957-1025  
PH 920.751.4200 FX 920.751.4284 MCMGRP.COM

McMahon Associates, Inc. provides professional engineering and architectural services. All rights reserved. The information contained herein is the property of McMahon Associates, Inc. and is to be used only for the project and site identified herein. McMahon Associates, Inc. and its employees shall not be held liable for any reuse or modification of this information without the written consent of McMahon Associates, Inc.

NO.	DATE	REVISION

**TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION**  
**TOWN OF CLAYTON, WINNEBAGO COUNTY, WI**  
**EXISTING SITE & DEMOLITION PLAN**



DESIGNED: **BTH**  
DRAWN: **CKA**

PROJECT NO.: **L0906-09-24-00497**

DATE: **JUNE 2024**

SHEET NO.: **03**

bhomblin, W:\PROJECTS\092400497\CADD\Civil3D\Plan Sheets\proposed site.dwg, 04 proposed site & dimensions, Plot Date: 7/10/2024 3:30 PM, xrefis: (x-exist topo trident holdings, x-all points trident holdings, x-exist shodetrident holdings, x-proposed shade trident holdings, x-proposed linework trident holdings, lamers\_shop\_comps.dwg)



- NOTES:
1. 60'x60' BUILDING ADDITION
  2. CONCRETE
  3. ASPHALT
  4. LANDSCAPING RETAINING WALL
  5. SERVICE DOOR
  6. GARAGE DOOR
  7. SALVAGED WALL PACK (SEE PHOTOMETRIC PLAN)
  8. BOLLARD (APPROXIMATE LOCATION)
  9. NEW LANDSCAPING AT BUILDING (SEE LANDSCAPING PLAN)
  10. NEW LAWN & AREA LANDSCAPING (SEE LANDSCAPING PLAN)
  11. NEW BUILDING ADDITION DOWNSPOUT (UNDERGROUND)
  12. NEW BUILDING ADDITION DOWNSPOUT (OVERLAND)

**McMAHON**  
**ENGINEERS ARCHITECTS**  
 McMAHON ASSOCIATES, INC.  
 1445 McMAHON DRIVE NEENAH, WI 54956  
 Mailing: P.O. BOX 1025 NEENAH, WI 54957-1025  
 PH 920.751.4200 FX 920.751.4284 MCMGRP.COM

McMahon Associates, Inc. provides  
 of form, or instruments of  
 service. All rights reserved.  
 McMahon Associates, Inc. The  
 McMahon Associates, Inc. hold  
 the full extent permitted by  
 law. McMahon Associates, Inc.  
 harmless for any reuse of or  
 drawing or data without prior  
 written consent by McMahon  
 Associates, Inc.

NO.	DATE	REVISION

**TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION**  
**TOWN OF CLAYTON, WINNEBAGO COUNTY, WI**  
**PROPOSED SITE & DIMENSIONS**

DESIGNED #	DRAWN #
PROJECT NO. L0906-09-24-00497	
DATE JUNE 2024	
SHEET NO. <b>04</b>	



**NOTES:**

T=TREES; S=SHRUB; E=EVERGREEN; B=B=BALLED IN BURLAP; B.R.=BARE ROOT; P=POTTED; T.S.= TREE SPADE.

THE LAYOUT OF THE PLANTING AND LOCATION OF PLANT HOLES OR BEDS SHALL BE STAKED BY THE CONTRACTOR SUBJECT TO ENGINEER/ ARCHITECTS APPROVAL.

ALL PLANTING AREAS TO BE FREE OF WEEDS AND GRASS, TREATED WITH A NON-LEACHING PRE-EMERGENT HERBICIDE, PREEN OR EQUAL, PER MANUFACTURER'S SPECIFICATIONS AND COVERED WITH TYPAR 3301 OR SUPAC 2P AND THEN WITH 4" OF STONE MULCH, FREE OF WEEDS AND DISEASE, AND MATCHING EXISTING STONE MULCH. THE MULCH SHALL BE 1"-1-1/2" DIA). THE MULCH SHALL BE RAKED TO PRODUCE A UNIFORM TEXTURE. SUBMIT SAMPLES OF STONE MULCH TO ENGINEER/ARCHITECT FOR APPROVAL.

SEE THIS PAGE FOR PLANTING AND STAKING DETAILS.

AREAS TO BE PAVED, SEEDED, AND BEDDED ARE INDICATED ON THE PLANS.

PLANT QUANTITIES INDICATED ON THE PLAN RULE OVER QUANTITIES ON THE PLANTS LIST.

CONTRACTOR TO VERIFY LOCATION OF ALL UNDERGROUND UTILITIES, PRIVATE AND PUBLIC, PRIOR TO DIGGING PITS FOR NEW TREES. CONTACT DIGGERS HOTLINE FOR UTILITY LOCATES.

ALL PLANTS TO BE SIZED AND GRADED AS RECOMMENDED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC. IN THE USA STANDARD FOR NURSERY STOCK.

PLANT SUBSTITUTIONS PERMISSIBLE WITH ENGINEER/ARCHITECT AND TOWN APPROVAL AND WRITTEN NOTIFICATION PRIOR TO INSTALLATION.

PLASTIC OR METAL POTS TO BE REMOVED. SCORE ROOTBALL 1" DEEP WITH SHARP KNIFE. REMOVE TOP PORTION OF FIBER POT THAT EXTENDS ABOVE FINISH GRADE AND CUT SIDES OF POT TO AID IN DECOMPOSITION.

ALL LAWN AREAS TO BE SEEDED, FERTILIZED AND PROTECTED WITH WILDLIFE FRIENDLY EROSION MAT.

MATURE TREES SHOULD BE LINED UP TO PROVIDE A SEVEN FOOT UNDERCLEARANCE.

SEE EROSION CONTROL PLAN FOR EROSION MAT AND SPECIAL RESTORATION INFORMATION.



LOCATE TREES AWAY FROM THE PROPOSED SWALES & UTILITIES.

ALL PLANTING BED EDGES SHALL BE EDGED WITH DIAMOND BLACK ROYAL POLY BED EDGING OR EQUAL, FORMED IN LINES OR CURVES AS SHOWN ON THE DRAWINGS.



RESTORE ALL DISTURBED AREAS AROUND PERIMETER OF SITE WITH LAWN.

**TOWN OF CLAYTON ZONING NOTES:**

- PER SECTION J(1)(b)(1) OF THE LANDSCAPE DESIGN STANDARDS, THIS LANDSCAPE PLAN IS TO BE REVIEWED AS AN ALTERNATIVE LANDSCAPE DESIGN, AS EXISTING MATURE TREES ARE TO BE USED TO HELP ACHIEVE THE TOWN REQUIREMENTS.
- PER SECTION G(e)(1)(b), THE BUILDING ADDITION IS APPROXIMATELY 3,630 SF. THE AMOUNT OF GROUNDS LANDSCAPING THAT IS REQUIRED AMOUNTS TO 1 TREE AND 4 SHRUBS.
  - APPROX. 100 EXISTING TREES REMAIN ON THE PROPERTY. PER THE ALLOWED SUBSTITUTIONS OF 1 SHADE TREE FOR 10 SHRUBS, THE EXISTING VEGETATION MEETS THE GROUNDS LANDSCAPING REQUIREMENT.
- PER SECTION G(e)(2)(b) BUILDING LANDSCAPING FOR ZONE B REQUIRES 100% OF BUILDING FACADE FACING PUBLIC STREETS TO BE IN A MINIMUM 6' WIDE MULCHED BED THAT CONTINUES AROUND THE CORNERS OF THE BUILDING A DISTANCE OF 25% OF THE LENGTH OF THE SIDE WALL.
  - THE EAST BUILDING FACADE IS SCREENED FROM THE STREET BY EXISTING MATURE VEGETATION. THE SOUTH BUILDING FACADE HAS A 6' WIDE MULCHED BED THAT EXTENDS AROUND THE CORNER ALONG THE WEST FACADE FOR 33% OF ITS LENGTH.



**Proper Tree Planting Diagram**



SHRUB PLANTING DETAIL TO SCALE

THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING RECORD DRAWINGS. MCMAHON DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES ILLUSTRATED ARE IN THE EXACT LOCATION INDICATED ALTHOUGH IT DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. MCMAHON HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES. EXCEPT SHOWN HEREON, THERE ARE NO VISIBLE EASEMENTS BENEFITING OR BURDENING THE PREMISES OR RIGHT-OF-WAY ACROSS THE LAND OR ANY OTHER UNRECORDED EASEMENTS OR RIGHTS-OF-WAY OF WHICH MCMAHON HAS BEEN ADVISED.

**PLANTING SCHEDULE**

KEY	QUANTITY	BOTANICAL NAME	COMMON NAME	ROOT CONDITION	SIZE AT PLANTING	HEIGHT AT MATURITY (HxW)
<b>SHRUB DECIDUOUS</b>						
GMS	6	Spiraea japonica 'Goldmound'	Goldmound Spirea	Potted	18"	3' x 3.5'
LHS	4	Itea virginica 'Sprich'	Little Henry Sweetspire	Potted	18"	3' x 3'
LLH	1	Hydrangea pan. 'Little Lime'	Little Lime Hydrangea	Potted	18"	4' x 4'
LPS	6	Spiraea japonica 'Little Princess'	Little Princess Spirea	Potted	18"	3' x 3'
<b>RELOCATED TREES</b>						
EXBW	3	Juglans nigra	Black Walnut	Existing	Existing	50' x 50'
EXWP	7	Pinus strobus	White Pine	Existing	Existing	75' x 30'

**McMAHON**  
ENGINEERS ARCHITECTS  
McMAHON ASSOCIATES, INC.  
1445 McMAHON DRIVE NEENAH, WI 54956  
Mailing: P.O. BOX 1025 NEENAH, WI 54957-1025  
PH 920.751.4200 FX 920.751.4284 MCMGRP.COM

McMahon Associates, Inc. provides professional engineering and architectural services. All rights reserved. The information herein is the property of McMahon Associates, Inc. and is to be used for the project and site only. It is not to be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written consent of McMahon Associates, Inc.


NO.	DATE	REVISION
2	5/20/22	SITE, GRADING, UTILITY, STORMWATER & BLDG REVISIONS

**TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION**  
**TOWN OF CLAYTON, WINNEBAGO COUNTY, WI**  
**LANDSCAPE PLAN**

DESIGNED ###	DRAWN ###
PROJECT NO. L0906-09-24-00497	
DATE JUNE 2024	
SHEET NO. <b>06</b>	

b:\blm\blm\w\PROJECTS\10906\092400497\CADD\Civil\03\Plan Sheets\09 Landscape Plan.dwg, 07 Landscape Plan, Plot Date: 7/10/2024 3:30 PM, xrefs: (x-american drive-topoints, x-american drive-existtop, x-american drive-propline), lammers shop comps dew, x-site-propline, x-existing shade, x-site-proshade, x-proposed linework, trident holdings

shamblin\_w:\PROJECTS\L0906\092400497\CADD\Civil3D\Plan\_Sheets\10\_Photometric\Plan.dwg\_08\_photometric\_cut\_sheets\_notes\_details\_Plot Date: 7/10/2024 3:30 PM\_xrefs: (x=proposed linework trident holdings)



Schedule											
Symbol	Label	Image	Description	Quantity	Manufacturer	Catalog Number	Number Lamps	Lumens Per Lamp	Light Loss Factor	Wattage	Plot
	<b>W1</b>		DSXW2 LED WITH 2 LIGHT ENGINES, 20 LED's, 700mA DRIVER, 3000K LED, TYPE FORWARD THROW MEDIUM OPTIC, BLACK FINISH	14	Lithonia Lighting	DSXW2 LED 20C 700 30K TFTM MVOLT SPD DBLXD	1	5075	1	47	

Statistics						
Description	Symbol	Avg	Max	Min	Avg/Min	
PARKING / DRIVES	+	1.1 fc	4.2 fc	0.2 fc	21.0:1	5.5:1
PROPERTY LINE	+	0.03 fc	0.31 fc	0.00 fc	N/A	N/A
RETAIL ENTRANCES	+	4.6 fc	6.8 fc	2.5 fc	2.7:1	1.8:1
SIDEWALK	+	2.0 fc	2.8 fc	0.8 fc	3.5:1	2.5:1
SITE - BETWEEN BLDGS	X	0.7 fc	2.2 fc	0.0 fc	N/A	N/A
BLDG 2 REAR	X	0.6 fc	2.5 fc	0.1 fc	25.0:1	6.0:1

**d-series**

**Specifications Luminaire**

Width: 18-1/2" (47.0 cm) Weight: 21 lbs (9.5 kg)

Depth: 10" (25.4 cm)

Height: 7-5/8" (19.4 cm)

**D-Series Size 2 LED Wall Luminaire**

Hit the Tab key or mouse over the page to see all interactive elements.

**Back Box (BBW)**

Width: 5-1/2" (14.0 cm) Weight: 1 lbs (0.5 kg)

Depth: 1-1/2" (3.8 cm)

Height: 4" (10.2 cm)

Catalog Number

Notes

Type

**Capable Luminaire**

This item is an A+ capable luminaire, which has been designed and tested to provide consistent color appearance and system-level interoperability.

- All configurations of this luminaire meet the Acuity Brands' specification for chromatic consistency.
- This luminaire is A+ Certified when ordered with DTL® controls marked by a shaded background. DTL, DLL equipped luminaires meet the A+ specification for luminaire to photocontrol interoperability!
- This luminaire is part of an A+ Certified solution for ROAM® or XPoint™ Wireless control networks, providing out-of-the-box control compatibility with simple commissioning, when ordered with drivers and control options marked by a shaded background!

To learn more about A+, visit [www.acuitybrands.com/aplus](http://www.acuitybrands.com/aplus).

1. See ordering tree for details.

2. A+ Certified Solutions for ROAM require the order of one ROAM node per luminaire. Sold Separately. [Link to Roam](#); [Link to DTL DLL](#).

Ordering Information		EXAMPLE: DSXW2 LED 30C 700 40K T3M MVOLT DDBTDX					
Series	LEDs	Drive Current	Color Temperature	Distribution	Voltage	Mounting	Control Options
DSXW2 LED	20C 20 LEDs (two engines)	350 350 mA	30K 3000K	T25 Type II Short	MVOLT <sup>1</sup> 120 <sup>1</sup>	Shipped included (blank) Surface mounting bracket	Shipped installed PE Photometric cell, button type <sup>1</sup> PER NEMA twist-lock receptacle only (control ordered separately) PER5 Five-wire receptacle only (control ordered separately) <sup>1</sup> PER7 Seven-wire receptacle only (control ordered separately) <sup>1</sup>
	30C 30 LEDs (three engines)	530 530 mA 700 700 mA 1000 1000 mA (1 A)	40K 4000K 50K 5000K AMBPC Amber phosphor converted <sup>2</sup>	T2M Type II Medium T3S Type III Short T3M Type III Medium T4M Type IV Medium TFTM Forward Throw Medium	277 <sup>4</sup> 347 <sup>4,5</sup> 480 <sup>4,5</sup>		
<b>Other Options</b> Shipped installed SF Single fuse (120, 277, 347V) <sup>1</sup> DF Double fuse (208, 240, 480V) <sup>1</sup> HS House-side shield <sup>4</sup> SPD Separate surge protection <sup>10</sup>							<b>Finish required</b> DDBX Dark bronze DBLX Black DNAX Natural aluminum DWHX White DSSX Sandstone DDBTX Textured dark bronze OBLBX Textured black DNATX Textured natural aluminum DWHX Textured white DSSTX Textured sandstone

LITHONIA LIGHTING COMMERCIAL OUTDOOR | One Lithonia Way • Conyers, Georgia 30012 • Phone: 1-800-705-SERV (7378) • www.lithonia.com | DSXW2-LED Rev. 04/19/21 Page 1 of 4

**McMAHON**  
ENGINEERS ARCHITECTS  
McMAHON ASSOCIATES, INC.  
1445 McMAHON DRIVE NEENAH, WI 54956  
Mailing: P.O. BOX 025 NEENAH, WI 54957-1025  
PH 920.751.4200 FX 920.751.4284 MCMGRP.COM

McMahon Associates, Inc. provides of form, fit, and instruments of service. All rights reserved. McMahon Associates, Inc. The use of this drawing and hold the copyright in it and hold the right to sue for infringement of this copyright. No part of this drawing may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written consent by McMahon Associates, Inc.

NO.	DATE	REVISION

**TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION**  
**TOWN OF CLAYTON, WINNEBAGO COUNTY, WI**  
**PHOTOMETRIC CUT SHEETS, NOTES, DETAILS**

DESIGNED ###	DRAWN JRR
PROJECT NO. L0906-09-24-00497	
DATE JUNE 2024	
SHEET NO. <b>07</b>	

# EROSION & SEDIMENT CONTROL PLAN

## CONTACT INFORMATION:

OWNER:  
TRIDENT HOLDINGS LLC  
ATTN: BARRY GILL  
501 S. NICOLET RD  
APPLETON, WI 54914  
PHONE: (920) 840-4112

DESIGNER:  
MCMAHON ASSOCIATES  
P.O. BOX 1025  
NEENAH, WI 54957-1025  
BEN HAMBLIN, PROJECT ENGINEER  
PHONE: (920) 751-4200

## BEST MANAGEMENT PRACTICES:

THE CONTRACTOR IS RESPONSIBLE FOR FURNISHING, INSTALLING, MAINTAINING AND REMOVING BEST MANAGEMENT PRACTICES IN ACCORDANCE WITH WISCONSIN DEPARTMENT OF NATURAL RESOURCES (DNR) TECHNICAL STANDARDS. THESE STANDARDS MAY BE FOUND ON THE DNR WEBSITE AT <http://www.dnr.state.wi.us/org/water/wm/nps/stormwater/techstds.htm>. RIP-RAP AND DE-WATERING SHALL COMPLY WITH THE WISCONSIN CONSTRUCTION SITE BMP HANDBOOK UNTIL TECHNICAL STANDARDS 1061 AND 1065 ARE COMPLETED BY THE DNR. THE MINIMUM BEST MANAGEMENT PRACTICES SPECIFIED FOR THIS PROJECT ARE AS FOLLOWS:

- |  |   |
|--|---|
| <input type="checkbox"/> LAND APPLICATION OF POLYACRYLAMIDE (1050) | <input type="checkbox"/> DE-WATERING (1061)             |
| <input type="checkbox"/> WATER APPLICATION OF POLYMERS (1051)      | <input type="checkbox"/> DITCH CHECK (1062)             |
| <input checked="" type="checkbox"/> NON-CHANNEL EROSION MAT (1052) | <input type="checkbox"/> SEDIMENT TRAP (1063)           |
| <input type="checkbox"/> CHANNEL EROSION MAT (1053)                | <input type="checkbox"/> SEDIMENT BASIN (1064)          |
| <input type="checkbox"/> VEGETATIVE BUFFER (1054)                  | <input type="checkbox"/> RIP-RAP (1065)                 |
| <input type="checkbox"/> SEDIMENT BALE BARRIER (1055)              | <input type="checkbox"/> CONSTRUCTION DIVERSION (1066)  |
| <input checked="" type="checkbox"/> SILT FENCE (1056)              | <input type="checkbox"/> GRADING PRACTICES (1067)       |
| <input checked="" type="checkbox"/> TRACKOUT CONTROL (1057)        | <input checked="" type="checkbox"/> DUST CONTROL (1068) |
| <input type="checkbox"/> MULCHING (1058)                           | <input type="checkbox"/> TURBIDITY BARRIER (1069)       |
| <input checked="" type="checkbox"/> SEEDING (1059)                 | <input type="checkbox"/> SILT CURTAIN (1070)            |
| <input type="checkbox"/> STORM DRAIN INLET PROTECTION (1060)       |   |

THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING CONSTRUCTION ACTIVITIES AND IMPLEMENTING BEST MANAGEMENT PRACTICES TO DO THE FOLLOWING TO THE MAXIMUM EXTENT PRACTICABLE:

- PRESERVE EXISTING VEGETATION WHERE POSSIBLE. TEMPORARILY STABILIZE EXPOSED SOILS THAT WILL NOT BE ACTIVE FOR 30 DAYS OR MORE. POLYACRYLAMIDE, MULCHING, SEEDING AND GRAVELING MAY BE USED TO TEMPORARILY STABILIZE EXPOSED SOILS.
- DIVERT CLEAR WATER AWAY FROM EXPOSED SOILS USING CONSTRUCTION DIVERSIONS.
- MANAGE SHEET FLOW THAT IS NOT CONTROLLED WITH A SEDIMENT TRAPPING DEVICE. SILT FENCE IS USED TO MANAGE SHEET FLOW. GRADING PRACTICES MAY BE USED TO SUPPLEMENT THE SILT FENCE.
- MANAGE CONCENTRATED FLOW WITH SEDIMENT TRAPPING DEVICES. STORM DRAIN INLET PROTECTION AND A SEDIMENT BASIN ARE USED TO MANAGE CONCENTRATED FLOW. POLYMERS ARE USED FOR THE SEDIMENT BASIN TO ENHANCE TRAPPING.
- MINIMIZE THE AMOUNT OF SOIL EXPOSED AT ANY ONE TIME.
- PROTECT INLETS FROM RECEIVING SEDIMENT WITH STORM DRAIN INLET PROTECTION.
- PREVENT TRACKING OF SEDIMENT ONTO ROADS AND PAVED SURFACES USING TRACKING PADS AND/OR TIRE WASHING. MINIMIZE TRACKING AT ALL SITE EXITS AND ENTRANCES.
- CLEANUP OFFSITE SEDIMENT DEPOSITS AT THE END OF EACH WORK DAY & BEFORE A RAIN.
- MANAGE THE USE, STORAGE AND DISPOSAL OF CHEMICALS, CEMENT, CONCRETE AND OTHER COMPOUNDS AND MATERIALS TO PREVENT THEIR DISCHARGE INTO THE DRAINAGE SYSTEM.
- STABILIZE DRAINAGE WAYS AND EROSION DISCHARGE LOCATIONS WITH CHANNEL EROSION MAT, MULCHING, SEEDING, DITCH CHECKS & RIP-RAP AS SOON AS POSSIBLE.
- PERMANENTLY STABILIZE EXPOSED SOILS WITH NON-CHANNEL EROSION MAT, MULCHING AND SEEDING AS SOON AS POSSIBLE.
- CONTROL AND MINIMIZE DUST FROM VEHICULAR TRAFFIC AND WIND EROSION. PRESERVING VEGETATION, MULCHING, SEEDING, WATERING, GRADING PRACTICES, POLYACRYLAMIDE, SOIL STABILIZERS, CHLORIDES, & BARRIERS MAY BE USED FOR DUST CONTROL.
- PREVENT THE DISCHARGE OF SEDIMENT AS PART OF DE-WATERING. GEOTEXTILE BAGS, SEDIMENT TANKS, SEDIMENT TRAPS, SEDIMENT BASINS, AND FILTRATION SYSTEMS MAY BE USED FOR DE-WATERING. POLYMERS ARE TO BE USED TO ENHANCE SEDIMENT TRAPPING.
- SOIL TYPES ON THE PROPERTY, PER NRCS SOIL MANUAL, IS HORTONVILLE SILT LOAM (HrB), A TYPE "C" SOIL AND MANAWA SILTY CLAY LOAM (MaA), A TYPE "D" SOIL. DEPTH TO GROUNDWATER IS >THAN 5'.

## EROSION CONTROL NOTES

- THIS PLAN COVERS SITE GRADING, UTILITY CONSTRUCTION AND PARKING LOT CONSTRUCTION.
- OBTAIN A STREET EXCAVATION PERMIT FOR ALL WORK WITHIN THE PUBLIC RIGHT OF WAY. OBTAIN AN EROSION & SEDIMENT CONTROL PERMIT PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES.
- EROSION CONTROL PLAN DESIGN CRITERIA, STANDARDS AND SPECIFICATIONS: ALL EROSION CONTROL MEASURES SHALL AT A MINIMUM, COMPLY WITH THE DESIGN CRITERIA, STANDARDS, AND SPECIFICATIONS FOR EROSION CONTROL BASED ON ACCEPTED DESIGN CRITERIA, STANDARDS, AND SPECIFICATIONS IDENTIFIED IN THE LATEST EDITION OF THE DEPARTMENT OF NATURAL RESOURCES' TECHNICAL STANDARDS AND BY THE REQUIREMENTS OF THE TOWN OF CLAYTON EROSION CONTROL ORDINANCE. AS INDIVIDUAL PRACTICES FROM WI-DNR CONSTRUCTION SITE BMP HANDBOOK ARE PUBLISHED AS WI-DNR TECHNICAL STANDARDS, THE STANDARD SHALL GOVERN.
- THE CONTRACTOR SHALL NOTIFY THE TOWN & COUNTY AT LEAST 2 DAYS PRIOR TO THE START OF SOIL DISTURBING ACTIVITIES.
- BUILDING/PAVING PERMITS WILL BE WITHHELD UNTIL ALL INITIAL EROSION CONTROL PRACTICES ARE IMPLEMENTED AND APPROVED BY THE TOWN & COUNTY EROSION CONTROL INSPECTOR.
- EROSION & SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED OR INSTALLED BEFORE LAND DISTURBING CONSTRUCTION ACTIVITIES BEGIN. EROSION CONTROL MEASURES SHALL BE MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION UNTIL THE SITE IS STABILIZED BY VEGETATION OR OTHER APPROVED MEANS. FINAL STABILIZATION ACTIVITIES SHALL COMMENCE WHEN LAND DISTURBING ACTIVITIES CEASE & FINAL GRADE HAS BEEN REACHED ON ANY PORTION OF THE SITE.
- ALL ACTIVITIES SHALL BE CONDUCTED IN A LOGICAL SEQUENCE AS TO MINIMIZE THE AMOUNT OF BARE SOIL EXPOSED AT ANY ONE TIME. MAINTAIN EXISTING VEGETATION AS LONG AS POSSIBLE.
- CONSTRUCTION ENTRANCES UTILIZING 3" CLEAR STONE SHALL BE MAINTAINED AT ALL CONSTRUCTION ENTRANCES TO THE SITE. THE ROCK DRIVE SHALL BE A MINIMUM OF 12 INCHES THICK AND BE A MINIMUM OF 50 FEET IN LENGTH BY THE WIDTH OF THE DRIVEWAY.
- ON-SITE SEDIMENT DEPOSITS OCCURRING AS A RESULT OF A STORM EVENT SHALL BE CLEANED UP BY THE END OF THE NEXT WORK DAY. ALL OFF-SITE SEDIMENT DEPOSITS OCCURRING AS A RESULT OF CONSTRUCTION ACTIVITIES, INCLUDING SOIL TRACKED BY CONSTRUCTION TRAFFIC, SHALL AT A MINIMUM BE CLEANED BY THE END OF EACH WORK DAY. EXCESSIVE AMOUNTS OF SEDIMENT OR OTHER DEBRIS TRACKED ONTO ADJACENT STREETS SHALL BE CLEANED IMMEDIATELY. FINE SEDIMENT ACCUMULATIONS SHALL BE CLEANED FROM ADJACENT STREETS BY THE USE OF MECHANICAL OR MANUAL SWEEPING OPERATIONS ONCE A WEEK AT A MINIMUM AND BEFORE IMMINENT RAIN EVENTS.
- ALL SEDIMENT LADEN WATER PUMPED FROM THE SITE SHALL BE TREATED BY A TEMPORARY SEDIMENT BASIN OR BE FILTERED BY OTHER APPROVED MEANS. WATER SHALL NOT BE DISCHARGED IN A MANNER THAT CAUSES EROSION OF THE SITE OR RECEIVING CHANNELS. DEWATERING TO MEET THE REQUIREMENTS OF DNR TECHNICAL STANDARD 1061.
- DISTURBED GROUND OUTSIDE OF THE EVERYDAY CONSTRUCTION AREA, INCLUDING SOIL STOCKPILES LET INACTIVE FOR MORE THAN 10 DAYS, SHALL AT A MINIMUM BE TEMPORARILY STABILIZED BY SEEDING/MULCHING OR OTHERS METHODS APPROVED BY THE CITY OF APPLETON EROSION CONTROL INSPECTOR. STRAW MULCH SHALL BE ANCHORED BY "CRIMPING" THE STRAW INTO THE SOIL.
- WASTE MATERIAL GENERATED ON THE CONSTRUCTION SITE SHALL BE PROPERLY DISPOSED OF AND NOT ALLOWED TO RUN INTO A RECEIVING WATER OR STORM SEWER SYSTEM.
- IN THE CASE OF LATE SEASON AND WINTER CONSTRUCTION, RESTORATION/LAND-SCAPING OF THE SITE SHALL ALL OCCUR NO LATER THAN JUNE 1 OF THE NEXT CONSTRUCTION SEASON. EROSION CONTROL MEASURES SHALL REMAIN INTACT UNTIL FINAL RESTORATION OF THE SITE IS COMPLETE. FABRIC INSIDE THE INLET AND CATCH BASIN GRATING SHALL BE REMOVED AS SOON AS FREEZING WEATHER EROSION CONTROL PRACTICES REMOVED OR DAMAGED DUE TO WINTER WEATHER SHALL BE REPLACED IN THE SPRING IMMEDIATELY AFTER THE THAW.
- EROSION CONTROL DEVICES DESTROYED AS A RESULT OF CONSTRUCTION ACTIVITIES SHALL BE REPAIRED BY THE END OF THE WORK DAY.
- INSPECT ALL EROSION CONTROL MEASURES AT LEAST ONCE A WEEK AND AFTER ANY RAINFALL OF 0.5 INCHES OR MORE AND MAKE NEEDED REPAIRS.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AT THE CONCLUSION OF CONSTRUCTION AFTER STABILIZATION OF DISTURBED SOIL HAS OCCURRED.
- ADJACENT STREET INLETS SHALL BE PROTECTED WITH WISDOT TYPE D-M INLET PROTECTION. INLET PROTECTION SHALL BE REMOVED WHEN DISTURBED AREAS FLOWING TO THE INLET ARE RESTORED OR HAVE OTHER PROTECTIVE MEASURES IN PLACE.
- FILLED/DISTURBED OUTLOTS SHALL BE SEEDED WITHIN 10 DAYS AFTER GRADES HAVE BEEN REACHED.
- SILT FENCE AND OTHER EROSION CONTROL DEVICES THAT ARE TEMPORARILY REMOVED FOR CONSTRUCTION ACTIVITY MUST BE REPLACED AS SOON AS THOSE ACTIVITIES ARE COMPLETED.
- CONTRACTOR IS RESPONSIBLE FOR REMOVING AND DISPOSING OF EROSION CONTROL DEVICES ONCE CONSTRUCTION IS COMPLETED AND VEGETATION HAS BEEN ESTABLISHED.
- AIRBORNE DUST SHALL BE CONTROLLED BY WATERING ALL DISTURBED SOIL AREAS AND GRAVEL DRIVES WHERE WHEEL TRAFFIC IS PRESENT AND MOISTURE CONTENT OF THE SURFACE IS LOW ENOUGH TO ALLOW DUST EMISSION.

## INSPECTION & MAINTENANCE:

### CONSTRUCTION INSPECTION & MAINTENANCE PLAN

ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED BY THE CONTRACTOR EVERY 7 DAYS AND WITHIN 24 HOURS AFTER A PRECIPITATION EVENT OF 0.5 INCHES OR GREATER. CONTRACTOR SHALL MAINTAIN WEEKLY WRITTEN REPORTS OF ALL INSPECTIONS AS NECESSARY TO MEET THE TOWN & COUNTY ORDINANCE, UNTIL THE SITE HAS UNDERGONE FINAL STABILIZATION AND RECEIVED FINAL ACCEPTANCE FROM THE TOWN & COUNTY. LOGS ARE TO BE KEPT ON SITE, AND SHALL INCLUDE THE FOLLOWING:

- TIME, DATE AND LOCATION OF INSPECTION.
- PERSONNEL COMPLETING THE INSPECTION.
- CURRENT PHASE OF THE CONSTRUCTION AT THE TIME THE INSPECTION IS OCCURRING.
- SPECIFIC ASSESSMENT OF EROSION CONTROL DEVICES.
- SPECIFIC DESCRIPTION OF MAINTENANCE OR REPAIR REQUIRED ON THE EROSION CONTROL DEVICES.
- DATE AND TIME WHEN THE REQUIRED MAINTENANCE OR REPAIRS WERE MADE.

CONTRACTOR SHALL INSPECT EROSION AND SEDIMENT CONTROLS FOR STRUCTURAL DAMAGE, EROSION, SEDIMENT ACCUMULATION, OR ANY OTHER UNDESIRABLE CONDITION. CONTRACTOR SHALL REPAIR ANY DAMAGED STRUCTURES PRIOR TO THE END OF THE WORKING DAY. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL DEVICES WHEN THE DEPTH OF SEDIMENT HAS ACCUMULATED TO ONE HALF THE HEIGHT OF THE DEVICE. ERODED OR TRACKED SEDIMENT SHOULD BE CLEANED FROM ROADWAYS BEFORE THE END OF THE BUSINESS DAY ON WHICH IT ACCUMULATED.

IN ADDITION TO THESE REQUIREMENTS, THE CONTRACTOR IS REQUIRED TO MEET ALL ADDITIONAL TOWN OR COUNTY REQUIREMENTS AS STATED ON PERMITS AND ON THE CONSTRUCTION PLAN SHEETS.

## AMENDMENTS:

THE CONTRACTOR IS RESPONSIBLE FOR AMENDING THE EROSION & SEDIMENT CONTROL PLAN IF: THERE IS A CHANGE IN CONSTRUCTION, OPERATION OR MAINTENANCE AT THE SITE WHICH HAS THE REASONABLE POTENTIAL FOR THE DISCHARGE OF POLLUTANTS; THE ACTIONS REQUIRED BY THE PLAN FAIL TO REDUCE THE IMPACTS OF POLLUTANTS CARRIED BY CONSTRUCTION SITE RUNOFF; OR IF THE TOWN OR COUNTY NOTIFIES THE APPLICANT OF CHANGES NEEDED IN THE PLAN. THE TOWN & COUNTY SHALL BE NOTIFIED 5 WORKING DAYS PRIOR TO MAKING CHANGES TO THE PLAN.

THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING OR REPLACING BEST MANAGEMENT PRACTICES DESTROYED AS A RESULT OF CONSTRUCTION ACTIVITIES BY THE END OF THE WORK DAY. THE CONTRACTOR IS RESPONSIBLE FOR REPLACING BEST MANAGEMENT PRACTICES TEMPORARILY REMOVED FOR CONSTRUCTION ACTIVITY AS SOON AS THOSE ACTIVITIES ARE COMPLETED. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING AND DISPOSING OF TEMPORARY BEST MANAGEMENT PRACTICES AFTER CONSTRUCTION IS COMPLETE AND PERMANENT VEGETATION IS ESTABLISHED.

## KEY NOTES

### CONSTRUCTION EROSION & SEDIMENT CONTROL PRACTICES

The following erosion and sediment control practices apply only to the proposed site development at American Drive & Clayton Ave. Site development equipment that is expected to be used will include backhoes, front end loaders and bulldozers.

All erosion and sediment control practices shall be in accordance with the Wisconsin Construction Site Technical Standards. Erosion and sediment control practices shall be in place prior to disturbing the site. Erosion and sediment control practices that may be used for this project are described as follows:

- Clear Stone, Hay Bale or Manufactured Ditch Check** - Purpose is to reduce runoff velocity in channels, ditches, or swales in order to allow larger sediment particles to settle.
- Rip-Rap Protection** - Rip-rap and filter fabric prevent scour and erosion from occurring within streams, channels, ditches, swales, culvert outlets, or storm sewer outlets.
- Silt Fence** - Purpose is to intercept and detain sheet flow runoff from disturbed areas for sufficient time to allow larger sediment particles to settle out.
- Construction Entrance** - Construction entrances reduce the amount of mud transported onto public roads by vehicles, equipment, and storm water runoff.
- Street Sweeping** - Street sweeping collects mud that is transported onto public roads by vehicles, equipment and storm water runoff.
- Mulching** - Purpose is to reduce erosion by dissipating raindrop impact energy and reducing sheet flow velocity. Mulching also fosters grass seed growth. Mulching shall be performed within 7 days of the end of active soil disturbance.
- Seeding** - Purpose is to stabilize disturbed areas by planting grass seed in order to minimize erosion and reduce runoff velocity. Seeding shall be performed within 7 days of the end of active soil disturbance.
- Erosion Blankets** - Erosion blankets protect disturbed slopes and ditches from erosion.

### ANTICIPATED CONSTRUCTION GRADING & EROSION CONTROL PLAN

This sequence is approximate. Days are measured as calendar days, not working days. Work tasks could be done concurrently.

- Hold preconstruction conference.
- Install gravel construction entrance and erosion control provisions as shown on the plan. (Days 1-2, Sept 3-4)
- Contact the town and county to notify them that the site grading is to begin and erosion control is installed. (Day 3, Sept 5)
- Strip topsoil & remove trees from areas where parking lot and buildings are to be constructed. Stockpile material on site. (Days 4-8, Sept 6-10)
- Fill and rough grade site as deemed necessary by the contractor. Stockpile excess material on site. Add parking lot gravel base. Install silt fence along its edge to minimize erosion. (Day 9-11, JSept 11-13)
- Begin and finalize substantial building construction. (Days 12-40, Sept 14 - Oct 12)
- Finalize pavement construction. (Days 41-49, Oct 13-21)
- Complete fine grading and landscaping. Permanently stabilize disturbed areas, cut and fill areas, and lawn areas. (Days 50-55, Oct 22-27)

### CONSTRUCTION INSPECTION & MAINTENANCE PLAN

All temporary and permanent erosion and sediment controls shall be inspected by the contractor every 7 days and within 24 hours after a precipitation event of 0.5 inches or greater. Contractor shall maintain weekly written reports of all inspections as necessary to meet the Town & County ordinances, until the site has undergone final stabilization and received final acceptance from the Town & County. Logs are to be kept on site, and shall include the following:

- Time, date and location of inspection.
- Personnel completing the inspection.
- Current phase of the construction at the time the inspection is occurring.
- Specific assessment of erosion control devices.
- Specific description of maintenance or repair required on the erosion control devices.
- Date and time when the required maintenance or repairs were made.

Contractor shall inspect erosion and sediment controls for structural damage, erosion, sediment accumulation, or any other undesirable condition. Contractor shall repair any damaged structures prior to the end of the working day. Sediment shall be removed from erosion control devices when the depth of sediment has accumulated to one half the height of the device. Eroded or tracked sediment should be cleaned from roadways before the end of the business day on which it accumulated.

In addition to these requirements, the contractor is required to meet all additional Town & County regulations as stated on permits and on the construction plan sheets.

### POST CONSTRUCTION WATER QUALITY, PEAK FLOW

This site eventually drains to a navigable stream tributary to Mud Creek, which is not listed on the State's 303d list of impaired waters. The use of stormwater devices, and good housekeeping maintenance practices will help to maintain the quality of the navigable stream and Fox River:

- Biofilters are used to trap suspended and dissolved solids prior to discharge.
- Detention ponds reduce peak flow rates & erosive stormwater discharge velocities.
- Fertilizers used on the lawn during the construction restoration process, and during post construction site maintenance, are to have low/no phosphorus component. At the discretion of the owner, fertilizer should be based on a soil sample from a trusted soil scientist.

hamblin, W:\PROJECTS\10906\092400497\CADD\Civil3D\Plan\_Sheets\01\_Abbrev\_Sym-Notes-Detail.dwg\_09\_erosion\_control\_notes\_Plot\_Date: 7/10/2024 3:30 PM\_xref:src:none

**MCMAHON**  
ENGINEERS ARCHITECTS


MCMAHON ASSOCIATES, INC.  
1445 MCMAHON DRIVE NEENAH, WI 54956  
Mailing: P.O. BOX 1025 NEENAH, WI 54957-1025  
PH 920.751.4200 FX 920.751.4284 MCMGRP.COM

NO.	DATE	REVISION


TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION  
TOWN OF CLAYTON, WINNEBAGO COUNTY, WI  
EROSION CONTROL NOTES

DESIGNED ###	DRAWN ###
PROJECT NO. L0906-09-24-00497	
DATE JUNE 2024	
SHEET NO.	

08




**STANDARD PARKING LOT PAVEMENT DETAIL**




**DOWNSPOUT CONNECTION**

NOTE: CONTRACTOR TO VERIFY WITH INDIVIDUAL BUILDING PLUMBING PLANS, ROOF DRAINAGE PLANS.




**CONCRETE PAVEMENT DETAIL**




**TRACKOUT CONTROL DETAIL**

- DIVERT FLOW AWAY FROM TRACKING PAD USING CULVERTS, SHALLOW TRENCH OR DIVERSION DAM.
- ROCKS LODGED BETWEEN THE TIRES OF DUAL VEHICLES SHALL BE REMOVED PRIOR TO LEAVING THE SITE.
- ON SITES WITH A HIGH WATER TABLE OR STURATED SOILS, INSTALL A DOT TYPE R GEOTEXTILE FABRIC UNDER STONE TRACKING PAD.
- MAINTAIN UNTIL SITE IS PAVED/STABILIZED
- USING A FOODS TRACKOUT SYSTEM INSTEAD OF THE STONE-BASED TRACKOUT CONTROL SYSTEM IS ACCEPTABLE.



**TEMPORARY CONCRETE WASHOUT FACILITY**



**TRENCH DETAIL**

- JOINING TWO LENGTHS OF SILT FENCE**
- GENERAL NOTES**
- HORIZONTAL BRACE REQUIRED WITH 2" x 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
  - TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
  - WOOD POSTS SHALL BE A MINIMUM SIZE OF 1" x 1" OF OAK OR HICKORY.
  - SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
  - CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS: A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.

NOTE: CAN SUBSTITUTE SILT SOCKS FOR SILT FENCE.

shamblin\_w:\PROJECTS\L0906\092400497\CADD\Civil\3D\Plan\_Sheets\01\_Abbrev\_Sym-Notes-Details.dwg, 10\_miscellaneous\_details\_Plot\_Date: 7/10/2024 3:30 PM\_xrefs:none

**McMAHON**  
ENGINEERS ARCHITECTS

McMAHON ASSOCIATES, INC.  
1445 McMAHON DRIVE NEENAH, WI 54956  
Mailing: P.O. BOX 025 NEENAH, WI 54957-1025  
PH 920/751-4200 FX 920/751-4284 MCMGRP.COM

TRIDENT HOLDINGS LLC - 2024 BUILDING ADDITION  
TOWN OF CLAYTON, WINNEBAGO COUNTY, WI  
MISCELLANEOUS DETAILS

NO.	DATE	REVISION

DESIGNED: BTH

DRAWN: RRS

PROJECT NO.: L0906-09-24-00497

DATE: JUNE 2024

SHEET NO.: 09