

**Bagdouma Park Soccer Field Lighting Project
Coachella, California
Date: July 15, 2024**

To: Brianna Greenwood- The City of Coachella

Sourcewell Contract: # 041123-MSL

Expiration Date: 06/16/2027

Sports Lighting Solutions with Related Technology, Equipment and Services

**All purchase orders should note the following:
Sourcewell purchase - contract number: 041123-MSL**

Bagdouma Park Soccer-

Musco's Lighting Equipment as described below and delivered to the job site:

- Soccer Field East / West Light poles- Musco Lighting Equipment: \$145,000.00
 - Option 1 - 70 B Class Light poles - 93% capacity

- Soccer Field East / West Light poles- Musco Lighting Equipment: \$153,000.00
 - Option 2 - 70 C Class Light poles- allows for future addition of low voltage devices, or added city provided components.

Estimated Sales Tax on Lighting Material only ~8.75%- Confirm at the time of order: ~\$12,687.50 or \$13,387.50 (pending option)

Confirm Sales tax rate at the time of order. Pricing furnished is effective for 90 days unless otherwise noted and is kindly considered confidential.

Bagdouma Park Field Size Descriptions- Musco is lighting half of each field as the center light poles have been retrofitted with a non-Musco LED light fixture as part of a separate city project.

Soccer #1 East- Half of the Soccer field- 325' x 195'

Field #2 West- Half of the Soccer field- 325' x 200'

Equipment Description-Soccer #1, and Soccer #2

- (4) Pre-cast concrete bases- S3, S4, S5, S6
- (4) 70' Galvanized steel poles- S3, S4, S5, S6
- (16) TLC LED 1200 Factory-aimed and assembled luminaries
- (4) TLC LED 900 Factory-aimed and assembled luminaries

On Field Performance - Control to benefit players, fans

Utilizing the Existing Control-Link® System installed in 2004. See Pages 3-4 of this quote for the original lighting control equipment.

***If the existing Musco Lighting Controller (CMC) will be replaced, please add \$12,000.00.**

Always Ready to Play - Control assuring the results you expect

Product assurance and warranty program for 10 years.

Structural Construction Note #1: Please review Option 1 and Option 2. Musco shall provide a stamped foundation design with structural calculations based off CBC 2022, 109 MPH. Class 5 Standard Soil has been used as a basis of design to prepare this quote. If the project GE will provide an addendum letter defining deep pier recommendations, Musco will prepare the structural design with these design parameters included.

Structural Construction Note #2: The installing electrical contractor can provide installation pricing based off a 30" to 36" diameter hole with a 12' to 14' embedment.

A project adder to include a rebar cage can be included should the final structural design require a reinforced pier – pending information from the project Geotechnical Engineer.

Notes

Quote is based on:

- Shipment of entire project together to one location
- See Musco Structural Design- TBD.
- Includes structural design services for the Musco Light poles. CBC 2022, mph 109.
- Delivery to the job site will be 10-14 weeks after submittal approval, confirmation of order details, and coordination with any test and inspection agency assigned to the project.

Available Cooperative Purchase Agreement (if a cooperative purchase agreement will be used, please confirm with Musco):

Sourcewell Contract: # 041123-MSL

Expiration Date: 06/16/2027

Sports Lighting Solutions with Related Technology, Equipment and Services

Thank you for the opportunity to discuss Musco's innovative lighting solutions; we are determined to provide you with the best value option for your facility. Please contact us if you have any questions.

Mike Higgins

Musco Sports Lighting, LLC

3002 Dow Ave, Suite #504

Tustin, CA 92780

Office: 800-659-0117x6121

Mobile: 714-614-0863