

ESTIMATE

Daizy Sweeps Inc

W11007 State Road 16 and 60
Columbus, WI 53925

daizysweeps@daizysweeps.com
920-386-9563
<http://www.daizysweeps.com>



Bill to

Dave Milbrandt
Abundance Acupuncture
126 N Dickason Blvd
Columbus, WI 53925

Estimate details

Estimate no.: 2123
Estimate date: 02/10/2026
Expiration date: 03/10/2026

Product/service	Description	Qty	Rate	Amount
Lift Rental	Lift Rental & Insurance Per Week	2	\$1,850.00	\$3,700.00
Scaffolding Set Up	Scaffolding Set Up on North side roof with carpeting and boards under feet.	1	\$625.00	\$625.00

This is an estimate to do restoration on masonry on entire building. The scope of work is on north and south side of building. There are quite a few bricks that need to be cut out and replaced due to deep holes on faces of brick. If brick face isn't very deep the brick will stay. In all areas of mortar joints that have cracks in or missing they will need to be ground out and re mortared with a natural color restoration mortar. The parapet wall on North and South side of building have missing or broken caps. The south east side of wall near back wall will need to be rebuilt on top corner. We will use closest color as possible bricks where they get removed. The lower portion of wall on south side will be ground out the entire length of building to improve integrity of wall and keep moisture out.

The lift will be used on north wall as far it can reach on east and west ends of building. Where lift can't reach we will use scaffolding on flat roof on accountants building to repair wall. We will put carpets

and boards under feet of scaffolding to protect rubber roof.

The chimney will also be repaired and make sure there is a plate on top so no water enters.

The work that needs to be done will take approximately 2-3 weeks. All work is charged out on time and material. Work hours are 8-10 hours a day. Week will consist of 5 days unless we get delayed from rain. then we will work on Saturday. Work will consist of 2 people unless we pull in more help if needed. Grinding blades, drill bits, mortar and sealant will be billed out on invoice. Labor hours will be billed out on how many hours either power washing, grinding, tuck pointing, setting up & moving scaffolding or cutting out brick. Hourly will be billed seperately for each person. Hourly rate per person will be \$90. In hourly price is the use of tools to get work done. Hours will be calculated and show daily hours.

h

Brick replacement	Cut out bad brick and replace with new. Closest match to existing.	50	\$25.00	\$1,250.00
Powerwash	Power wash all masonry on north and south wall. Power Washer and gas in rate	1	\$425.00	\$425.00
Mortar	Mortar Natural Color (Cost per bag) If more are needed there will be additional charges per bag	15	\$32.50	\$487.50
Misc Item	Diamond double Grinding Blades (If more are needed there will be additional charges)	5	\$88.00	\$440.00
Misc Item	Masonry Drill bits (If more are needed there will be additional charges)	6	\$10.21	\$61.26
Labor	Man Hours 2 weeks	80	\$185.00	\$14,800.00
The final ending balance is all determined on hours, material, bits and blades used to finish job. Price may go up and it may go down. IT all depends on how long job takes. This is time needed is unknown due to the severity and work proposed.				
COST OF PARAPET WALL CAPS ARE UNKNOWN TILL BE MEASURE THEM AND FIND OUT WHAT SIZE THEY ARE.				

Total **\$21,788.76**

Note to customer

Thank you for the inquiry with Daizy Sweeps.

All work requires signed acceptance contract and signed estimate.

Expiry date 03/10/2026

Work will not be started without down payment or other arrangements,

Accepted date

Accepted by