

Quote

Date: June 19, 2025

To: Cooper City

Project: Suellen Fardelmann Cooper City Sports Complex

Cooper City, FL

Quotation Price – Materials Delivered to Job Site and Installation

Suellen Fardelmann Sports Complex - Security Lighting

.....\$ 89,500.00

All purchase orders should note the following:

Clay County RFP 23/24-074

Sales tax, permitting fees, and bonding are not included.

Pricing furnished is effective for 90 days unless otherwise noted and is considered confidential.

Field Description	Quantity	Pricing Per Clay County	Extended Price
(Section 1 B) LED Security Fixture	46	\$2,500.00	\$115,000.00
Deduct / Design Parameters / Labor			-\$25,500.00
Total			\$89,500.00

Supplemental Lighting

- 46 luminaires
- 10-year materials and labor warranty



Installation Services Provided

Customer Responsibilities:

1. Complete access to the site for construction using standard 2-wheel drive rubber tire equipment.
2. Locate existing underground utilities not covered by your local utilities. (i.e. water lines, electrical lines, irrigation systems, and sprinkler heads). Musco or Subcontractor will not be responsible for repairs to unmarked utilities.
3. Locate and mark field reference points per Musco supplied layout. (i.e. home plate, center of FB field).
4. Ensure usability of existing underground wiring.
5. Pay any necessary power company fees and requirements.
6. Pay all permitting fees.
7. Provide any existing as-built documents or drawings.

Musco Responsibilities:

1. Provide required fixtures, electrical enclosures, mounts, hardware, wire harnesses.
2. Provide poletop luminaire assembly on 46 poles.
3. Provide fixture layout and aiming diagram.
4. Provide Project Management as required.
5. Assist our installing subcontractor and ensure our responsibilities are satisfied.

Subcontractor Responsibilities

General:

1. Obtain any required permitting.
2. Contact your local UDig for locating underground public utilities and confirm they have been clearly marked.
3. Contact the facility owner/manager to confirm the existing private underground utilities and irrigation systems have been located and are clearly marked to avoid damage from construction equipment. Notify owner and repair damage to marked utilities. Notify owner and Musco regarding damage which occurred to unmarked utilities.
4. Provide labor, equipment, and materials to off load equipment at jobsite per scheduled delivery.
5. Provide storage containers for material (including electrical components enclosures), as needed.
6. Provide necessary waste disposal and daily cleanup.
7. Provide adequate security to protect Musco delivered products from theft, vandalism, or damage during the installation.
8. Keep all heavy equipment off playing fields when possible. Repair damage to grounds which exceeds that which would be expected. Indentations caused by heavy equipment traveling over dry ground would be an example of expected damage. Ruts and sod damage caused by equipment traveling over wet grounds would be an example of damage requiring repair.
9. Provide startup and aiming as required to provide complete and operating sports lighting system.
10. Installation to commence upon delivery and proceed without interruption until complete. Musco to be immediately notified of any breaks in schedule or delays.



Quote

Demolition:

1. Remove and dispose of the existing fixtures, and electrical enclosures. This will include the recycling of lamps, aluminum reflectors, ballast, and steel, as necessary.
2. Leave existing ground wires and power feed in place for connection to new lighting equipment.

Retrofit Musco Equipment to Existing Poles:

1. Provide labor, materials, and equipment to assemble and install equipment on existing poles and terminate grounding and power feed. Power feed may need to be reworked to adapt to the new Musco equipment.

Electrical:

1. Provide materials and equipment to reuse existing electrical service panels as required.
2. Provide materials and equipment to reuse existing electrical wiring as permitted.

Payment Terms

Net 30 days.

Delivery Timing

8 - 12 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations.

Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.

Notes

Quote is based on:

- Shipment of entire project together to one location.
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees.
- Confirmation of pole locations prior to production.

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.



Jason Frucht
Sales Representative
Musco Sports Lighting, LLC
Phone: 954-732-5674
E-mail: jason.frucht@musco.com

