# WEEKLEY ASPHALT PAVING, INC.

20701 Stirling Road · Pembroke Pines, Florida 33332

Date 2/27/2025
Owner **CITY OF COOPER CITY**
Attention TIM FLEMMING
Email

Job Name/Location: **CITY OF COOPER CITY : PHASE 2 - SPORTS COMPLEX**
*UTILIZING BROWARD COUNTY CONTRACT #* ***PNC2124420B1***

**SPORTS COMPLEX PHASE 2**
**STIRLING ROAD / PALM AVE**

**PROPOSAL**

| ITEM # | QTY | UNIT | DESCRIPTION | | PRICE | | Total |
|---|---|---|---|---|---|---|---|
| -01-01 | 1.00 | LS | MOBILIZATION | @ | $ 2,500.00 | = | $ 2,500.00 |
| -02-02 | 30.00 | DAY | WORK ZONE SIGNS, F & I | @ | $ 0.29 | = | $ 8.70 |
| -02-09 | 500.00 | DAY | TRAFFIC CONES, F & I | @ | $ 0.05 | = | $ 25.00 |
| -03-03 | 11.00 | EA | INLET PROTECTION SYSTEM | @ | $ 130.00 | | $ 1,430.00 |
| -05-02 | 6,304.00 | SY | MILLING EXIST ASPH PAVT, 1 IN AVG DEPTH (MORE THAN 1,000 SY) | @ | $ 3.00 | = | $ 18,912.00 |
| -05-10 | 560.00 | TN | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC A, B, C, D, OR E, 101 to 500 TON | @ | $ 180.00 | = | $ 100,800.00 |
| -08-05 | 25.00 | EA | RETRO-REFLECTIVE PAVEMENT MARKERS | @ | $ 6.50 | = | $ 162.50 |
| -08-06 | 2,210.00 | LF | PAINT PAVEMENT MARKINGS, STND., WHITE/YELLOW, SOLID, 6 IN | @ | $ 0.80 | = | $ 1,768.00 |
| -08-06* | 328.00 | LF | PAINT PAVEMENT MARKINGS, STND., WHITE/YELLOW, SOLID, 6 IN *DOUBLE YELLOW* | @ | $ 0.80 | = | $ 262.40 |
| -08-09 | 9.00 | EA | PAINT PAVEMENT MARKINGS-STND., WHITE, ARROWS | @ | $ 80.00 | = | $ 720.00 |
| -08-11 | 50.00 | SF | PAINT PAVEMENT MARKINGS-STANDARD, WHITE/YELLOW, ISLAND NOSE | @ | $ 2.90 | = | $ 145.00 |
| -08-12 | 27.00 | LF | PAINT PAVEMENT MARKINGS, STND., WHITE/YELLOW, SOLID, 8 IN | @ | $ 0.35 | = | $ 9.45 |
| -08-15 | 48.000 | LF | PAINT PAVEMENT MARKINGS, STND., WHITE/YELLOW, SOLID, 24 IN | @ | $ 1.00 | = | $ 48.00 |
| -08-22 | 461.000 | LF | THERMO, STND., OR 10-30 SKIP, 2-4 DOTTED, SOLID 6 IN, WHITE/YELLOW | @ | $ 0.35 | = | $ 161.35 |
| -08-22* | 152.000 | LF | THERMO, STND., OR 10-30 SKIP, 2-4 DOTTED, SOLID 6 IN, WHITE/YELLOW *DOUBLE YELLOW* | @ | $ 0.35 | = | $ 53.20 |
| -08-24 | 27.000 | LF | THERMO, STND., WHITE/YELLOW, SOLID, 8 IN | @ | $ 0.45 | = | $ 12.15 |
| -08-27 | 58.000 | LF | THERMO, STND., WHITE/YELLOW, SOLID, 24 IN | @ | $ 4.75 | = | $ 275.50 |
| -08-30 | 9.000 | EA | THERMO-STND., WHITE, ARROW | @ | $ 95.00 | = | $ 855.00 |
| | | | | | | | |
| -08-39 | 2.000 | EA | MINIMUM CHARGE FOR STRIPING FOR EACH PROJECT | @ | $ 2,500.00 | = | $ 5,000.00 |
| -09-04 | 4.000 | HOUR | SKILLED LABOR | @ | $ 44.00 | = | $ 176.00 |
| | | | | @ | | = | $ - |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | **TOTAL QUOTE** | | **$ 133,324.25** |

**Notes:** **NO BOND , NO PERMIT.**

Quoted By:

Clint Parrish
Asphalt General Manager

Accepted By:

Name
Title

Kelly Reed