

**Cottage City - 43rd
Maintenance Project
PROJECT BID FORM**

Contractor Name: _____

	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
Cottage City 43rd Avenue					
101-01	Clearing and Grubbing	LS	1		\$ -
104-01	Maintenance of Traffic	LS	1		\$ -
107-01	Construction Stakeout	LS	1		\$ -
108-01	Mobilization and Demobilization	LS	1		\$ -
109-01	Critical Path Method Project Schedule	LS	1		\$ -
203-01	Earth Fill (Contingency)	LS	1		\$ -
206-01	Removal of Existing Curb and Gutter; any type	LF	1000		\$ -
206-02	Removal of Existing Concrete Sidewalk	CY	5		\$ -
206-03	Removal of Existing Asphalt Pavement, Full Depth	CY	150		\$ -
206-04	Removal of Existing Concrete Pavement	CY	7		\$ -
306-01	6" Solid PVC Schedule 40	LF	10		\$ -
306-02	4" Perforated PVC Schedule 40	LF	10		\$ -
306-03	4" Solid PVC Schedule 40	LF	4		\$ -
306-04	Miscellaneous Polyvinyl Chloride (P.V.C.) Fittings	LS	1		\$ -
306-05	Trench Drain System - Materials & Installation	LF	365		\$ -
308-01	Overall Sediment Control	LS	1		\$ -
501-01	4" Graded Aggregate Base	SY	740		\$ -
504-01	Hot Mix Asphalt Superpave 9.5MM for Surface; PG 64-22, 1.5 inch in depth	SY	710		\$ -
504-02	Hot Mix Asphalt Superpave 19.0 MM for Surface; PG 64-22, 3 inch in depth	SY	355		\$ -
504-03	Hot Mix Asphalt Superpave 9.5 MM for Base; PG 70-22, 2 inch in depth	SY	1800		\$ -
508-01	Milling Existing Hot Mix Asphalt Pavement and Disposal, 2 inch in depth	SY	1800		\$ -
520-01	Reinforced 8" Concrete MSHA Mix No. 9 (Air-Entrained Concrete Paving)	SY	385		\$ -
549-01	5" Wide Double Yellow Pavement Markings - (Non-Thermoplastic and Non-Toxic)	LF	60		\$ -
549-02	Yellow Pavement Markings (For Curb) - (Non-Thermoplastic and Non-Toxic)	LF	60		\$ -
549-03	12" Wide Solid White Pavement Marking for Crosswalk Yellow - (Thermoplastic)	LF	80		\$ -
549-04	24" Wide White Pavement Marking for Stop Bar - (Thermoplastic)	LF	10		\$ -
602-01	Standard Concrete Curb and Gutter, any type	LF	1360		\$ -
603-01	Commercial Driveway Entrance (per PG DPWT Std. 200.03)	CY	8		\$ -
603-02	Concrete Driveways Strips in Alleyway (MSHA Mix No. 3)	CY	15		\$ -
603-03	5 Inch Concrete Sidewalk	SF	25		\$ -
705-01	Permanent Stabilization By Seed and Mulch	LS	1		\$ -
715-01	Tree Root Pruning	LF	30		\$ -
1012-01	MSHA Washed No. 57 Stone	CY	2		\$ -
	Cottage City 43rd Avenue Total				\$ -