March 31, 2025

Special Use Permit Request for Ground Mounted Solar PV at 501 Caton Farm Road Crest Hill, IL 60441

To Whom It May Concern,

Verde Solutions is partnering with Hendrickson USA to develop a 4.8-acre ground mounted solar PV system at their facility located at 501 Caton Farm Road. The 12-acre field is owned by Hendrickson. Verde Solutions has over 10 years of experience in the solar industry, specializing in Illinois with our office located in Chicago.



Nearmap Imagery Taken October 10, 2024

Design and Intent

The system consists of (1,992) solar modules, equating to 1.185 MW DC capacity, and is intended to offset approximately 100% of Hendrickson's annual electric consumption. The panels are fixed at a 30-degree tilt to the south and arranged into nine rows. The array is enclosed with a fence and is setback approximately 180 feet south of Caton Farm Road. The solar system interconnects to Hendrickson's electrical infrastructure to supply their electrical needs behind the utility meter. The project received ComEd's interconnection and net metering approval



March 7, 2025. All proposed solar equipment complies with the 2020 National Electric Code and City of Crest Hill ordinances. The inverters and utility AC disconnect are to be fenced in and located near their existing utility transformer on the west side of the main building.

Site Improvements

The proposed developed area of 4.8 acres will comply with the City's Building Ordinance Chapter 15. The landscaping plan includes (216) new trees and shrubs. Much of the proposed landscaping will screen the array from Caton Farm Road. The ground under the array will be covered with a native seed mix and include an erosion control blanket. The stormwater report describes how the ground mounted solar will affect the current drainage plan. It was determined that site runoff storage is not required for this project.

The fence is 6 feet tall chain link style with 1 foot of barbed wire. There is a 16-foot-wide vehicle access gate located at the northeast corner of the array.

Upon discussion with the City and Lockport Fire Protection District (LFPD), a gravel access path will be provided around the perimeter of the array within the fence to be used for emergency access. The gravel will be ¾" limestone loosely compacted. A variance is requested to accommodate this, as the path will be used for emergencies. Adequate turn clearance is provided per the Pierce Turning Performance Analysis provided by LFPD.

Operations and Maintenance

Once the solar system is installed, there is very little maintenance required. The solar system is fully static and rarely requires hands-on troubleshooting after energization. We offer maintenance packages custom to the client but a small percentage of our clients choose to do so. We recommend it is not necessary in the first five years of operation because adequate IL rainfall and the tilt of the modules naturally minimize dust and debris accumulation.

Maintenance and operations are primarily supported by the remote monitoring system, which alerts us and the client of any potential system faults. Most of these faults occur during system testing and commissioning, so our installers are still on site to address them. If a fault arises after we leave the site, we will first detect it remotely and work to resolve it. Should the issue require on-site attention, we will send 1-2 team members to troubleshoot. It usually takes a few hours to half a day.

The equipment has long warranties: Modules - 30 year performance, inverters - 20 year extended, and racking - 20 years.

If the client opts for our standard Verde Maintenance & Operations plan, we will perform a site visit once a year for one day, typically involving a visual inspection and documentation (1-2 people). If the plan is not selected, the system will remain hands-off.

Decommissioning Plan

While a decommissioning plan is not included in the active and current EPC contract with Hendrickson, we will offer to do so at the client's request when the time comes. As an industry standard, the expected useful life of the solar system is 30 years. The solar panels are warrantied against a 0.5% production degradation each year. By year



Go Green Get Ahead

30, the solar panels will be producing 85% of their original output. The solar system will continue to produce long after that, and it would be up to the client to decide to leave the system as is, upgrade to newer technology, or explore system removal.

During system removal, Verde would remove all of the tangible property relating to the solar system. The land would be restored to its original condition with the exception of buried conduits.

Verde Solutions would use Com2 Recycling Solutions for the Removal and Decommissioning of the dated solar panels. Com2 Recycling Solutions is an R2 Certified recycling company located in Chicagoland which complies with all rules and regulations relative to the recycling of solar panels and inverters. The Certificate of Recycling (COR) would be issued once fully recycled.

About Verde Solutions

Verde Solutions, founded in 2012 by Christopher Gersch, is a leader in energy efficiency and sustainability solutions. With over 2,600 completed projects across 48 states, we bring proven expertise in energy reduction and generation solutions for commercial, industrial, educational, and municipal projects. We have consistently demonstrated growth and leadership, earning recognition on the INC 5000 list multiple times and inclusion in Solar Power World's top commercial solar contractors in 2024. Our extensive experience with educational institutions and municipalities ensures that we are well-equipped to deliver a successful project. Notable similar projects that we have completed include a 777kW-DC ground mount for the Minooka Wastewater Treatment plant, a 1.2 MW ground mount at a gravel pit in Lakemoor, a combo rooftop and ground mount for a commercial client in St. Charles, and a 2MW rooftop and ground mount for the College of Lake County.

Further Discussion

The City identified a wetland on the neighboring parcel to the south (ComEd, 11-04-33-100-006-0000). The wetland firm is unable to complete a full delineation until ground conditions are favorable in May. Due to the IL Shines solar incentive block closing on June 1, 2025, which requires Special Use Permit approval, it was mutually agreed with the City that, following the wetland delineation results, the solar array will be adjusted if necessary to avoid negatively impacting the current drainage to the wetland. However, given the wetland is not in close proximity to the array, Verde does not anticipate the array moving much, if at all. The official wetland delineation will be promptly shared with the City and the impact to the array will be identified. The IL Shines solar incentive is lucrative and essential to the progress of this project.

Given our vast experience with solar ground mounts and Greater Chicagoland municipalities, we consider the landscaping and fire protection requirements to be above and beyond what other municipalities have required for parcels without neighboring residential zones. However, we fully understand that this project is subject to Crest Hill's approval and are eager to coordinate a successful solar system with the City.



We thank you for your consideration of this project and look forward to continuing discussions.

Regards,

Grace Rasmussen, Verde Solutions Project Engineer grasmussen@verdesolutions.com 312-268-2025

Site Plan Documents included in submission:

- 1. ALTA Survey
- 2. Electrical Construction Set Site Plan, Equipment Elevations, Single Line Diagram, NEC Labels
- 3. Racking Construction Set
- 4. Racking Structural Calculations
- 5. Landscaping Plan
- 6. Stormwater Report

Hey and Associates, Inc.

Solar Ground Mount System at Hendrickson USA

Crest Hill, Will County, Illinois
Stormwater Management Permit

Hey Project No. 25-0072

Prepared For: Verde Solutions

Prepared by:

Hey and Associates, Inc.

Engineering, Ecology and Landscape Architecture

Main Office:

26575 W. Commerce Dr., Ste 601 Volo, Illinois 60073 847-740-0888 (phone) 847-740-2888 (fax)

Additional Offices:

Chicago, IL 8755 W. Higgins Rd., Ste 835 Chicago, Illinois 60631 773-693-9200 (phone) 773-693-9202 (fax)

Illinois Professional Design Firm 184.002429 / Wisconsin Architectural and Engineering License # 2340-11 Staff licensed to practice in Illinois, Wisconsin, Indiana, Michigan and Oregon IDOT and WisDOT Prequalified

Table of Contents

Introduction	2
Site Runoff and Site Runoff Storage	2
Groundcover Vegetation	3
Impervious Areas	3
Solar Panel Spacing and Sheet Flow	3
Sediment and Erosion Control	3
Special Management Areas	3

Exhibits

Exhibit 1 - Location Map

Exhibit 2 - Drainage Plan

Exhibit 3 – FEMA FIRMETTE

Appendices

Appendix A – Planset

INTRODUCTION

Hey and Associates, Inc. (Hey) was retained by Verde Solutions to prepare permit documentation as part of the Solar Ground Mount System at Hendrickson USA project (Project). The site is located in the City of Crest Hill, Will County, Illinois. The project is further located in Section 33 of Township 36 North, Range 10 East in Lockport Township. See Exhibit 1 for an overall project location map.

The project includes the installation of solar panels on a grass field to provide energy for the manufacturing facility on site. Some existing trees will be removed to avoid interference with the solar panel performance. The area under the solar panels will be seeded with a pollinator habitat seed mix, and a variety trees and shrubs will be planted as well.

SITE RUNOFF AND SITE RUNOFF STORAGE

The site generally drains towards the southeast. After leaving the site boundaries, the drainage pattern continues towards the southwest into a swale along the north of the railroad. The swale then joins with a channel that flows towards the east and eventually empties into the Des Plaines River. This drainage pattern will be maintained in the proposed conditions. The drainage plan for the site is included as Exhibit 2.

According to section 55.020.C.3 of the Will County Code of Ordinances, solar farm developments are exempt from site runoff storage provided the following criteria are met:

- a) Groundcover vegetation is maintained in good condition
- b) The total proposed impervious area is less than 25,000 square feet
- c) The open space between the panels are equal or greater than the panel width
- d) The runoff will sheet flow through the site with a slope of less than 5 percent

These criteria are met, as described in the sections below, and therefore site runoff storage is not required for this project. Additionally, the following sections illustrate compliance with sections 15.20.030 and 15.20.070 from the Crest Hill Code of Ordinances.

GROUNDCOVER VEGETATION

The entire area under the proposed solar panels will be seeded with a native seed mix. The seed mix and location is described in the landscaping plan sheets, which are included in Appendix A. The proposed groundcover vegetation will be maintained in good condition by the owner.

IMPERVIOUS AREAS

No impervious area is proposed on the site. An access road constructed of loosely compacted 3/4" gravel is proposed around the solar panels. However, loosely compacted gravel is not considered impervious by the City of Crest Hill and so is not counted as proposed impervious area.

SOLAR PANEL SPACING AND SHEET FLOW

The solar panels have a width of 12.97 feet, and each row of panels will be installed with a 19.17 foot space between them, meeting the requirement that the open space must be wider than the solar panels. The panels will be at a 30-degree angle, so runoff will sheet flow onto the ground. The slope of the ground underneath the panels varies, with the northwestern area containing a generally steeper slope that becomes more gradual at the southeast corner. The average ground slope is approximately 2.15% underneath the panels, which is within the ordinance guidelines.


SEDIMENT AND EROSION CONTROL

The seeding mix proposed for the solar panel area will be installed with erosion control blanket to protect against erosion and promote seed establishment and growth. Additionally, a total of 216 trees and shrubs are to be planted on site in accordance with section 15.04.040 of the Crest Hill Ordinance. These plantings will provide further permanent erosion control on site.

SPECIAL MANAGEMENT AREAS

There is no floodway or floodplain on site, as shown in Exhibit 3. There are also no wetlands on site.

3



Scale: 1 inch = 2000 feet

et Orientation:

Legend:



Project Site

Project Number: 25-0072


Date: 3/13/2025

Project Name:

Solar Ground Mount at Hendrickson USA

Prepared for:

Verde Solutions



National Flood Hazard Layer FIRMette




Basemap Imagery Source: USGS National Map 2023

Exhibit 3 - FEMA FIRMETTE

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 3/13/2025 at 9:32 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



Appendix A

Plan Set

BUILDING CORNER IS

TO THE SURVEYOR'S KNOWLEDGE, BASED ON FIELD EVIDENCE AND PROVIDED DOCUMENTATION, THERE ARE NO ENCROACHMENTS ONTO ADJOINING PROPERTY. STREETS OR ALLEYS OR ANY EASEMENTS BURDENING THE LEASE AREA BY ANY BUILDINGS, STRUCTURES, OR OTHER IMPROVEMENTS.

THERE ARE ALSO NO ENCROACHMENTS ONTO THE LEASE AREA OR EASEMENTS BENEFITING THE SURVEYED PROPERTY BY BUILDINGS, STRUCTURES, OR OTHER IMPROVEMENTS SITUATED ON ADJOINING PROPERTIES.

S 84°26'24" W 831.95

NORTH LINE OF LAND CONVEYED IN BOOK 661, PAGE 564 AS DOCUMENT #419036

LIST OF POSSIBLE ENCROACHMENTS

PIN #: 11-04-33-100-006 OWNER: COMMONWEALTH EDISON CO.

SEE SHEETS SUR-2 & SUR-3 FOR

TOPOGRAPHIC FEATURES

· 日本日本

88

— TOP OF (CURR, WALL, E SPOT GRADE — BOTTOM OF (ORDUND,

MONITOR WELL

GAS VALVE

LEGEND UTILITY POLE TYPICAL SIGN MAILBOX

SOIL BORING TELCO/ELEC MANHOLE - HANDRAIL

CONTOUR LINE
CONTOUR LINE
EDGE GRAVEL/STONE
FENCE LINE
FLARED END SECTION
STORM SEWER
SANITARY SEWER
COMBO SEWER
WATER SERVICE LINE
WATER MAIN
OVERHEAD LINE
FIBER OPTIC LINE
GAS LINE

SCALE: 1" = 50"

BAR SCALE

BASIS OF BEARINGS IS TRUE NORTH BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, ILLINOIS EAST 1201 ZONE.

⊕_{SB} ⊕E

______ GUARDRAIL

12 - EASEMENT DATED JULY 26, 1954 AND RECORDED DECEMBER 11, 1961 AS DOCUMENT NO. 945505 MADE BY A E PATTON AND MABEL MARGARET PATTON TO COMMON WEALTH EDISON COMPANY AND ILLINOIS BELL TELEPHONE COMPANY RECORDED IN THE WILL COUNTY RECORDERS OFFICE OFFICE.
EASEMENT FALLS IN RIGHT OF WAY.

> STATE OF ILLINOIS COUNTY OF COOK

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN INIS 3 TO CENTIF THAT THIS WAR OF FLATAND THE SORVELLOW MADE IN A SCORDANCE WITH THE 2021 MINIMUM STANDARD BETAIL REQUIREMENTS FOR ALTA/ANSP LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 3, 8A, 7A, 8, 9, 11A, 13, 14, AND 16 OF TABLE "A" THEREOF. THE FIELD WORK WAS COMPLETED ON 12/4/2024.

GIVEN UNDER MY HAND AND SEAL THIS _____ DAY OF ___ AT HOFFMAN ESTATES, ILLINOIS.

PRELIMINARY 2/7/2025

FRANJO I. MATICIC - PLS #035-003556 EXPIRES 11/30/2026 ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184.007570-0015

CHECK:FIM DRAWN:REM JOB: S2400104

HENDRICKSON USA 501 CATON FARM ROAD CREST HILL, ILLINOIS

SHEET 1 OF 3

ISSUE

12/19/2

1/17/25

2/7/2


LIENT


LIENT

LIENT

SUR-1

GROUP





PLAT OF SURVEY

SPACECO UAV **AERIAL IMAGE** DATE OF FLIGHT: 03/19/2024

PROPERTY DESCRIPTION:

FOUND 5/8*IR -33.31'S & ON-LINE

EXCEPTION TO PARCEL 2

BY QUIT-CLAIM DEED RECORDED IN SAID RECORDER'S OFFICE AS DUCUMENT 40-VIDO, WHICH FOUR WEST FROM THE EAST LIKE OF SAID NORTHWEST TO QUARTER MEASURED PERPENDICULARLY THEREFURE OF TABLE OF THE ASSOCIATION OF THE SAID THE SOUTHEAST CORNER OF SAID TRACT OF LAIND CONVEYED BY DOCUMENT 7 SOUTHEAST CORNER IS ON THE EAST LIKE OF SAID WEST LIVES A FEET AND THECK INFORTH ALO, LIKE OF SAID TRACT CONVEYED BY DOCUMENT 75-202 AND ALONG SAID EAST LIKE OF THE WEST AS DISTANCE OF 65.50-FEET TO THE WEST AS DISTANCE OF 65.50-FEET TO THE PLACE OF BEGINNING, IN WILL COUNTY, LIKINGS.

FENCE CORNER 34.10'S & 0.10'E

S84°26'43"W

THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF A TITLE COMMITMENT. IT IS POSSIBLE THAT ADDITIONAL EASEMENTS, RESTRICTIONS OR OTHER ENCLMBRANCES EXIST OVER THE PROPERTY THAT HAVE NOT BEEN SHOWN HEREON.

BEARINGS SHOWN HEREON ARE BASED ON NAD83 ILLINOIS STATE PLANE COORDINATE SYSTEM, EAST ZONE (2011 ADJUSTMENT) AND NAVD88 (GEOID 12B) UTILIZING GNSS EQUIPMENT AND TOPNETLIVE RTK NETWORK. LAST DATE OF FIELD WORK: APRIL I, 2024

PROPERTY SURVEYED: 1,072,114 SQ. FT. OR 24.612 ACRES MORE OF LESS.

P.I.N: II-04-33-I00-002-0000 (PARCEL 2) II-04-33-I00-003-0000 (PARCEL I)



LEGEND CACTO BASIN'
NILET
FLARED FAID SEPROM
ELECTRIC MANANCE
TELEPHONE MANANCE
TELEPHONE WITH EMBORIT
ELECTRIC UPRISHT
FIRE HYDRAIT
VALVE AND VALUT
WATER MAVE
B BOX
AUX_BY VALVE
GAS WILVE ASPHALT COMORETE GRAVEL

__ * ___ * ___

STATE OF ILLINOIS)
) SS
COUNTY OF GRUNDY)

FOUND 3/4"IP -0.72'W & ON-LINE

WE, SPACECO, INC., AN ILLINOIS PROFESSIONAL DESIGN FIRM, NUMBER 184-001157, DO HEREBY DECLARE THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED IS A TRUE AND CORRECT REPRESENTATION OF SAID SURVEY.

FOUND 3/4"IP 0.70'W & ON-LINE

-FOUND 5/8"IR (BENT) 0.70'E & ON-LINE

THIS PROFESSIONAL SERVICE CONFORMS TO THE CURRENT ILLINOIS MINIMUM STANDARDS OF PRACTICE APPLICABLE TO BOUNDARY SURVEYS.

20

(VALID ONLY IF EMBOSSED SEAL AFFIXED)

COMPARE ALL DIMENSIONS BEFORE BUILDING AND REPORT ANY DISCREPANCIES AT ONCE. REFER TO DEED OR TITLE POLICY FOR BUILDING LINES AND EASEMENTS.

GIVEN UNDER OUR HAND AND SEAL THIS 2ND DAY OF APRIL, 2024 IN MORRIS, ILLINOIS.

CONSULTING ENGINEERS
SITE DEVELOPMENT ENGINEERS
LAND SURVEYORS

224 ½ N. Liberty Street, Morris, Illinois 60450 Phone: (815) 941-0260 Fax: (815) 941-0263

SOLAR GROUND MOUNT SYSTEM AT HENDRICKSON USA

501 CATON FARM RD, LOCKPORT, IL 60441







SYSTEM PLAN

TOTAL SYSTEM SUMMARY:

TOTAL DC SYSTEM SIZE:

1,185.24 kWDC

TOTAL AC SYSTEM SIZE: 900.00/947.700 kWAC/KVA

MODULE MANUFACTURER: JINKO SOLAR

(1,992) JKM595N-72HL4-BDV (QTY) MODULE TYPE 1:

MODULE TILT:

180° MODULE AZIMUTH:

INVERTER MANUFACTURER: CHINT POWER SYSTEMS

(QTY) INVERTER TYPE 1: (9) CPS SCH100KTL DO/US-480

NOTES SPECIFIC TO ILLINOIS ADOPTED NEC VERSION: 2008 (SET DESIGNED TO NEC 2023) ADOPTED IBC VERSION: 2021

SCOPE OF WORK SUMMARY

GROUND MOUNT PY ARRAY:

INSTALL SOLAR MODULES AND RACKING SYSTEM ON GROUND LEVEL.

INSTALL INVERTERS AND ELECTRICAL DISTRIBUTION EQUIPMENT.

INTERCONNECT AT EXISTING ELECTRICAL DISTRIBUTION EQUIPMENT.

DEVELOPER:



2211 N ELSTON AVE SUITE 208 CHICAGO, IL 60614

ENGINEERED BY:



111 RIVER STREET, SUITE 1110 HOBOKEN, NEW JERSEY 07030

DRAWING	INDEX
GENERAL	

GENER	RAL			1	1
G001	TITLE SHEET	•	•	•	
ELECT	RICAL				/
E001	ELECTRICAL NOTES & SYMBOLS LIST		•	•	
E100	OVERALL ELECTRICAL PLAN	•	•	•	
E101	AC ELECTRICAL PLAN		•	0	
E200	DC ELECTRICAL PLAN		•	0	
E300	ONE LINE DIAGRAM	•	•	0	
E310	SCHEDULES & CALCULATIONS		•	0	
E410	GROUNDING DETAILS		•	•	
E420	ELECTRICAL DETAILS		•	0	
E500	LABELS & SIGNAGE		•	0	
E600	EQUIPMENT DATA SHEETS		•	0	
E601	EQUIPMENT DATA SHEETS		•	0	

LEGEND:

UPDATED DRAWING ISSUED								
UNCHANGED, PREVIOUSLY ISSUED DRAWING STILL CURRENT	0							
DRAWING REMOVED FROM SET	×							

TITLE SHEET

G001

- 6.F. ALL ELECTRICAL EQUIPMENT SHALL BE LISTED OR LABELED BY A RECOGNIZED TESTING AGENCY.
 6.G. ARC FLASH HAZARD WARNING LABELS SHALL BE PROVIDED AND MOUNTED ON EVERY NEW ENCLOSURE CONTAINING SERVICEABLE COMPONENTS SUCH AS CONDUCTOR TERMINATIONS, DISCONNECTS, OR OCPDS. THIS INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING COMPONENTS: COMBINER BOX, TERMINAL BOX, INVERTER, AC AND DC SWITCH, TRANSFORMER, AND SWITCHGEST
- TRANSFORMER, AND SWITCHGEAR.

 HAND HOLES, PULL BOXES, OR CONDUIT BODIES SHALL BE INSTALLED (WHETHER OR NOT SHOWN ON DRAWINGS) WHEN THE RACEWAY HAS MORE THAN 360° OF BENDS, OR AS NECESSARY TO NOT EXCEED MANUFACTURER'S MAXIMUM CABLE PULLING TENSION.

 SWITCHBOARDS AND SWITCHGEARS SHALL BE PROVIDED WITH TEMPORARY INTERNAL HEATERS DURING LONG TERM STORAGE WHILE NOT ENFENCIED AS REQUIRED BY THE MANUFACTURER. ALL OTHER EQUIPMENT SHALL BE STORED IN ACCORDANCE WITH MANUFACTURER.

 ALL OTHER EQUIPMENT SHALL BE STORED IN ACCORDANCE WITH MANUFACTURER.
- INSTRUCTIONS.

 6.J. ALL ELECTRICAL EQUIPMENT CONTAINING A CIRCUIT BREAKER OR FUSE SHALL BE INSTALLED IN COMPLIANCE WITH NEC ARTICLE 240.24.

 6.K. CONTRACTOR SHALL FIELD VERIFY DESIGN COMPLIES WITH NEC 312.8 PRIOR TO INSTALLATION.

 6.L. ALL NEW ELECTRICAL EQUIPMENT INSTALLED INDOORS REQUIRES GFCI OUTLET TO BE

7. GROUNDING
7.A. THE CONTRACTOR SHALL FURNISH AND INSTALL GROUNDING NECESSARY IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.

- 8. <u>IESTS</u>
 8.A. ALL TESTS SHALL BE PERFORMED BY TRAINED TECHNICIANS CERTIFIED TO DO THE PROCEDURES.
- B.B. FINAL TESTS AND INSPECTIONS SHALL BE HELD IN THE PRESENCE OF THE OWNER'S REPRESENTATIVES AND TO THEIR SATISFACTION.

 ALL APPLICABLE TESTS SHALL BE PERFORMED IN ACCORDANCE WITH NETA/ANSI ATS—2021 STANDARDS AND PRACTICES.

- 8.C. ALL APPLICABLE TESTS SHALL BE PERFORMED IN ACCORDANCE WITH NETA/ANSI ATS-2021 STANDARDS AND PRACTICES.
 8.D. ALL APPLICABLE TESTS SHALL BE PERFORMED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
 8.E. ALL TESTS SHALL BE PERFORMED PRIOR TO ENERGIZATION.
 8.F. TESTING IS LIMITED TO NEW EQUIPMENT RELATED TO THIS PROJECT.
 (OR EQUIVALENT DEVICE) AND SUBMITTED TO THE OWNER FOR APPROVAL IF MUPPE IS USED, MODULE TRACES ARE PERMITTED TO BE GENERATED THROUGH THE INVERTER PORTAL. TESTING TO BE PERFORMED DURING APPROVED WEATHER CONDITIONS.
 8.H. OPEN-CIRCUIT VOLTAGE (VCo.) MEASUREMENTS SHALL BE PERFORMED ON ALL DC STRING CIRCUITS DURING APPROVED WEATHER CONDITIONS.
 8.I. ALL PV CONNECTORS MATED TOGETHER SHALL BE CONFIRMED TO BE OF THE SAME MAKE/MODEL.
 8.J. INSULATION TESTS SHALL BE PERFORMED ON ALL STRING AND FEEDER DC CIRCUIT CABLES.
 8.L. ISSULATION TESTS SHALL BE PERFORMED ON ALL STRING AND FEEDER AC CIRCUIT CABLES.
 8.L. ISSULATION TESTS SHALL BE PERFORMED ON ALL STRING AND FEEDER AC CIRCUIT CABLES.
 8.L. ISSULATION TESTS SHALL BE PERFORMED ON ALL STRING AND FEEDER AC CIRCUIT CABLES.
 8.L. SALUATION TESTS SHALL BE PERFORMED ON ALL STRING AND FEEDER AC CIRCUIT CABLES.
 8.L. ROUND FAULT PROTECTION SYSTEMS SHALL BE FUNCTIONALLY TESTED IN ACCORDANCE WITH MANUFACTURER INSTRUCTIONS (NEC 230-95(C)).
 8.M. RELAY PROTECTION SYSTEM FUNCTIONAL TESTS SHALL BE IN ACCORDANCE WITH THE SETTINGS PROVIDED AND WITHIN THE OPERATIONAL INTENT OF THIS PROJECT NOTED IN EOR DRAWING. TESTING SHALL ENSURE RELAY READS VALUES ACCURATELY AND ALL LOGIC FACILITATES THE NECESSARY OPERATIONAL BEHAVIOR.
 8.N. ACCEPTANCE TESTING SHALL BE PERFORMED ON ALL COMBINER BOXES, PANELBOARDS SWITCHBOARDS AND SWITCHGEAR.

GENERAL NOTES

- THE GENERAL NOTES APPLY TO ALL DRAWINGS UNDER THE CONTRACT. REFER TO INDIVIDUAL DRAWINGS FOR ADDITIONAL NOTES.
 DRAWINGS ARE DIAGRAMS AND INDICATE GENERAL ARRANGEMENT OF SYSTEMS AND WORK. FOLLOW DRAWINGS IN LAYING OUT OF WORK AND CHECK DRAWINGS OF OTHER TRADES TO VERIFY SPACE CONDITIONS. MAINTAIN HEADROOM, SPACE CONDITIONS, AND REQUIRED CLEARANCES.

 PV SYSTEM CONTRACTOR SHALL COORDINATE ALL THE WORK WITH THE ENGINEER, THE CONSTRUCTION MANAGER AND ALL OTHER CONTRACTORS TO INSURE THAT THE PV SYSTEM IS INSTALLED AS SPECIFIED IN THESE DRAWINGS.

 PRESENCE PROTECTIVE FOUNDMENT (SPEC) SCHALL BE REPOWED AS REQUIRED IN ACCORDANCE.
- 4. PERSONAL PROTECTIVE EQUIPMENT (PPE) SHALL BE PROVIDED AS REQUIRED IN ACCORDANCE WITH NFPA 70E AND OSHA REQUIREMENTS.
- 5. ALL STRUCTURAL AND MISCELLANEOUS EXTERIOR STEEL, INCLUDING STRUT CHANNEL (SUCH AS UNISTRUT OR KINDORF) SHALL BE CORROSION RESISTANT, HOT DIP GALVANIZED OR GALVANNEALED WITH A COATED FINISH MINIMUM.

<u>LEGEND — GENERAL</u>							
SYMBOL DESCRIPTION							
	LIGHT LINE INDICATES EXISTING OR BEYOND THE SCOPE OF PROJECT						
	DARK LINE INDICATES NEW OR WITHIN THE SCOPE OF PROJECT						
	DASHED LINE INDICATES EQUIPMENT AT A DIFFERENT ELEVATION						
EXISTING TEXT	LIGHT TEXT INDICATES EXISTING OR BEYOND THE SCOPE OF PROJECT						
NEW TEXT	DARK TEXT INDICATES NEW OR WITHIN THE SCOPE OF PROJECT						

<u>LEGEND - CIRCUITS</u>								
SYMBOL	SYMBOL DESCRIPTION							
_xxxx	ABOVE-GROUND CABLE							
	UNDER-GROUND CABLE							
NOTE: XX REPRESENTS CIRC	NOTE: XX REPRESENTS CIRCUIT TYPE BELOW							
ABBREVIATION	DESCRIPTION							
DC	DIRECT CURRENT							
AC	ALTERNATING CURRENT							
MV	MEDIUM VOLTAGE							
С	COMMUNICATIONS							
GND	GROUND							
CAB	CAB MESSENGER							
MES	MESSENGER WIRE							
F0	FIBER OPTIC							

	LEGEND - PLAN SYMBOLS
SYMBOL	DESCRIPTION
	RACEWAY TURNING UP OR TOWARDS OBSERVER
	RACEWAY TURNING DOWN OR AWAY FROM OBSERVER
J OR J	JUNCTION BOX
P	GROUND FAULT CIRCUIT INTERRUPTER DUPLEX RECEPTACLE, RATED: 125-VOLTS AC, 20A
•	GROUND ROD
•	GROUND ROD W/ TEST WELL
	SLOPE DIRECTION INDICATOR

	LEGEND - ONE LINE DIAGRAM & WIRING DIAGRAM SYMBOLS
SYMBOL	DESCRIPTION
- ←	CIRCUIT BREAKER, FRAME SIZE AND TRIP SETTING AS NOTED
~~	DISCONNECT SWITCH
7	INVERTER
+	BUSS CONNECTION POINT
+ +	CROSSING POINT (NO CONNECTION)
‡ ‡	NORMALLY CLOSED - NORMALLY OPEN CONTACTS
жμ.	TRANSFORMER CONTROL/POWER, SIZE AND RATING AS NOTED
₽	CURRENT TRANSFORMER
∃ ⊱	POTENTIAL TRANSFORMER
	FUSE, SIZE/RATING AS NOTED
~ ~□	FUSED DISCONNECT SWITCH
=	EARTH GROUND
≐	BATTERY
K	KEYED INTERLOCK (KIRK KEY OR EQ.)
ST (0)	SHUNT TRIP COIL; MOTORIZED CLOSE
Ø	SURGE ARRESTOR
M	METER
N	NEUTRAL BUS
G	GROUND BAR

BBREVIATION A	DESCRIPTION AMPERES
AERMS	ARC ENERGY REDUCING MAINTENANCE SYSTEM
AF	AMPERE FRAME
A.F.F.	ABOVE FINISH FLOOR
A.F.G.	ABOVE FINISH GRADE
AFDI	ARC FAULT DETECTION & INTERRUPTER
AIC	AMPS INTERRUPTING CAPACITY
AL	ALUMINUM
ATC	AMPERE TRIP AUTOMATIC TRANSFER SWITCH
ATS AWG	AMERICAN WIRE GAUGE
BKR	CIRCUIT BREAKER
C	CONDUIT
СВ	COMBINER BOX
CKT	CIRCUIT
CL	CLOSE
COU	CONDITIONS OF USE
CP	CONTROL PANEL
CT	CURRENT TRANSFORMER
CU	COPPER
DAS	DATA ACQUISITION SYSTEM
DB	DIRECT BURIAL
DISC	DISCONNECT
EGC	EQUIPMENT GROUNDING CONDUCTOR
ELEC	ELECTRIC, ELECTRICAL
EMERG	EMERGENCY FLEGTRIC METALLIC TURNING
EMT	ELECTRIC METALLIC TUBING
EQUIP	EQUIPMENT
EVCS	ELECTRIC VEHICLE ELECTRIC VEHICLE CHARGING STATION
G, GND	
GEC GEC	GROUND GROUNDING ELECTRODE CONDUCTOR
GEC	GROUND-FAULT CIRCUIT INTERRUPTER
GFPE	GROUND-FAULT PROTECTION OF EQUIPMENT
HID	HIGH-INTENSITY DISCHARGE (LIGHTING)
HZ	HERTZ
IMC	INTERMEDIATE METAL CONDUIT
kAIC	1000 AMPS INTERRUPT CAPACITY
kCMIL	1000 CIRCULAR MILS
kVA	KILO-VOLT AMPERE
kW	KILOWATT
LA	LIGHTNING & SURGE ARRESTOR
LED	LIGHT-EMITTING DIODE
LSIG	LONG, SHORT, INSTANTANEOUS, & GROUND-FAULT
LTG	LIGHTING
мсм	1000 CIRCULAR MILS
MFG	MANUFACTURER
MLO	MAIN LUGS ONLY
MLPE	MODULE LEVEL POWER ELECTRONICS
MPPT	MAXIMUM POWER POINT TRACKING
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NTS	NOT TO SCALE
OH	OVERHEAD OVER VOLTAGE
OV .	OVER VOLTAGE
P	POLE POWER FACTOR
PF DI O	POWER FACTOR
PLC	PROGRAMMABLE LOGIC CONTROLLER PLANE OF ARRAY
POA	
POI PRI	POINT OF INTERCONNECTION PRIMARY
PT	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE
PWR	POLITINITE CHLORIDE POWER
RAC	RIGID ALUMINUM CONDUIT
RCPT	RECEPTACLE
RGS	RIGID GALVANIZED STEEL CONDUIT
RMC	RIGID METAL CONDUIT
SA	SURGE ARRESTOR
SEC	SECONDARY
SPD	SURGE PROTECTION DEVICE
SSBJ	SUPPLY SIDE BONDING JUMPER
ST	SHUNT TRIP
STP	SHIELDED TWISTED PAIR
SW	SWITCH
TBD	TO BE DETERMINED
TP	TWISTED PAIR
TYP	TYPICAL
UG	UNDERGROUND
UON	UNLESS OTHERWISE NOTED
UV	UNDER VOLTAGE OR ULTRAVIOLET
V	VOLT
VA	VOLT-AMPERE
	WATT
W	WELTHER REGISTER
W WR	WEATHER RESISTANT
	WEATHER RESISTANT TRANSFORMER

ABBREVIATIONS


ELECTRICAL NOTES & SYMBOLS LIST


E001

SON FARM


ARE PROTECT INTENDED F INTENDED F PROJECT, UN DISTRIBUT PROJECTS

Verde





STRING SUMMARY STRING NAME PER STRING 1-1 24 1-2 24 1-3 24 1-4 24 1-5 24 1-6 24 1-7 24 1-8 24 1-9 24 1-10 24 2-1 24 2-2 24 2-3 24 2-4 24 2-5 24 2-6 24 2-7 24 2-8 24 2-9 24	8-5 24 8-6 24 8-7 24 8-8 24 8-9 24 9-1 24 9-2 24 9-3 24 9-4 24 9-5 24 9-6 24 9-7 24 9-8 24 9-9 24 TOTAL 1992									TABLE ASSL PV SOURCE STRING WRI	WITH ALLOWANCE FOR CONDUIT TRADE SIZE 3/4" 1" 1.25" 1.5" 2" 2.5" 3" 3.5" 4" MING: ANY CONDUIT TYPE AND CU CIRCUIT (SIMULATED) WITH 17.15A NO NOTE:	(PVWIRE, 2000VDC MAX) OF CU #10 PV WIRES. NA ADDITIONAL GROUND WIRE) ENGTH 24" OR LESS (60% FILL) 3	REPOWER DATE REVISION DESCRIPTION PM FING CI N E R I N G CI N
2-10 24 3-1 24 3-2 24 3-3 24 3-4 24 3-5 24 3-6 24 3-7 24		1-5(24)		1-4(24)		1-3(24)		1-2(24)		1-10(24)			PURE E N G I N 111 RVERS STREET, WWILL STREET, WANTE LOWN
3-8 24 3-9 24 4-1 24 4-2 24 4-3 24 4-4 24 4-5 24	•	2-5(24)		2-4(24)		2-3(24)		2-2(24)		2-10(24)	B CB-2		S IN THIS PLANSET ENGINEER PRINCH THIS PROPERTY OF THIS PRESENT OF THE ON THE O
4-5 24 4-6 24 4-7 24 4-8 24 4-9 24 5-1 24 5-2 24			3-5(24)	3-4(24)		3-7(24)	• • •	3-2(24)		3-1(24)	CB-3		NOTE: CETAN PETAS IN THE PANSET REPORT OF RESERVATION OF SERVATION OF SERVATION OF SERVATION OF USE
5-3 24 5-4 24 5-5 24 5-6 24 5-7 24 5-8 24 5-9 24			4-5(24)	4-4(24)		4-7(24)	• •	4-2(24)		4-9(24)	CB-4		VERDE SOLUTIONS Z211 N ELSTON AVE CHICAGO, L. 08614 WWW.FERSSOLUTIONS.COM
5-9 24 6-1 24 6-2 24 6-3 24 6-4 24 6-5 24 6-6 24		H		5-4(24)									
6-7 24 6-8 24 6-9 24 7-1 24 7-2 24 7-3 24			6-5(24)	6-6(24)		6-3(24)-6-7(24)-	• •	6-2(24)		6-9(24)	CB-6		DEVELOPER SOLUTIONS
7-4 24 7-5 24 7-6 24 7-7 24 7-8 24 7-9 24			7-5(24)	7-4(24)		7-3(24)-	•	7-2(24)		7-1(24)	S CB-7		PAGE SIZE 36" x 24" PROJECT # 11015.01
8-1 24 8-2 24 8-3 24 8-4 24				8-4(24) 							CB-8		INT SYSTEM AT ON USA RM ROAD 60441
			9-5(24)	9-4(24)		9-3(24)	•	9-2(24)		9-1(24)	CB-9		SOLAR GROUND MOUNT SYSTEM HENDRICKSON USA 501 CATON FARM ROAD 10CKPORT. IL 60441
2			DR. AS	IMPORTANT INTRACTOR MUST REDLINE AWINGS TO REFLECT EXACT —BUILT STRINGING AND RETURN PURE POWER.	1 DC SCALE	ELECTRICAL P	LAN N		2-3	LABEL KEY STRING # INVERTER #		DC ELECTRICAL PLAN	DRAWING #



							AC	CIRCUIT CA	LCULATIONS												
EQUIPMENT SUPPLIED	FED FROM	VOLTAGE	FULL LOAD AMPS (FLA)	FLA x 1.25	OCPD SIZE [A]	CONDUIT TYPE	CONDUIT SIZE	CONDUCTORS PER PHASE	PHASE CONDUCTOR SIZE	NEUTRAL CONDUCTOR SIZE	GROUND CONDUCTOR SIZE	75° AMPACITY	90' AMPACITY	90° AMPACITY WITH C.O.U.	CABLE TRAY AMPACITY WITH C.O.U	C.O.U DERATE	C.O.U. DERATE	FEEDER LENGTH (ONE-WAY) [FT]		TOTAL VOLTAGE DROP AT FLA	
OLAR SYSTEM AC DISCONNECT SWITCH	POINT OF INTERCONNECTION	480	1140.3	1425	1600	RMC	3.5"	5	CU 500MCM	CU 500MCM	CU #3/0 GEC	1900	2150	2150	N/A	1.00	1.00	75	0.18%	0.18%	
SOLAR AC SWITCHBOARD	SOLAR SYSTEM AC DISCONNECT SWITCH	480	1140.3	1425	1600	BUS	N/A	N/A	1600A BUS	1600A BUS	BUS	1600	1600	1600	N/A	1.00	1.00	10	0.00%	0.18%	
INVERTER 1	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	15	0.07%	0.25%	
INVERTER 2	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	20	0.09%	0.27%	
INVERTER 3	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	25	0.11%	0.29%	
INVERTER 4	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	30	0.14%	0.32%	
INVERTER 5	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	35	0.16%	0.34%	
INVERTER 6	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	40	0.18%	0.36%	- (
INVERTER 7	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	45	0.21%	0.38%	
INVERTER 8	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	50	0.23%	0.41%	
INVERTER 9	SOLAR AC SWITCHBOARD	480	126.7	158	175	PVC	2"	1	CU #2/0	NONE	CU #6	175	195	195	N/A	1.00	1.00	55	0.25%	0.43%	

	PV DC FEEDER CALCULATIONS																					
COMBINER BOX	CABLE MANAGEMENT	QTY OF STRINGS	OPERATING VOLTAGE Vmp [V]	STRING MAXIMUM CURRENT (SAM SIMULATED Imax) [A]	FEEDER MAX CURRENT (Imax) [A]	FEEDER CONTINUOUS CURRENT (Imax x 1.25) [A]	OCPD SIZE [A]	CONDUIT TYPE	CONDUIT SIZE	CONDUCTORS PER POLE	CONDUCTOR SIZE	GROUND SIZE	75* AMPACITY	90* AMPACITY	90° AMPACITY WITH C.O.U. ADJUSTME NT	CABLE TRAY AMPACITY WITH C.O.U.	C.O.U DERATE FOR AMBIENT TEMPERATURE	C.O.U. DERATE FOR NUMBER OF CURRENT CARRYING CONDUCTORS	STRING OPERATING CURRENT (STRING Imp) [A]	FEEDER OPERATING CURRENT [A]	FEEDER LENGTH (ONE WAY) [FT]	FEEDER VOLTAGE DROP
CB-1	CONDUIT	10	1063	17.15	172	214	225	PVC	2.5"	1	AL 300MCM	CU #4	230	260	260	N/A	1	1	13.43	134	360	0.6%
CB-2	CONDUIT	10	1063	17.15	172	214	225	PVC	2.5"	1	AL 300MCM	CU #4	230	260	260	N/A	1	1	13.43	134	368	0.7%
CB-3	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	405	0.7%
CB-4	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	442	0.7%
CB-5	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	480	0.8%
CB-6	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	519	0.8%
CB-7	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	555	0.9%
CB-8	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	595	1.0%
CB-9	CONDUIT	9	1063	17.15	154	193	225	PVC	2.5"	1	AL 300MCM	CU #6	230	260	260	N/A	1	1	13.43	121	629	1.0%

INVERTERS 1-9

COMBINER BOXES TO INVERTERS: 0.9	
	3 Z %
/	
1	

SAM SIMULATE	D VALUES
MAXIMUM CURRENT [A]	17.15
MAXIMUM VOLTAGE [V]	1408.76
THE STRING MAX CURRENT IS CAL	

THE STRING MAX CURRENT IS CALCULATED BY SYSTEM ADVISOR MODEL SIMULATION PROGRAM PROVIDED BY THE NATIONAL RENEWABLE ENERGY LABORATORY, REFERENCE SAND 2004—3535, PHOTOVOLTAIC ARRAY PERFORMANCE MODEL, AS ALLOWABLE BY NEC 690.8(A)(1)(2), THE CALCULATED CURRENT IS 97.1% OF THE VALUE USING 690.8(A)(1)(1).

MODULE SPECIFICATIONS								
MAKE/MODEL	JKM595N-72HL4-BDV							
POWER [W]	595							
ISC [A]	14.13							
IMP [A]	13.43							
voc [v]	53.10							
VMP [V]	44.31							
β VOC [%/degC]	-0.250%							
SITE CLIMATE CRITERIA (WE	EATHER STATION NAME)							
ASHRAE HIGH [℃]	29.9							
ASHRAE LOW [℃]	-23.5							
ELEVATION (m)	201							
STRING SPECIFICA	TIONS AT STC							
MODULES/STRING	24							
POWER [W]	14280							
STRING ISC [A]	14.13							
STRING IMP [A]	13.43							
STRING VMP [V]	1063.44							

INVERTERS 1-9	INV	ERTERS	1-5	INV	ERTERS (6-9
STRING WIRE GAUGE 10AWC	CTDING	TOTAL STRING DISTANCE	STRING VOLTAGE	STRING NUMBER	TOTAL STRING DISTANCE	STRING VOLTAGE
OPERATING VOLTAGE [VDC] 100		[FT]	DROP	NOMBER	[FT]	DROP
OPERATING CURRENT 17	.2 1-1	55	0.23%	6-1	55	0.23%
[AMP]	1-2	145	0.61%	6-2	145	0.61%
	1-3	235	0.98%	6-3	235	0.98%
	1-4	325	1.36%	6-4	325	1.36%
	1-5	415	1.73%	6-5	395	1.65%
	1-6	415	1.73%	6-6	325	1.36%
	1-7	325	1.36%	6-7	235	0.98%
	1-8	235	0.98%	6-8	145	0.61%
	1-9	145	0.61%	6-9	55	0.23%
	1-10	55	0.23%	7-1	55	0.23%
	2-1	50	0.21%	7-2	145	0.61%
	2-2	145	0.61%	7-3	235	0.98%
	2-3	235	0.98%	7-4	325	1.36%
	2-4	325	1.36%	7-5	395	1.65%
	2-5	415	1.73%	7-6	325	1.36%
	2-6	415	1.73%	7-7	235	0.98%
	2-7	325	1.36%	7-8	145	0.61%
	2-8	235	0.98%	7-9	55	0.23%
	2-9	145	0.61%	8-1	55	0.23%
	2-10	55	0.23%	8-2	145	0.61%
	3-1	55	0.23%	8-3	235	0.98%
	3-2	145	0.61%	8-4	325	1.36%
	3-3	235	0.98%	8-5	395	1.65%
	3-4	325	1.36%	8-6	325	1.36%
	3-5	395	1.65%	8-7	235	0.98%
	3-6	325	1.36%	8-8	145	0.61%
	3-7	235	0.98%	8-9	55	0.23%
	3-8	145	0.61%	9-1	50	0.21%
	3-9	55	0.23%	9-2	145	0.61%
	4-1	55	0.23%	9-3	235	0.98%
	4-2	145	0.61%	9-4	325	1.36%
	4-3	235	0.98%	9-5	395	1.65%
	4-4	325	1.36%	9-6	325	1.36%
	4-5	395	1.65%	9-7	235	0.98%
	4-6	325	1.36%	9-8	145	0.61%
	4-7	235	0.98%	9-9	50	0.21%
	4-8	145	0.61%	AVERAGE VO	DLTAGE DROP	0.91%
	4-9	55	0.23%			
	5-1	55	0.23%			
	5-2	145	0.61%			
	5-3	235	0.98%			
	5-4	325	1.36%			
	5-5	395	1.65%			

INVERTERS 6-9

INVERTERS 1-5

5-5 5-6

395 325

5-7 235 0.98% 5-8 145 0.61% 5-9 55 0.23%

1.65%

1.36%


SHEET NOTES:


1. DISTANCES ARE ONE-WAY ESTIMATES GENERATED FOR ENGINEER'S CALCULATIONS, CONTRACTOR IS RESPONSIBLE FOR OWN MEASUREMENTS AND TAKEOFFS.

RAWING TITLE

SCHEDULES & CALCULATIONS

S E310





GENERAL NOTES FOR LABELS:

1. LABEL SCALE 1:2 UNLESS NOTED

2. LETTERING ON SIGNS SHALL BE CAPITAL LETTERS

3. CLEARLY LABEL ALL CIRCUIT BREAKERS IN SUBPANEL(S) / PANELBOARD(S) / SWITCHBOARD(S). THE LABEL SHALL INDICATE THE NAME OF THE DEVICE IT SERVES. USE LABEL FORMAT 5.

4. ALL LABELS SHALL BE OUTDOOR RATED. BACKGROUND COLOR TEXT HEIGHT TITLES (3/8") ALL OTHER TEXT (5/32") FORMAT 1 ENGRAVED MELAMINE TITLES (3/8") ALL OTHER TEXT (5/32") FORMAT 2 ENGRAVED MELAMINE WHITE BLACK FORMAT 3 REFLECTIVE UV RATED RED AT LEAST (3/8") TITLES (5/32") ALL OTHER TEXT (3/32") FORMAT 4 ENGRAVED MELAMINE RED (3/8") FORMAT 5 VINYL FILM WHITE BLACK TITLES (3/8" FORMAT 6 ENGRAVED MELAMINE ORANGE BLACK ALL OTHER TEXT (5/32") $\underline{\text{PER}}$ 2023 NEC 690.31(B)(2): PV SYSTEM CIRCUIT CONDUCTORS SHALL BE IDENTIFIED AT ALL ACCESSIBLE POINTS OF TERMINATION, CONNECTION, AND SPLICES. STRING HOMERUNS AT ARRAY
DC INPUT TERMINALS OF COMBINER BOX
DC OUTPUT TERMINALS OF COMBINER BOX
DC INPUT TERMINALS OF INVERTER
AC OUTPUT TERMINALS OF INVERTER
AC INPUT & OUTPUT TERMINALS OF ACH SUCCESSIVE DEVICE
(WHERE APPLICABLE) CIRCUIT BREAKER AND SWITCH LABELS:
UNLESS LABELED OTHERWISE, ALL CIRCUIT BREAKERS AND SWITCHES
SHALL BE LABELED WITH THE NAME OF THE EQUIPMENT IT IS SUPPLYING. 1 NOTES AND FORMATS SWITCHBOARD(S) COMBINER(S)



 PV MAIN DISCONNECT FORMAT: WHITE TEXT ON BLUE BACKGROUND CODES: NFPA1 11.12.2.1.5 NOTES: FILL WITH SITE O&M PROVIDER'S CONTACT NEODMATCH. CONFIDER INFORMATION. CONFIRM INFO WITH PROJECT OWNER.

INSTALL LABEL ON:
• EVERY 75' OF FENCELINE FORMAT: SCALE 1:4

WARNING: PHOTOVOLTAIC ! POWER SOURCE

INSTALL LABEL ON:

• ALL DC EXPOSED RACEWAYS, CABLE TRAYS, PULL BOXES, AND JUNCTION BOXES.

BUXES.
FORMAT: 3
CODES: NEC 690.31(D)(2), NFPA 11.12.2.1.3
NOTES: HELLERMANNTYTON #: 596-00206
OR EQUAL, LABELS SHALL BE PERMANENTLY
AND SPACED NO GREATER THAN 10 FEET
APART.



NELL AWAY

NISTALL LABEL ON:

ALL CABLE TRAYS CONTAINING CONDUCTORS OPERATING OVER 600 VOLTS.

FORMALI 3

CODES: NEC 392.18(H).

NOTES: LABELS SHALL BE PERMANENTLY AFFIXED AND SPACED NO GREATER THAN 10 FEET APART.


AWARNING ARC FLASH AND SHOCK HAZARD **Appropriate PPE and Tools Required**

when working on this equipment.

INSTALL LABEL ON:

• ALL EQUIPMENT NOT OTHERWISE LABELED IN POWER STUDY
FORMACT: 1.1 SCALE
NOTES: OUTDOOR RATED STICKER.

(2) GENERAL SIGNAGE



(3) DIRECTORY LABEL

DISCONNECT(S)/ BREAKER(S)

INVERTER(S)

MONITORING/AUXILIARY

MONITORING PANEL INSTALL LABEL ON:
 NAMED EQUIPMENT

WEATHER STATION INSTALL LABEL ON:

NAMED EQUIPMENT

SOLAR AC SWITCHBOARD WARNING: SUPPLIED BY UTILITY & PV SOURCES. OPERATING CURRENT: 1140.3A OPERATING VOLTAGE: 480V DO NOT CONNECT NON-SOLAR LOADS TO THIS PANEL INSTALL LABEL ON:

NAMED EQUIPMENT FORMAT: 2

COMBINER BOX X WARNING: ELECTRIC SHOCK HAZARD DC DISCONNECT MAXIMUM VOLTAGE: INSTALL LABEL ON:

COMBINERS CB 1-CB 9 FORMAT: 2 CODES: NEC 690.7(D)

SOLAR SYSTEM DISCONNECT SWITCH WARNING: PHOTOVOLTAIC POWER SOURCE. OPERATING CURRENT: NOMINAL VOLTAGE:

INSTALL LABEL ON:

NAMED EQUIPMENT FORMAT: 2 CODES: NEC 690.54 & 705.10, NFPA 11.12.2.1.1

INVERTER X DC AC DISCONNECT DISCONNECT MAXIMUM AC OPERATING CURRENT: 126.7A NOMINAL AC OPERATING VOLTAGE: 480V MAXIMUM VOLTAGE: 1500V

FORMAT: 2 CODES: NEC 690.7(D), NFPA 11.12.2.1.1

Verde

PURE STREET,

E500

(4) EQUIPMENT LABELS

LABELS & SIGNAGE

100 kW, 1500 Vdc/480 Vac String Inverters for North America



CPS SCH100KTL-DO/US-480

The 100 kW high power CPS three-phase string invertes row (LFS Schild County)—480

The units are high performance, advanced, and reliable inverters designed for ground-mount applications with 480 Vac service voltage. The units are high performance, advanced, and reliable inverters designed specifically for the North American environment and grid. High efficiencies, wide operating voltages, broad temperature ranges, and a NRMA Type AK ordiocaure enable this inverter platform to operate at high performance across many applications. The CPS 100 kW products ship with the Distributed or Centralized Wire Box, each fully integrated and separable with AC and OC disconnect switches. The Enhanced DV Wire Box includes touch-safe fusing for up to 20 strings. The CPS FlexOM solution enables communication, controls and remote product upgrades.

- NFPA 70 and NEC compliant
- Touch-safe DC fuse holders adds convenience and safety
- CPS FlexOM Gateway enables remote firmware upgrades
 Integrated AC and DC disconnect switches
- 1 MPPT with 20 fused inputs for maximum flexibility ■ Copper- and aluminum-compatible AC connections



FC This device complex with

NEMA Type 4X outdoor rated, tough tested enclosu

Advanced Smart-Grid features (CA Rule 21 certified)

■ kVA headroom yields 100 kW @ 0.95 PF ■ Generous DC/AC inverter load ratios

Separable wire box design for fast service

Enhanced DC wire boxes available









ENGINEERING DRAWINGS

Multi Busbar Half Cell Technology
Better light trapping and current col

ELECTRICAL PERFORMANCE & TEMPERATURE DEPENDENCE

ELECTRICAL CHARACTERISTICS

BUILDING YOUR TRUST IN SOLAR, WWW.JINKOSOLAR US







MECHANICAL CHARACTERISTICS

Front Glass 2.0mm, Anti-Reflection Coating

Pressure Rating 5400Pa (Snow) & 2400Pa (Wind)
Hailstone Test 45mm Hailstone at 30.7m/s

TEMPERATURE CHARACTERISTICS

Temperature Coefficients of Pmax Temperature Coefficients of Voc

PACKAGING CONFIGURATION

RIEACIAL OUTPUT-REARSIDE POWER GAIN

12-year product and 30-year linear power warranty

5% Maximum Power (Pmax) 609Wp 614Wp 620Wp 625Wp 630Wp Module Efficiency (%) 23.57% 23.78% 23.98% 24.18% 24.39% 15% Maximum Power (Pmax) 667Wp 672Wp 679Wp 684Wp 699Wp Module Efficiency (%) 25.82% 26.05% 26.27% 26.49% 26.71% 25% Maximum Power (Pmax) 725Wp 731Wp 738Wp 744Wp 750Wp Module Efficiency (%) 28.06% 28.31% 28.55% 28.79% 29.03%

60 595Wp 448Wp 600Wp 452Wp 44.31V 41.36V 44.45V 41.52V 13.43A 10.84A 13.50A 10.89A 7 53.10V 50.44V 53.30V 50.63V

JinKO

MAXIMUM RATINGS

WARRANTY

STC NOCT STC NOCT STC NOCT

| STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | NOCT | STC | STC | STC | NOCT | STC | ST

Module Efficiency STC (%) 22.45% 22.65% 22.84%

Protected Against All Environments



-0.29%/°C -0.25%/°C



LONG SPAN GROUND MOUNT SYSTEMS Solar Racking with the Industry's Most Topographically Adaptable PV System

Elevating the Future of Solar



LONG SPAN

Structural Components

All above ground members are constructed from G115 galvanized steel with ground penetrating components from G235 or better.





	TECHNICAL SPECIF	TECHNICAL SPECIFICATIONS								
	Wind Load	90 - 150 MPH *								
	Snow Load	0 - 70 PSF *								
	Leading Module Height	18" - 60" MAX								
	Tilt Angle									
UL 2703	Module Suitability	All Major Brands *								
	Panel Orientation	Portrait (2H x 12W) *								
	Warranty	20 years								

LONG SPAN

Most advanced table based racking solution with the DCE Long **Span Racking System.**

- » Newly designed Long-Span pivot bracket allows for superior purlin adjustability
- » Integrated wire management & direct panel frame mounting & bonding
- » Driven Beam, ballast, or screw foundations accommodating all soil & site conditions
- » Structurally independent tables to diminish terrain challenges

HIGHER YIELD PER FOUNDATION Purlins spanning up to twelve panels in portrait orientation result in fewer foundations throughout the entire installation. More panels on each table with fewer posts installed reduce labor & material cost; compounding value per watt

elevates each one-point purlin connection to drastically improve every table's adaptability to challenging topography. The fully grounded rows can adjust to changes up to 20% grade.





INTEGRATED RONDING Each continuous row is bonded INTEGRATED BONDING Each continuous row is bonded using serrated hardware, therefore only one ground is needed per row. No additional costly grounding components needed such as WEEBS and star washers, lowering material and installation costs. This reduces labor time, hardware, and cost for additional bonding components (Costfelia) and the components of the cost for additional bonding components.



INTEGRATED WIRE MANAGEMENT The undersid

DCE Solar delivers industry-leading racking products with unbeatable customer service. All Long Span solutions have been designed to minimize grading, lower foundation costs, and facilitate greater energy performance.



Elevating the Future of Solar | Made in America

19410 Jetton Road Suite 220 Cornelius, NC 28031 USA 704-659-7474 | info@dcesolar.com | www.dcesolar.com

EQUIPMENT DATA SHEETS

E600

SOLAR GROUND MC HENDRICKS 501 CATON F

PURE IN I

The CPS FlexOM Meter offers a revenue-grade metering solution for CPS 25, 36, 50, 60, 100, and 125 kW inverters. The FlexOM meter solution includes a FlexOM Gateway and revenue-grade meter integrated into a NEMA 4 enclosure. FlexOM Portal Bundles are offered by CPS with web portal data access to features such as data charting, monitoring alerts, kiosk view, and more!

- Low-cost, complete hardware and software package
- Includes revenue-grade site-level meter (CTs not supplied, and must have output voltage of 0.333Vac at full scale)
- Full access to inverter data (15+ parameters per inverter)


- 5 years of monitoring included (extensions available)
- Automated site commissioning report
- Up to 32 devices per Flex Gateway (no additional fees for each inverter connection)
- Site activation with "CPS Connect Pro" app (iOS and Android)
- Inverter on/off, remote arc-fault reset, PF and active power curtailment controls capability
- Remote CT reversal capability



The CPS FlexOM Meter offers a revenue-grade metering solution for CPS 25, 36, 50, 60, 100, and 125 kW inverters. The FlexOM meter solution includes a FlexOM Gateway and revenue-grade meter integrated into a NEMA 4 enclosure. FlexOM Portal Bundles are offered by CPS with web portal data access to features such as data charting, monitoring alerts, kiosk view, and more!


- Low-cost, complete hardware and software package
- Includes revenue-grade site-level meter (CTs not supplied, and must have output voltage of 0.333Vac at full scale)


- 1- to 20-minute interval data (download up to 5 years of site data)
- 5 years of monitoring included (extensions available) Automated site commissioning report
- Up to 32 devices per Flex Gateway (no additional fees for each inverter connection)
- Site activation with "CPS Connect Pro" app (iOS and Android)
- Inverter on/off, remote arc-fault reset, PF and active power curtailment controls capability
- Remote CT reversal capability





EQUIPMENT DATA SHEETS


E601
















Copyright © 2024 Hey and Associates, Inc.





Hey and Associates, Inc.

Engineering, Ecology and Landscape Architecture
8755 W. H IGGINS ROAD, SUITE 835
CHICAGO, ILLINOIS 60631
OFFICE (773) 693-9200
FAX (847) 740-2888
CHICAGO @ HEYASSOC.COM

Professional Design Firm License No. 184-002429

Verde Solutions

Crest Hill

Landscape Plan

PROJECT NO:	25-0072	SHEET NO:
ESIGNED BY	BMJ	
DRAWN BY	BMJ	1 1
CHECKED BY	RJA	
APPROVED BY	TP	PAGE NO:
SSUE DATE	3/31/25	2 OF 3

For Review

Quantity	Code	Size	Botanical Name	Common Name
DECIDUOL	ISTREES			
10	OSM	2.5" CAL	Ostrya virginiana	American Hophornbeam
10	TIAM	2.5" CAL	Tilia americana	American Basswood
10	QUBI	2.5" CAL	Quercus bicolor	Swamp White Oak
10	QUMA	2.5" CAL	Quercus macrocarpa	Bur Oak
CONIFERO	USTREES			
26	JJM	6HT	Juniperus virginiana	Eastern Red Cedar
10	PIBA	6HT	Pinus banksiana	Jack Pine
20	PIRE	6HT	Pinus resinosa	Red Pine
36	PIST	6HT	Pinus strobus	Eastern White Pine
ORNAMEN	TAL TREES			
12	AMCA	6HT	Amelanchier canadensis	Shadblow Serviceberry
12	COAL	6HT	Cornus alternifolia	Pagoda Dogwood
12	CRMO	6HT	Crataegus mollis	Downy Hawthorn
DECIDUOL	IS SHRUBS			
12	COAM	#5 CONT	Cornus amomum	Silky Dogwood
12	∐BE	#5 CONT	Lindera benzoin	Northern Spicebush
12	SACA	#5 CONT	Sambucus canadensis	American Ederberry
12	VIPR	#5 CONT	Viburnum prunifolium	Blackhaw Viburnum

Solar Field Pollinator Habitat Seed Mix

Source: Stantec

Apply at 41.25 PLS pounds per acre Mature height of species selected = under 3'

Forbs		
Scientific Name	Common Name	Total Ozs.
Allium cernuum	Nodding Onion	6.0
Aquilegia canadensis	Wild Columbine	1.0
Asclepias syriaca	Common Milkweed	4.0
Chamaecrista fasciculata	Partridge Pea	12.0
Coreopsis lanceolata	Sand Coreopsis	10.0
Dalea purpurea	Purple Praire Clover	6.0
Liatris pychnostachya	Prairie Blazing Star	2.0
Lupinus perennis var. occidentalis	Wild Lupine	2.0
Monarda punctata	Horse Mint / Spotted Bermagot	1.5
Penstemon hirsutus	Hairy Beard Tongue	1.5
Solidago nemoralis	Old-Field Goldenrod	1.0
Symphyotrichum pilosum	Hairy Aster	1.0
Verbena stricta	Hoary Vervain	2.0
Zizia aurea	Golden Alexander	2.0
	TOTAL	52.0
Grasses		
Bouteloua curtipendula	Side-Oats Grama	24.0
Carex bicknellii	Copper-Shouldered Oval Sedge	3.5
Koeleria macrantha	June Grass	1.5
Schizachyrium scoparium	Little Bluestem	64.0
Sporobolus heterolepis	Prairie Dropseed	3.0
	TOTAL	96.0
Cover Crop		
Avena sativa	Common Oat	512.0
	TOTAL	512.0

IDOTClass 2A (salt tolerant roadside mix)

Source: IDOT

Seeding rate: 200 lbs/acre (3,834 seeds / square foot) Mature height of species selected = under 3'

		-		ī
ort	ĸ			
٠	_			

Forts			
Scientific Name	Common Name	%Mix	Total Ozs.
Festuca arundinacea	Tall Fescue	30	60.0
Festuca rubra	Red Fescue	15	30.0
Festuca trachyphylla	Hard Fescue	15	30.0
Lolium perenne	Perennial Rye	10	20.0
Puccinellia distans	Alkali Grass	30	60.0
	TOTAL		200.0

Ordinance code: 15.04.040 (2)

1 planting (tree or shrub) per 725 sf 10 sf groundcover per planting

226,939 sf existing / 725 = 313 plantings 313 plantings x 10 sf groundcover = 3,130 sf

EXISTING

313 - 97 = 216

216 (168 trees, 48 shrubs) 155,840 sf groundcover

> DEPTH TO BE FINALIZED WITH FINAL ENGINEERING PLANS BASED ON GEOTECHNICAL 12"-18" MIN. GRAVEL BASE COMPACTED SUBGRADE
> (REMOVE UNSUITABLES AS REQUIRED) MIRAFI 140N GEOTEXTILE FILTER FABRIC WIDTH VARIES (SEE PLANS)

- NOTES:

 1. REMOVE TOPSOIL AND ALL UNSUITABLE MATERIAL AS REQUIRED AND REPLACE WITH GRAVEL.


 2. ACCESS DRIVES TO SLOPE IN THE DIRECTION OF THE EXISTING GRADE AT A MINIMUM OF 2.0% DRIVEWAY SHALL BE GRADED TO ALLOW STORMWATER TO SHEET ACROSS IT AND TO PREVENT PUDDLING.

 3. ROAD SECTION SHALL COMPLY WITH RECOMMENDATIONS FROM GEOTECHNICAL REPORT.

 4. FILTER FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION 592
 GEOTEXTILE, TABLE 1 OR 2, CLASS I, II, OR IV AND SHALL BE PLACED OVER THE CLEARED AREA PRIOR TO THE PLACING OF ROCK.

ACCESS DRIVE/TEMPORARY LAYDOWN AREA CROSS SECTION

Notes: 1- Trees shall be of quality prescribed in crown observations and root observations details and specifications. Original slope should pass 2- See specifications for further requirements related to this detail. through the point where the trunk base meets substrate/soil Prior to mulching, lightly tamp soil around the root ball in 6" lifts to brace tree. Do not over compact. When the planting hole has been backfilled, pour water around the root ball to settle the soil. Trunk caliper shall meet ANSI Z60 current edition for root ball size. 3" layer of mulch. No more than 1" of mulch on top of root ball. (See specifications for Root ball modified as Round-topped soil — berm 4" high x 8" wide above root ball surface shall be centered on the downhill side of the root ball for 240°. Berm shall begin at root ball varies. (See soil preparation Bottom of root ball rests on SECTION VIEW existing or recompacted soil.



LEGEND

Hey and Associates, Inc.

Engineering, Ecology and Landscape Architecture 8755 W. HIGGINS ROAD, SUITE 835 CHICAGO, ILLINOIS 60631 Office (773) 693-9200 FAX (847) 740-2888 CHICAGO @ HEYASSOC.COM

> Professional Design Firm LICENSE NO. 184-002429

> Verde Solutions

Crest Hill

Landscape Details

PROJECT NO: 25-0072		SHEET NO:	
ESIGNED BY	BMJ		
DRAWN BY	BMJ	1 2	
CHECKED BY	RJA		
APPROVED BY	TP	PAGE NO:	
SSUE DATE	3/31/25	3 OF 3	

For Review