



LAYOUT NOTES

- 1. Contractor responsible for field layout of all new improvements. Digital files of geometric information will be provided upon request in AutoCAD format. No additional payment will be made for adjustments necessary to construct the work as drawn.
- 2. Contractor responsible to coordinate work in order to obtain approval of all layout by Owners Representative prior to construction. No additional payment will be made to correct work if constructed incorrectly without pre-approval by Owners Representative.
- 3. Contractor responsible to maintain all layout stakes during construction. No additional payment will be made to replace layout stakes.
- 4. Place stakes at edges of sport courts, fields, limits of playground, shelter, and every 25 feet on center along centerline of all pathways for review by the Owner's Representative prior to earthwork operations.
- 5. All walls are dimensioned to Face of Wall unless otherwise noted.
- 6. All dimensions from roadway are from Back of Curb unless otherwise noted.
- 7. All curves and radii to be smooth and not segmented.
- 8. Contractor to provide layout stakes every 10 feet minimum for large arcs where radius points are not accessible.
- 9. Adjustment to stake locations due to discrepancies between coordinates and dimensions is incidental to the contract. No additional payments will be made for this work.
- 10. All roadway widths are measured from edge of pavement to edge of pavement unless otherwise shown on the plans.
- 11. Contractor responsible to take delivery, assemble and install all materials and furnishings per manufacturer's instructions.
- 12. Place control and expansion joints as shown on plans and details for all curbs, walks, walls, steps, and concrete paving. Where joints are not shown, place control joints a maximum of 10 feet on center, expansion joints a maximum of 30 feet on center, and between all separate pours.
- 13. Refer to specifications for additional conditions, standards and notes.

LAYOUT LEGEND

- Expansion Joint
- Asphalt Paving, Vehicular
- Concrete Paving, Vehicular
- Concrete Paving, Pedestrian
- Asphalt Paving, Pedestrian
- Asphalt Paving, Sport Court



22 E. Chicago Avenue  
Suite 200A  
Naperville, IL 60540  
T 630.961.1787  
hitchcockdesigngroup.com

PREPARED FOR  
**Lockport Township  
Park District**  
1811 South Lawrence Avenue  
Lockport, Illinois 60441

PROJECT  
**Prairie Bluff  
Pickleball-Range**  
19433 Renwick Road  
Crest Hill, Illinois 60403

CONSULTANTS  
**Civil Engineer**  
Rueffiger, Tonelli &  
Associates, Inc.  
Shorewood, IL 60404  
T 815.744.6800  
**Electrical Engineer**  
Nova Engineering PC  
Schereville, IN 46375  
T 219.865.3352  
**Architect**  
Jon S. Ditter Architect PLLC  
Lockport, IL 60441  
T 815.834.0522

ISSUE FOR BID  
September 1, 2022  
REVISIONS

No	Date	Issue

CHECKED BY  
EFH

DRAWN BY  
L.J. / AMM

SHEET TITLE  
**Layout and  
Materials Plan**

SCALE IN FEET  
1" = 30'

0' 15' 30' 90'

NORTH

SHEET NUMBER  
**L1.1**

©2022 Hitchcock Design Group