

CITY OF CREST HILL  
CITY CENTER

Change Order

Date: 7/15/2022  
Project: Crest Hill City Center  
Contractor: P.T. Ferro Construction Co.  
Change Order #: 1

Description:

C-12: Add Concrete Pads for Benches and Trash Bins  
\* Excavation, Compacted Stone Backfill and Concrete Pads in the Dimensions, Thickness, Types / Materials as shown for Benches and Trash Bins  
C-13: Add / Create Drop of Lane including Islands & Pads for Mail Boxes  
\* Sawcut Existing Asphalt for New Concrete Island to Create a Drop of Lane; Excavate Existing Subbase as needed for New Concrete Curbs for Island; Stone Backfill as Req'd; Frame & Pour New Concrete Curbs to Form New Island.  
C-20.A: Add Concrete Curb to Backside of West Drive  
\* Sawcut as Req'd; Excavation to Subgrade; Compacted Stone Subbase; Frame & Pour Curb  
C-28: Encasement of Existing Gas Feeds to Generators  
\* Excavation; Trench Pour Concrete to Encase Gas Pipe; Backfill with Spoils  
C-29: Relocate Dumpster Coral to East Side of Facility  
\* Demo Existing Dumpster Coral Pad; Sawcut Existing Dumpster Coral Depressed Curb & Remove Frame & Pour New Curb to match Existing; Backfill Existing Location w/ Topsoil; Sawcut Existing Asphalt on East Side; Rework Subbase for New Thicken Edge Slab for Coral; Frame & Pour New Coral Pad with Thicken Edge.  
Memorial Garden Items  
\* Undercuts as required for Bad Soils  
\* Brick Paver Concrete  
\* Foundations for Monuments  
Labor Escalation  
\* Labor Increase for Work Completed after May 1, 2022  
*Note: See Attached RCO / Proposals*

Original Contract:	\$ 686,748.75
Previous Change Orders:	\$ -
Contract Total Prior to this CO:	\$ 686,748.75
New Change Order Amount:	\$ 162,000.25
New Contract Amount:	\$ 848,749.00

Approved:

\_\_\_\_\_  
Administrator Date

\_\_\_\_\_  
Shawn Thompson - Project Manager Date

\_\_\_\_\_  
Sub-Contractor Date

\_\_\_\_\_  
Dan Skiera - Superintendent Date



# P. T. Ferro Construction Co.

700 SOUTH ROWELL AVENUE • P. O. BOX 156 • JOLIET, ILLINOIS 60434-0156 • (815) 726-6284

6/23/22

Harbour Contractors, Inc.  
Attn: Shawn Thompson  
23830 W. Main St.  
Plainfield, IL 60544


Re: City Center - Site Concrete & Asphalt - Extra Site Concrete Work

Mr. Thompson,

We respectfully submit for your approval the following Agreed Unit Prices for:

<u>ITEM</u>	<u>QUAN</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
UNDERCUTS MEMORIAL GARDEN AREA	111.00	CY	\$100.00	\$11,100.00
BRICK PAVER CONCRETE	1989.00	SF	\$21.00	\$41,769.00
NEW TRASH PAD 8 "	65.00	SY	\$250.00	\$16,250.00
CONCRETE SLAB	35.00	SY	\$235.00	\$8,225.00
NEW ISLAND	1.00	EA	\$9,600.00	\$9,600.00
CONC SLAB FOR EMPLOYEE TABLES	45.00	SY	\$250.00	\$11,250.00
DEMO EXISTING TRASH ENCLOSURE PAD	8.00	SY	\$115.00	\$920.00
B6.12 CURB PATCH	100.00	LF	\$75.00	\$7,500.00
MONUMENT FOUNDATIONS	10.00	EA	\$3,700.00	\$37,000.00

Sincerely,



Andrew Hess  
Estimator/Project Manager

\_\_\_\_\_  
Terms Accepted By

PLEASE SIGN AND RETURN ACCEPTANCE COPY



# *P. T. Ferro Construction Co.*

700 SOUTH ROWELL AVENUE • P. O. BOX 156 • JOLIET, ILLINOIS 60434-0156 • (815) 726-6284

6/23/22

Harbour Contractors, Inc.  
Attn: Shawn Thompson  
23830 W. Main St.  
Plainfield, IL 60544

Re: City Center - Site Concrete & Asphalt - Completed Trash Pad Foundation & Utility Pads

Mr. Thompson,

We respectfully submit for your approval the following Agreed Unit Prices for:

<u>ITEM</u>	<u>QUAN</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
TRASH PAD FOUNDATION	8.00	SY	\$90.00	\$720.00
UTILITY PADS	27.00	SY	\$100.00	\$2,700.00

Sincerely,

Andrew Hess  
Estimator/Project Manager

\_\_\_\_\_  
Terms Accepted By

PLEASE SIGN AND RETURN ACCEPTANCE COPY



# *P. T. Ferro Construction Co.*

700 SOUTH ROWELL AVENUE • P. O. BOX 156 • JOLIET, ILLINOIS 60434-0156 • (815) 726-6284

6/23/22

Harbour Contractors, Inc.  
Attn: Shawn Thompson  
23830 W. Main St.  
Plainfield, IL 60544

Re: City Center - Site Concrete & Asphalt - Labor Increase

Mr. Thompson,

We respectfully submit for your approval the following Agreed Unit Prices for:

<u>ITEM</u>	<u>QUAN</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
LABOR COST ESCALATION **FOR WORK COMPLETED AFTER ORIGINAL COMPLETION DATE OF MAY 1, 2021**	1.00	LS	\$10,271.24	\$10,271.24

Sincerely,

Andrew Hess  
Estimator/Project Manager

\_\_\_\_\_  
Terms Accepted By

PLEASE SIGN AND RETURN ACCEPTANCE COPY