



Vivid Outdoor Lighting

13715 Lakeshore Court | Manhattan, Illinois 60442
815-715-8980 | vividoutdoorlights@gmail.com |
www.vividoutdoorlighting.com

RECIPIENT:

Don Seeman

20600 City Center Boulevard
Crest Hill, Illinois 60403

Estimate #1300

Sent on Jul 31, 2025

Total \$32,647.54

Product/Service	Description	Qty.	Unit Price	Total
Optional				
Track - 3/4" Hat Track (1,184 Raw Feet 7% for cuts etc. +83' Total: 1,267 Linear Feet Color Timberwolf	Track - 3/4" Hat Track to be color matched to the homes soffit/fascia color. Sections consist of 6.5' lengths. 1,184 Raw Feet 7% for cuts etc. +83' Total: 1,267 Linear Feet Color Timberwolf	198	\$34.95	\$6,920.10
Optional				
Gemstone RGB-WW Lights Per Bag	9 Lights/string. 10 daisy chains per bag 90 Lights/bag. Must be purchased by the bag. ETL Certified.	20	\$513.99	\$10,279.80
Optional				
400 Watt Power Kit 12 Volt	400 Watt Power Kit 12 Volt to power the Gemstone System 1 - 20 foot standard power cord NEMA5-15P to C13 1 - loom adapter/clamp 1 - 8" loom sleeve	4	\$320.00	\$1,280.00
Optional				
150Watt Power Kit 12 Volt	150 Watt Power Kit 12 Volt to power the Gemstone System 1 - 20 foot standard power cord NEMA5-15P to C13 1 - loom adapter/clamp 1 - 8" loom sleeve	4	\$220.00	\$880.00
Optional				
Hub Controller	The Gemstone Lights HUB Controller provides the ultimate in quality, flexibility, and upgradeability. The Controller functions using both WiFi & Bluetooth connectivity to provide the ultimate control for your lighting system.	8	\$180.00	\$1,440.00



Vivid Outdoor Lighting

13715 Lakeshore Court | Manhattan, Illinois 60442
815-715-8980 | vividoutdoorlights@gmail.com |
www.vividoutdoorlighting.com

Product/Service	Description	Qty.	Unit Price	Total
Optional				
14/2 Stranded Cable 500'	14/2 Stranded Cable is used as a power injection line to compensate for the voltage drop across the track light system. Please see the installation section for more information on proper boosting methods.	6	\$185.00	\$1,110.00
Optional				
Cable Extension	Gemstone Lights Cable Extension packs are used when jumps between Track Lights have to be made. Cable extensions come in a variety of different sizes from 1 to 20 feet. All extensions have a compression fit waterproof connector on each end. Various sizes are needed to complete a job.	2	\$280.00	\$560.00
Optional				
Split Loom	Loom / 50' in White/Black option	4	\$27.50	\$110.00
Optional				
Colored Screws Grey	Color matching screws for the track system #6X5/8	8	\$11.50	\$92.00
Optional				
Labor For Gemstone	Labor for the Gemstone project. We typically charge a 60% to material basis for the labor cost. Project should take 3-5 full days for completion. This product comes with a 15 year warranty and we also give 3 years of service for free for any required service calls if need be.	1	\$13,603.14	\$13,603.14

Subtotal	\$36,275.04
Discount (10.0%)	- \$3,627.50
Total	\$32,647.54



Vivid Outdoor Lighting

13715 Lakeshore Court | Manhattan, Illinois 60442
815-715-8980 | vividoutdoorlights@gmail.com |
www.vividoutdoorlighting.com

Signature: _____ Date: _____