

Invitation to Bid: Crockett Public Library Sidewalk / Retaining Wall Projects

The City of Crockett invites bids for construction projects at the Crockett Public Library at 709 East Houston Ave, Crockett TX 75835.

1. Sidewalk Construction:

- Scope: Construct new sidewalks to tie in with existing sidewalk.
- Details: 3500 PSI concrete with 4" depth with 3/8" rebar grid. Broom finish. Must tie in with existing sidewalk.
 1. 92'6" x 36"
 2. 82' x 42"
 3. 50' x 48"

2. Retaining Wall Construction:

- Scope: Construct block retaining wall and ledge with 1 set of steps.
- Details: Retaining wall with 8" block ledge. Minimum depth of 6" maintaining a 2' height plus cap. Block ledge will be dowelled with 3/8" rebar. Total run of 246'.
- Line side overflow parking with cinderblock wall on back and library side. Drill and anchor with rebar and concrete. Total run of 242'.

Submission Deadlines: All bids must be submitted by the respective deadlines mentioned above to:

Butch Calvert
Program & Grants Manager
200 N. 5th Street, Crockett, TX 75835

Requirements:

- Contractors must take their own measurements prior to submitting a bid and provide breakdowns of materials, labor, and expenses for each project.
- Proof of insurance, and adherence to safety regulations required.
- References are encouraged to be included.

Contact Information: To schedule a site walk-through, contact Dennis Callahan at 936-544-5156, Ext 208 and visit website for bid specs.

Closing Time/Date: 2:00 P.M. on 8/15/2024

CITY OF CROCKETT
BID TALLY SHEET

CONTRACT

- ☒ Sealed Bid
☐ Telephone Bid
☐ Letter Bid

BID DESCRIPTION: 2024 Library Sidewalk/Retaining Wall Construction

BID OPENING DATE/TIME: August 15, 2024 at 2:30 PM

[illegible]

Bid Opener Name and Signature BUTCH LAURET BLS

Velazquez Brothers' Concrete LLC

10894 Forsthoff Road Bryan, TX 778084

Miguelvazquez875@gmail.com

Proposal Form

For: Crockett Public Library

Location: Crockett, TX

Date: August 3, 2024

Velazquez Brothers' Concrete will perform all labor
necessary to complete the following:

- Total for the sidewalk is 1,177 square feet
- Total for the footings is 387 square feet
- Total for the curve is 55 square feet

Materials and Cost:

- For the sidewalk:
 - 38 ft x 8 ft = 304 ft
 - 103 ft x 3 ft = 309 ft
 - 12 ft x 7 ft = 84 ft
 - 26 ft x 4 ft = 104 ft
 - 22 ft x 4 ft = 88 ft
 - 14 ft x 4 ft = 56 ft
 - 7 ft x 4 ft = 28 ft
 - 30 ft x 4 ft = 120 ft
 - 21 ft x 4 ft = 84 ft

- \$6.50 per square foot
- The total for the sidewalk will come out to \$7,650.
- 4000 PSI of concrete will be used for the entire project.

- For the footings:

- 149 ft x 1 ft •31 ft x 1 ft
- 7 ft x 1 ft •10 ft x 1 ft
- 23 ft x 1 ft •158 ft x 1 ft
- 4 ft x 1 ft. •5 ft x 1 ft

- \$11 per square foot
- The total for the footings will come out to \$4,257.
- ½ inch rebar will be used

- For the curve:

- 11 ft
- 22 ft
- 22 ft

- \$20 per square foot
- The total for the curve will come out to \$1,100.

Acceptance:

Signature: _____

Date: _____

JUAN AYALA
2748 FM 3154
GROVETON, TEXAS 75845
936-239-6709

August 09, 2024

This is a bid for the City of Crockett.

Labor \$11,700,
Split color Tan block \$10,800 -1000 split cinder block & 350 caps
Mortar Mix \$1100.00 -using Tx Buff color to match cinder blocks
Sand \$600.00
Sacrete \$700.00
Labor includes installing rebar 5/8" & fill up cells w/concrete as
needed.

Total \$ 24,900.00

****2nd Option**

Use Regular Split Block

Total \$19,900.00

Juan Ayala, Contractor

City Of Crockett