



11/15/2022

City of Cartersville - Fibercom
Gatlin Pruitt
1 N Erwin St
Cartersville, GA 30120
404-520-2944
gpruitt@cartersvillega.gov

Thank you for giving Network Cabling Infrastructures the opportunity to provide you with a proposal for the Anheuser-Busch Werner Building project. Please take the time to review the below scope of work and feel free to contact me if you have any questions or concerns.

All work will meet state and local codes, follow strict industry standards set forth by the Building Industry Consulting Service International, Inc. (BICSI).

Safety Standards:

All NCI (Network Cabling Infrastructures, LLC.) on-site technicians shall be aware of, and strictly adhere to any and all safety requirements mandated by OSHA, General Contractor and any applicable governmental agency.

Assumptions:

Technicians will have free access to required work areas.
Aerial Work Platforms, bucket trucks, or other overhead equipment will be provided by NCI.
Customer's employees, visitors, and others will be kept clear of active construction areas.
Work will be completed during normal business hours (7AM to 5PM, Monday-Friday).
Additional time requirements or delays may incur additional cost.

Rock Adders:

Directional Drill w/Rock Head = \$80.00 per foot
Directional Drill w/Rock Hammer @ 10,000 PSI = \$120.00 per foot
Rock excavation via open trench \$18.00 per foot
Rock excavation via open trench w/Rock Hammer = \$25.00 per foot
All adders are in addition to the previously agreed upon foot price

Bill Of Materials			
DESCRIPTION	UNITS	UNIT PRICE	EXTENDED PRICE
MATERIAL			
(2050) ft Directional Bore (1) 2" HDPE	2050	\$ -	\$ -
(3) ea Install 24"x36"x36" (Handhole With Gravel)	3	\$ 7.18	\$ 21.55
(2) ea Install Marker Pole	2	\$ -	\$ -
(1) ea Install Test Stations	1	\$ -	\$ -
(2350) ft Fiber Pulling (HDPE installed by NCI)	2350	\$ -	\$ -
(1) ea Private Locates	1	\$ 2,160.00	\$ 2,160.00
LABOR			
(2050) ft Directional Bore (1) 2" HDPE	2050	\$ 12.00	\$ 24,593.03
(3) ea Install 24"x36"x36" (Handhole With Gravel)	3	\$ 450.00	\$ 1,350.00
(2) ea Install Marker Pole	2	\$ 30.00	\$ 60.00
(1) ea Install Test Stations	1	\$ 37.00	\$ 37.00
(2350) ft Fiber Pulling (HDPE installed by NCI)	2350	\$ 0.75	\$ 1,765.91
(1) ea Private Locates	1	\$ -	\$ -

Material: \$ 2,181.55
 Labor: \$ 27,805.93
 Total: \$ 29,987.48

All Pricing is Valid for 7 calendar days from date at top of this proposal unless otherwise specified. Material manufacture subject to change based on distributor availability. All substituted products will be of similar quality and functionally interchangeable.

Scope of Work

From Existing HH on ROW of Busch Dr directional bore South East along ROW to the East side of the Anheuser-Busch front entrance set a new 24"x36" HH provided by other. From the Anheuser-Busch front entrance directional bore North East on Anheuser-Busch property around the tree line following an access road. Set a new 24"x36" HH provided by other before crossing the retainage ditch approaching the new Werner building (Directional Bore 2,500'). NCI will be responsible for Installing (2,550') of tracer wire provided by other. NCI will be responsible for installing (2,600') of fiber provided by other.

NCI would like to thank you for this great opportunity and once again feel free to contact me if you have any questions or concerns.

Sincerely,

Logan Ghorley
Project Manager
Phone: 470-255-4476
Fax: 770-495-6220
Email: logan.ghorley@ncicabling.com