

DATE: 10/07/2024  
HD EXCAVATIONS & UTILITIES LLC  
Wesley Dickinson  
[wesley@hd-excavations.com](mailto:wesley@hd-excavations.com)  
404-852-6817

# HD Excavations & Utilities



QUOTE: CO 1  
CUSTOMER: Barge Eng  
PROJECT: Terrell Heights  
LOCATION: Cartersville Ga  
Attn: David Lavergne

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Dog House new storm line with pedestal Top to catch water from car wash	1.00	Ea	11,000.00	\$11,000.00
Rip Rap around new pedestal top	1.00	Single/axle	950.00	\$950.00
12" HDPE in existing swell (Hauling in dirt to insure adequate cover on pipe is included in this price)	48.00	Lf	225.00	\$10,800.00
12" Headwall	1.00	Ea	5,550.00	\$5,550.00
Core 44x27 RCP and grout	1.00	Ls	1,600.00	\$1,600.00
Steel plates at lower curb inlets due to insufficient depth to brick catch basin	2.00	Ea	2,685.00	\$5,370.00
Trench Cap where gas company relocated gas main and left compacted GAB to top of ditch (Price includes removing 9" GAB saw cutting additional 1' on each side of trench and placing concrete •Gas Trench Measurements (9x8)(7x6)(36x5)(10x8) =14.1 Cbyds •Water Trench Measurments (5x30)= 5.5 Cbyds •Storm Trench @ Conflict (6x40) = 8.8 Cbyds	14.10	Sqyds	470.64	\$6,636.02
<b>CO #1 Total</b>				<b>\$41,906.02</b>

Approved: \_\_\_\_\_

Signature

Date: \_\_\_\_\_

Name: \_\_\_\_\_

Print Name

Please sign and return approved quote.

Work is warranted for 1 year from date of completion.